

## **BUILDING NOTES**

All work to be carried out by suitably licensed and qualified tradesmen, and to comply with all relevant standards and Councils requirements.

Main contractor to be responsible for obtaining all necessary inspection certificates.

An approved sedimentation control system is to be installed and maintained for the duration of the contract.

Adjoining properties to be adequately protected at all times.

Asbestos ( if encountered ) is to be removed and disposed of by a suitably qualified contractor.

All dimensions, heights and clearances of excavations, landing areas, existing structures, rail and support structure to be confirmed by manufacturer and builder onsite.


Lift noise level not to exceed 60dB(A) when measured from the outside face of the nearest adjoining dwelling.


Railcars to be painted in neutral colours to blend in with the natural landscape.

Proposed Incline Passenger Lift and associated handarails, gates and safety mechanisms to Railius details and designed and constructed to NZS 5270-2005.


## EROSION AND SEDIMENT CONTROL PLAN

- I. All excavations and backfilling associated with the erection or demolition of a building must be executed safely and in accordance with appropriate professional standards.
- 2. All excavations associated with the erection or demolition of a building must be properly guarded and protected to prevent them from being dangerous to life or property.
- 3. Where excavations extend below the level of the base of the footings of a building on an adjoining allotment of land, the person causing the excavation must preserve and protect the building from damage and, if necessary, underpin and support the adjoining building in an approved manner.
- 4. Temporary sedimentation and erosion controls are to be constructed prior to commencement of any work to eliminate the discharge of sediment from the site.
- 5. Adequate measures shall be undertaken to remove clay from vehicles leaving the site so as to maintain public roads in a clean condition.
- 6. Builder to confirm the locations of barrier fences and stockpiles onsite, see suggested main barrier fence location on site plan.
- 7. Sediment fences and stockpiles to be constructed in arcordance with modern standards and the diagrams below.
- 8. Due to the steeply sloping site and proximity to Pittwater, special care will be taken to prevent soil runoff into existing drains or the waterway.
- 9. Note that due to the constraints of the site, barriers may need to be relocated during construction.
- 10. All ESCP measures are to be in accordance with Landcom's Managing Urban Stormwater: Soils and Construction 2004.





brace top of rail to existing steel frame



Landings 3 \$ 4 existing steel frame timber decks, modify handrails to Railius details

PRO IFCT

DRAWING

new conc footing to eng's details

Drawing to be read in conjuction with Arborist and Geotech reports, Drawing O3 NOTES, and all associated supporting documentation

455 ISSUE NOT FOR CONSTRUCTION



LANDINGS 3\$4 3D 1:100

BUILDING
DESIGNERS
AUSTRALIAN



TROSECT	Proposed modification of DA2020/0776 -
	deletion of Lift 1 at 16 Cabarita Rd, Avalon

DRAWN CHECKED SD SCALE DATE 19.3.20

2003 03A

NOTES / ESCP

REV A 29.9.24

address 77 Riviera rd, Avalon 2017 0488 662 445 www.peterdownes.com.au