

Landscape Referral Response

Application Number:	DA2025/1058
Date:	28/08/2025
Proposed Development:	Construction of a dwelling house including swimming pool
Responsible Officer:	Phil Lane
Land to be developed (Address):	Lot 308 DP 238382 , 34 Tatiara Crescent NORTH NARRABEEN NSW 2101

Reasons for referral

This application seeks consent for the following:

- Construction / development works within 5 metres of a tree or
- New residential works with three or more dwellings. (RFB's, townhouses, seniors living, guesthouses, etc). or
- Mixed use developments containing three or more residential dwellings.
- New Dwellings or

Officer comments

The proposal is supported with regard to landscape issues.

Council's Landscape Referral is assessed against the Pittwater Local Environment Plan clause C4 zone Environmental Living, and the following Pittwater 21 DCP controls (but not limited to):

- B4.22 Preservation of Trees and Bushland Vegetation
- C1.1 Landscaping
- D11 North Narrabeen Locality

The Arboricultural Impact Assessment (AIA) identified 17 trees. Trees 1, 9, 10, 14, 15, 16 and 17 are outside the property boundaries and as such must be retained and protected during works. Their retention is supported in the AIA. Tree 2 is dead and trees 6, 7 and 8 are exempt; these trees may be managed or removed at the discretion of the applicant without consent. From a landscape perspective trees 5, 11 and 13 can be supported for removal subject to native tree replacement planting. All tree removals are subject to comment from Council's Biodiversity referral team. All works in the tree protection zone of trees to be retained shall be supervised by a Project Arborist.

The submitted Landscape Plan does not meet the requirements outlined in the Development Application Lodgement Requirements; however, in this instance the existing front setback landscaped area will be retained, including rock outcropping and established trees, which will help to satisfy the requirements of the PDCP with regard to front setback landscape and streetscape character. An amended Landscape Plan will be required before issuing a Construction Certificate to ensure the proposed planting scheme is documented correctly and sufficient soil depths are provided for planting on structure.

Concern is raised that the proposed bin store and inclinor landing are approximately 1.5 metres above the existing road kerb level and no details are provided as to how this transition will be treated, which may impact the streetscape.

Should the application be approved, conditions of consent have been provided.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

Recommended Landscape Conditions:

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

Amended Landscape Plan

a) Amended Landscape Plan(s) shall be issued to the Certifier prior to the issue of a Construction Certificate to include the following details:

- i) proposed planting scheme including species selection, location, quantities, mature heights and pot sizes,
- ii) two replacement native trees to achieve at least 6 metres height at maturity,
- iii) all tree planting shall be a minimum pre-ordered planting size of 75 litres and be generally selected from Northern Beaches Council's Native Planting Guide, or Council's Tree Guide,
- iv) mass planting shall be installed at minimum 1 metre intervals (or less) for shrubs of a minimum 200mm container size at planting, and at minimum 4 plants per metre square for groundcovers of a minimum 140mm container size at planting,
- v) the on slab planting above the garage shall include shrub planting capable of achieving a mature height of 1-1.5 metres; provide 600mm soil depth.

b) Certification shall be submitted to the Certifier that these amendments have been documented.

Reason: Landscape amenity.

On Slab Landscape Planters

a) Details shall be submitted to the Certifier prior to the issue of the Construction Certificate indicating the proposed method of waterproofing and drainage to all planters over slab, over which soil and planting is being provided. Landscape treatment details shall be submitted to the Certifier prior to the issue of the Construction Certificate indicating the proposed soil type, planting, automatic irrigation, and services connections.

b) The following soil depths are required to support planting: 300mm for groundcovers, grasses, and lawn; 600mm for shrubs; and 1m for small trees.

c) Design certification shall be submitted to the Certifier by a qualified Structural Engineer, that the planters are designed structurally to support the 'wet' weight of landscaping (soil, materials and established planting).

Reason: To ensure appropriate soil depth for planting and ensure waterproofing and drainage is installed.

CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

Project Arborist

a) A Project Arborist with minimum AQF Level 5 in arboriculture shall be engaged prior to any

commencement of works on site to provide tree protection measures in accordance with AS 4970-2025 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment.

b) The Project Arborist shall be in attendance and supervise all works as nominated in the Arboricultural Impact Assessment, and including:

i) the installation of the inclinometer and its proposed alignment.

c) All tree protection measures specified must:

i) be in place before work commences on the site, and

ii) be maintained in good condition during the construction period, and

iii) remain in place for the duration of the construction works.

d) The Project Arborist shall provide certification to the Certifier that all tree protection measures under AS 4970-2025 have been satisfied, and the recommendations listed for the protection of the existing tree(s) have been carried out satisfactorily to ensure no impact to the health of the tree(s). Photographic documentation of the condition of all trees to be retained shall be recorded, including at commencement, during the works and at completion.

Note: any potential impact to trees as assessed by the Project Arborist will require redesign of any approved component to ensure existing trees upon the subject site and adjoining properties are preserved and shall be the subject of a modification application where applicable.

Reason: Tree protection.

Tree Removal Within the Property

a) This consent approves the removal of existing prescribed trees on the subject site as identified in the approved Arboricultural Impact Assessment.

b) A qualified AQF level 5 Arborist shall identify these trees on site and tag or mark prior to removal.

Reason: To enable authorised development works.

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

Protection of Rock and Sites of Significance

a) All rock outcrops outside the area of approved works are to be preserved and protected at all times during demolition, excavation and construction works.

b) Should any Aboriginal sites be uncovered during the carrying out of works, those works are to cease and Council, the NSW Office of Environment and Heritage (OEH) and the Metropolitan Local Aboriginal Land Council are to be contacted.

Reason: Preservation of significant environmental features.

Tree and Vegetation Protection

a) Existing trees and vegetation shall be retained and protected, including:

i) all trees within the site not approved for removal, including trees and vegetation nominated for retention on the approved Plans,

ii) all trees and vegetation located on adjoining properties,

iii) all trees and vegetation within the road reserve.

b) Tree protection shall be undertaken as follows:

- i) tree protection shall be in accordance with AS 4970-2025 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment,
- ii) existing ground levels shall be maintained within the tree protection zone of trees to be retained, unless authorised by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture,
- iii) removal of existing tree roots at or >25mm (Ø) diameter is not permitted without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture,
- iv) no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,
- v) structures are to bridge tree roots at or >25mm (Ø) diameter unless directed by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture on site,
- vi) excavation for stormwater lines and all other utility services is not permitted within the tree protection zone, without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture including advice on root protection measures,
- vii) should either or all of v) or vi) occur during site establishment and construction works, an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture shall provide recommendations for tree protection measures. Details including photographic evidence of works undertaken shall be submitted by the Arborist/Project Arborist to the Principal Certifier,
- viii) any temporary access to, or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of AS 4970-2025 Protection of trees on development sites,
- ix) the activities listed in section 4.2 of AS 4970-2025 Protection of trees on development sites, shall not occur within the tree protection zone of any tree on the lot or any tree on an adjoining site,
- x) tree pruning from within the site to enable approved works shall not exceed 10% of any tree canopy, and shall be in accordance with AS 4373-2007 Pruning of amenity trees,
- xi) the tree protection measures specified in this clause must: be in place before work commences on the site, be maintained in good condition during the construction period, and remain in place for the duration of the construction works.

c) The Principal Certifier must ensure that:

- i) If activated, the arboricultural works listed in a) and b) are undertaken and certified by an Arborist/Project Arborist as complaint to AS 4970-2025 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment.

Reason: Tree and vegetation protection.

CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

Landscape Completion

a) Landscape works are to be implemented in accordance with the approved amended Landscape Plan(s), and inclusive of the following conditions:

- i) landscape works are to be contained within the legal property boundaries,
- ii) planting shall be installed as indicated on the approved Landscape Plan(s) unless otherwise imposed by any conditions,
- iii) two (2) native trees shall be installed within the property boundaries; all tree planting shall be a minimum pre-ordered planting size of 75 litres or as otherwise scheduled if greater in size; generally selected from Northern Beaches Council's Native Planting Guide, or Council's Tree Guide; to achieve at least 6 metres height at maturity; meet the requirements of AS2303 – Tree Stock for Landscape Use; planted into a prepared planting hole 1m x 1m x 600mm depth generally, backfilled with a sandy loam mix or approved similar, mulched to 75mm depth minimum and maintained, and watered until

established; and shall be located at least 3.0 metres from buildings and other trees or more, at least 1.5 metres from common boundaries; and located either within garden bed or within a prepared bed within lawn,

iv) mass planting shall be installed at minimum 1 metre intervals (or less) for shrubs of a minimum 200mm container size at planting or as otherwise scheduled if greater in size, and at minimum 4 plants per metre square for groundcovers of a minimum 140mm container size at planting or as otherwise scheduled if greater in size, and shall be in a garden bed prepared with a suitable free draining soil mix and minimum 75mm depth of mulch,

v) all proposed tree planting shall be positioned in locations to minimise significant impacts on neighbours in terms of blocking winter sunlight to living rooms, private open space and where the proposed location of trees may otherwise be positioned to minimise any significant loss of views from neighbouring and nearby dwellings and from public spaces.

b) Prior to the issue of an Occupation Certificate, details shall be submitted to the Principal Certifier, certifying that the landscape works have been completed in accordance with any conditions of consent.

Reason: Environmental amenity.

Condition of Retained Vegetation

a) Prior to the issue of an Occupation Certificate, a report prepared by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture shall be submitted to the Principal Certifier, assessing the health and impact on all existing trees required to be retained on the approved Plans or as listed in the Arboricultural Impact Assessment, including the following information:

i) compliance to any Arborist recommendations for tree protection generally and during excavation works,

ii) extent of damage sustained by vegetation as a result of the construction works,

iii) any subsequent remedial works required to ensure the long term retention of the vegetation.

Reason: Tree and vegetation protection.

ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

Landscape Maintenance

a) If any landscape materials/components or planting under this consent fails, they are to be replaced with similar materials/components.

b) Trees, shrubs and groundcovers required to be planted under this consent are to be mulched, watered and fertilised as required at the time of planting.

c) If any tree, shrub or groundcover required to be planted under this consent fails, they are to be replaced with similar species to maintain the landscape theme and be generally in accordance with the approved Landscape Plan(s) and any conditions of consent.

d) A maintenance activity schedule for on-going maintenance of planters on slab shall be incorporated to monitor and replenish soil levels as a result of soil shrinkage over time.

e) The approved landscape planted areas, whether containing lawn, gardens or planters shall in perpetuity remain as planting under the development consent, and shall not be replaced with any hard paved surfaces or structures.

Reason: To maintain local environmental amenity.



northern
beaches
council