

REPORT ON GEOTECHNICAL SITE INVESTIGATION

for

PROPOSED ALTERATIONS AND ADDITIONS

at

15 BURRENDONG PLACE, AVALON BEACH

Prepared For

Andrea Musacchio and Monique Ryan-Musacchio

Project No.: 2020-142

July, 2020

Document Revision Record

Issue No	Date	Details of Revisions
0	31 st July 2020	Original issue

Copyright

© This Report is the copyright of Crozier Geotechnical Consultants. Any unauthorised reproduction or usage by any person other than the addressee is strictly prohibited.

GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER **FORM NO. 1 – To be submitted with Development Application**

Development Application for	Andrea Musacchio & Monique Ryan-Musacchio
	(Name of Applicant)
Address of site	15 Burrendong Place, Avalon, NSW

Declaration made by geotechnical engineer or engineering geologist or coastal engineer (where applicable) as part of a geotechnical report

I, Troy Crozier on behalf of Crozier Geotechnical Consultants

on this the 31st July 2020 certify that I am a ~~geotechnical engineer or engineering geologist or coastal engineer~~ as defined by the Geotechnical Risk Management Policy for Pittwater - 2009 and I am authorised by the above organisation/company to issue this document and to certify that the organisation/company has a current professional indemnity policy of at least \$2million.

I:

- ☐ have prepared the detailed Geotechnical Report referenced below in accordance with the Australia Geomechanics Society's Landslide Risk Management Guidelines (AGS 2007) and the Geotechnical Risk Management Policy for Pittwater - 2009
- ☒ am willing to technically verify that the detailed Geotechnical Report referenced below has been prepared in accordance with the Australian Geomechanics Society's Landslide Risk Management Guidelines (AGS 2007) and the Geotechnical Risk Management Policy for Pittwater - 2009
- ☐ have examined the site and the proposed development in detail and have carried out a risk assessment in accordance with Section 6.0 of the Geotechnical Risk Management Policy for Pittwater - 2009. I confirm that the results of the risk assessment for the proposed development are in compliance with the Geotechnical Risk Management Policy for Pittwater - 2009 and further detailed geotechnical reporting is not required for the subject site.
- ☐ have examined the site and the proposed development/alteration in detail and I am of the opinion that the Development Application only involves Minor Development/Alteration that does not require a Geotechnical Report or Risk Assessment and hence my Report is in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009 requirements.
- ☐ have examined the site and the proposed development/alteration is separate from and is not affected by a Geotechnical Hazard and does not require a Geotechnical Report or Risk Assessment and hence my Report is in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009 requirements.
- ☐ have provided the coastal process and coastal forces analysis for inclusion in the Geotechnical Report

Geotechnical Report Details:


Report Title:	Geotechnical report for proposed alterations and additions at 15 Burrendong Place, Avalon	
Report Date:	30 th July 2020	Project No.: 2020-142
Author:	Joshua Cotton	
Author's Company/Organisation:	Crozier Geotechnical Consultants	

Documentation which relate to or are relied upon in report preparation:

Architectural Drawings – Laura Cook, Project Name: 'Ryan-Musacchio Residence', Page No.: DA.01(P1) – DA.14(P1), Dated: 06/05/2020
Landscape Drawings – Grant Clement, landscape architect and pool designer, Project No.: 100, Drawing No.: L100B – L300B, Dated: 30/01/2018
Survey Drawing – Burton & Field Surveying and Land Development, Comp Ref.: 80531_C, Dated: 19/12/19

I am aware that the above Geotechnical Report, prepared for the abovementioned site is to be submitted in support of a Development Application for this site and will be relied on by Pittwater Council as the basis for ensuring that the Geotechnical Risk Management aspects of the proposed development have been adequately addressed to achieve an "Acceptable Risk Management" level for the life of the structure, taken as at least 100 years unless otherwise stated and justified in the Report and that reasonable and practical measures have been identified to remove foreseeable risk.

Signature
 Name ...Troy Crozier.....
 Chartered Professional Status...RPGeo (AIG).....
 Membership No. ...10197.....
 Company... Crozier Geotechnical Consultants



GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER
FORM NO. 1(a) - Checklist of Requirements For Geotechnical Risk Management Report for Development Application

Development Application for	Andrea Musacchio & Monique Ryan-Musacchio (Name of Applicant)
Address of site	15 Burrendong Place, Avalon, NSW

The following checklist covers the minimum requirements to be addressed in a Geotechnical Risk Management Geotechnical Report. This checklist is to accompany the Geotechnical Report and its certification (Form No. 1).

Geotechnical Report Details:

Report Title: Geotechnical report for proposed alterations and additions at 15 Burrendong Place, Avalon	Project No.: 2020-142
Report Date: 30 th July 2020	
Author: Joshua Cotton	
Author's Company/Organisation: Crozier Geotechnical Consultants	

Please mark appropriate box

- ☒ Comprehensive site mapping conducted 22/07/2020 (date)
- ☒ Mapping details presented on contoured site plan with geomorphic mapping to a minimum scale of 1:200 (as appropriate)
- ☒ Subsurface investigation required
 - ☐ No Justification
 - ☒ Yes Date conducted22/07/2020.....
- ☒ Geotechnical model developed and reported as an inferred subsurface type-section
- ☒ Geotechnical hazards identified
 - ☐ Above the site
 - ☒ On the site
 - ☐ Below the site
 - ☐ Beside the site
- ☒ Geotechnical hazards described and reported
- ☒ Risk assessment conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009
 - ☒ Consequence analysis
 - ☒ Frequency analysis
- ☒ Risk calculation
- ☒ Risk assessment for property conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009
- ☒ Risk assessment for loss of life conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009
- ☒ Assessed risks have been compared to "Acceptable Risk Management" criteria as defined in the Geotechnical Risk Management Policy for Pittwater - 2009
- ☒ Opinion has been provided that the design can achieve the "Acceptable Risk Management" criteria provided that the specified conditions are achieved.
- ☒ Design Life Adopted:
 - ☒ 100 years
 - ☐ Other specify
- ☒ Geotechnical Conditions to be applied to all four phases as described in the Geotechnical Risk Management Policy for Pittwater - 2009 have been specified
- ☒ Additional action to remove risk where reasonable and practical have been identified and included in the report.
- ☐ Risk assessment within Bushfire Asset Protection Zone.

I am aware that Pittwater Council will rely on the Geotechnical Report, to which this checklist applies, as the basis for ensuring that the geotechnical risk management aspects of the proposal have been adequately addressed to achieve an "Acceptable Risk Management" level for the life of the structure, taken as at least 100 years unless otherwise stated, and justified in the Report and that reasonable and practical measures have been identified to remove foreseeable risk.

Signature *T Crozier*
 Name ... **Troy Crozier**
 Chartered Professional Status... **RPGGeo (AIG)**
 Membership No. ... **10197**
 Company... **Crozier Geotechnical Consultants**




TABLE OF CONTENTS

1.0	INTRODUCTION	Page 1
2.0	PROPOSED DEVELOPMENT	Page 2
3.0	SITE FEATURES	
3.1	Description	Page 3
3.2	Geology	Page 5
4.0	FIELD WORK	
4.1	Investigation Methods	Page 5
4.2	Field Observations	Page 6
4.3	Ground Conditions	Page 9
5.0	GEOTECHNICAL ASSESSMENT	
5.1	Comments	Page 10
5.2	Site Specific Risk Assessment	Page 12
5.3	Design & Construction Recommendations	
5.3.1	New Footings	Page 13
5.3.2	Excavation	Page 14
5.3.3	Retaining Structures	Page 16
5.3.4	Drainage & Hydrogeology	Page 16
5.4	Conditions Relating to Design & Construction Monitoring	Page 17
5.5	Design Life of Structure	Page 18
6.0	CONCLUSION	Page 19
7.0	REFERENCES	Page 20

APPENDICES

- 1** Notes Relating to this Report
- 2** Figure 1 ñ Site Plan, Figure 2 Geological Model
Borehole Log sheets and Dynamic Penetrometer Test Results
- 3** Landslip Risk Assessment Tables
- 4** AGS Terms & Description
- 5** Hillside Construction Guidelines

Date: 30th July 2020

Project No: 2020-142

Page: 1 of 20

**GEOTECHNICAL REPORT FOR PROPOSED ALTERATIONS AND ADDITIONS
15 BURRENDONG PLACE, AVALON**

1. INTRODUCTION:

This report details the results of a geotechnical investigation and assessment carried out for proposed alterations and additions including construction of a first floor level on the existing dwelling, a two storey garage/ studio and a swimming pool at 15 Burrendong Place, Avalon, NSW. The investigation was undertaken by Crozier Geotechnical Consultants (CGC) at the request of the clients Andrea Musacchio and Monique Ryan-Musacchio.

The proposed works involve the addition of a first floor level, which will extend to a proposed ridge at R.L.41.135m. Proposed works at the rear of the site include the removal of the existing carport and construction of a two storey structure, comprising a ground level single car garage and first floor studio apartment, excavation will likely only be required for footings. A partly in ground swimming pool is to be constructed within the rear of the site, requiring bulk excavation along north eastern portions of the structure to 0.3m depth.

The site is located within the H1 (highest category) landslip hazard zone as identified within Northern Beaches Councils Geotechnical Risk Management Policy for Pittwater ñ 2009 öSheet GTH_016ö To meet the Councils Policy requirements for land classified as H1 this Geotechnical Report includes a landslide risk assessment to the methods of AGS 2007 for the site and proposed works, plans, geological sections and provides recommendations for construction and to ensure the öAcceptable Risk Managementö criteria is maintained for a preferred design life of 100 years. It is recommended that the client make themselves aware of the Policy and its requirements.

The investigation and reporting were undertaken as per the Tender: P20-263 Dated: 11th June 2020.

The geotechnical investigation included:

- a) Drilling of three boreholes using hand tools along with Dynamic Cone Penetrometer (DCP) tests to determine the subsurface geology, depth to bedrock, and identification of groundwater
- b) Excavation of one test pit to identify footing details and founding conditions
- c) Detailed geotechnical mapping of the entire site and adjacent land, with identification of geotechnical conditions and hazards including landslip related to the existing site and structures
- d) A photographic record of site conditions.

The following documents have been supplied in regard to the proposed investigation:

- Architectural Drawings ñ Laura Cook, Project Name: *ñRyan-Musacchio Residence'*, Page No.: DA.01(P1) ñ DA.14(P1), Dated: 06/05/2020
- Landscape Drawings ñ Grant Clement, landscape architect and pool designer, Project No.: 100, Drawing No.: L100B ñ L300B, Dated: 30/01/2018
- Survey Drawing ñ Burton & Field Surveying and Land Development, Comp Ref.: 80531_C, Dated: 19/12/19

2. PROPOSED DEVELOPMENT:

The proposed works include the construction of an additional storey on the existing structure, the installation of a swimming pool and the construction of a two storey garage and studio structure. The proposed swimming pool is to be positioned partly within a retained grassed lawn. This will incur a maximum excavation of approximately 2.3m depth within north eastern portions of the structure and a minimum excavation depth of 0.20m within south western portions of the structure due to the ground surface slope. Excavation for the swimming pool will extend to 1.10m from the south eastern boundary and will be located 1.0m from all other boundaries.

The garage and studio structure is to be located at the rear of the site, replacing the existing cantilevered steel carport structure. A 3.0m wide shared driveway is located to the rear of the existing garden fence, with the proposed structure to be located on the south western side of this driveway. The proposed structure is to extend to 1.0m from the rear boundary and to 1.0m from the north western side boundary. No bulk excavation is required for the garage studio structure, however, isolated excavation for footings will be required.

The proposed first floor level addition to the main structure will include two bedrooms, a living space and a bathroom. Alterations to the existing ground floor level of the main structure include the removal and addition


of internal walls with adjustments to the building envelope at the front of the structure. Further alterations include the extension of the existing rear covered deck area to the edge of the top retaining wall, within the rear of the site. The existing main structure has a minimum north west side setback of 1.2m and a south east side setback of 2.8m, the rear elevated decking area extends to 0.5m from the north western boundary.

3. SITE FEATURES:

3.1. Description:

The site is a rectangular shaped block located on the low east side of Burrendong Place, with vehicle access to the rear of the site via a shared driveway with an entrance point to the south west of No. 16 Burrendong Place. It has a front north east boundary of 17.97m, a south east side boundary of 38.375m, a north west side boundary of 38.36m, and a rear south west boundary of 18.55m, as referenced from the provided topographical survey plan.

An aerial photograph of the site and its surrounds is provided below (Photograph 1), as sourced from NSW Government Six Map spatial data.



Photograph 1: Aerial photo of site and surrounds

The site is located within moderate ($\approx 15^\circ$) southwest dipping topography, with a high of RL=40.7m at the front of the site and a low of RL=28.82m at the rear of the site. The site is currently occupied by a one and two storey brick residence with a rear elevated timber decking area. The front and rear of the site consist of retained terraced gardens and lawns, with a shared driveway intersecting the site to the south west of the 1.8m timber garden fence. General views of the front and rear of the site are shown in Photograph 2 and Photograph 3.



Photograph 2: View of the rear of the site and main structure, looking north east



Photograph 3: View of the front of the site and main structure, looking south

Reference to the Sydney 1: 100,000 Geological Series sheet (9130) indicates that the site is underlain by Newport Formation (Rnn) of the Upper Narrabeen Group. Newport Formation (Upper Narrabeen Group) is of middle Triassic Age and typically comprises interbedded laminite, shale and quartz to lithic quartz sandstones and pink clay pellet sandstones.

Narrabeen Group rocks are dominated by shales and thin siltstone/ sandstone beds and often form rounded convex ridge tops with moderate angle ($<20^{\circ}$) side slopes. These side slopes can be either concave or convex depending on geology, internally they comprise interbedded shale and siltstone/sandstone beds with close spaced bedding partings that have either close spaced vertical joints or in extreme cases large space convex joints. The shale often forms deeply weathered profiles with silty or medium to high plasticity clays and a thin silty colluvial cover.



Photograph 1:100,000 geological reference

4.1. Investigation Methods:

The field investigation comprised a geotechnical inspection of the site and adjacent land on the 22nd July 2020. It involved a photographic record of site conditions as well as geotechnical assessment of the site and adjacent land with examination of soil slopes and existing structures. It also included the drilling of three auger boreholes (BH1 ñ BH3) and one test pit (TP1) using hand tools to determine sub-surface geology as well as footing details and founding conditions.

DCP testing was carried out from ground surface adjacent to BH1-BH3 and TP1 in accordance with AS1289.6.3.2 – 1997, ‘Determination of the penetration resistance of a soil – 9kg Dynamic Cone Penetrometer’ to estimate near surface soil conditions and confirm depths to bedrock.

Explanatory notes are included in Appendix: 1. Mapping information and test locations are shown on Figure: 1, along with detailed borehole log sheets and DCP test sheet in Appendix: 2. The geological model/section is provided as Figure: 2, Appendix: 2.

4.2. Field Observations:

The site is situated on the low south west side of Burrendong Place within moderate to steep south west dipping topography. Burrendong Place is formed with a bitumen pavement and concrete kerb and gutter which moderately dips north west and west down the winding road reserve. There were no signs of excessive cracking or deformation within the road pavement to suggest any movement or underlying geotechnical issues.

The front of the site is limited to pedestrian access only; vehicle access to the rear of the site and existing carport structure is available via a stripped concrete shared driveway. This shared driveway intersects Burrendong Place along the south western boundary of the neighbouring property to the north west (No. 16 Burrendong Place).

Retaining walls and grassed terrace lawns occupy the front of the site. The top dry stack stone retaining wall is ~1.2m high with the lower retaining wall within the front of the site extending to a height ~0.8m. The base of the lower retaining wall is level with the front decking area and concrete side access walkway. The sub vertical retaining walls within the front of the site appear to be in good condition, the lower retaining wall is shown in Photograph 5. Large gum trees are positioned within the front of the site and along the front boundary.



Photograph 5: Lower front retaining wall, facing south east

The rear of the site similarly consists of retained grassed lawns and gardens, with the retaining systems utilizing a similar dry stack, rough cut sandstone block design. The rear retaining wall includes a 0.45m high timber bordered garden bed with a 0.8m high dry stack retaining wall; this stone retaining wall extends across the width of the site. Cut sandstone block stairs provide access between the upper and lower portions of the rear landscaped area. The rear retaining walls appear to be in moderate to good condition. A 1.8m high timber fence is located approximately 9m from the rear boundary, on the north eastern side of the shared driveway.

Sandstone rock outcrops were observed on the high side of Burrendong Place within No.2 Burrendong Place. The interpreted outcropping bedrock is formed with tabular blocks, consisting of medium to coarse grained sandstone. Approximately ten individual outcrops were noted across the front portion of the adjacent property, some of these outcrops are shown in Photograph 6, 7 and 8.



Photograph 6 & 7: Rock outcrops within No. 2 Burrendong Place.



Photograph 8: Rock outcrops within eastern portion of the front of No. 2 Burrendong Place.

The existing site dwelling is of one and two storey brick and timber construction located in the center of the site. The composition of the structure is dictated by the natural topography of the site, with one storey to the front and two storeys to the rear. The lower ground sub-floor level consists of a basement storage and work area, however only the south western portion of the sub floor level is of a standing height clearance. The footings for the house are visible within this sub floor level, with approximately 25 brick footings observed, ranging in height from 0.3m to 1.2m. The stepped silty sand fill soil profile on the north western side of the sub-floor basement walkway is 0.1m high, minor seepage was observed on the surface, this is shown in Photograph 9. it is unknown whether these footings are founded on rock, fill or residual soil. The main structure had no signs of significant cracking or movement.



Photograph 8: Stepped soil profile in basement sub floor level, facing south east



Photograph 9: Exposed footings in basement sub floor level, facing south east

The existing carport within the rear of the site on the south western side of the approximately 3.0m wide shared driveway is positioned 0.1m from the rear boundary. The structure consists of steel SHS vertical members bolted to a cantilevered steel awning, square concrete footings are located at the base of the structure. An approximate 1.1m drop and brick retaining wall is located along the rear boundary.

The property to the south east (No.14 Burrendong Place) contains a one and two storey brick residence positioned within similar topography as the site. The main structure is located within the center of the property, the structure has a side setback of approximately 3.0m to the common boundary. A high 3.0m timber fence extends along the common boundary with the site, therefore inspection of the neighbouring property to the south east was limited.

The property to the north west (No. 16 Burrendong Place) contains a one and two storey rendered residence, situated within moderate south west to west dipping topography. The main structure is located 1.0m from the common boundary with the site. Stormwater downpipes appear to extend to a drainage point at the front and rear of the main structure near the common boundary with the site. The dwelling appears to be 50 years of age and in a good condition with no sign of cracking or settlement on the external walls.

The properties to the rear of the site (No. 164 & No. 166 Central Road) both contain dwellings located towards the front of the properties. An approximate 30m setback between the main structures and the common boundary with the site exists. No. 166 Central Road contains a shed within the northern corner of the property. The rear of both properties contain retaining walls 1.5m along the common boundary with the site.

4.3. Ground Conditions:

The boreholes (BH1 to BH3) were drilled using a hand auger at select locations within the site with refusal encountered at depths varying from 0.65m (BH1a) to 1.95m (BH3).

Dynamic Cone Penetrometer (DCP) tests were carried out from the ground surface adjacent to the boreholes (DCP1-DCP3) and test pit (DCP4). All DCP tests encountered refusal between 0.75m (DCP4) and 1.75m (DCP3) on interpreted sandstone bedrock of at least very low strength.

Based on the borehole logs and DCP test results, the sub-surface conditions at the project site can be classified as follows:

- **TOPSOIL/ FILL** – this layer was encountered in all boreholes to varying depths between to 0.40m (BH2) and 1.20m (BH3). It is classified as loose to dense, dark brown, fine to medium grained, moist silty sand. BH1 and BH1a refused in fill soils as coarse gravel, sandstone cobbles and bricks were intersected in both boreholes.
- **SANDY CLAY** – Based on the borehole logs and DCP test results, residual soil underlays the silty sand fill to depths between 1.00m (BH2) and 1.80m (BH3). This layer is classified as stiff, light brown and orange, low to medium plasticity, moist, sandy clay.

- **SANDSTONE BEDROCK** ñ Extremely low strength/ extremely weathered sandstone grading to at least very low strength sandstone was encountered at 1.00m (BH2) and 1.80m (BH3). Refusal on interpreted sandstone bedrock of at least very low strength was encountered at 1.95m depth at BH3 and 1.48m at DCP2. Test pit 1 encountered refusal on interpreted sandstone bedrock of at least low strength at 0.75m depth.

A free standing ground water table or significant water seepage were not identified within any of the boreholes. No signs of ground water were observed after the retrieval of the DCP rods.

5. GEOTECHNICAL ASSESSMENT:

5.1. Comments:

The site investigation identified the presence of silty sand topsoil/ fill to a maximum drilled depth of 1.20m (BH3), with BH1 and BH1a refusing in fill soils. Fill soils are underlain by stiff sandy clay between 1.20m ñ 1.80m depth (BH3) and 0.40m ñ 1.00m depth (BH2). Interpreted sandstone bedrock underlies the residual soil layer, with extremely low strength grading to at least very low strength sandstone bedrock encountered across the site. DCP refusals on interpreted sandstone bedrock of at least very low strength were recorded at the following depths; 1.60m (DCP1a), 1.48m (DCP2), 1.75m (DCP3) and 0.75m (TP1).

The bedrock profile appears to step down the moderate south west to west dipping slope. Exposed planar bedrock is evident on the high side of the street, as shown in Photograph 6, it is anticipated that these cliff drops continue throughout the site. No seepage or groundwater was encountered during the investigation however, it is likely that minor seepage will be intersected at the soil - rock interface and on defects in the bedrock during excavation. A freestanding water table was not encountered and is not expected within the site due to the topography of the site and surrounds.

It is understood that bulk excavation is required for the swimming pool. The location of the proposed swimming pool will intersect the existing 1.25m high retaining wall in the southern portion of the site. The upper side of the swimming pool will require an estimated 2.3m depth excavation. According to the borehole results encountered at BH3, rock excavation within this deeper region of excavation will be minimal if any (0.25m). The lower south western side of the swimming pool is expected to require minimal bulk excavation, due to the location of the retaining wall and the slope of the natural surface level. It is understood that the deep end of the swimming pool will be at the south eastern end, extending to 1.1m from the site boundary. Due to the proximity of the excavation to the boundary line and the soils that will likely be intersected, temporary support systems will need to be established along this south eastern portion of

excavation. Temporary batter slopes appear to be achievable at all other sides of the swimming pool excavation.

Careful consideration should be taken in regards to the foundations of the swimming pool, as the base of the upper portion of the swimming pool will likely be founded on sandstone bedrock of at least low strength, however the base of the lower portion of the pool will likely be in silty sand topsoil/fill. This is due to the location of the retaining wall and the natural slope of the site. Therefore, it is recommended that the lower, south western portion of the pool includes piers to rock of at least low strength, to reduce the risk of differential settlement. The proposed swimming pool appears to be positioned on the high side of an existing Sydney Water Sewer asset. The landscape architectural drawings depicts this sewer line within close proximity of the proposed works, careful consideration should be taken to avoid intersecting the sewer.

The proposed garage and studio structure at the rear of the site consists of a narrow two storey structure, stepping out from a minimum width of 2.5m, to a maximum width of 3.5m along the north western wall. The two neighbouring properties to the rear of the site (No.164 & No.166 Central Road) contain brick retaining walls along the common boundary with the site to an approximate height of 1.1m. During borehole drilling multiple bricks, bottles and sandstone cobbles were encountered, with varying strength characteristics recorded between both DCP1 and DCP1a. BH1 and DCP1 both refused at the same depth, with both locations positioned in relative proximity to one of the carport supports (0.7m), therefore it is likely that at 0.75m large footings for the existing carport structure step out.

It is understood that no bulk excavation for the garage studio structure is required, however, excavation for footings will be required as the variable nature of the fill encountered, and its apparent uncontrolled nature make it unsuitable for structural footings. As a result, footings for ancillary structures including the proposed garage studio structure, requiring less than 150kPa may extend into stiff to very stiff sandy clay residual soil, however, it would be prudent to extend all footings to bedrock of at least low strength to reduce potential swelling of adjacent retaining walls and creep movement. The founding conditions and structural details of the existing footings for the carport are unknown and it is therefore recommended that these footings are discarded upon demolition of the structure.

The test pit was conducted along the exterior of the rear wall of the existing house approximately 2.5m from the north western side wall of the main structure. A concrete strip footing extended 150mm out horizontally from the wall and down 250mm with an approximate 5° gradient towards the structure observed within the 0.4m x 0.2m x 0.35m test pit. The footing appeared to be resting on a thin, very dense layer of ironstone gravel, within the compacted fill layer, comprising medium dense silty sand with gravel. These footings are

believed to continue around the perimeter of the structure. The main structure was observed to be in good condition with no visible signs of movement or cracking.

The proposed alterations and additions for the main structure include a first floor living level, removal and addition of ground floor level internal walls with adjustments to the front external walls as well as the extension of the existing covered decking area south-west. The footings of the main structure appear stable with the foundation considered to be suitable for an allowable bearing pressure of 150kPa prior to the original structures construction. The extension of the covered decking area will require new footings at the base of the south-western supports. Footings for the ancillary structure, if requiring less than 150kPa may extend into stiff to very stiff sandy clay residual soil, however, it would be prudent to extend all footings to bedrock of at least low strength, to reduce the risk of differential settlement.

The site is classified as being within a H1 (highest category) landslide hazard zone as identified within Northern Beaches Councils Geotechnical Risk Management Policy for Pittwater ñ 2009. However, the on-site inspection and previous geotechnical experience within the area identified no evidence of landslide issues within the site or adjacent properties/ areas.

The proposed works are considered suitable for the site and may be completed with negligible impact to the adjacent properties provided the recommendations of this report are implemented in the design and construction phases.

The recommendations and conclusions in this report are based on an investigation utilising only surface observations and hand drilling tools due to access limitations. This test equipment provides limited data from small isolated test points across the entire site with limited penetration into rock, therefore some minor variation to the interpreted sub-surface conditions is possible, especially between test locations. The results of the investigation provide a reasonable basis for the analysis and subsequent design of the proposed works.

5.2. Site Specific Risk Assessment:

Based on our site investigation we have identified the following geological/geotechnical hazards which need to be considered in relation to the existing site and the proposed works. The hazards are:

- A. Landslip (earth slide < 3m³) of surficial soils from proposed excavation

The hazards have been assessed in accordance with the methods of the Australian Geomechanics Society (Landslide Risk Management, AGS Subcommittee, May 2002 and March 2007), see Tables: A and B, Appendix: 3 The Australian Geomechanics Society Qualitative Risk Analysis Matrix is enclosed in

Appendix: 4 along with relevant AGS notes and figures. The frequency of failure was interpreted from existing site conditions and previous experience in these geological units.

The **Risk to Life** from **Hazard A** was estimated to be up to 1.33×10^{-7} for persons within the neighbouring property adjacent to the excavation, while the **Risk to Property** was considered to be ‘**Moderate**’ in some situations.

Although the ‘Moderate’ Risk to Property for Hazard A is considered to be ‘Unacceptable’, the assessments were based on excavations with no support or planning or implementation of the proposed engineered structures. Provided the recommendations of this report are implemented including the installation of the proposed engineered support around the critical boundaries the likelihood of any failure becomes ‘Rare’ and as such the consequences reduce and risk becomes within ‘Acceptable’ levels when assessed against the criteria of the AGS. As such the project is considered suitable for the site provided the recommendations of this report are implemented.

5.3. Design & Construction Recommendations:

Design and the construction recommendations are tabulated below:

5.3.1. New Footings:	
Site Classification as per AS2870 ñ 2011 for new footing design	Class ‘A’ Class ‘B’ due to fill within retained sections
Type of Footing	Slab at base of north eastern portion of swimming pool where into bedrock, piers founded on bedrock at base of south western portion of swimming pool and elsewhere
Sub-grade material and Maximum Allowable Bearing Capacity	- Stiff Sandy Clay: 100kPa - Very Stiff Silty Clay: 200kPa - Weathered, VLS Sandstone: 800kPa - Weathered LS Sandstone: 1000kPa
Site sub-soil classification as per <i>Structural design actions AS1170.4 – 2007, Part 4: Earthquake actions in Australia</i>	B _e ñ rock site
Remarks: All footings for each structure should be founded off material of similar strength to prevent differential settlement. Ancillary structures may be founded off stiff to very stiff residual clay where minor soil creep movement can be tolerated. All new footings must be inspected by an experienced geotechnical professional before concrete or steel are placed to verify their bearing capacity and the in-situ nature of the founding strata. This is mandatory to allow them to be ‘certified’ at the end of the project.	

5.3.2. Excavation:		
Depth of Excavation	North eastern side of swimming pool excavation Û2.3m depth	
Distance of Excavation to Neighbouring Properties	No. 14 Burrendong Place: 1.1m from boundary, further 3.0m to neighbouring house No. 16 Burrendong Place: 10.6m from boundary, further 1.0m to neighbouring house	
Type of Material to be Excavated	- Very loose to dense silty sand topsoil/fill to maximum depth of 1.20m (BH3) and 0.40 (BH2) - Stiff sandy clay; to a maximum of 1.80m (BH3) and 1.0m (BH2) - ELS to VLS bedrock ñ from a depth of 1.80m to a maximum of 1.95m (BH3) and from a depth of 1.0m to 1.48m (DCP2) - VLS to LS bedrock ñ from a minimum depth of 1.70m (DCP4) and maximum depth of 1.87m (DCP3).	
Guidelines for un-surcharged batter slopes for general guidance are tabulated below:		
Material	Safe Batter Slope (H:V)	
	Short Term/ Temporary	Long Term/ Permanent
Fill and natural soils	1.5:1	2:1
Extremely Low to Very Low strength or fractured bedrock	1:1	1.25:1
Low to Medium strength (defect free) bedrock	Vertical *	Vertical *
*Subject to geotechnical inspection		
Remarks: Seepage through fill and sandy soils can reduce the stability of batter slopes and invoke the need to implement additional support measures. Where safe batter slopes are not implemented the stability of the excavation cannot be guaranteed until the installation of permanent support measures. This should also be considered with respect to safe working conditions. All excavation should be planned and geotechnically assessed continually during excavation. Where insufficient space exists for the batters as per above for boundaries, any existing footing or significant tree, then temporary or permanent retention measures should be designed and implemented. The installation of which will require geotechnical inspection.		
Equipment for Excavation	Fill and natural soils	Excavator with bucket
	ELS bedrock	Excavator with bucket

	VLS bedrock	Excavator with bucket and ripper
	LS bedrock	Excavator with bucket and ripper /small (<150kg) rock hammer
ELS ñ extremely low strength, VLS ñ very low strength, LS ñ low strength		
Remarks: The saw cut faces generally remain more stable and require a lower level of rock support than hammer cut excavations, ground vibrations from rock saws are minimal and the saw cuts will provide a slight increase in buffer distance for use of rock hammers.		
Recommended Vibration Limits (Maximum Peak Particle Velocity (PPV))	No. 14 Burrendong Place = 5mm/s No. 16 Burrendong Place = 5mm/s Road Reserve Burrendong Place = 5mm/s Service lines = 3mm/s	
Vibration Calibration Tests Required	If medium to high strength bedrock is exposed at base of excavation and large rock hammers (Q250kg) are proposed for use.	
Full time vibration Monitoring Required	Pending proposed equipment and vibration calibration testing results	
Geotechnical Inspection Requirement	Yes, recommended that these inspections be undertaken as per below mentioned sequence: • Installation of support systems • Upon clearing of all soils from the bedrock surface, • Inspection of temporary and permanent batter slopes • At completion of the excavation and for footings • Any unsupported excavation.	
Dilapidation Surveys Requirement	Recommended within 5.0m of excavation perimeter	
Remarks: Water ingress into exposed excavations can result in erosion and stability concerns in both soil and rock portions. Drainage measures will need to be in place during excavation works to divert any surface flow away from the excavation crest and any batter slope. It is recommended that a drainage excavation extend to below the basement floor slab level to reduce the potential for dampness problems in the completed structure.		

5.3.3. Retaining Structures:					
Required			New retaining structures are required as part of the proposed development		
Types			Steel reinforced concrete/concrete block walls post excavation where temporary batters are possible, soldier piles with shotcrete or similar engineered system where temporary batters are not achievable. Designed in accordance with Australian Standards AS4678-2002 Earth Retaining Structures.		
Parameters for calculating pressures acting on retaining walls for the materials likely to be retained:					
Material	Unit Weight (kN/m3)	Long Term (Drained)	Earth Pressure Coefficients		Passive Earth Pressure Coefficient *
			Active (Ka)	At Rest (K ₀)	
Fill Soils	18	ϕ' = 30°	0.41	0.50	N/A
Silty/ Sandy Clay (very stiff)	20	ϕ' = 35°	0.27	0.50	N/A
ELS bedrock	22	ϕ' = 38°	0.32	0.20	200kPa
LS or fractured bedrock	23	ϕ' = 40°	0.25	0.36	400kPa
Remarks: In suggesting these parameters it is assumed that the retaining walls will be fully drained with suitable subsoil drains provided at the rear of the wall footings. If this is not done, then the walls should be designed to support full hydrostatic pressure in addition to pressures due to the soil backfill. It is suggested that the retaining walls should be back filled with free-draining granular material (preferably not recycled concrete) which is only lightly compacted in order to minimize horizontal stresses.					
Retaining structures near site boundaries or supporting existing structures should be designed with the use of at rest (K ₀) earth pressure coefficients to reduce the risk of movement in the excavation support and resulting surface movement in adjoining areas. Backfilled retaining walls within the site, away from site boundaries or existing structures, that may deflect can utilize active earth pressure coefficients (Ka).					

5.3.4. Drainage and Hydrogeology		
Groundwater Table or Seepage identified in Investigation		No
Excavation likely to intersect	Water Table	No
	Seepage	Minor, at interpreted soil - rock interface

Site Location and Topography	Low east side of the road, within moderate north east and east dipping topography. Site towards low northern end of Bruce Street, formed with gently north dipping bitumen pavement.
Impact of development on local hydrogeology	Negligible
Onsite Stormwater Disposal	Possible via dispersal system
Remarks: Exposed excavation faces should be expected to receive seepage from surface and subsurface water flow down slope. This can result in relaxation of excavation faces causing instability prior to installation of permanent retention systems. Therefore excavation faces should not remain open for long periods of time unless assessed to be stable by a geotechnical professional. A stormwater diversion drain should be installed upslope of excavation crests to intercept stormwater runoff and prevent erosion and softening of the excavation faces. An excavation trench should also be installed at the base of excavation cuts to below floor slab levels to reduce the risk of long term dampness. Trenches, as well as all new building gutters, down pipes and stormwater intercept trenches should be connected to a stormwater system designed by a Hydraulic Engineer which preferably discharges to the Council's stormwater system off site.	

5.4. Conditions Relating to Design and Construction Monitoring:

To allow certification at the completion of the project it will be necessary for Crozier Geotechnical Consultants to:

1. Review and approve the structural design drawings prior to the Construction Certificate.
2. Inspect excavation, unsupported cuts/slopes batters and temporary support systems.
3. Inspect all new footings and earthworks to confirm compliance to design assumptions with respect to allowable bearing pressure, basal cleanness and stability prior to the placement of steel or concrete.
4. Inspect excavation equipment to determine whether vibration monitoring is required where large (>250kg) rock hammers are proposed.

The client and builder should make themselves familiar with the requirements spelled out in this report for inspections during the construction phase. CGC cannot complete the certification (Form 3) if it has not been called to site to undertake the required inspections.

5.5. Design Life of Structure:

We have interpreted the design life requirements specified within Councils Risk Management Policy to refer to structural elements designed to support the house etc, the adjacent slope, control stormwater and maintain the risk of instability within acceptable limits. Specific structures and features that may affect the maintenance and stability of the site in relation to the proposed development are considered to comprise:

- Stormwater and subsoil drainage systems,
- Retaining walls and soil slope erosion/instability,
- Maintenance of trees/vegetation on this and adjacent properties.

Man-made features should be designed and maintained for a design life consistent with surrounding structures (as per AS2870 ñ 2011 (100 years)). It will be necessary for the structural and geotechnical engineers to incorporate appropriate design and inspection procedures during the construction period. Additionally the property owner should adopt and implement a maintenance and inspection program.

If this maintenance and inspection schedule are not maintained the design life of the property cannot be attained. A recommended program is given in Table: C in Appendix: 3 and should also include the following guidelines.

- The conditions on the block don't change from those present at the time this report was prepared, except for the changes due to this development.
- There is no change to the property due to an extraordinary event external to this site
- The property is maintained in good order and in accordance with the guidelines set out in;
 - a) CSIRO sheet BTF 18
 - b) Australian Geomechanics 'Landslide Risk Management' Volume 42, March 2007.
 - c) AS 2870 ñ 2011, Australian Standard for Residential Slabs and Footings

Where changes to site conditions are identified during the maintenance and inspection program, reference should be made to relevant professionals (e.g. structural engineer, geotechnical engineer or Council). Where the property owner has any lack of understanding or concerns about the implementation of any component of the maintenance and inspection program the relevant engineer should be contacted for advice or to complete the component. It is assumed that Council will control development on neighbouring properties, carry out regular inspections and maintenance of the road verge, stormwater systems and large trees on public land below the site so as to ensure that stability conditions do not deteriorate with potential increase in risk level to the site. Also individual Government Departments will maintain public utilities in the form of power lines, water and sewer mains to ensure they don't leak and increase either the local groundwater level or landslide potential.

6. CONCLUSION:

The site investigation identified the presence of very loose to loose silty sand fill to varying depths between 0.40m (BH2) and 1.20m (BH3) across the site due to multiple retained gardens and landscape works. The topsoil/ fill layer is underlain by stiff sandy clay encountered to depths between 1.00m (BH2) and 1.80m (BH3). Sandstone bedrock underlies all residual soils grading from extremely low strength to at least low strength at 1.48m (DCP2) and 1.95m (BH3). Groundwater or significant seepage was not identified to 1.95m depth.

It is understood the proposed works involve the construction of an additional first floor level on the main structure with further alterations within the main structure, construction of a rear 2 storey garage studio structure and the installation of a swimming pool. The high, north eastern side of the swimming pool will require bulk excavation up to 2.3m depth, the pool is to be positioned partly within a retained garden, thus requiring a deeper excavation in north eastern portions and very minimal excavation within south western portions.

It is recommended that all new footings for the swimming pool and for the two storey garage studio structure extend beyond fill soils and are founded on bedrock of at least low strength. It is also recommended that all new footings, temporary batter slopes and excavation support systems are to be inspected by a geotechnical professional to confirm the actual founding conditions prior to placement of steel and casting concrete.

The risks associated with the proposed development are considered to achieve and can be maintained within the 'Acceptable' Risk Management Criteria provided the recommendations of this report and any future geotechnical directive are implemented. As such the site is considered suitable for the proposed construction works provided that the recommendations outlined in this report are followed.

Prepared by:



Josh Cotton
Engineer

Reviewed by:



Troy Crozier
Principal Engineering Geologist
MAIG. RPGeo; 10197

7. REFERENCES:

1. Australian Geomechanics Society 2007, "Landslide Risk Assessment and Management", Australian Geomechanics Journal Vol. 42, No 1, March 2007.
2. Australian Standard AS 3798 - 2007, Guidelines on Earthworks for Commercial and Residential Developments.
3. Australian Standard AS 2870 - 2011, Residential Slabs and Footings - Construction
4. Australian Standard AS1170.4 - 2007, Part 4: Earthquake actions in Australia

Appendix 1

NOTES RELATING TO THIS REPORT

Introduction

These notes have been provided to amplify the geotechnical report in regard to classification methods, specialist field procedures and certain matters relating to the Discussion and Comments section. Not all, of course, are necessarily relevant to all reports.

Geotechnical reports are based on information gained from limited subsurface test boring and sampling, supplemented by knowledge of local geology and experience. For this reason, they must be regarded as interpretive rather than factual documents, limited to some extent by the scope of information on which they rely.

Description and classification Methods

The methods of description and classification of soils and rocks used in this report are based on Australian Standard 1726, Geotechnical Site Investigation Code. In general, descriptions cover the following properties - strength or density, colour, structure, soil or rock type and inclusions.

Soil types are described according to the predominating particle size, qualified by the grading of other particles present (eg. Sandy clay) on the following bases:

<u>Soil Classification</u>	<u>Particle Size</u>
Clay	less than 0.002 mm
Silt	0.002 to 0.06 mm
Sand	0.06 to 2.00 mm
Gravel	2.00 to 60.00mm

Cohesive soils are classified on the basis of strength either by laboratory testing or engineering examination. The strength terms are defined as follows:

<u>Classification</u>	<u>Undrained Shear Strength kPa</u>
Very soft	Less than 12
Soft	12 - 25
Firm	25 - 50
Stiff	50 - 100
Very stiff	100 - 200
Hard	Greater than 200

Non-cohesive soils are classified on the basis of relative density, generally from the results of standard penetration tests (SPT) or Dutch cone penetrometer tests (CPT) as below:

<u>Relative Density</u>	<u>SPT</u> "N" Value (blows/300mm)	<u>CPT</u> Cone Value (Qc - MPa)
Very loose	less than 5	less than 2
Loose	5 - 10	2 - 5
Medium dense	10 - 30	5 - 15
Dense	30 - 50	15 - 25
Very dense	greater than 50	greater than 25

Rock types are classified by their geological names. Where relevant, further information regarding rock classification is given on the following sheet.

Sampling

Sampling is carried out during drilling to allow engineering examination (and laboratory testing where required) of the soil or rock.

Disturbed samples taken during drilling to allow information on colour, type, inclusions and, depending upon the degree of disturbance, some information on strength and structure.

Undisturbed samples are taken by pushing a thin-walled sample tube into the soil and withdrawing a sample of the soil in a relatively undisturbed state. Such samples yield information on structure and strength, and are necessary for laboratory determination of shear strength and compressibility. Undisturbed sampling is generally effective only in cohesive soils.

Drilling Methods

The following is a brief summary of drilling methods currently adopted by the company and some comments on their use and application.

Test Pits – these are excavated with a backhoe or a tracked excavator, allowing close examination of the insitu soils if it is safe to descent into the pit. The depth of penetration is limited to about 3m for a backhoe and up to 6m for an excavator. A potential disadvantage is the disturbance caused by the excavation.

Large Diameter Auger (eg. Pengo) – the hole is advanced by a rotating plate or short spiral auger, generally 300mm or larger in diameter. The cuttings are returned to the surface at intervals (generally of not more than 0.5m) and are disturbed but usually unchanged in moisture content. Identification of soil strata is generally much more reliable than with continuous spiral flight augers, and is usually supplemented by occasional undisturbed tube sampling.

Continuous Sample Drilling – the hole is advanced by pushing a 100mm diameter socket into the ground and withdrawing it at intervals to extrude the sample. This is the most reliable method of drilling soils, since moisture content is unchanged and soil structure, strength, etc. is only marginally affected.

Continuous Spiral Flight Augers – the hole is advanced using 90 – 115mm diameter continuous spiral flight augers which are withdrawn at intervals to allow sampling or insitu testing. This is a relatively economical means of drilling in clays and in sands above the water table. Samples are returned to the surface, or may be collected after withdrawal of the auger flights, but they are very disturbed and may be contaminated. Information from the drilling (as distinct from specific sampling by SPT's or undisturbed samples) is of relatively lower reliability, due to remoulding, contamination or softening of samples by ground water.

Non-core Rotary Drilling - the hole is advanced by a rotary bit, with water being pumped down the drill rods and returned up the annulus, carrying the drill cuttings. Only major changes in stratification can be determined from the cuttings, together with some information from 'feel' and rate of penetration.

Rotary Mud Drilling – similar to rotary drilling, but using drilling mud as a circulating fluid. The mud tends to mask the cuttings and reliable identification is again only possible from separate intact sampling (eg. From SPT).

Continuous Core Drilling – a continuous core sample is obtained using a diamond-tipped core barrel, usually 50mm internal diameter. Provided full core recovery is achieved (which is not always possible in very weak rocks and granular soils), this technique provides a very reliable (but relatively expensive) method of investigation.

Standard Penetration Tests

Standard penetration tests (abbreviated as SPT) are used mainly in non-cohesive soils, but occasionally also in cohesive soils as a means of determining density or strength and also of obtaining a relatively undisturbed sample. The test procedures is described in Australian Standard 1289, "Methods of Testing Soils for Engineering Purposes" – Test 6.3.1.

The test is carried out in a borehole by driving a 50mm diameter split sample tube under the impact of a 63kg hammer with a free fall of 760mm. It is normal for the tube to be driven in three successive 150mm increments and the 'N' value is taken

as the number of blows for the last 300mm. In dense sands, very hard clays or weak rock, the full 450mm penetration may not be practicable and the test is discontinued.

The test results are reported in the following form.

- In the case where full penetration is obtained with successive blow counts for each 150mm of say 4, 6 and 7 as 4, 6, 7 then $N = 13$
- In the case where the test is discontinued short of full penetration, say after 15 blows for the first 150mm and 30 blows for the next 40mm then as 15, 30/40mm.

The results of the test can be related empirically to the engineering properties of the soil. Occasionally, the test method is used to obtain samples in 50mm diameter thin wall sample tubes in clay. In such circumstances, the test results are shown on the borelogs in brackets.

Cone Penetrometer Testing and Interpretation

Cone penetrometer testing (sometimes referred to as Dutch Cone – abbreviated as CPT) described in this report has been carried out using an electrical friction cone penetrometer. The test is described in Australia Standard 1289, Test 6.4.1.

In tests, a 35mm diameter rod with a cone-tipped end is pushed continually into the soil, the reaction being provided by a specially designed truck or rig which is fitted with an hydraulic ram system. Measurements are made of the end bearing resistance on the cone and the friction resistance on a separate 130mm long sleeve, immediately behind the cone. Transducers in the tip of the assembly are connected by electrical wires passing through the centre of the push rods to an amplifier and recorder unit mounted on the control truck.

As penetration occurs (at a rate of approximately 20mm per second) their information is plotted on a computer screen and at the end of the test is stored on the computer for later plotting of the results.

The information provided on the plotted results comprises: -

- Cone resistance – the actual end bearing force divided by the cross-sectional area of the cone – expressed in MPa.
- Sleeve friction – the frictional force on the sleeve divided by the surface area – expressed in kPa.
- Friction ratio - the ratio of sleeve friction to cone resistance, expressed in percent.

There are two scales available for measurement of cone resistance. The lower scale (0 – 5 MPa) is used in very soft soils where increased sensitivity is required and is shown in the graphs as a dotted line. The main scale (0 – 50 MPa) is less sensitive and is shown as a full line. The ratios of the sleeve friction to cone resistance will vary with the type of soil encountered, with higher relative friction in clays than in sands. Friction ratios 1% - 2% are commonly encountered in sands and very soft clays rising to 4% - 10% in stiff clays.

In sands, the relationship between cone resistance and SPT value is commonly in the range: -

$$Q_c \text{ (MPa)} = (0.4 \text{ to } 0.6) N \text{ blows (blows per 300mm)}$$

In clays, the relationship between undrained shear strength and cone resistance is commonly in the range: -

$$Q_c = (12 \text{ to } 18) C_u$$

Interpretation of CPT values can also be made to allow estimation of modulus or compressibility values to allow calculations of foundation settlements.

Inferred stratification as shown on the attached reports is assessed from the cone and friction traces and from experience and information from nearby boreholes, etc. This information is presented for general guidance, but must be regarded as being to some extent interpretive. The test method provides a continuous profile of engineering properties, and where precise information on soil classification is required, direct drilling and sampling may be preferable.

Dynamic Penetrometers

Dynamic penetrometer tests are carried out by driving a rod into the ground with a falling weight hammer and measuring the blows for successive 150mm increments of penetration. Normally, there is a depth limitation of 1.2m but this may be extended in certain conditions by the use of extension rods.

Two relatively similar tests are used.

- Perth sand penetrometer – a 16mm diameter flattened rod is driven with a 9kg hammer, dropping 600mm (AS1289, Test 6.3.3). The test was developed for testing the density of sands (originating in Perth) and is mainly used in granular soils and filling.
- Cone penetrometer (sometimes known as Scala Penetrometer) – a 16mm rod with a 20mm diameter cone end is driven with a 9kg hammer dropping 510mm (AS 1289, Test 6.3.2). The test was developed initially for pavement sub-grade investigations, and published correlations of the test results with California bearing ratio have been published by various Road Authorities.

Laboratory Testing

Laboratory testing is generally carried out in accordance with Australian Standard 1289 “Methods of Testing Soil for Engineering Purposes”. Details of the test procedure used are given on the individual report forms.

Borehole Logs

The bore logs presented herein are an engineering and/or geological interpretation of the subsurface conditions, and their reliability will depend to some extent on frequency of sampling and the method of drilling. Ideally, continuous undisturbed sampling or core drilling will provide the most reliable assessment, but this is not always practicable, or possible to justify on economic grounds. In any case, the boreholes represent only a very small sample of the total subsurface profile.

Interpretation of the information and its application to design and construction should therefore take into account the spacing of boreholes, the frequency of sampling and the possibility of other than ‘straight line’ variations between the boreholes.

Details of the type and method of sampling are given in the report and the following sample codes are on the borehole logs where applicable:

D	Disturbed Sample	E	Environmental sample	DT	Diatube
B	Bulk Sample	PP	Pocket Penetrometer Test		
U50	50mm Undisturbed Tube Sample	SPT	Standard Penetration Test		
U63	63mm “ “ “ “ “	C	Core		

Ground Water

Where ground water levels are measured in boreholes there are several potential problems:

- In low permeability soils, ground water although present, may enter the hole slowly or perhaps not at all during the time it is left open.
- A localised perched water table may lead to an erroneous indication of the true water table.
- Water table levels will vary from time to time with seasons or recent weather changes. They may not be the same at the time of construction as are indicated in the report.
- The use of water or mud as a drilling fluid will mask any ground water inflow. Water has to be blown out of the hole and drilling mud must first be washed out of the hole if water observations are to be made. More reliable measurements can be made by installing standpipes which are read at intervals over several days, or perhaps weeks for low permeability soils. Piezometers, sealed in a particular stratum, may be interference from a perched water table.

Engineering Reports

Engineering reports are prepared by qualified personnel and are based on the information obtained and on current engineering standards of interpretation and analysis. Where the report has been prepared for a specific design proposal (eg. A three-storey building), the information and interpretation may not be relevant if the design proposal is changed (eg. to a twenty-storey building). If this happens, the Company will be pleased to review the report and the sufficiency of the investigation work.

Every care is taken with the report as it relates to interpretation of subsurface condition, discussion of geotechnical aspects and recommendations or suggestions for design and construction. However, the Company cannot always anticipate or assume responsibility for:

- unexpected variations in ground conditions – the potential for this will depend partly on bore spacing and sampling frequency,
- changes in policy or interpretation of policy by statutory authorities,
- the actions of contractors responding to commercial pressures,

If these occur, the Company will be pleased to assist with investigation or advice to resolve the matter.

Site Anomalies

In the event that conditions encountered on site during construction appear to vary from those which were expected from the information contained in the report, the Company requests that it immediately be notified. Most problems are much more readily resolved when conditions are exposed than at some later stage, well after the event.


Reproduction of Information for Contractual Purposes

Attention is drawn to the document “Guidelines for the Provision of Geotechnical Information in Tender Documents”, published by the Institution of Engineers Australia. Where information obtained from this investigation is provided for tendering purposes, it is recommended that all information, including the written report and discussion, be made available. In circumstances where the discussion or comments section is not relevant to the contractual situation, it may be appropriate to prepare a special ally edited document. The Company would be pleased to assist in this regard and/or to make additional report copies available for contract purposes at a nominal charge.

Site Inspection

The Company will always be pleased to provide engineering inspection services for geotechnical aspects of work to which this report is related. This could range from a site visit to confirm that conditions exposed are as expected, to full time engineering presence on site.

PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007




SYMBOL	GROUND PROFILE	
		Convex
		Concave
		Convex
		Concave
		Breaks of slope
		Changes of slope
		Sharp
		Rounded
		Cliff or escarpment or sharp break 40° or more (estimated height in metres)
		Uniform slope
		Concave slope
		Convex slope
		Top
		Bottom
		Hummocky or irregular ground
		Open drain, unfilled
		Open drain, filled
		Fence line
		Property boundary
		Dry stone wall
		Major joint in rock face (opening in millimetres)
		Tension crack (opening in millimetres)

Example of Mapping Symbols

(after V Gardiner & R V Dackombe (1983). Geomorphological Field Manual. George Allen & Unwin).


PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

APPENDIX E - GEOLOGICAL AND GEOMORPHOLOGICAL MAPPING SYMBOLS AND TERMINOLOGY





Examples of Mapping Symbols (after Guide to Slope Risk Analysis Version 3.1 November 2001, Roads and Traffic Authority of New South Wales).

Appendix 2



A

A'



VL - Very Loose	VS - Very Soft	ELS - Extremely Low Strength	EW - Extremely Weathered	fg - Fine Grained
L - Loose	S - Soft	VLS - Very Low Strength	HW - Highly Weathered	mg - Medium Grained
MD - Medium Dense	F - Firm	LS - Low Strength	DW - Distinctly Weathered	cg - Coarse Grained
D - Dense	St - Stiff	MS - Medium Strength	MW - Moderately Weathered	MAS - Massive
VD - Very Dense	VSt - Very Stiff	HS - High Strength	SW - Slightly Weathered	BD - Bedded
	H - Hard	VHS - Very High Strength	FR - Fresh	OC - Outcrop

NB. FOR LOCATION OF SECTION A-A', PLEASE REFER TO FIGURE 1. SITE PLAN AND TEST LOCATIONS

GEOLOGICAL MODEL FIGURE 2.

LEGEND

 AUGER / DYNAMIC CONE PENETROMETER LOCATION	 DCP DYNAMIC CONE PENETROMETER	 EXISTING STRUCTURES	 PROPERTY BOUNDARY
		 CROSS-SECTION REFERENCE LINE	 PROPOSED STRUCTURES

SCALE: 1:200 @ A3
DRAWING: FIGURE 1
DATE: 23/07/2020

APPROVED BY: TMC
DRAWN BY: JC
PROJECT: 2020-142

PREPARED FOR:
Andrea Musacchio &
Monique Ryan-Musacchio

ADDRESS:
15 Burrendong Place,
Avalon

BOREHOLE LOG

CLIENT: Andrea Musacchio & Monique
Ryan-Musacchio

DATE: 22/07/2020

BORE No.: 1

PROJECT: Alterations and Additions

PROJECT No.: 2020-142

SHEET: 1 of 1

LOCATION: 15 Burrendong Place, Avalon

SURFACE LEVEL: RL=29.2m

Depth (m)	Classification	Description of Strata PRIMARY SOIL - consistency / density, colour, grainsize or plasticity, moisture condition, soil type and secondary constituents, other remarks	Sampling		In Situ Testing	
			Type	Tests	Type	Results
0.00						
0.20		FILL: Very soft, dark brown, medium plasticity, moist, sandy clay with gravel and organics				
0.40		ē very loose, dark brown, fine to medium grained, silty sand with gravel				
0.75		ē with sandstone cobbles and bricks				
1.00		AUGER REFUSAL @ 0.75m depth on interpreted concrete slab/footings for adjacent carport				
2.00						

RIG: N/A

DRILLER: AC

METHOD: Hand Auger

LOGGED: JC

GROUND WATER OBSERVATIONS: No Freestanding Groundwater Encountered During Drilling

REMARKS:

CHECKED:

BOREHOLE LOG

CLIENT: Andrea Musacchio & Monique Ryan-Musacchio

DATE: 22/07/2020

BORE No.: 1a

PROJECT: Alterations and Additions

PROJECT No.: 2020-142

SHEET: 1 of 1

LOCATION: 15 Burrendong Place, Avalon

SURFACE LEVEL: RL=28.85m

Depth (m)	Classification	Description of Strata PRIMARY SOIL - consistency / density, colour, grainsize or plasticity, moisture condition, soil type and secondary constituents, other remarks	Sampling		In Situ Testing	
			Type	Tests	Type	Results
0.00						
0.10		FILL: Very soft, yellow and brown, medium plasticity, moist, sandy clay ë very loose, dark brown, fine to medium grained, silty sand with some gravel	D	0.20		
0.30		ë medium dense				
0.60 0.65		ë dense				
1.00		AUGER REFUSAL at 0.65m depth on interpreted tree root				

RIG: N/A

DRILLER: AC

METHOD: Hand Auger

LOGGED: JC

GROUND WATER OBSERVATIONS: No Freestanding Groundwater Encountered During Drilling

REMARKS:

CHECKED:

BOREHOLE LOG

CLIENT: Andrea Musacchio & Monique Ryan-Musacchio

DATE: 22/07/2020

BORE No.: 2

PROJECT: Alterations and Additions

PROJECT No.: 2020-142

SHEET: 1 of 1

LOCATION: 15 Burrendong Place, Avalon

SURFACE LEVEL: RL=30.2m

[illegible]

RIG: N/A

DRILLER: AC

METHOD: Hand Auger

LOGGED: JC

GROUND WATER OBSERVATIONS: No Freestanding Groundwater Encountered During Drilling

REMARKS:

CHECKED:

BOREHOLE LOG

CLIENT: Andrea Musacchio & Monique
Ryan-Musacchio

DATE: 22/07/2020

BORE No.: 3

PROJECT: Alterations and Additions

PROJECT No.: 2020-142

SHEET: 1 of 1

LOCATION: 15 Burrendong Place, Avalon

SURFACE LEVEL: RL=31.91m

Depth (m)	Classification	Description of Strata PRIMARY SOIL - consistency / density, colour, grainsize or plasticity, moisture condition, soil type and secondary constituents, other remarks	Sampling		In Situ Testing	
			Type	Tests	Type	Results
0.00						
0.10		TOPSOIL/ FILL: Very loose, brown, coarse grained, moist sand è silty sand, dark brown with rootlets				
0.40		è light brown				
0.60		è dark brown with gravel				
1.00		è medium dense, moist to wet				
1.20	CL	Sandy CLAY: Stiff, light brown, low to medium plasticity, moist, sandy clay		1.30		
			D	1.50		
				1.70		
1.80			D	1.90		
1.95			D	1.95		
		SANDSTONE (ELS/XW): orange red, medium to coarse grained				
		AUGER REFUSAL at 1.95m on interpreted sandstone bedrock of at least very low strength				

RIG: N/A

DRILLER: AC

METHOD: Hand Auger

LOGGED: JC

GROUND WATER OBSERVATIONS: No Freestanding Groundwater Encountered During Drilling

REMARKS:

CHECKED:

DYNAMIC PENETROMETER TEST SHEET

CLIENT: Andrea Musacchio & Monique
Ryan-Musacchio

DATE: 22/07/2020

PROJECT: Alterations and Additions

PROJECT No.: 2020-142

LOCATION: 15 Burrendong Place, Avalon

SHEET: 1 of 1

Depth (m)	Test Location							
	DCP1	DCP1a	DCP2	DCP3	DCP4			
0.00 - 0.15	1	0	2	1	6			
0.15 - 0.30	0	1	3	2	5			
0.30 - 0.45	0	3	3	3	15			
0.45 - 0.60	2	4	4	1	7			
0.60 - 0.75	8	11	3	2	10*B @0.75m			
0.75 - 0.90	8*B @0.78m	8	6	4				
0.90 - 1.05		9	7	6				
1.05 - 1.20		11	12	5				
1.20 - 1.35		10	17*B @1.33m	6				
1.35 - 1.50		11*B @1.45m		6				
1.50 - 1.65					7			
1.65 - 1.80				15*B @1.75m				
1.80 - 1.95								
1.95 - 2.10								
2.10 - 2.25								
2.25 - 2.40								
2.40 - 2.55								
2.55 - 2.70								
2.70 - 2.85								
2.85 - 3.00								
3.00 - 3.15								
3.15 - 3.30								
3.30 - 3.45								
3.45 - 3.60								
3.60 - 3.75								
3.75 - 3.90								
3.90 - 4.05								

TEST METHOD: AS 1289. F3.2, CONE PENETROMETER

REMARKS: (B) Test hammer bouncing upon refusal on solid object
-- No test undertaken at this level due to prior excavation of soils

TEST PIT REPORT

Client: Andrea Musacchio & Monique Ryan-Musacchio

DATE: 22/07/2020

Test Pit No.: 1

Project: Extensive Alterations and Additions

PROJECT No.: 2020-108

SHEET: 1 of 1

Location: 19 Burrendone Place, Avalon Beach

SURFACE LEVEL: RL = 34.50m

[illegible]

EXCAVATOR: Hand Tools

DRILLER: AC

BUCKET SIZE: N/A

LOGGED: JC

GROUND WATER: No free standing groundwater encountered during excavation

CHECKED: TMC



Appendix 3

TABLE : A**Landslide risk assessment for Risk to life**

HAZARD	Description	Impacting	Likelihood of Slide	Spatial Impact of Slide		Occupancy	Evacuation	Vulnerability	Risk to Life
A	Landslip (earth slide 3m³) from soils at crest of excavation for swimming pool		Soil excavations up to 2.3m depth	a) House 4.0m from 2.3m deep excavation, 10% impacted b) rear gardens and grassed lawns 1.1m from 2.3m excavation, 40% impacted c) House 13.6m from 2.3m deep excavation, 2% impacted d) South eastern access path 10.6m from excavation, 5% impacted		a) Person in house 16hrs/day avge. b) Person in garden 1hr/day c) Person in house 16hrs/day avge. d) Person on path 0.25hr/day avge.	a) Almost certain to not evacuate b) Unlikely to not evacuate c) Almost certain to not evacuate d) Unlikely to not evacuate	a) Person in building, minor damage only b) Person in open space, possible buried c) Person in building, minor damage only d) Person in open space, unlikely buried	
			Possible	Prob. of Impact	Impacted				
		a) House No. 16 Burrendong Place	0.001	0.20	0.10	0.6667	1	0.01	1.33E-07
		b) Rear gardens and grassed lawn No. 16 Burrendong Place	0.001	0.80	0.25	0.0417	0.25	0.05	1.04E-07
		c) House No. 14 Burrendong Place	0.001	0.05	0.02	0.6667	1	0.01	6.67E-09
		d) South eastern access path No. 14 Burrendong Place	0.001	0.10	0.05	0.0104	0.25	0.01	1.30E-10

* hazards considered in current condition and/or without remedial/stabilisation measures or poor support systems

* likelihood of occurrence for design life of 100 years

* Spatial Impact - Probability of Impact refers to slide impacting structure/area expressed as a % (i.e. 1.00 = 100% probability of slide impacting area if slide occurs).

Impacted refers to expected % of area/structure damaged if slide impacts (i.e. small, slow earth slide will damage small portion of house structure such as 1 bedroom (5%), where as large boulder roll may damage/destroy >50%)

* neighbouring houses considered for impact of slide to bedroom unless specified, due to high occupancy and lower potential for evacuation.

* considered for person most at risk, where multiple people occupy area then increased risk levels

* for excavation induced landslip then considered for adjacent premises/buildings founded off shallow footings, unless indicated

* evacuation scale from Almost Certain to not evacuate (1.0), Likely (0.75), Possible (0.5), Unlikely (0.25), Rare to not evacuate (0.01). Based on likelihood of person knowing of landslide and completely evacuating area prior to landslide impact.

* vulnerability assessed using Appendix F - AGS Practice Note Guidelines for Landslide Risk Management 2007

TABLE : B**Landslide risk assessment for Risk to Property**

HAZARD	Description	Impacting	Likelihood		Consequences		Risk to Property
A	Landslip (earth slide 3m³) from soils at crest of excavation for swimming pool	a) House No. 16 Burrendong Place	Unlikely	The event might occur under very adverse circumstances over the design life.	Medium	Moderate damage to some of structure or significant part of site, requires large stabilising works or MINOR damage to neighbouring property.	Low
		b) Rear gardens and grassed lawn No. 16 Burrendong Place	Possible	The event could occur under adverse conditions over the design life.	Minor	Limited Damage to part of structure or site requires some stabilisation or INSIGNIFICANT damage to neighbouring properties.	Moderate
		c) House No. 14 Burrendong Place	Rare	The event is conceivable but only under exceptional circumstances over the design life.	Minor	Limited Damage to part of structure or site requires some stabilisation or INSIGNIFICANT damage to neighbouring properties.	Very Low
		d) South eastern access path No. 14 Burrendong Place	Rare	The event is conceivable but only under exceptional circumstances over the design life.	Minor	Limited Damage to part of structure or site requires some stabilisation or INSIGNIFICANT damage to neighbouring properties.	Very Low

* hazards considered in current condition, without remedial/stabilisation measures and during construction works.

* qualitative expression of likelihood incorporates both frequency analysis estimate and spatial impact probability estimate as per AGS guidelines.

* qualitative measures of consequences to property assessed per Appendix C in AGS Guidelines for Landslide Risk Management.

* Indicative cost of damage expressed as cost of site development with respect to consequence values: Catastrophic : 200%, Major: 60%, Medium: 20%, Minor: 5%, Insignificant: 0.5%.

Appendix 4

APPENDIX A

DEFINITION OF TERMS

INTERNATIONAL UNION OF GEOLOGICAL SCIENCES WORKING GROUP
ON LANDSLIDES, COMMITTEE ON RISK ASSESSMENT

Risk – A measure of the probability and severity of an adverse effect to health, property or the environment.

Risk is often estimated by the product of probability x consequences. However, a more general interpretation of risk involves a comparison of the probability and consequences in a non-product form.

Hazard – A condition with the potential for causing an undesirable consequence (*the landslide*). The description of landslide hazard should include the location, volume (or area), classification and velocity of the potential landslides and any resultant detached material, and the likelihood of their occurrence within a given period of time.

Elements at Risk – Meaning the population, buildings and engineering works, economic activities, public services utilities, infrastructure and environmental features in the area potentially affected by landslides.

Probability – The likelihood of a specific outcome, measured by the ratio of specific outcomes to the total number of possible outcomes. Probability is expressed as a number between 0 and 1, with 0 indicating an impossible outcome, and 1 indicating that an outcome is certain.

Frequency – A measure of likelihood expressed as the number of occurrences of an event in a given time. See also Likelihood and Probability.

Likelihood – used as a qualitative description of probability or frequency.

Temporal Probability – The probability that the element at risk is in the area affected by the landsliding, at the time of the landslide.

Vulnerability – The degree of loss to a given element or set of elements within the area affected by the landslide hazard. It is expressed on a scale of 0 (no loss) to 1 (total loss). For property, the loss will be the value of the damage relative to the value of the property; for persons, it will be the probability that a particular life (the element at risk) will be lost, given the person(s) is affected by the landslide.

Consequence – The outcomes or potential outcomes arising from the occurrence of a landslide expressed qualitatively or quantitatively, in terms of loss, disadvantage or gain, damage, injury or loss of life.

Risk Analysis – The use of available information to estimate the risk to individuals or populations, property, or the environment, from hazards. Risk analyses generally contain the following steps: scope definition, hazard identification, and risk estimation.

Risk Estimation – The process used to produce a measure of the level of health, property, or environmental risks being analysed. Risk estimation contains the following steps: frequency analysis, consequence analysis, and their integration.

Risk Evaluation – The stage at which values and judgements enter the decision process, explicitly or implicitly, by including consideration of the importance of the estimated risks and the associated social, environmental, and economic consequences, in order to identify a range of alternatives for managing the risks.

Risk Assessment – The process of risk analysis and risk evaluation.

Risk Control or Risk Treatment – The process of decision making for managing risk, and the implementation, or enforcement of risk mitigation measures and the re-evaluation of its effectiveness from time to time, using the results of risk assessment as one input.

Risk Management – The complete process of risk assessment and risk control (*or risk treatment*).

Individual Risk – The risk of fatality or injury to any identifiable (named) individual who lives within the zone impacted by the landslide; or who follows a particular pattern of life that might subject him or her to the consequences of the landslide.

Societal Risk – The risk of multiple fatalities or injuries in society as a whole: one where society would have to carry the burden of a landslide causing a number of deaths, injuries, financial, environmental, and other losses.

Acceptable Risk – A risk for which, for the purposes of life or work, we are prepared to accept as it is with no regard to its management. Society does not generally consider expenditure in further reducing such risks justifiable.

Tolerable Risk – A risk that society is willing to live with so as to secure certain net benefits in the confidence that it is being properly controlled, kept under review and further reduced as and when possible.

In some situations risk may be tolerated because the individuals at risk cannot afford to reduce risk even though they recognise it is not properly controlled.

Landslide Intensity – A set of spatially distributed parameters related to the destructive power of a landslide. The parameters may be described quantitatively or qualitatively and may include maximum movement velocity, total displacement, differential displacement, depth of the moving mass, peak discharge per unit width, kinetic energy per unit area.

Note: Reference should also be made to Figure 1 which shows the inter-relationship of many of these terms and the relevant portion of Landslide Risk Management.

PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007
APPENDIX C: LANDSLIDE RISK ASSESSMENT
QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY

QUALITATIVE MEASURES OF LIKELIHOOD

Approximate Annual Probability		Implied Indicative Landslide Recurrence Interval		Description	Descriptor	Level
Indicative Value	Notional Boundary					
10 ⁻¹	5x10 ⁻²	10 years	20 years	The event is expected to occur over the design life.	ALMOST CERTAIN	A
10 ⁻²		100 years		The event will probably occur under adverse conditions over the design life.	LIKELY	B
10 ⁻³	5x10 ⁻³	1000 years	200 years	The event could occur under adverse conditions over the design life.	POSSIBLE	C
10 ⁻⁴		10,000 years		The event might occur under very adverse circumstances over the design life.	UNLIKELY	D
10 ⁻⁵	5x10 ⁻⁵	100,000 years	20,000 years	The event is conceivable but only under exceptional circumstances over the design life.	RARE	E
10 ⁻⁶	5x10 ⁻⁶	1,000,000 years	200,000 years	The event is inconceivable or fanciful over the design life.	BARELY CREDIBLE	F

Note: (1) The table should be used from left to right; use Approximate Annual Probability or Description to assign Descriptor, not *vice versa*.

QUALITATIVE MEASURES OF CONSEQUENCES TO PROPERTY

Approximate Cost of Damage		Description	Descriptor	Level
Indicative Value	Notional Boundary			
200%	100%	Structure(s) completely destroyed and/or large scale damage requiring major engineering works for stabilisation. Could cause at least one adjacent property major consequence damage.	CATASTROPHIC	1
60%		Extensive damage to most of structure, and/or extending beyond site boundaries requiring significant stabilisation works. Could cause at least one adjacent property medium consequence damage.	MAJOR	2
20%	40%	Moderate damage to some of structure, and/or significant part of site requiring large stabilisation works. Could cause at least one adjacent property minor consequence damage.	MEDIUM	3
5%	10%	Limited damage to part of structure, and/or part of site requiring some reinstatement stabilisation works.	MINOR	4
0.5%	1%	Little damage. (Note for high probability event (Almost Certain), this category may be subdivided at a notional boundary of 0.1%. See Risk Matrix.)	INSIGNIFICANT	5

- Notes:** (2) The Approximate Cost of Damage is expressed as a percentage of market value, being the cost of the improved value of the unaffected property which includes the land plus the unaffected structures.
- (3) The Approximate Cost is to be an estimate of the direct cost of the damage, such as the cost of reinstatement of the damaged portion of the property (land plus structures), stabilisation works required to render the site to tolerable risk level for the landslide which has occurred and professional design fees, and consequential costs such as legal fees, temporary accommodation. It does not include additional stabilisation works to address other landslides which may affect the property.
- (4) The table should be used from left to right; use Approximate Cost of Damage or Description to assign Descriptor, not vice versa

PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

APPENDIX C: – QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY (CONTINUED)

QUALITATIVE RISK ANALYSIS MATRIX – LEVEL OF RISK TO PROPERTY

LIKELIHOOD		CONSEQUENCES TO PROPERTY (With Indicative Approximate Cost of Damage)				
	Indicative Value of Approximate Annual Probability	1: CATASTROPHIC 200%	2: MAJOR 60%	3: MEDIUM 20%	4: MINOR 5%	5: INSIGNIFICANT 0.5%
A – ALMOST CERTAIN	10 ⁻¹	VH	VH	VH	H	M or L (5)
B - LIKELY	10 ⁻²	VH	VH	H	M	L
C - POSSIBLE	10 ⁻³	VH	H	M	M	VL
D - UNLIKELY	10 ⁻⁴	H	M	L	L	VL
E - RARE	10 ⁻⁵	M	L	L	VL	VL
F - BARELY CREDIBLE	10 ⁻⁶	L	VL	VL	VL	VL

Notes: (5) For Cell A5, may be subdivided such that a consequence of less than 0.1% is Low Risk.

(6) When considering a risk assessment it must be clearly stated whether it is for existing conditions or with risk control measures which may not be implemented at the current time.

RISK LEVEL IMPLICATIONS

Risk Level		Example Implications (7)
VH	VERY HIGH RISK	Unacceptable without treatment. Extensive detailed investigation and research, planning and implementation of treatment options essential to reduce risk to Low; may be too expensive and not practical. Work likely to cost more than value of the property.
H	HIGH RISK	Unacceptable without treatment. Detailed investigation, planning and implementation of treatment options required to reduce risk to Low. Work would cost a substantial sum in relation to the value of the property.
M	MODERATE RISK	May be tolerated in certain circumstances (subject to regulator's approval) but requires investigation, planning and implementation of treatment options to reduce the risk to Low. Treatment options to reduce to Low risk should be implemented as soon as practicable.
L	LOW RISK	Usually acceptable to regulators. Where treatment has been required to reduce the risk to this level, ongoing maintenance is required.
VL	VERY LOW RISK	Acceptable. Manage by normal slope maintenance procedures.

Note: (7) The implications for a particular situation are to be determined by all parties to the risk assessment and may depend on the nature of the property at risk; these are only given as a general guide.


Appendix 5

PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

APPENDIX G - SOME GUIDELINES FOR HILLSIDE CONSTRUCTION

ADVICE		GOOD ENGINEERING PRACTICE	POOR ENGINEERING PRACTICE
GEOTECHNICAL ASSESSMENT	Obtain advice from a qualified, experienced geotechnical practitioner at early stage of planning and before site works.		Prepare detailed plan and start site works before geotechnical advice.
PLANNING			
SITE PLANNING	Having obtained geotechnical advice, plan the development with the risk arising from the identified hazards and consequences in mind.		Plan development without regard for the Risk.
DESIGN AND CONSTRUCTION			
HOUSE DESIGN	Use flexible structures which incorporate properly designed brickwork, timber or steel frames, timber or panel cladding. Consider use of split levels. Use decks for recreational areas where appropriate.		Floor plans which require extensive cutting and filling. Movement intolerant structures.
SITE CLEARING	Retain natural vegetation wherever practicable.		Indiscriminately clear the site.
ACCESS & DRIVEWAYS	Satisfy requirements below for cuts, fills, retaining walls and drainage. Council specifications for grades may need to be modified. Driveways and parking areas may need to be fully supported on piers.		Excavate and fill for site access before geotechnical advice.
EARTHWORKS	Retain natural contours wherever possible.		Indiscriminatory bulk earthworks.
CUTS	Minimise depth. Support with engineered retaining walls or batter to appropriate slope. Provide drainage measures and erosion control.		Large scale cuts and benching. Unsupported cuts. Ignore drainage requirements
FILLS	Minimise height. Strip vegetation and topsoil and key into natural slopes prior to filling. Use clean fill materials and compact to engineering standards. Batter to appropriate slope or support with engineered retaining wall. Provide surface drainage and appropriate subsurface drainage.		Loose or poorly compacted fill, which if it fails, may flow a considerable distance including onto property below. Block natural drainage lines. Fill over existing vegetation and topsoil. Include stumps, trees, vegetation, topsoil, boulders, building rubble etc in fill.
ROCK OUTCROPS & BOULDERS	Remove or stabilise boulders which may have unacceptable risk. Support rock faces where necessary.		Disturb or undercut detached blocks or boulders.
RETAINING WALLS	Engineer design to resist applied soil and water forces. Found on rock where practicable. Provide subsurface drainage within wall backfill and surface drainage on slope above. Construct wall as soon as possible after cut/fill operation.		Construct a structurally inadequate wall such as sandstone flagging, brick or unreinforced blockwork. Lack of subsurface drains and weepholes.
FOOTINGS	Found within rock where practicable. Use rows of piers or strip footings oriented up and down slope. Design for lateral creep pressures if necessary. Backfill footing excavations to exclude ingress of surface water.		Found on topsoil, loose fill, detached boulders or undercut cliffs.
SWIMMING POOLS	Engineer designed. Support on piers to rock where practicable. Provide with under-drainage and gravity drain outlet where practicable. Design for high soil pressures which may develop on uphill side whilst there may be little or no lateral support on downhill side.		
DRAINAGE			
SURFACE	Provide at tops of cut and fill slopes. Discharge to street drainage or natural water courses. Provide general falls to prevent blockage by siltation and incorporate silt traps. Line to minimise infiltration and make flexible where possible. Special structures to dissipate energy at changes of slope and/or direction.		Discharge at top of fills and cuts. Allow water to pond on bench areas.
SUBSURFACE	Provide filter around subsurface drain. Provide drain behind retaining walls. Use flexible pipelines with access for maintenance. Prevent inflow of surface water.		Discharge roof runoff into absorption trenches.
SEPTIC & SULLAGE	Usually requires pump-out or mains sewer systems; absorption trenches may be possible in some areas if risk is acceptable. Storage tanks should be water-tight and adequately founded.		Discharge sullage directly onto and into slopes. Use absorption trenches without consideration of landslide risk.
EROSION CONTROL & LANDSCAPING	Control erosion as this may lead to instability. Revegetate cleared area.		Failure to observe earthworks and drainage recommendations when landscaping.
DRAWINGS AND SITE VISITS DURING CONSTRUCTION			
DRAWINGS	Building Application drawings should be viewed by geotechnical consultant		
SITE VISITS	Site Visits by consultant may be appropriate during construction/		
INSPECTION AND MAINTENANCE BY OWNER			
OWNER'S RESPONSIBILITY	Clean drainage systems; repair broken joints in drains and leaks in supply pipes. Where structural distress is evident see advice. If seepage observed, determine causes or seek advice on consequences.		

EXAMPLES OF **GOOD** HILLSIDE PRACTICE



EXAMPLES OF **POOR** HILLSIDE PRACTICE

