

## Landscape Referral Response

Application Number:	DA2025/1002
Date:	13/08/2025
Proposed Development:	Demolition Works and construction of a building for use as a fruit shop and pet shop
Responsible Officer:	Brittany Harrison
Land to be developed (Address):	Lot 4 DP 737411 , 62 Myoora Road TERREY HILLS NSW 2084

### Reasons for referral

This application seeks consent for the following:

- Construction / development works within 5 metres of a tree or
- New residential works with three or more dwellings. (RFB's, townhouses, seniors living, questhouses, etc). or
- Mixed use developments containing three or more residential dwellings.
- New Dwellings or

#### Officer comments

The proposal is supported with regard to landscape issues.

The application is assessed by Landscape Referral against Warringah Local Environmental Plan 2011 and the following Warringah Development Control Plan 2011 controls (but not limited to):

- D1 Landscaped Open Space and Bushland Setting
- E1 Preservation of Trees or Bushland Vegetation

The Arboricultural Impact Assessment (AIA) outlines trees which need to be removed to facilitate the works. Majority of these trees are exempt and no concerns are raised with the removal of exempt trees, subject to tree replacement to help mitigate the loss of canopy. Exempt trees may be managed or removed at the discretion of the applicant without consent. Prescribed trees 40, 41, 42 and 101 are proposed to be removed and it is noted these trees were approved for removal under DA2023/1224. Prescribed tree 102 will also require removal and the AIA states that this tree is a "tree in a pot that has rooted into the ground", and as such no concerns are raised with its removal.

The landscaped buffers provided as part of the proposal along all boundaries will improve the amenity of the surrounding streetscapes and neighbouring properties. The overall quantity of landscaped area is deficient and this matter will be assessed and determined on merit consideration by planning. The landscape proposal is generally supported and all proposed planting shall be installed in accordance with the requirements outlined in the conditions of consent. The tree planting shown on the Landscape Plans will sufficiently offset any loss of canopy.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

DA2025/1002 Page 1 of 4



## **Recommended Landscape Conditions:**

## CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

## **Tree Removal Within the Property**

- a) This consent approves the removal of existing prescribed trees on the subject site as identified in the Arboricultural Impact Assessment, or as listed below:
- i) trees 40 Syncarpia glomulifera, 41 Corymbia citriodora, 42 Eucalyptus tereticornis, 102 Eucalyptus saligna.
- b) A qualified AQF level 5 Arborist shall identify these trees on site and tag or mark prior to removal.

Reason: To enable authorised development works.

#### Tree Removal Within the Road Reserve

- a) This consent approves the removal of existing trees within the road reserve as identified in the Arboricultural Impact Assessment, or as listed below:
- i) tree 101 Eucalyptus haemastoma.
- b) A qualified AQF level 5 Arborist shall identify these trees on site and tag or mark prior to removal.
- c) Removal of the approved tree/s by the applicant in the road reserve shall only be undertaken by a Council approved tree contractor. Details of currently approved tree contractors can be obtained from Northern Beaches Council's Trees Services business unit prior to removal.

Reason: Public liability.

## CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

### **Tree and Vegetation Protection**

- a) Existing trees and vegetation shall be retained and protected, including:
- i) all trees within the site not approved for removal, including trees and vegetation nominated for retention on the approved Plans,
- ii) all trees and vegetation located on adjoining properties,
- iii) all trees and vegetation within the road reserve.
- b) Tree protection shall be undertaken as follows:
- i) tree protection shall be in accordance with AS 4970-2025 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment,
- ii) existing ground levels shall be maintained within the tree protection zone of trees to be retained, unless authorised by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture.
- iii) removal of existing tree roots at or >25mm ( $\emptyset$ ) diameter is not permitted without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture,
- iv) no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,
- v) structures are to bridge tree roots at or >25mm (Ø) diameter unless directed by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture on site,
- vi) excavation for stormwater lines and all other utility services is not permitted within the tree protection zone, without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture including advice on root protection measures,
- vii) should either or all of v) or vi) occur during site establishment and construction works, an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture shall provide recommendations for

DA2025/1002 Page 2 of 4



tree protection measures. Details including photographic evidence of works undertaken shall be submitted by the Arborist/Project Arborist to the Principal Certifier,

- viii) any temporary access to, or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of AS 4970-2025 Protection of trees on development sites.
- ix) the activities listed in section 4.2 of AS 4970-2025 Protection of trees on development sites, shall not occur within the tree protection zone of any tree on the lot or any tree on an adjoining site,
- x) tree pruning from within the site to enable approved works shall not exceed 10% of any tree canopy, and shall be in accordance with AS 4373-2007 Pruning of amenity trees,
- xi) the tree protection measures specified in this clause must: be in place before work commences on the site, be maintained in good condition during the construction period, and remain in place for the duration of the construction works.
- c) The Principal Certifier must ensure that:
- i) If activated, the arboricultural works listed in a) and b) are undertaken and certified by an Arborist/Project Arborist as complaint to AS 4970-2025 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment.

Reason: Tree and vegetation protection.

#### **Condition of Trees**

- a) During the construction period the applicant is responsible for ensuring all existing trees required to be retained are maintained in a healthy and vigorous condition. This is to be done by ensuring that all identified tree protection measures are adhered to, or by seeking arboricultural advice from an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture during the works. In this regard all protected trees shall not exhibit:
- i) a general decline in health and vigour,
- ii) damaged, crushed or dying roots due to poor pruning techniques,
- iii) more than 10% loss or dieback of roots, branches and foliage,
- iv) mechanical damage or bruising of bark and timber of roots, trunk and branches,
- v) yellowing of foliage or a thinning of the canopy untypical of its species,
- vi) an increase in the amount of deadwood not associated with normal growth,
- vii) an increase in kino or gum exudation,
- viii) inappropriate increases in epicormic growth that may indicate that the plants are in a stressed condition.
- ix) branch drop, torn branches and stripped bark not associated with natural climatic conditions.
- b) Any mitigating measures and recommendations required by the Arborist/Project Arborist are to be implemented.
- c) The owner of the adjoining allotment of land is not liable for the cost of work carried out for the purpose of this clause.

Reason: Protection of trees.

# CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

## **Landscape Completion**

a) Landscape works are to be implemented in accordance with the approved Landscape Plan(s) (drawings 000 Issue B, 101 Issue B, 102 Issue B, 501 Issue A by Site Image dated 12/06/25), and

DA2025/1002 Page 3 of 4



inclusive of the following conditions:

- i) landscape works are to be contained within the legal property boundaries,
- ii) planting shall be installed as indicated on the approved Landscape Plan(s) unless otherwise imposed by any conditions,
- iii) all carpark tree planting shall be a minimum pre-ordered planting size of 100 litres and all boundary tree planting shall be a minimum pre-ordered planting size of 45 litres; meet the requirements of AS2303
- Tree Stock for Landscape Use; planted into a prepared planting hole 1m x 1m x 600mm depth generally, backfilled with a sandy loam mix or approved similar, mulched to 75mm depth minimum and maintained, and watered until established; and shall be located at least 3.0 metres from buildings or more, at least 1.5 metres from common boundaries; and located either within garden bed or within a prepared bed within lawn.
- iv) mass planting shall be installed in a garden bed prepared with a suitable free draining soil mix and minimum 75mm depth of mulch,
- v) where the property is certified Bush Fire Prone Land, any new planting may be managed in accordance with Planning for Bushfire Protection 2019.
- b) Prior to the issue of an Occupation Certificate, details (from a landscape architect, landscape designer or qualified horticulturalist) shall be submitted to the Principal Certifier, certifying that the landscape works have been completed in accordance with any conditions of consent.

Reason: Environmental amenity.

## ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

## **Landscape Maintenance**

- a) If any landscape materials/components or planting under this consent fails, they are to be replaced with similar materials/components.
- b) Trees, shrubs and groundcovers required to be planted under this consent are to be mulched, watered and fertilised as required at the time of planting.
- c) If any tree, shrub or groundcover required to be planted under this consent fails, they are to be replaced with similar species to maintain the landscape theme and be generally in accordance with the approved Landscape Plan(s) and any conditions of consent.
- d) The approved landscape planted areas, whether containing lawn, gardens or planters shall in perpetuity remain as planting under the development consent, and shall not be replaced with any hard paved surfaces or structures.

Reason: To maintain local environmental amenity.

DA2025/1002 Page 4 of 4