

Environmental Compliance 8am to 5.30pm Mon - Thurs, 8am to 5pm Fri Phone 9970 1111

3 August 2006

Stuart Thor & Andrew van Wensveen PO Box 806 NARRABEEN NSW 2101



Dear Stuart & Andrew

Re: Construction Certificate CC0355/06

Property: 104 & 106 Wakehurst Parkway, Elanora Heights

Please find enclosed your approved Construction Certificate and stamped plans.

Did you know that work is unable to commence until such time as a completed Notification of Commencement Form has been submitted to Council at least two (2) days prior to starting work? Not to do so is a breach of the Environmental Planning and Assessment Act, which would result in a Penalty Infringement Notice (on-the-spot fine) being issued to you and the builder.

To assist you please find enclosed a "Notification of Commencement and Principal Certifying Authority Service Agreement" form to enable you to appoint Pittwater Council as your Principal Certifying Authority (PCA). Please complete this form and return it to Council's Customer Service together with the PCA appointment fee as detailed in the form.

If appointed as the PCA, Council would engage the services of <Council Consultant> to carry out the various inspections as indicated in Part 6 of the enclosed "Notification of Commencement and Principal Certifying Authority Service Agreement" form and ultimately issue an Occupation Certificate for your development. Appointment and inspection fees are also detailed in the enclosed form.

Council will endorse your completed "Notice of Commencement and Principal Certifying Authority Service Agreement" form and return a copy to the applicant with advice as to the required critical stage and other inspections to be carried out on behalf of Council.

Council is committed to providing a quality service and would value your business in being appointed as the Principal Certifying Authority for your development.

Yours faithfully

Development Compliance Group

Per:

11/19

SCANNED

8 AUG 2006



Pittwater Council

Construction Certificate No: CC 0355/06

Site Details:

104 & 106 Wakehurst Parkway, Elanora Heights

Legal Description:

Lot 10 & 11, DP 1014199

Type of Development:

Subdivision

Description:

Driveways, drainage works, retaining walls & associated landscaping

works

Associated Development Consent No: N0432/04

Dated:

10 January 2006

Copy

Building Code of Australia Classification: Class 10b

Details of plans, documents or Certificates to which this Construction Certificate relates:

Working Drawing No CMS TH02 MODEL MAR04 Rev G (24/09/04), CMS PROPOSED SUBDIVISION MAR04 Rev G (24/09/04), CMS TH02 DRIVEWAYDESIGN MAR04 Rev B (02/06/04), 476detail200 Rev A (06/04/04), prepared by C.M.S. Surveyors P/L

 Structural Engineering Details, Drawing No 051149 S01 Rev A (18/07/06), C01 (Mar 06), C02 (Jan 06), C03 (Mar 06), C04 (Mar 06), C05 Rev B (Mar 06), C06 (Mar 06), C07 (Mar 06), C08 Rev A (18/07/06), D01 (Mar 06), D02 (Mar 06), prepared by Northern Beaches Consulting Engineers P/L

Stormwater Details, Drawing No 051149 D02, prepared by Northern Beaches Consulting

Engineers P/L, dated March 2006

Structural Engineering Certificate on stormwater design prepared by Northern Beaches Consulting Engineers P/L dated 13/04/06

 Landscape Details, Drawing No 63.06 (05)/051, prepared by lan Jackson Landscape Architects P/L. dated March 2006

Landscaper Certificate on landscape design prepared by Ian Jackson Landscape Architects P/L dated 16/06/06

Form No 2 Geotechnical Risk Management, prepared by B.F.Walker, dated 28/06/06

Driveway Certificate on driveway design prepared by Northern Beaches Consulting Engineers P/L dated 13/04/06

 Erosion & Sediment Design Certificate, prepared by Northern Beaches Consulting Engineers P/L, dated 13/04/06

Pittwater Council Driveway Levels dated 15/06/05

Sydney Water Notice of Requirements

Landscape Specification, prepared by Ian Jackson Landscape Architect P/L, dated October 2005

Ecological Sustainability Plan, prepared by Hayes Environmental, dated June 2006

I hereby certify that the above plans, documents or Certificates satisfy:

The relevant provisions of the Building Code of Australia.

The relevant conditions of Development Consent No: N0432/04

SCANNED

PITTWATER COUNCIL

8 AUG 2006





Pittwater Council

Construction Certificate No: CC 0355/06

Further that the work, completed in accordance with the Building Code of Australia, all relevant Australian Standards and these plans and specifications, will comply with the requirements of Section 81A(5) of the Environmental Planning and Assessment (Amendment) Act, 1997.

Issued By: Mark Wysman

Accreditation Number: Dept of Planning P0061

Pittwater Council Consultant

Building Surveyor

Date of Endorsement: 3 August 2006

<u>Note</u>: You are reminded that pursuant to provisions of Clause 81A, you must nominate whether Council or an accredited certifier will be the principal certifying authority, also you must give notice to Council of your intention to commence work at least two days beforehand.





Site Stormwater Management **Design Certificate**

Date:

13th April 2006

Job No.

051149

Builder:

Stuart Thor

Engineer: LM

Site: 104 and 106 Wakehurst Parkway Elanora

We hereby certify that the plans prepared by NB Consulting Engineers P/L have been designed and detailed in accordance with Condition B20 of the DA approval.

We trust that this certificate meets with your requirements. Please contact the author if further clarification is required.

0355/06 TCG(NV) 03 AUG 2006

NB CONSULTING ENGINEERS P/L

Per Lucas Molloy BE CPEng NPER Director

N:\ENG NBC\2005\051149\SC001 SW Design.doc

SCANNED

8 AUG 2006



LANDSCAPE ARCHITECT'S CERTIFICATION

PROJECT: Subdivision & Driveway — DATE: -- 16 June 2006

104 - 106 Wakehurst Parkway

Elanora Heights

PRINCIPAL: Mr S. Thor

This is to certify that the Landscape Plan Dwg No. 63.06(05)/051 dated March 2006 has been prepared in accordance with Pittwater Council's Development Control Plan No. 23 - Landscape and Vegetation Management. It has also met the conditions of consent for Development Application No. N0432/04 and specifically Condition No.s B45 & B45a 1, 2, 3, 4, 5, 6 & 12..

Signed:

lan Jackson Landscape Architect

SCANNED

8 AUG 2006

									•	
	Development Ap	olication for	·				•			
	Development (F)	•		Name of App				. [
		101.010	6 Wake	laust I	art war	Flam	ora			
	Address of site	10-7-910	6 Wan	10:01	4 Nay	Q4 - 1				•
	n made by Structu	- las Civil Sacia		the incornoral	tion of the Geo	technical iss	ues Into the s	roject desig	an .	
ciaretio	n made by Structu	ten of Atan Eußin	Hack I	the incorporal	res Care	عمالها يح	Engin	ومنح		
Luca	s Mollo y	on behalf	of	(trading	or company na	me)	U			
	7316 3	une 200	6				• •			-
this the					• •					
rtify thai		r Civil Engineer a	s defined by the	Geotechnical R	isk Managemen	t Policy for Pi	kiwater. 1 am	aulnorised t ndamnity oo	y the Tovof	
ove org	I am a Structural o mization/company 1 million. I also cert	o issue this docum	nent and to cartif	/ that the organi listed sinuctural (zavon/company documents in 80	cordance wit	h the recomm	endations gh	ven in	
least \$2 a Geotei	thnical Report for U	JG BDOAR GRAFIDH	TIGITE					•		•
	Geotechnical Rep	ort Details:				OF SHAKE	שטעציר ל	AFKIL AY	1320	LABEE
	Report Title: 🖼	SCACHINE	42_ ABGES!	om en.	10 am L				<i>e</i> .	•
•	Report Date:	16104	topt-No-	184782	acrpe	•	•			
•	Author: PAUL	<u>, DAVID</u>	RABER	rs.						
		. 11				•.		•		
	Structural Docum		RIVEWAY	ony;	(0)	100	106			
		51149-1	209 # 2	Of COL	<u>w>,u</u>	14 July 1	, u e	, 	•	: .
	CO7 C	08 DO	17601_			 -	 · ·	 i		
	ware that Pittwater	<u> </u>		<u> </u>	technical Blok	Management	Policy includ	ing this	-	
am also	aware that Pittwater							an extension	٧	
	and the book for at	resided that the de	olechnical risk ri	anagement asp	ects of the prop	osed develop	weut uavá bes	sil acedoeici	- 4 4	
STUNCTIO	n as the basis for el	Council relies on reuring that the ge entable Risk Marn	electroical risk manager	nanagement asp ir the life of the s	ects of the properties	osed develop: s at least 100	Assur nujess	otherwise st	sted	
ddressed nd fustifi	n as the basis for ei I to achieve an "Acc ed	suring that the go eptable Risk Mari	epiechnical risk magement level fo	snagement asp ir the life of the s	ects of the properties a structure taken a	osed developi s at least 100	ment nave per years unless	otherwise st	sted	
ddiessed nd fustifi	n as the basis for ei I to achieve an "Acc ed	nauring that the ge eptable Risk Mari	potechnical risk m agement level fo	enagement asp ir the life of the s	ects of the prop tructure taken a	s at least 100	years unless	otherwise st	sted	٠.
ddiessed nd fustifi	n as the basis for ei I to achieve an "Acc	eptable Risk Mari	polechnical risk magement/ level fo	senagement asp r the life of the s	ects of the prop structure taken a	osed develop s at least 100 (signature	years unless	otherwise st	sted	· .
iddressed ind fustific Luca	n as the basis for el I to achieve an "Acc ad. 5 Molloy (name	eptable Risk Mari	agement level fo	r the life of the s	structure taken a	s at least 100 (signature	years unless	otherwise st	•	
iddiessed ind fustifie Luca Declarati	n as the basis for ell to achieve an "Acc sd. 5 Molloy (name	eptable Risk Man	or Engineering	r the life of the s Geologist in re	structure taken a	s at least 100 (signatum tural Drawing	years unless >}	otherwise st		
ddressedind fustification of the contract of t	n as the basis for ell to achieve an "Acc ad. 5	eptable Risk Mari	or Engineering	r the life of the s Geologist in re echnical Report	structure taken a	s at least 100 (signatum tural Drawing	years unless (a) (b) (c) (c) (c) (c) (c) (c) (c	otherwise st	we. Zhave in the	```
ddressed ind fustific Luca Declarati prepared	n as the basis for ed to achieve an "Acc of. 5 Molloy (name on made by Geoter I and/or technically a above listed stru	eptable Risk Mari chnical Engureer verified the spove chural documents	or Engineering	r the life of the s Geologist in re echnical Report s same develop	election to Struct as per Form 1 ment. Jain sa	s at least 100 (signatum (signatum tural Drawing dated 9 14 th	Pa- and not be recommend from stricts	otherwise sti	we. Thave in the	-cludy
Declared prepared prepared prepared prepared prepared	n as the basis for ed to achieve an "Acc of. 5 Molloy (name on made by Geoter I and/or technically a above listed stru- ical Report have be-	eptable Risk Mari chnical Engureer verified the spove chural documents en appropriate tal	or Engineering	r the life of the s Geologist in re echnical Report s same develop by the structural	section to Struct as per Form 1 in ment. Talk sa engineer in the	s at least 100 (signature tural Drawing dated 9 16 / tisfied that / preparation or	P4- and nove recommend these structuricy, including t	w cartify that lations given ral documen this certificati	w¢. Zhave in the is, & 14 on as	
Declaration of the basis of the basis	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Genter is and/or technically e above listed structal Report have beet that Rittwater Coulor distalling and the	eptable Risk Mari chnical Engineer verified the spove ctural documenta en appropriate tal incil relies on the geotechnical risk	or Engineering	Geologist in re echnical Report a same develop by the structural d by the Geolec pects of the pro-	as per Form 1 ment. Jain sa engineer in the brincal Risk Mar posed developed as a seat 100	s at least 100 (signatum (signatum tural Drawing dated 9 16 / isfied that th preparation or tagement Police that sunless	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that lations given ral documen had ressed to ted and justi	w¢. Zhave in the is, & 14 on as	
ddressed on fustific LuCo. Declarati prepared the Septechnian swall he basis schieve a he Report	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Geoter is above listed structured in the control of the control	eptable Risk Mari chnical Engineer verified the spove ctural documents en appropriate tal incil relies on the geolechnical risk Management level	or Engineering prepared for the secount in focesses covern management as a first the site of the secount in focesses covern management as a first the site of the secount in the second in the secon	Geologist in re echnical Report s same develop by the structural d by the Geolec pects of the pro- e structure take en identified to r	as per Form 1 ment. 12 miles a engineer in the chrical Risk Mar posed development as at least 100 move foresees	s at least 100 (signatum (signatum tural Drawing dated 9 16 / isfied that th preparation or tagement Police that sunless	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that stions given ral document his certificati addressed to ted and just	we Thave in the its, it is on as cu	rovide letter
ddressed of fusitive declaration of the control of	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Genter is and/or technically e above listed structal Report have beet that Rittwater Coulor distalling and the	eptable Risk Mari chnical Engineer verified the spove ctural documents en appropriate tal incil relies on the geolechnical risk Management level	or Engineering prepared for the secount in focesses covern management as a first the site of the secount in focesses covern management as a first the site of the secount in the second in the secon	Geologist in re echnical Report s same develop by the structural d by the Geolec pects of the pro- e structure take en identified to r	as per Form 1 ment. 12 miles a engineer in the chrical Risk Mar posed development as at least 100 move foresees	s at least 100 (signatum (signatum tural Drawing dated 9 16 / isfied that th preparation or tagement Police that sunless	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that stions given ral document his certificati addressed to ted and just	we Thave in the its, it is on as cu	rovide letter
ddressed of fusitive declaration of the control of	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Geoter is above listed structured in the control of the control	eptable Risk Mari chnical Engineer verified the spove ctural documents an appropriate tal incil relies on the geotechnical risk Management lev- le and practical m Signature	or Engineering prepared for the second assert the second to easure here the second to easure have be sured to the second to easure have be sured to the second to easure have be sured to the second t	Geologist in rescholate Report is same develope by the structural and by the Geolec pects of the projects of the Libert Challer	as per Form 1 ment. 12 miles a engineer in the chrical Risk Mar posed development as at least 100 move foresees	s at least 100 (signatum (signatum tural Drawing dated 9 16 / isfied that th preparation or tagement Police that the preparation or tagement police that the preparation or the preparation of the preparation or the preparation of the preparat	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that ations given rai documen this certificati addressed to ted and justice of the certificati addressed to ted and justice of the certification o	we what in the is, it is on as in the interest in th	novide letter 1987ele
ddressed of fusitive declaration of the control of	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Geoter is above listed structured in the control of the control	chnical Engineer verified the apove cural documents en appropriate tal incil relies on the geolechnical risk Management leve le and practical m Signature	or Engineering imprisoned Geot prepared for the processes covern imprisoned in the first account in the first the first account in the first the first account in the first the	Geologist in rescholate Report is same develop by the structural ad by the Geolec pects of the program identified to restructure takes an identified to rescholate Report	as per Form 1 ment. Lam sa engineer in the truical Rick Mar posed developed as a teast 100 move foresees.	s at least 100 (signatum tural Drawing tated 9 16/ tisfied that th preparation or tagement Police tent have been years unless ble risk, \$5	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that lations given rai documen this certificati addressed to ted and just of the certification of the ce	we we we in the in the is, it is on as critical in Post of ITA	novide letter 1982eli 10/4/
ddressed of fusitive declaration of the control of	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Geoter is above listed structured in the control of the control	chnical Engineer verified the apove cural documents en appropriate tal incil relies on the geolechnical risk Management leve le and practical m Signature	or Engineering imprisoned Geot prepared for the processes covern imprisoned in the first account in the first the first account in the first the first account in the first the	Geologist in rescholate Report is same develop by the structural ad by the Geolec pects of the program identified to restructure takes an identified to rescholate Report	as per Form 1 ment. Lam sa engineer in the truical Rick Mar posed developed as a teast 100 move foresees.	s at least 100 (signatum tural Drawing tated 9 16/ tisfied that th preparation or tagement Police tent have been years unless ble risk, \$5	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that lations given rai documen this certificati addressed to the dand just of the dand for the dand	we drawe in the is, it is on as critical in Post of 172	rovide letter 10/4/ 10/4/
eclarati preparec ewed the ensurement ensurement existing preparec ewed the ensurement existing existi	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Geoter is above listed structured in the control of the control	chnical Engineer verified the spove chural documents en appropriate tak incil relies on the i geotechnical risk Management lev le and practical m Signature Name	or Engineering important for the second into account into	Geologist in rescholate Report is same develop by the structural ad by the Geologiest of the properties of the properties of the properties.	as per Form 1 ment. Lam sa engineer in the truical Rick Mar posed developed as a teast 100 move foresees.	s at least 100 (signatum tural Drawing tated 9 16/ tisfied that th preparation or tagement Police tent have been years unless ble risk, \$5	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that lations given rai documen this certificati addressed to the dand just of the dand for the dand	we drawe in the is, it is on as critical in Post of 172	rovide letter 10/4/ 10/4/
eclarati preparec eved the even was eved the even was even basis chieve a even Report	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Geoter is above listed structured in the control of the control	chnical Engineer verified the apove cural documents en appropriate tal incil relies on the geolechnical risk Management leve le and practical m Signature	or Engineering imprisoned Geot prepared for the processes covern imprisoned in the first account in the first the first account in the first the first account in the first the	Geologist in rescholate Report is same develop by the structural ad by the Geologiest of the properties of the properties of the properties.	as per Form 1 ment. Lam sa engineer in the truical Rick Mar posed developed as a teast 100 move foresees.	s at least 100 (signatum tural Drawing tated 9 16/ tisfied that th preparation or tagement Police tent have been years unless ble risk, \$5	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that lations given rai documen this certificati addressed to the dand just of the dand for the dand	we drawe in the is, it is on as critical in Post of 172	10/4) 10/4) 10/4) 19820 2/10/0
ddressed of fusitife function fusitife function fusitife function	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Geoter is above listed structured in the control of the control	chnical Engineer verified the spove chural documents en appropriate tak incil relies on the i geotechnical risk Management lev le and practical m Signature Name	or Engineering important for the second into account into	Geologist in rescholate Report is same develop by the structural ad by the Geologiest of the properties of the properties of the properties.	as per Form 1 ment. Lam sa engineer in the truical Rick Mar posed developed as a teast 100 move foresees.	s at least 100 (signatum tural Drawing tated 9 16/ tisfied that th preparation or tagement Police tent have been years unless ble risk, \$5	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that lations given rai documen this certificati addressed to the dand just of the dand for the dand	we drawe in the is, it is on as critical in Post of 172	10/4) 10/4) 10/4) 19826 2/10/0
ddressed of fusitive declaration of the control of	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Geoter is above listed structured in the control of the control	chnical Engineer verified the spove chural documents en appropriate tak incil relies on the i geotechnical risk Management lev le and practical m Signature Name	or Engineering important for the second into account into	Geologist in rescholate Report is same develop by the structural ad by the Geologiest of the properties of the properties of the properties.	as per Form 1 ment. Lam sa engineer in the truical Rick Mar posed developed as a teast 100 move foresees.	s at least 100 (signatum tural Drawing tated 9 16/ tisfied that th preparation or tagement Police tent have been years unless ble risk, \$5	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that actions given riel documen his certifical addressed to ted and just be a confident of the con	we thave in the tage in on as a read of 1814 de 2-	10/4) 10/4) 10/4) 19826 2/10/0
ddressed of fusitive declaration of the control of	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Geoter is above listed structured in the control of the control	chnical Engineer verified the spove chural documents en appropriate tak incil relies on the i geotechnical risk Management lev le and practical m Signature Name	or Engineering important for the second into account into	Geologist in rescholate Report is same develop by the structural ad by the Geologiest of the properties of the properties of the properties.	as per Form 1 ment. Lam sa engineer in the truical Rick Mar posed developed as a teast 100 move foresees.	s at least 100 (signatum tural Drawing tated 9 16/ tisfied that th preparation or tagement Police tent have been years unless ble risk, \$5	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that lations given rai documen this certificati addressed to the dand just of the dand for the dand	we thave in the tage in on as a read of 1814 de 2-	10/4) 10/4) 10/4) 19826 2/10/0
ddressed of fusitive declaration of the control of	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Geoter is above listed structured in the control of the control	chnical Engineer verified the spove chural documents en appropriate tak incil relies on the i geotechnical risk Management lev le and practical m Signature Name	or Engineering important for the second into account into	Geologist in rescholate Report is same develop by the structural ad by the Geologiest of the properties of the properties of the properties.	as per Form 1 ment. Lam sa engineer in the truical Rick Mar posed developed as a teast 100 move foresees.	s at least 100 (signatum tural Drawing tated 9 16/ tisfied that th preparation or tagement Police tent have been years unless ble risk, \$5	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that actions given riel documen his certifical addressed to ted and just be a confident of the con	we thave in the tage in on as a read of 1814 de 2-	10/4) 10/4) 10/4) 19820 2/10/0
ddressed of fusitive declaration of the control of	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Geoter is above listed structured in the control of the control	chnical Engineer verified the spove chural documents en appropriate tak incil relies on the i geotechnical risk Management lev le and practical m Signature Name	or Engineering important for the second into account into	Geologist in rescholate Report is same develop by the structural ad by the Geologiest of the properties of the properties of the properties.	as per Form 1 ment. Lam sa engineer in the truical Rick Mar posed developed as a teast 100 move foresees.	s at least 100 (signatum tural Drawing tated 9 16/ tisfied that th preparation or tagement Police tent have been years unless ble risk, \$5	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that actions given riel documen his certifical addressed to ted and just be a confident of the con	we thave in the tage in on as a read of 1814 de 2-	10/4) 10/4) 10/4) 19820 2/10/0
ddressed on fustific LuCo. Declarati prepared the Septechnian swall he basis schieve a he Report	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Geoter is above listed structured in the control of the control	chnical Engineer verified the spove chural documents en appropriate tak incil relies on the i geotechnical risk Management lev le and practical m Signature Name	or Engineering important for the second into account into	Geologist in rescholate Report is same develop by the structural ad by the Geologiest of the properties of the properties of the properties.	as per Form 1 ment. Lam sa engineer in the truical Rick Mar posed developed as a teast 100 move foresees.	s at least 100 (signatum tural Drawing tated 9 16/ tisfied that th preparation or tagement Police tent have been years unless ble risk, \$5	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that actions given riel documen his certifical addressed to ted and just be a confident of the con	we thave in the tage in on as a read of 1814 de 2-	10/4) 10/4) 10/4) 19820 2/10/0
ddressed of fusitive declaration of the control of	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Geoter is above listed structured in the control of the control	chnical Engineer verified the spove chural documents en appropriate tak incil relies on the i geotechnical risk Management lev le and practical m Signature Name	or Engineering important for the second into account into	Geologist in rescholate Report is same develop by the structural ad by the Geologiest of the properties of the properties of the properties.	as per Form 1 ment. Lam sa engineer in the truical Rick Mar posed developed as a teast 100 move foresees.	s at least 100 (signatum tural Drawing tated 9 16/ tisfied that th preparation or tagement Police tent have been years unless ble risk, \$5	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that actions given riel documen his certifical addressed to ted and just be a confident of the con	we thave in the tage in on as a read of 1814 de 2-	10/4) 10/4) 10/4) 19820 2/10/0
ddressed on fustific LuCo. Declarati prepared the Septechnian swall he basis schieve a he Report	n as the basis for et it to achieve an "Acc of d. 5 Molloy (name on made by Geoter is above listed structured in the control of the control	chnical Engineer verified the spove chural documents en appropriate tak incil relies on the i geotechnical risk Management lev le and practical m Signature Name	or Engineering important for the second into account into	Geologist in rescholate Report is same develop by the structural ad by the Geologiest of the properties of the properties of the properties.	as per Form 1 ment. Lam sa engineer in the truical Rick Mar posed developed as a teast 100 move foresees.	s at least 100 (signatum tural Drawing tated 9 16/ tisfied that th preparation or tagement Police that have been by ears unless ble risk, \$5	e pears unless Ph— and now e recommend f these structu icy, including to n adequately a	w certify that actions given riel documen his certifical addressed to ted and just be a confident of the con	we thave in the tage in on as a read of 1814 de 2-	rovide letter 1987ele 10/4/

0355/00

8 AUG 2006

03 AUG 2006

Jeffery and Katauskas Pty Ltd

CONSULTING GEOTECHNICAL AND ENVIRONMENTAL ENGINEERS
A.B.N. 17 003 550 801 A.C.N. 003 550 801



Principals
B F WALKER BE DIC MSc
P STUBBS BSc MICE FGS
D TREWEEK Dip Tech
E H FLETCHER BSc (Eng) ME

Senior Associates
F A VEGA BSc(Eng) GDE
A ZENON BSc(Eng) GDE
P C WRIGHT BE(Hons) MEngSc
L J SPEECHLEY BE(Hons) MEngSc

Associates A B WALKER BE(Hons) MEngSc

Consultant R P JEFFERY BE DIC MSc 39 BUFFALO ROAD GLADESVILLE NSW 2111 Tel: 02-9809 7322 02-9807 0200 Fax: 02-9809 7626 10 April 2006

Ref: 18498ZRlet2

Mr Stuart Thor 106 Wakehurst Parkway NARRABEEN NSW 2101

Dear Stuart

REVIEW OF STRUCTURAL DRAWINGS 104 – 106 WAKEHURST PARKWAY, NARRABEEN

At your request, we have reviewed the supplied structural drawings (Job No. 051149, Drg. Ref. SO1, CO1 to CO8, inclusive and DO1, dated March 2006) prepared by Northern Beaches Consulting Engineers Pty Ltd, for the above site. However, we have not carried out a check of any aspects of the structural design.

We have provided additional hand written notes on the supplied drawings as underlined in red. With the inclusion of the additional notes, we consider that the supplied structural drawings have been completed in accordance with the recommendations presented in our geotechnical report (Ref. 18498ZRrpt) dated 9 June 2004.

Should you require any further information regarding the above please do not hesitate to contact the undersigned.

Yours faithfully

Paul Roberts

Senior Engineering Geologist

For and on behalf of

JEFFERY AND KATAUSKAS PTY LTD

ANNED

8 AUG 2006

WARER COUNCIL



ENVIRONMENTAL INVESTIGATION SERVICES, FOUNDATION AND SLOPE STABILITY INVESTIGATIONS, ENGINEERING GEOLOGY, PAVEMENT DESIGN, EXPERT WITNESS REPORTS, DRILLING SERVICES, EARTHWORKS COMPACTION CONTROL, MATERIALS TESTING, ASPHALTIC CONCRETE TESTING, QA AND QC TESTING, AUDITING AND CERTIFICATION. N.A.T.A. REGISTERED LABORATORIES





Access and Internal Driveway Design Certificate

Date:

13th April 2006

Job No.

051149

Builder:

Stuart Thor

Engineer: LM

Site: 104 and 106 Wakehurst Parkway Elanora

We hereby certify that the plans prepared by NB Consulting Engineers P/L have been designed and detailed in accordance with Condition B28 of the DA approval.

We trust that this certificate meets with your requirements. Please contact the author if further clarification is required.

0355/00 TCG-(NV) 03 AUG 2006

NB CONSULTING ENGINEERS P/L

Per Lucas Molloy BE CPEng NPER Director

\\NBSBS\COMPANY\ENG NBC\2005\051149\SC002 driveway.doc

SCANNED

8 AUG 2006

Erosion Sediment Control Design Certificate

Date:

13th April 2006

Job No.

051149

Builder:

Stuart Thor

Engineer: LM

Site: 104 and 106 Wakehurst Parkway Elanora

We hereby certify that the plans prepared by NB Consulting Engineers P/L have been designed and detailed in accordance with Condition B29 of the DA approval.

We trust that this certificate meets with your requirements. Please contact the author if further clarification is required.

0355/cc 0 0 0 TCG (NV)


NB CONSULTING ENGINEERS P/L

Per Lucas Mollov BE CPEng NPER Director

N:\ENG NBC\2005\051149\SC003 Erosion.doc

SCANNE

8 AUG 2006



PITTWATER COUNCIL

Unit 9/5 Vuko Place, Warriewood NSW 2102 Telephone 9970 1111

Date:

15-Jun-05

Receipt No: 169572

Amount:

\$465:00

Name:

Stuart Thor & Andrew Van Wensveen

28000

Postal Address:

PO Box 805

Narrabeen 2101

APPROVED ACCESS DRIVEWAY PROFILE AT:

104 & 106 Wakehurst Parkway, Elanora

The future vehicular access profile will be as per the enclosed plan NH.

WORK REQUIRED:

Construct:

Vehicular access slab 3.6m long x 4.0m wide at gutter crossing to 4.0m

wide at the boundary.

Type of Construction: Domestic

Note:

"G" (see attached diagram) to be 450mm from edge of road

and 50mm below edge of road.

VEHICULAR ACCESS

All work within the road reserve (including excavation) in connection with the above, is to be carried out by authorised contractors only. (a)

Quotations for the work specified above should be obtained from any of the contractors on the list and should be for the whole of the work stated. (b)

Construction of vehicular access will be strictly in accordance with the profile supplied and where the drive within the property is to be (c) constructed first, it shall be the responsibility of the owner to have the work carried out in such a manner as to provide a smooth join and continuity of grading.

Please Note: Council will only permit an absolute maximum gradient of 25% (1 in 4) measured at any point on the driveway and that an ease may be required for access into the car stand area, carport or garage. Refer to relevant attached profile.


Sigi Melderis ASSETS / RESTORATIONS OFFICER


SCANNED

8 AUG 2006

STANDARD DRIVEWAY PROFILES FOR ALL DEVELOPME

NORMAL (N)






POINT REMARKS	LEVELS
R ROAD CENTRELINE	
G INVERT OF GUTTER L BACK OF LAYBACK	100 ABOVE "G"
TIDOD FROM BACK U	F LAYBACK 130 ABOVE "G" INF MAX 200 ABOVE "G"
2400 FROM KERB L	INE MAX 400 ABOVE "G"
C 3600 FROM KERB L	THE EASE REQUIRED AT GRADE CHANGE

- All construction within the road reserve to be in plain uncoloured 20MPa concrete unless otherwise approved by Council. 1.
- Single dwellings 20Mpa concrete 130mm thick.
- <u>Dual occupancies</u> where the crossing services both dwellings 20Mpa concrete 150mm thick with F72 reinforcement.
- The Vehicular crossing and the driveway to 2400 behind the kerbline is to be graded parallel with the road centre line grading.
- Driveway pavers to be laid on a 100mm concrete base.

SCANNED 8 AUG 2006 PITTWATER COUNC!!



PLAN

Sydney

0355/06 T/2/ANA

Case Number: 88028

Stuart Thor c/- Byrne & Associates Pty Ltd

Dear Applicant

NOTICE OF REQUIREMENTS

for

SECTION 73 SUBDIVIDER/DEVELOPER COMPLIANCE CERTIFICATE (Sydney Water Act 1994, Part 6, Division 9)

Developer:

Stuart Thor

Your reference:

20595

Development address:

104 Wakehurst Parkway Elanora Heights (Lot 11 DP 1014199) Development description: Demolition of existing structures, subdivision of 2 lots into 4 lots &

driveway construction.

Consent No:

432/04 by Pittwater Council of 31 May 2005

Your application:

28 September 2005

Your attention is drawn to the requirements in this Notice that must be met before a Section 73 Subdivider/ Developer Compliance Certificate (the Certificate) can be issued. This Notice is given by Sydney Water on 27 October 2005, and the requirements are to apply for a year from that date after which the requirements will be updated on reapplication.

You must engage your current or another authorised Water Servicing Coordinator (the Coordinator) to manage and facilitate the construction of the sewer works that you must provide, at your cost, to service your development.

For a list of authorised Coordinators, either see www.sydneywater.com.au and refer to Developing Your Land under Building Developing and Plumbing, or call 13 20 92. Coordinators may provide you with a quote or advice regarding costs for their and other supplier's services/ works as well as other Sydney Water costs.

The Coordinator will generally be the single point of contact between you and Sydney Water and can answer any questions in the first instance you may have on Sydney Water's developer process and developer charges.

SUMMARY OF REQUIREMENTS TO OBTAIN A CERTIFICATE:

You must:

- 1. Note water service requirements for your development.
- 2. Engage a Coordinator prior to signing the enclosed Agreement.
- 3. Sign both copies of the enclosed Minor Works Agreement and lodge with a Water Servicing Coordinator.

SCANNEL

- inserting junctions into existing VC (see Note) and PVC sewers; (i)
- constructing property connection sewers (formerly called "sidelines") of length not greater (ii) than twelve (12) metres excluding any rodding point;
- concrete encasing up to 25 metres of an existing sewer, excluding CI and AC sewers; (iii)
- replacing up to 25 metres of existing sewer pipe, normally as a precursor to concrete (iv) encasement: and
- sealing disused customer sanitary drains at the connection to Sydney Water's sewer. (v).

Note: For purposes of these Requirements, VC includes all types of earthenware and clay-lined

The Constructor must give Sydney Water at least two (2) working days notice of the intended connection date. The Council for the area must be consulted before any work is carried out in, on or over a public road.

Upon completion of the required works, your Coordinator must submit to Sydney Water a "Work as Constructed" package indicating what was actually constructed.


Sydney Water's specific requirements for your project are:

A sewerage point of connection within the property boundaries to adequately drain lot 1. Lots 2, 3 & 4 appear to have an existing connection within the property boundaries. Your Water Servicing coordinator can determine whether any further construction of sewer connections are required.

In providing these works to Sydney Water you will need to pay construction costs directly to your suppliers. You should consult with your Coordinator in regard to Sydney Water's application and inspection fee (currently \$121.00) and the Coordinator's Minor Works management fee.

In addition, if the water main/ sewer main located in the footway/ your property is found, after the issue of this notice, to require adjustment or deviation this work must be completed to Sydney Water's satisfaction prior to the issue of the Certificate (see also section on building plan stamping). You must use a Sydney Water authorised Coordinator to make an additional application for approval to undertake the works. For a list of authorised Coordinators please refer to the instructions detailed on page 1 of this Notice.

You must then sign a Major Works Agreement to construct the necessary works at no cost to Sydney Water. After the adjustment/ deviation design has been completed and its nature and complexity considered, Sydney Water may require your lodgement of an appropriate security that will be refunded upon completion.



5. Developer charges.

Development Servicing Plan (DSP)	Basis of Calculation	Charge (\$) for Applicable period (27/10/05-30/06/06)	Charge (\$) for Applicable Period (01/07/06-26/10/06) (*CPI adjusted)
Warringah Water DSP Area	Residential Development Density 0-20 dwellings per ha band 4 dwellings @ \$871 = \$3,484 Less Credit of \$1,742 for previous payment/ use plus Upsizing Development Density 0-20 dwellings per ha band 4 dwellings @ \$192 = \$768 Less Credit of \$384 for previous payment/ use	\$1,742 \$384	ТВА ТВА
Warriewood Sewer DSP Area	Residential Development Density 0-20 dwellings per ha band 4 dwellings @ \$6,765 = \$27,060 Less Credit of \$13,530 for previous payment/ use plus Upsizing Development Density 0-20 dwellings per ha band 4 dwellings @ \$89 = \$356 Less Credit of \$178 for previous payment/ use	\$13,530 \$178	ТВА ТВА
Reticulation Recovery	Not applicable	\$NIL	ТВА
[OFFICE USE- I	CHARGES TOTAL: nvoice Charges total- Developer \$15,272 and Upsizing \$562] or 12 months to 31/03/06)	\$15,834	ТВА

Notes:

- Sydney Water has commenced its five-yearly review of developer charges in accordance with IPART Determination No. 9 2000. Developer charges will be revised to take into account Sydney Water's latest capital expenditure projections as well as current development forecasts. The revised developer charges and associated DSPs will be placed on public exhibition for 30 working days in February / March 2006. You will have the opportunity to comment on the new charges during this time. The new developer charges will then take effect from 1 July 2006.
- The charge(s) quoted above is/are being reviewed based on a new IPART Determination with new charges to apply from 1 July 2006. Some charges may significantly decrease, others may increase and new charges may be introduced. Consequently it may be to your advantage to consider when you will make payment. That is:
 - > If payment is made before 1 July 2006, then Sydney Water must apply the charges quoted in this Notice; or
 - If payment is made on or after 1 July 2006, then:
 - If the charges have decreased you will only have to pay the new lower charges that will automatically be advised to you when you seek to make payment; or
 - If the charges have increased and/or new charges introduced then Sydney Water will apply the old lower charges for the remainder of the applicable period of this Notice. After that time, Sydney Water is required to apply the higher charges when you re-apply.

SCANNED

8 AUG 2006

PITTWATER COUNCIL

Sydney Water is unable to advise possible new charges until the DSPs are exhibited in February/March 2006, or to advise firm new charges until registration of the DSPs with IPART in approximately May 2006. Contact your Coordinator for advice on charges during this period.

Also:

- If you do not pay the charges identified in column 3 of the above table by 30 June, the total will be adjusted for inflation (based on the weighted average of the capital cities CPI for the 12 months to the end of the previous March) from 1 July for the balance of the 12 month period. The charge from 1 July is shown in column 4 when the inflation figure is known.
- DSP charges are a contribution towards the cost of systems (eg treatment plants) which serve your development. They have been calculated using base developer charges that cannot be changed or waived by Sydney Water having been established in Plan(s), available on request, and registered with the Independent Pricing and Regulatory Tribunal (IPART) under its relevant Determination. For further details, and a copy of the IPART Act 1992 including section 31 that refers to arbitration rights, see the IPART web site www.IPART.nsw.gov.au. Costs of arbitration, if appropriate, are borne equally by you and Sydney Water irrespective of outcome.
- These charges are directly payable to Sydney Water. Credit card payments (to a maximum of \$1,000) may be made on Bankcard, MasterCard or Visa card only at a Sydney Water Customer Service Centre.
- You must pay your Developer Charges total before you will be given permission to construct the sewer works and/or connect your development to Sydney Water's water system
- Reticulation Recovery Charges recover part of the cost of works that have been provided by Sydney Water or other developers that benefit your development. This charge has been calculated before your detailed designs are completed. If later design investigation shows your development will be connected to other main/s, the Reticulation Recovery charge may be varied and/or you may need to construct other works.

Stamping and approval of your engineering and building plans.

While NOT a requirement for the Certificate, you are reminded that, on development of each lot, building plans must be stamped and approved at either:

- a Quick Check agency (for an agency list either see www.sydneywater.com.au, refer to Quick Check under Building Developing and Plumbing or call 13 20 92); or
- a Sydney Water Customer Service Centre.

Approval is required as construction/building works (eg earthworks, roadworks, drainage, landscaping, excavation, foundation works) may impact on existing Sydney Water assets (eg water, sewer and stormwater mains). Approval of the plans may take up to 21 days and the results may affect the construction/building activities.

SCANNED

8 AUG 2006

יים אאעבנים א MATER COLIMCיים א

POSSIBLE FUTURE COSTS

Requirements in this Notice relate to your Certificate application and may not cover all aspects of Sydney Water's involvement with your development. During design and construction of your development other Sydney Water fees/requirements may be necessary, including:

- construction/building plan stamping fees including fees to ensure the protection of Sydney Water assets
- plumbing and drainage inspection costs for private service lines (including property service connection and inspection fees)

trade waste requirements when constructing a building

council fire fighting requirements (if not catered for by your current Sydney Water main). You should investigate fire fighting facility requirements for your development as soon as possible, including a standard pressure inquiry to Sydney Water if needed

redress under Sydney Water's Customer Contract.

END OF NOTICE

SCANNED 8 AUG 2006 ITTWATER COUNCIL



Landscape Specification

0355/06

TCG (NV) 03 AUG 2006

Proposed Subdivision 104-106 Wakehurst Parkway Elanora Heights October 2005

postal. 25 bent street lindfield nsw 2070 office. 16/303 pacific highway lindfield phone. 9416 4290 fax. 9416 4735 mobile 0411 196735 email. ijla@netspace.net.au acn. 097 328580

SCANNED

8 AUG 2006

PITTWATE-

∃Oł{

LANDSCAPE SPECIFICATION

This Landscape Specification shall cover all work to be accomplished and materials to be used in the landscape works. It is intended that this landscape specification be read in conjunction with the following documentation dated October 2005:

Landscape Plan Dwg No. 63.05/153

GENERAL CONDITIONS 1.

GENERAL CONDITIONS 1.1

Refer to main architectural specification for all general conditions.

STAGING OF WORKS 1.2

Any contractor asked to submit a tender for the landscape works must examine the program for the building works and develop a program to suit.

DEFECTS LIABILITY & PLANTING ESTABLISHMENT PERIODS 1.3

The landscape contractor shall be held responsible for replacement of any work and/or materials which fail during the first twelve (12) months following the date of issue of a final occupation certificate.

This includes the replacement of all failed plants, including any that are damaged or stolen.

Also refer to Maintenance.

Four (4) weeks before final completion an inspection shall be undertaken to ensure all works are in a satisfactory condition. The contractor shall give two (2) weeks notice of the date and time of this meeting. Any defects requiring rectification shall be issued in writing to the contractor.

A final meeting shall be held on the date of final completion and after a satisfactory inspection the project shall be handed over to the client. This shall be confirmed in writing. All retention monies shall be returned to the contractor at this time (refer to main specification).

Also refer to Council's conditions of development consent.

Jan Jackson

SCANNED

2. LANDSCAPE WORKS

2.1 SITE PREPARATION

Any minor levelling, either cutting or filling, shall be undertaken by the Landscape Contractor so that areas are left ready for final finishes. Adequate watering points shall be provided to enable the Landscape Contractor to maintain planted area throughout construction and the maintenance period. Weeds are to be sprayed with 'Roundup', or equal, to manufacturers directions and must be dead before being disturbed.

2.2 DEMOLITION WORKS

The following items are to be demolished and removed by the landscape contractor:

- Weeds within proposed planting and lawn areas
- Unwanted planting areas

All demolished material is removed from site (unless indicated otherwise below) and disposed of in accordance with waste management requirements. All demolished material shall be deemed the property of the landscape contractor.

2.3 WORKS BY BUILDER (prior to landscape works)


The following work shall be carried out before the commencement of the landscape works by the builder:

- Tree protection measures;
- Existing trees to be removed (unless otherwise stated below);
- All earthmoving and earthworks required to form the ground levels to the profiles and levels shown on the drawings, ie. to the finished levels to allow for pavements, mulching, topsoiling and turfing (unless stated otherwise below);
- Any required drainage works (unless stated otherwise below);
- Stencil concrete paving;
- Concrete steps;
- Masonry retaining works;
- Replacement boundary fencing;
- Internal fencing & gates;
- Concrete ramps;
- Provision of hose cocks for hand watering;
- Construction zone fencing (see 2.4 below); and
- Soil erosion control measures (see 2.5 below).

2.4 CONSTRUCTION ZONE FENCING

Refer to main architectural specification. By builder.

Jan Jackson



2.5 SOIL AND WATER MANAGEMENT WORKS

Refer to main architectural specification. By builder.

2.6 PROTECTION OF EXISTING TREES

2.6.1 Generally

There are a number of existing trees adjacent to the construction zone to be retained and protected. All existing trees which are shown on Drawings and/or specified to be retained, shall be adequately protected from damage as described hereafter. Also refer to Pittwater Council's Development Consent requirements.

2.6.2 Tree Protection Fencing

All existing trees indicated that are to be retained on the plans are to be protected during construction. Fencing for tree protection to be comprised from 1.8m high chainwire mesh and galv. tube steel frame. Fencing firmly secured four (4) metres from the trunk of each tree (if possible). All care must be taken to avoid damage to existing trees and adequately protected from damage as described hereafter.

2.6.3 Tree roots

During excavation for service or other excavation, tree roots in excess of 50mm diameter shall not be cut. Hand digging and tunnelling shall be carried out wherever necessary to avoid cutting roots and especially under the branch spread of trees. Where necessary tree roots shall be saw cut back to a clean cut and then treated with an approved bitumen emulsion dressing. Trenches dug under the branch spread of trees shall remain open for as short a time as possible. Backfilling shall remain open for as short a time as possible. Backfilling shall be carefully rammed and watered in around the roots to eliminate voids.

2.6.4 Around trees

Disturbance to existing ground levels beneath branch spread, either by compaction, heavy machinery, piling up materials or cutting away soil, shall not take place unless so specified. If ground has been unavoidably compacted by heavy machinery, the soil shall be loosened by tyning.

Construction materials generally, and particularly oil, paints, waste concrete, cleanings or other deleterious materials shall not be stored or dumped under branch spread. Concrete mixers shall be sited in positions where the deposit of wind-blown cement on the trees is reduced to a minimum. No fires shall be lit under the branch spread or where damage to trees could result.

In the event that oil or other harmful material has been spilt under the trees on the sub-grade or topsoil to be retained, the affected soil is to be excavated and the damaged vegetation removed to the approval and under the direction of the Superintendent. Dispose of soil and replace with soil as specified for mass planted areas.

Ian Jackson

SCANNED

8 AUG 2006

2.6.5 Tree Pruning

All works to be in accordance with AS 4373-1996 Pruning Amenity Trees, modern arboricultural practices and Workcover's Code of Practice: Amenity Tree Industry - 1998.

2.6.6 Damage

The Contractor shall be responsible for damage to or destruction of any new or existing trees, unless such trees are cut or removed as specified or as directed in writing by the Superintendent.

Partial damage to any tree shall be rectified immediately damage occurs at the Contractor's expense, as specified previously and under the direction of the Superintendent.

In the case of total destruction of a tree or trees, damages shall be assessed by the Superintendent and shall be calculated as the amount necessary to replace and establish in that position a similar tree of a similar species from within a radius of 150km.

2.7 DRAINAGE WORKS

In general the mass planted areas are to be build atop existing levels to improve drainage and to deflect water runoff around the site. Due to the sloping nature of the site it is considered that sub-surface drains are not be required to drain the mass planted areas and lawns.

If the contractor considers that certain other areas require drainage then the Superintendent should be immediately notified for an inspection. Set out below are the requirements for any drainage works.

2.7.1 Materials

Agricultural drains to be 100mm flexible coil & filter sock.

Aggregate to be 10-20mm blue metal.

Connections to be 100mm black polyethylene stormwater pipe.


2.7.2 Installation

Install agricultural drains with a maximum 1:60 gradient and backfill trenches with a minimum 200mm layer of aggregate. Connect into the stormwater system for the buildings.

2.8 MASONRY WALLS

Refer to details by architect and engineer. To be constructed by main building contractor.

Jan Jackson



2.9 SANDSTONE WALLS

Refer to details by architect and engineer. To be constructed by main building contractor.

2.10 CONCRETE PAVING & STEPS

Refer to details by architect and engineer. To be constructed by main building contractor.

2.11 EXISTING PLANTING TO BE RELOCATED

2.11.1 Generally

The existing commemorative garden is to be relocated to accommodate the proposed covered outdoor area. A number of existing plants are to be removed and temporarily stored for re-use in the finished landscape works. The existing and proposed locations are indicated on the Landscape Plan. This work is to be accomplished by a qualified arborist and in general terms is to:

- Prune roots in a 600mm diameter x 600mm deep 4 6 weeks before transplanting and treat area with a suitable hormone powder to encourage regrowth of roots
- Excavate a hole for each palm 2 times the size of the root ball and backfill with a premium quality imported soil mix.
- Transplant on a day not exceeding max. 25 degrees
- Apply a liquid fertiliser and keep well watered for three months
- Stake with 3 x star pickets and rope for each palm. Where ropes are secured to trunk enclose in hessian to prevent bruising or rubbing.

2.12 SANDSTONE BOULDER WALLS


2.12.1 Materials

Stone to be ripped sandstone pieces with 'flattish' tops and bottoms for stability and suitable for sitting upon. It should also be hard and durable.

Some pieces to be a minimum 2 tonne (as drawn on plan) to give the landscape works a sense of scale to relate to the large open surrounding area.

Ian Jackson

, *2*



2.12.2 Installation

Install bottom course of boulders on existing excavated ground with a minimum 1/3 of each rock below finished ground levels for stability. Backfill between and Stack boulders in a stretcher bond behind boulders with crushed sandstone. pattern (with each rock overlapping the two below) until desired heights are achieved (maximum 1m high). Boulders are to be machine-placed.

Refer to engineer's details for maximum batter allowances and any special drainage or backfilling requirements.

The Superintendent (or representative) is to be on site during the placement of all boulders.

PLANTING PREPARATION 2.13

2.13.1 Materials

Imported soil mix to be Organic Garden Mix from Australian Native Landscapes or equal. Samples to be shown to Superintendent for approval before installation. Also provide written breakdown of contents, pH and trace elements and suitability for improving existing soil. Soil mix to comply with AS 3743-2003: Potting mixes, AS 4419-2003: Soils for landscaping and garden use & AS 4454-2003: Composts, soil conditioners and mulches.

2.13.2 Installation

Destroy existing grass and weeds (refer above). Excavate to a minimum 350mm below finished levels. Deep rip existing base to a depth of 300mm (avoid existing tree roots) and apply Gypsum at a rate as recommended by the supplier (if required). Install imported soil mix to a depth of 300mm and cultivate into the top 300mm of existing soil to ensure the materials integrate.

2.14 PLANTS AND PLANTING METHODS

2.14.1 Materials

Trees and plants shall be true to name and variety. Substitutes in size or variety shall not be made without the approval. All plants shall be true to size, in well developed healthy condition, free from insect and diseases, with well established root systems.

Samples of each species to be shown to Superintendent prior to installation.

Page 6

Water crystals to be Garden King Wettasoil Granular deep watering agent from Amgrow or equal product.

Ian Jackson

2.14.2 Installation

The contractor is to rigidly observe planting positions as shown on plan and planting shall not be carried out in dry soil or in extreme weather conditions.

The root system must be moist before planting to ensure the turgidity. The plants shall be removed from their containers with as little disturbance as possible to the root system. Plants should be planted at the same depth as the plants were in the containers and allow for a shallow saucer of soil to be formed around the plant to aid penetration of water.

Avoid hilling up of top soil around young plant stems. Firm soil around the root ball and thoroughly soak the areas after planting. On completion, cultivate, rake and leave all garden areas in a neat and tidy condition.

Fertilise with an approved 9 months formulation general purpose slow release fertiliser such as "Nutricote" or "Osmocote" that is mixed into the prepared planting space just prior to planting. Fertiliser to be applied at the rate as specified by the manufacturer for the plant size and type. Also apply water crystals around each plant (dug into the soil) in accordance with supplier's recommendations.

Labels shall be removed entirely from the plants. Stake according to the Schedule of Plant Material with $50 \times 50 \times 1800$ mm long hardwood stakes and hessian ties. Stakes to be located outside the rootball of the nominated plant.

Maintain all plants and ties and provide adequate watering for the duration of contract.

2.15 MULCHING


2.15.1 Materials

Mulch to be comprised of maximum 25mm fresh hardwood chips such as Eucalyptus Mulch from Australian Native Landscapes or equal. Samples to be shown to Superintendent for approval before installation. Mulch to comply with AS 4454-2003: Composts, soil conditioners and mulches.

2.15.2 Installation

Mulch shall be applied to all disturbed areas where bare earth is exposed indicated on plan. Following planting, rake all garden areas and tamp lightly to give an even graded surface. Spread 75mm layer of leaf chip mulch over the surface of all new garden beds.

Care shall be taken not to mix soil and mulch together.





2.16 PRACTICAL COMPLETION


Sweep down, clean up and remove all waste landscape material from the site. Hose down paved areas, fences, footpaths, etc. Check plant ties and replace plants which fail. Regularly water and maintain landscaped areas for a six month period from completion to ensure establishment.


2.17 MAINTENANCE

To ensure the rapid establishment and long term success of the landscape works the contractor shall undertake a twelve month maintenance period after Practical Completion. During this time the contractor shall be responsible for the replacement of any failed plants or other materials.

The following general maintenance tasks shall also be undertaken:

- Hand watering of plants on a regular basis equating to four times per week for the first month and two times per week for the next two months (depending on weather conditions & subject to water restrictions).
- · Checking of plants, stakes and ties every month
- Spraying of weeds every month
- · Replacement of failed plants every three months
- Pruning plants (where applicable) every three months
- Topping up of mulch at the end of six months and at the end of twelve months to maintain a 100mm cover
- Re-application of water crystals around plants after six months and after twelve months
- Analysing soil after twelve months and applying fertiliser in accordance with the recommendations of the soil analysis





- 4. Consequent to signing the Agreement, build sewer works required at your cost and pay associated charges.
- 5. Pay a total of \$15,834 for the charges identified in Section 5 of this notice.

Please note:

The Developer Charges total will need to be paid before you will be given permission to construct the sewer works and connect into Sydney Water's water system;

You need to obtain a Tax Invoice before you can pay this charge in person at a Sydney Water Customer Service Centre (located in the City, Wollongong and Katoomba). If you require an invoice, please contact your Coordinator; and

Credit card payments (to a maximum of \$1,000) may be made on Bankcard, MasterCard or Visa only at a Sydney Water Customer Service Centre.

DETAILED REQUIREMENTS

1. Water service requirements.

A 100mm water main in Wakehurst Parkway is available to serve your development. Each lot must have a separate connection & meter. Lot 2 & 4 must have the water main constructed within the "Right of Carriageway & Easement for Services". Provide a copy of plan showing easement details to Sydney Water.

2. Water Servicing Coordinator

You must engage an authorised Coordinator to manage and facilitate the construction of sewer works that you must provide, at your cost, to service your development.

3. Minor Works Agreement

After you engage a Coordinator, you will need to sign and lodge both copies of the enclosed Minor Works Agreement with your nominated Coordinator.

Notes:

- If construction must take place on a neighbouring property, written consent on the Sydney Water Permission to Enter form must be obtained from the relevant property owner and tenant (i) by you, or your Coordinator. Your Coordinator has copies of the form(s) (also available on the Internet at the address as above) and can negotiate on your behalf. This consent must be lodged with the Agreement.
- The authorisation of the Coordinator must be current at all times throughout the project. (ii)

4. Sewer works.

The Coordinator will facilitate the engagement of a Sydney Water accredited Constructor of Minor Works (Sewer)/ Sewer Constructor (the Constructor) to build the works.


The Coordinator, in conjunction with the Constructor, shall determine the location of the works that will adequately drain the property. Minor Works (Sewer) relates to gravity sewers of size ≤DN 225 and depth ≤2.5m (measured from the invert of the sewer to the ground surface) and covers the following activities:



104-106 WAKEHURST PARKWAY, ELANORA HEIGHTS

ECOLOGICAL SUSTAINABILITY PLAN

June 2006





104-106 WAKEHURST PARKWAY, ELANORA HEIGHTS

ECOLOGICAL SUSTAINABILITY PLAN



ABN 89 877 340 321

Wombeyan Caves Road, High Range 2575

Tel 02 4878 5542

Fax 02 4878 5543

Mob 0412 600 173

Email rhayes@hayesenv.com.au

Table A. Check List

Item	Chapter
Site Preparation Description of: Tree, vegetation and habitat protection, Sediment and erosion control for natural features, Weed control, Top soil/ litter layer treatment, Surface treatment and stabilisation (mulch etc), Site drainage with respect to natural features,	2.1.1 2.1.2 2.1.3 2.1.4 2.1.5 2.1.6
Weed Removal and Regeneration List of Noxious and Environmental Weeds Timeline for removing Noxious Weeds and controlling/removing Environmental Weeds (for updated weeds list see Dept of Agriculture web page). Timeline to include the area / number of weed species acceptable as a background level. Cross reference location with Map.	
Description of Planting (if planting) Planting aims, e.g. supplementary planting in a regeneration area, or a native vegetation area or planting in a landscape area.	2.3.1
 Species list recommended for planting—as appropriate (if the ESP is replacing a Landscaping Plan give details of species to be planted and size range / species). Local native species to be used (for at least 70% of plantings, 80% in Endangered Ecol. Comm.). Identify source of local native, plant stock. 	
Description of areas for bush regeneration, trees to be retained, trees to be planted (and what size), etc A schedule of materials-including elements such as weed matting, mulch, edging, walling paving and fencing. Description of works meeting minimum requirements of Landscaping Policy (i.e. 50% of development screened in 3 yrs).	Map 1
Long-term Management Management of habitat features, including protection during construction and for the life of development. Also include the provision of nesting boxes etc as appropriate. Maintenance period for 12 to 24 months after Issue of Occupation Certificate. NB maintenance can be by land occupier.	:
 Indicate areas that are to be maintained as 'bushland' for the life of the development Description of exclusion areas for domestic animals as relevant Reference to other documents if relevant (e.g. frequency and type of fuel reduction, care for onsite water disposal system) 	2.4.2 2.4.3 2.4.4
Check-sheets listing activities to be completed on an on-going basis. List of Noxious Weeds to be managed/removed (at all times). List of Environmental Weeds to be managed/removed (all times). Area of native vegetation and trees to be maintained/retained. Area from which domestic animals are not permitted.	Table 1 Table 1 Map 1 2.4.3

Alberres

Rebecca Hayes BSc (Environmental Biology) MEngMngt MEIANZ MECA SCANNED

8 AUG 2006

TABLE OF CONTENTS

Page No.

1	INTE	RODUCT	FION	1
	1.1	Backg	round	1
	1.2	Existin	g Environment	1
		1.2.1	General Description	1
		1.2.2	Floristic Details	1
	1.3	Descri	ption of the Proposed Development	2
2	ACT	IONS F	OR ECOLOGICAL SUSTAINABILITY	2
	2.1	Site P	reparation	2
		2.1.1	Protection of trees and other natural features to be retained	2
		2.1.2	Sediment and erosion control	3
		2.1.3	Removal of weeds	3
		2.1.4	Top soil/litter layer treatment	3
		2.1.5	Surface stabilisation	3
		2.1.6	Site Drainage	3
	2.2	Weed	Removal	3
		2.2.1	Existing Weeds	3
		2.2.2	Timeframe for Weed Removal	4
	2.3	Reveg	etation/Landscaping	5
		2.3.1	Objectives	£
		2.3.2	Details	£
	2.4	Long-t	erm Management	5
		2.4.1	Management of habitat features	5
		2.4.2	Areas to be maintained as bushland	5
		2.4.3	Exclusion areas for domestic animals	5
		2.4.4	Asset Protection Zones	6
3	RES	PONSIE	BILITY FOR ACTIONS	6



104-106 WAKEHURST PARKWAY, ELANORA HEIGHTS

ECOLOGICAL SUSTAINABILITY PLAN

May 2006

1 INTRODUCTION

1.1 Background

This Ecological Sustainability Plan has been prepared to accompany an application for a Construction Certificate for a proposed subdivision of 104 and 106 Wakehurst Parkway, Elanora Heights, within the Pittwater Local Government Area (LGA).

The purpose of this plan is to document actions to be taken on the site to maximise the long-term sustainability of the site and its ecological processes.

1.2 Existing Environment

1.2.1 General Description

Numbers 104 and 106 Wakehurst Parkway, Elanora Heights (the subject site) are two parallel allotments located on the northern side of the Wakehurst Parkway. The two allotments are together approximately 135m in length by 30.5m in width, thus approximately 4210sqm in size in total.

The southern portion of the site slopes gently up to the north, away from the Wakehurst Parkway. This area of the site has been previously cleared and disturbed, with existing dwellings located on each allotment, and occasional remnant and planted trees.

The central portion of the site slopes upwards relatively steeply, to the base of a natural sandstone escarpment. This portion of the site has also been previously cleared and disturbed, although some remnant native trees and shrubs occurs to the north, and in retained garden beds.

The northern portion of the site, above the sandstone escarpment, slopes moderately up to the rear boundary of the site. This portion of the site supports native vegetation in relatively intact condition, although with some weed-invasion.

1.2.2 Floristic Details

Native vegetation present across the central and northern portions of the site has been identified as Sydney Sandstone Gully Forest (as described by Benson & Howell 1994).

8 AUG 2006

SCANNED

PITTIVAL SUNCE

Hayes Environmental - Ref: 04010 - 15th June 2006

The canopy is fairly sparse, consisting of scattered occurrences of Bangalay *Eucalyptus botryoides* to approximately 20m in height.

The shrub layer, where present, is moderate to dense and dominated by Cheese Tree Glochidion ferdinandi, Bastard Rosewood Synoum glandulosum, Blueberry Ash Elaeocarpus reticulatus, and the exotic weed Small-leaved Privet Ligustrum sinense, to approximately 8m in height.

The groundcover, where not consisting of maintained lawn, varies in density from sparse to dense, and includes the following native grasses and herbs: False Bracken Fern Calochlaena dubia, Gristle Fern Blechnum cartilagineum, Native Sarsaparilla Smilax glyciphylla and King Fern Todea barbara, to 1.2m in height.

Common exotic weeds present in the groundcover include Japanese Honeysuckle Lonicera japonica, Wandering Jew Tradescantia albiflora, Crofton Weed Ageratina adenophora, Panic Veldt Grass Ehrharta erecta and Cape Ivy Delairea odorata.

Dense thickets and mats of Lantana and other exotic weeds have been removed from some areas in the central portion of the site.

1.3 Description of the Proposed Development

The proposed subdivision involves creation of two new allotments. One at the rear of number 104 Wakehurst Parkway, and one at the rear of 106 Wakehurst Parkway. A new dwelling would be constructed on each of the two new allotments.

The proposed subdivision has been designed to minimise impacts on native flora and fauna present on the site. However, several trees would need to be removed from the central portion of the site, for construction of new dwellings.

The sandstone escarpment and vegetation to the north of it are to be retained in a natural condition.

2 ACTIONS FOR ECOLOGICAL SUSTAINABILITY

2.1 Site Preparation

2.1.1 Protection of trees and other natural features to be retained

An exclusion fence is to be constructed to be protect existing native vegetation and habitats present across the rear (upslope) portion of the site. The fence would be located approximately 2-5m downslope from the base of the natural sandstone escarpment, see accompanying Map 2.

Where native trees which are to be retained occur close to construction works, protective fencing will be installed around each tree, at a minimum distance of 1 metre outside of the dripline of the tree canopy. In the instance where construction activities are essential beneath the tree canopy, protective fencing will extend as far from the tree trunk as practicable.

A qualified arborist/tree surgeon will be engaged to treat cuts to any significant tree roots encountered during construction activities, and to manage any removal of tree limbs. This measure is intended to maximise tree health and long term viability.

SCANNIED

8 AUG 7886
2
PITTMOLEN SUNCIL

Hayes Environmental - Ref: 04010 - 15th June 2006

All exposed bushrock and other habitat features present outside of the development footprint will be retained. The majority of these features are located away from the proposed construction zone, and do not require specific protection measures. However, where protection is necessary to avoid accidental damage by machinery or stockpiles, this will consist of fencing as for protection of retained trees.

2.1.2 Sediment and erosion control

Parts of the site not being disturbed directly for construction works are to be retained with existing vegetation cover.

Sediment and erosion control features will be located to minimise impacts on trees and other natural features to be retained on the site, in addition to standard requirements.

2.1.3 Removal of weeds

Weed control prior to construction works is intended to minimise the potential for weed propagules to be spread from the site during construction.

The native bushland present above the sandstone escarpment is in relatively intact condition. Weeds present in this area will be targeted for removal following initial construction works (refer to Chapter 2.2 below).

Weeds present in the area to be directly disturbed by construction activities will be carefully removed from the site by small machinery (eg dingo or mini-bobcat) and destroyed prior to construction works. Hand tools will be used in difficult to access areas, and in sensitive areas, such as close to natural rock features and close to trees being retained.

2.1.4 Top soil/litter layer treatment

Construction works on the site do not require extensive excavations. Landscaping of the site does not require extensive excavation works. The majority of the site is to be retained in its natural condition.

Special storage and re-spreading of top soil at this site is not required.

2.1.5 Surface stabilisation

Surfaces across the site are generally to be retained in their existing condition. Those in the vicinity of construction works are mostly lawn, and do not require further stabilisation works. Mulch will be used in areas where mats of Wandering Jew and other groundcover weeds have been removed, if required.

2.1.6 Site Drainage

Virtually all natural features on the site are located upslope of the proposed development, and would not be affected by alteration to site drainage.

2.2 Weed Removal

2.2.1 Existing Weeds

A large number of weeds have been recorded on the site (refer to previous Flora and Fauna Assessment report prepared by Hayes Environmental in June 2004). Many of these are fairly benign garden ornamentals, and do not require targeted removal from the site.




Table 1 below lists weeds that are present on the site, and which are either listed as 'noxious' for the Pittwater area under the NSW Noxious Weeds Act 1993, or are regarded as environmental weeds due to their invasive or otherwise destructive nature.

Table 1 Existing noxious and environmental weeds present on the site.

Status	Scientific Name	Common Name	
	Shrubs/Trees		
N	Ochna serrulata	Mickey Mouse Plant	
N	Ligustrum sinense	Small-leaved Privet	
N	Lantana camara	Lantana	
	Tall Groundcovers		
N	Cestrum parqui	Green Cestrum	
N	Cortaderia sellona	Pampas Grass	
	Conyza albida	Tall Fleabane	
	Low Groundcovers		
	Tradescantia fluminensis	Wandering Jew	
	Ageratina adenophora	Crofton Weed	
	Vines		
N	Acetosa sagitata	Turkey Rhubarb	
	Lonicera japonica	Japanese Honeysuckle	
	Hedera helix	English Ivy	
	Ferns		
N	Protasparagus densiflorus	Asparagus Fern	
	Nephrolepis cordifolia	Fish Bone Fern	

N Noxious Weed listed under the NSW Noxious Weeds Act 1993 for the Pittwater LGA.

2.2.2 Timeframe for Weed Removal

The three shrubs and taller groundcover weeds on the site are generally single plants or clumps. The woody species will be cut and painted with herbicide such as Roundup Bioactive ®, and others will be removed by either small machinery or hand tools, depending on location. Initial control of these weeds will involve removal of all adult individuals from the site, prior to or at the time of occupation of new dwellings¹. Follow-up control of seedlings of these species will be undertaken as frequently as necessary and possible by the landowner, to prevent re-infestations.

The lower groundcovers, vines and herbs are generally present in low densities amongst the lawn and native groundcover. Where mats of weeds occur in accessible areas close to the construction site, these will be removed by small machinery. Elsewhere, weeds will be removed carefully by hand (including hand tools).

Timing of removal for these weeds is less dependent upon season, and will be undertaken as frequently as necessary and possible by the landowner. With the exception of Fishbone Fern,

8 AU 7003 PITTWALE OUGAL

4

Herbicide is generally more effective when applied during the warmer active-growing months of the year. The initial removal of these weeds could be delayed if construction occurs over winter.

Japanese Honeysuckle and English Ivy, which may be retained in small discrete areas as ornamentals, these weeds will gradually (over 2-5 years) be removed completely from the site.

2.3 Revegetation/Landscaping

2.3.1 Objectives

The dual primary purposes of revegetation/landscaping of the site are:

- to replace noxious and environmental weeds on the site with local native plants; and
- to provide screening for visual amenity from the street and for the occupants of the proposed new dwellings.

2.3.2 Details

Details of landscaping such as plant species to be used, sizes, densities, areas of bushland to be retained, and materials (edging, stepping stones, paving, *etc*), are illustrated on the accompanying Landscape Plan prepared by lan Jackson Landscape Architect P/L, dated March 2006.

2.4 Long-term Management

2.4.1 Management of habitat features

Protection of habitat features during construction works is described in Chapter 2.1.1 above. Much of the sandstone escarpment, and the bushland above it at the rear of the site, is inaccessible from the new development, and therefore does not require on-going specific protection measures.

The proposed development does not involve loss of notable tree-hollows. It is therefore not necessary to impose construction or installation of nesting boxes as an environmental management requirement for the site.

Other areas of habitat such as rock boulders and native vegetation which will be within the backyards of new houses cannot practicably be protected through specific measures.

2.4.2 Areas to be maintained as bushland

The natural bushland present across the rear of the site is to be maintained in its existing condition, as 'bushland', for the life of the development. This area is essentially inaccessible from the developed part of the site, and therefore does not require on-going specific protection measures.

The disturbed bushland area in the central part of the site will be backyards for the two new houses. This area will be retained in a similar 'altered bushland' condition to that currently present, but with removal and control of noxious weeds, and with landscaping to meet asset protection zone requirements. This area does not require on-going specific protection measures.

Native vegetation being retained as bushland will not be subject to gradual introduction of exotic or non locally native ornamental plant species. Pesticides and fertilisers will not be used in these parts of the site, other than when absolutely necessary during establishment of new plantings.

2.4.3 Exclusion areas for domestic animals



Domestic pets will be contained, chained up, or kept indoors at night, to reduce the likelihood of disturbance to, and predation of, native fauna such as the Long-nosed Bandicoot *Perameles nasuta*. The rear of the site, above the sandstone escarpment, is essentially inaccessible to domestic pets from the new development. Domestic pets will be prevented from gaining access to this part of the site.

Boundary fencing will contain openings accessible to ground dwelling native fauna with a minimum dimension of 150mm, to avoid obstructing the passage of wildlife.

2.4.4 Asset Protection Zones

The lower and central parts of the site, up to the base of the sandstone escarpment, are to be managed as an Asset Protection Zone, refer to the accompanying Landscape Plan.

3 RESPONSIBILITY FOR ACTIONS

Responsibility for the actions set out in Chapter 2 above will rest with the owner of the land for the life of the development. Responsibility will transfer to new owner/s if and when the land is sold.

Tenants may be required by the owner to manage certain aspects of the ecological sustainability plan, but will not remove responsibility from the owner.

The owner may rely on advice provided by specialist consultants with regard to tree health and safety, management of ecological values within the native bushland at the rear of the site, care and maintenance of native plant landscaping, and other matters relating to ecological sustainability of the site, at their discretion.




Table B. Check List for attached plans

- Map 1 Landscape Plan, also showing existing vegetation.
- Map 2 Construction access, material storage and exclusion fencing.
- Map 3 Noxious and Environmental Weeds.
- Map 4 Native vegetation, regeneration and habitat features.

	Plan
	Map 4
All areas of native vegetation	Arborist
Malive Rees include phospers 1	report
Accurate survey and describe native trees within 5m of proposed works	Мар 1
	Map 4
Areas with medium to high regeneration potential	Map 4
Areas of native vegetation to be retained	Map 4
Areas of vegetation proposed to be removed	Map 3
Areas of Noxious and Environmental Weeds	Map 4
Areas of habitat features, bushrock (over 2m), caves, termite mounds etc	Map 1
Footprint of house and associated works (fuel reduced zones, waste-water etc)	Map 2
Areas for exclusion fencing-during development/establishment phase	•
Areas appropriate for storage of materials during construction	Map 2
Recommended access ways during construction	Map 2
Areas for bush-regeneration	Map 1
Areas for planting trees (if appropriate)	Map 1
	Map 1
Areas for planting low and or mid strata	Map 1
Areas for landscaping	Map 1
Fuel reduced zone	N/a
Fuel free zone	N/a
Waste-water disposal zone	N/a
Recommended Environmental Protection Zone (EPZ) if appropriate Recommended Environmental Protection Zone (EPZ) if appropriate Recommended Environmental Protection Zone (EPZ) if appropriate	N/a
Recommended Environmental Protection 25.16 (2.1.2) Areas for managing domestic animals (see requirements of Pittwater Council Control Documents Pittwater	
21) Wildlife Corridors and Core/Fragmented Bushland (as per Pittwater Council Maps)	Map 4

SCANNED

8 AUG 2006

PITTWATER COUNCIL



Eclipse Landscapes PTY LTD

23 May, 2004

Wade Chick
798 Barrenjoey Rd
Palm Beach 2108
Phone 9974 2590
Fax 9974 2591
Mobile 0411 821 806
Lic 76588C
A.C.N. 093339505
A.B.N. 42093339505

Tree report

Re: 104 & 106 Wakehurst Parkway Elanora Heights

This report is to be read with plan by C.M.S Surveyors CMS ref 476

Trees to be relocated:

All Livistona australis (cabbage tree palms) in the way of proposed buildings are to be transplanted and relocated on site (tree No 19, 44, 47, 50 and 53). All the affected trees are in good health with no visible disease or ill health. Prior to any demolition or excavation the palms are to be transplanted to appropriate location and protected from all building works. The transplanting of palms is to be done by a qualified tree transplanter and/or arborist. The transplanted palms are to be fenced of 2m from trunk and mulched to a depth of 75mm. The palms are to be inspected at 2 month intervals by qualified arborist to assess health and recommend appropriate treatment.

Trees to be removed:

- ◆ Tree No 49 Syzygium oleosum (Lillypilly) Tree is in excellent health with no visible disease or ill health. Recommend to replant 1 Syzygium oleosum in 45 litre container for each proposed development (4 in total to be replanted)
- ◆ Tree No 45 Araucaria heterophylla (Norfolk Island Pine) Tree is in good health with no visible disease or ill health. No replanting required as it is not native and is to large for proposed area in consideration with bush fire

SC	ARIMITATION
8	A > 2006
Plits	

- Tree No 43 Eucalyptus pilularis (Blackbutt) Tree is in poor health is suckering at top.
 With relation to trees health and position considering bushfire and proximity to residence tree should be removed.
- Tree No 32 (mandarin). To be removed introduced species.

Trees to be retained

- ◆ Tree No 25,51,52,54, and 55 Livistona australis (Cabbage Tree Palm). Palms are in good health with no visible signs of disease or ill health. Palms are to be fenced off 1m from trunk and native leafmulch spread to a depth of 75mm.
- ◆ Tree No 46 Eucalyptus pilularis (Blackbutt). Tree in moderate health, deadwood to be removed. To be fenced off around rock outcrop and native leaf mulch spread 75mm deep.


The overall impact of transplanting removal and replanting of trees for proposed development as listed will in time have a positive effect on the area. There will be more canopy with the replanting of lillypilly on each block and the retention of Cabbage tree palms.


Kind Regards

Wade Chick

Arboriculture 0503U 1991

SCANTE 8 ALE 2006 Phile Leader






*** Exclusion fence

Areas for exclusion during construction


SCANNED 8 AUG 2006

PITTWATER COUNCIL

Z 9AM



SCANNED
8 AUG 2006
PITTWATER COUNCIL





- 2 Wildlife corridor or core/fragmented bushland (as per Pittwater Council Maps); degraded bushland with medium regeneration potential to be retained; will be managed as asset protection zone and as backyard
- Areas of habitat features, bushrock (over 2m)
- Degraded bushland to be removed for proposed new dwelling




A State of the state of

NOTE: THESE PLANS MUST BE READ IN CONJUNCTION WITH THE CONDITIONS OF DEVELOPMENT CONSENT







GENERAL NOTES:

GENERAL

- GI. The drawings are to be read together with all Architects drawings and specifications.
- G2. Dimensions shall not be obtained by scaling from the drawings. All setting out dimensions shall be verified and discrepancies shall be referred to the Engineer prior to commencement of work.
- G3. Care is required during construction so that structural elements are not over stressed and that the works and excavations required therefore are kept stable at all times.
- G4. Design, materials and workmanship are to be in accordance with current S.A.A standards and statutory authority regulations except where varied by these documents.
- G5. Design live loads are in accordance with AS 1170.1
- G6. Builder to ensure stability of existing structures in the vicinity of excavation works.

FOOTINGS

- FI. FOUNDATION STRATA IS ASSUMED FOR DESIGN PURPOSES IN ACCORDANCE WITH AS 2870-1996 "RESIDENTIAL SLAB AND FOOTINGS-CONSTRUCTION". SEE FOOTNOTE, CLASSIFICATION TO BE VERIFIED BY A GEOTECHNICAL ENGINEER COMMISSIONED BY THE CLIENT FOR CERTIFICATION OF FOUNDATIONS.
- F2. Footings to be constructed and back filled as soon as possible following excavation to avoid softening by rain or drying out by exposure.
- F3. Footings must bear into undisturbed natural ground clear of organic material. Refer to details.
- F4. If rock or variable bearing strata is encountered during excavation of the footings all footings/piers are to be excavated to similar material of greater bearing capacity.
- The Engineer is to be contacted at that time for approval or review.
- F5. Footings to be cast in approved material having an allowable capacity as follows: AND AS OUTLINED IN GEOTECHNICAL REPORT (ref 18498Z Rrpt dated: 09-06-04)
 PREPARED BY ' JEFFERY & KATAUSKAS PTY LTD' Sand Foundations: SAI. Required bearing capacity 100 kPa.

SA2. Trenches must be cleaned of all debris and hand compacted prior

- to placement of reinforcement.
- Clay Foundations: CLI. Required bearing capacity 150 kPa. CL2. Trenches must be cleaned of all debris. Soft spots must be cut

of reinforcement.

Shale Foundations: SHI. Required bearing capacity 400 kPa.

out and filled as per compacted fill notes, prior to placement

SH2. Excavation for footings into shale must be cast or capped with plain

- concrete on the same day as excavation. Sandstone Foundations:
- SSI. Required bearing capacity 600 kPa. SS2. Scrape weathered surface to remove cleaved sandstone under footings.

Refer adjacent for assumed Design bearing strata.

F6. Future development of neighboring properties may effect ground water conditions on this site. Consequently, reactivity in subgrade beneath footings may be locally altered therefore putting footing at risk of differential settlement. We recommend that, particularly in clay subgrades, agricultural drainage is installed to the upstream perimeter of the building at a distance from the building which is outside the zone of influence of the footings. The agricultural drain must be installed below the fluctuating seasonal zone which should be identified by geotechnical investigation.

CONCRETE

- C1. All workmanship and materials shall be in accordance with AS 3600.
- C2. Concrete quality shall be as follows and shall be verified by tests.
- C3. All concrete unless otherwise noted shall have a slump of 80mm at point of placement, a max. aggregate size of 20 mm. No water shall be added to the mix prior to or
- during placement of concrete. Strength as specified on plans.
- C4. Clear concrete cover to reinforcement shall be as follows unless otherwise shown-

ELEMENT	INTERIOR	EXTERIOR	EXTERIOR CAST AGAINST GROUND
F00TINGS	-	-	50
COLUMNS/PEDESTALS	30 UNO	REFER TO PLAN	•
SLABS/WALLS	25	REFER TO PLAN	40 ON MEMBRANE
BEAMS	25 UNO	REFER TO PLAN	50
BLOCKWORK	55 FROM APPROPRIATE FACE		

- C5. Sizes of concrete elements do not include thickness of applied finishes.
- C6. All Construction Joints locations shall be approved by the Structural Engineer.
- C7. Beam depths are written first and include slab thickness, if any.
- C8. No holes or chases other than those shown on the structural drawings shall be made in concrete elements without the prior approval of the enaineer.
- C9. Shrinkage reducing admixtures such as 'Eclipse' or approved equivalent,

- C10. Water reducing agents, if specified, must be added to mix prior to pour. No extra water is to be added to increase slump.
- CII. Where vertical slab/beam surfaces are formed against a masonry (or other) wall, provide 10 mm styrene separation material.
- C12. Water must not be added to concrete mix prior to placement of concrete.
- C13. Above covers may have to be adjusted if fire rating is a requirement.

REINFORCEMENT

- RI. All reinforcement specified is Grade D500 unless noted otherwise.
- R2. Reinforcement is represented diagrammatically it is not necessarily shown in true projection.
- R3. Top reinforcement is to be continuous over supports.
- Bottom reinforcement to be lapped at supports. R4. Welding of reinforcement shall not be permitted unless shown on the structural drawinas.
- R5. Pipes or conduits shall not be placed within the zone of concrete cover to the reinforcement without the approval of the engineer.
- R6. All reinforcing bars and fabric shall comply with AS 4671-2001.
- R7. Reinforcement symbols:
- N Grade 500N deformed bar (D500) Normal Ductility R - Grade 250N plain round bar (R250) Normal Ductility
- SL Grade 500L welded deformed ribbed mesh (D500) Square Low Ductility.
- RL Grade 500L welded deformed ribbed mesh (D500)
- Rectangular Low Ductility. The number immediately following these symbols is the number of

millimeters in the bar diameter. Example

- 8 NI2-250, denotes 8, Grade 500N deformed bars, 12 mm diameter at 250 cts. R8. Fabric reinforcement to be lapped 1 complete square + 25 mm unless noted otherwise.
- R9 All reinforcement shall be firmly supported on bar chairs spaced at a maximum of 750 centres both ways under rod and fabric reinforcement. Reinforcement shall be tied at alternate intersections.

FORMWORK

- FWI. Formwork must be cleaned of all debris prior to casting of concrete.
- FW2. Minimum stripping times for form work shall be as recommended in AS 3610 - 1990 or as directed by the engineer.
- FW3. The finished concrete shall be a dense homogeneous mass, completely filling the form work, thoroughly embedding the reinforcement and free of stone pockets. All concrete elements including slabs on ground and footings shall be compacted with mechanical vibrators.
- FW4. Curing of all concrete is to be achieved by keeping surfaces continuously wet for a period of 3 days, followed by prevention of loss of moisture for seven days followed by a gradual drying out. Approved sprayed on curing compounds may be used where no floor finishes are proposed Polythene sheeting or wet hessian may be used if protected from wind and traffic.

BRICKWORK

- BRI. Brickwork is to be constructed to AS 3700.
- BR2. Two layers of approved greased metal based slip material shall be used over all load bearing walls that support concrete slabs and placed on smooth brickwork or trowelled mortar finish. Non load-bearing walls shall have 10 mm compressible material and ties to the slab soffit.
- BR3. No brickwork shall be constructed on suspended slabs until all propping has been removed from the underside of the slab and the concrete has the specified 28 day cylinder strength verified by tests.
- BR4. Control joints to be placed at a maximum of 8m centres or in accordance with AS 3700.
- BR5. Exposure grade bricks to be used below damp proof course. BR6. Vertical control joint material where specified on plan between slabs and brick walls shall be: 10 mm Spandex External UNO.
- BR7. Provide stainless steel wall ties below DPC to AS 3700. Provide galvanized wall ties above DPC to AS 3700 \$ Local Council Specifications.

Bitumastic fibreboard internal UNO.

BLOCKWORK

- BLI. Concrete blocks shall have a minimum compressive strength of 15 MPa and conform to AS 1500. Masonry to be constructed to AS 3700.
- BL2. Where cores of hollow blocks are to be filled, properly compacted 20MPa concrete with 10 mm aggregate and 230 mm slump shall be used. Clean out openings must be utilized for all cores.
- BL3. Location of actual starters is critical to suit block cores, allow 55 mm cover from the outside face of blockwork. All reinforcement lap lengths to conform to AS 3600.
- BL4. Control joints to be placed at a maximum of 8 m centres or in accordance with AS 3700.
- BL5. Vertical control joint material where specified on plan between slabs and brick walls shall be: 10 mm Spandex External UNO. Bitumastic fibreboard internal UNO

- BL6. Retaining walls or any reinforced and concrete core filled block walls
- to be of Double 'U' Block Construction. BL7. No blockwork shall be constructed on suspended slabs until all propping has been removed from the underside of the slab and the concrete has the specified 28 day cylinder strength verified by tests. unless approved by the Structural Engineer.
- BL8. Max. ipour height for unrestrained blockwork is 2000.

STEEL.

SI. All Structural steelwork to be Grade 300 or greater. Design, fabrication and erection to be in accordance

Unless moted otherwise, all bolts will be 8.85.

- with 45 4100.
- S2. Materials and workmanship shall comply with AS 1250 1981, SAA Steel Structures Code and the specification for Structural Steel
- S3. Rolled steel sections including steel plates shall comply with AS 3678 1990. 54. Cold formed steel sections shall be Grade 450 Zinc coated in accordance
- with AS 1538-1988. S5. Welded and seamless steel hollow sections shall comply with AS 1163. Grade 350.
- S6. Bolt Designation: 4.65 - Commercial bolts Grade 4.6, snug tightened. 8.85 - High Strength structural bolts Grade 8.8, snug tightened.
- 8.8TB High Strength structural bolts Grade 8.8, fully tightened to AS 1511 and acting as a Bearina Joint.
- 8.8TF High Strength structural bolts Grade 8.8, fully tensioned to AS 1511 and acting as a Bearing Joint.
- S7. Unless shown otherwise, minimum connection shall be 2M16 bolts, 10 thick gusset plates, 6mm continuous fillet welds. 58. Load implication washers shall be used in all fully tensioned joints. (8.8TF \$ 8.8TB).
- S9. All wellding shall be carried out in accordance with AS 1554 SAA Structural Steel
- SIO. Unless noted otherwise all welds shall be category SP using E41xx Electrodes. All butt, welds shall be complete penetration butt welds category SP.
- SII. Grouting of anchor bolt sleeves and base plates shall be completed by the contraction using High Strength, Non-Shrink grout.
- S12. Fabrication and erection tolerances for Structural Steelwork shall be in accordance with AS 4100.
- S13. Purlin bolts shall be M12 4.65 galvanised. SI4. Steel work shall have one of the following grades of corrosion protection:-INTERNAL
 - a. Thorroughly cleaned wire brushing, followed by two coats of zinc phosphate primer equivalent to Dulux Luxaprime applied by hand using brushes to achieve a total dry film thickness of 70

EXTERNAL ELEMENTS, & ELEMENTS WITHIN EITHER SKIN OF EXTERNAL CAVITY WALLS

- b. Preparation Blast clean to a minimum standard Class 2.5 in accordance with AS 1627 Part 4.
- Primer 2-pack epoxy phosphate at dft 75 microns (Dulux Durepon P14). Barrier Coat 2-pack epoxy micaeous iron oxide, dft 100 microns
- Finiish Coat 2-pack epoxy high gloss acrylic to dft 75 microns (e.g. Dulux Acrathane I F) in an approved colour. c. Hot dipped galvanized to AS 4680. Where the galyanic (Hot Dip Galyanized) coating is compromised by welding,
- boltting or damage, inorganic zinc-rich paint (minimum 95% zinc content) is to be applied after wire brushing affected area (use 3 coats minimum). or Hoth Metal Spray in accordance with AS 4680.
- S15. Worksthop drawings shall be prepared and two copies submitted to the engineer for review prior to fabrication commencement.

TIMBER

- TI. All workmanship and materials to be in accordance with AS 1684, AS 172:0 and as 3959. All soft wood to be Grade F7 unless noted otherwiise. All hardwood to be minimum Grade F14 unless otherwise noted. Exposed timber to be CCA treated (to AS 1604) redried after full impregnation, or durability class 1, 2 or 3. ALL SIOFTWOOD TIMBER FRAMING TO HAVE A MINIMUM TREATMENT PROTECTION OF H2 or T2 TREATED FOR TERMITE PROTECTION UNLESS NOTED OTHERWISE.
- T2. All joists deeper than 150 to have blocking over support bearers and at a maximum 3000 centres.
- T3. Roof trusses to be designed by the manufacturer to the relevant standards. Pre camber to be an amount equal to dead load deflection u.n.o.
- T4. All holes for bolts to be exact size. Washers to be used under all heads and nuts and to be at least 2.5 times the bolt diameter. Bolts to be M16 grade 4.6 unless noted otherwise.
- T5. Treat all exposed cut ends with Reseal by Protim to manufacturers specification to achieve required Hazard Level Exposure Classification.
- T6. Battens for T \$ G to be Kiln Dried to 12 %. 38mm minimum deep treated pine or as recommended by supplier. Flooring to be installed no sooner than 28 days after slab pour.
- T7. Hot dip galvanized nails/clouts/screws to be used with all timber connections.
- T8. Continuous nailing must not be used for any timber connections. T9. All exposed CCA treated pine to have an application of penetrating sealer to reduce warping and twist of the timber due to varying moisture content in service.

DRAWING SCHEDULE:

- SOI GENERAL NOTES AND DRAWING SCHEDULE
- COI SITE PLAN
- CO2 WORKS TO WAKEHURST PARKWAY FRONTAGE
- CO3 WAKEHURST PARKWAY FRONTAGE ROADWORKS SECTIONS AND DETAILS
- CO4 DRIVEWAY LAYOUT PLAN
- CO5 DRIVEWAY LONGITUDINAL AND CROSS SECTIONS
- COG DRIVEWAY SLAB PLAN AND DETAILS
- CO7 DRIVEWAY SLAB DETAILS SHEET
- CO8 DRIVEWAY SLAB DETAILS SHEET 2
- DOI EROSION AND SEDIMENT CONTROL PLAN AND DETAILS
- DO2 STORMWATER DRAINAGE PLAN AND DETAILS

0355/00

TCG (NV) D 3 AUG 2006

ISSUED FOR CONSTRUCTION CERTIFICATE SUBMISSION ONLY

COMPACTED FILL

- CFI. Only to be used with approval Engineer \$ to be certified by a aeotechnical Engineer.
- CF2. Clear organic material and topsoil under proposed slabs/footings. CF3. Filling shall be granular material compacted in not more than 200 mm layers to a minimum dry density ratio (AS 1289/E4.2 1982)
- of 98 percent. CF4. During clearing and excavation for slabs and footings cut out soft spots and fill as above.

- INSPECTIONS BY ENGINEER
- 48 HOURS NOTICE IS REQUIRED BEFORE ANY SITE INSPECTION 1. Bearing strata of all footings prior to concrete pour.
- 2. Any reinforcement prior to concrete pour.

EFFECTIVE JULY 1, 2004.

- 3. Timber and Steel framing prior to cladding or lining. 4. Steel lintels after installation.
- 5. CONTACT YOUR PCA (Principal Certifying Authority) AS TO REQUIREMENTS FOR MANDATORY CRITICAL STAGE INSPECTIONS IN ACCORDANCE WITH REVISED EP\$A ACT REGULATIONS SCANIED

8 AUG 1006 PITTWATERIC DUNCIL

ASSUMED FOUNDATION CLASSIFICATION FOR DESIGN PURPOSES - 'A' & 'M' ASSUMED BEARING STRATA FOR DESIGN PURPOSES - ROCK, 650 kPa. \$ CLAY, 250 kPa CONTRACTOR TO ENGAGE GEOTECHNICAL CONSULTANT TO VERIFY FOUNDATION CLASSIFICATION

if specified, must be added to mix prior to pour. DOCUMENT CERTIFICATION 18-07-06 REVISION A Lucas Molloy Amendment: (Director Northern Beaches Consulting Engineers)

I hold the following qualifications: BE(Civil), CPEng, MIEAust., NPER. Institute of Engineers Membership No. 788184 I hereby state that this drawing is in compliance with the provisions of the Building Code of Australia and/or relevant Australian/Industry Standards.

I am a qualified Structural/Civil Engineer.



NORTHERN BEACHES | Project: Consulting Engineers P/L. A.C.IN. 076 121 616 A.B.N. 24 076 121 616 Suite 207, 30 FISHER ROAD **DEE WHY N.S.W. 2099** Ph: ((02) 9984 7000 Fax: (02) 9984 7444 e-mail: nb@nbconsulting.com.au

PROPOSED DEVELOPMENT at: 104 \$ 106 Wakehurst Parkway Elanora

for: Stuart Thor

Drawing Title: GENERAL NOTES AND DRAWING SCHEDULE

Job No: The copyright of this drawing remains with Northern Beaches Consulting Engineers P/L.

Paul R Bruce RW Mar 2006 OMIEAust. Rev: Drawing No: 051149 501

Drawn:

