

J3808B. 27th July, 2023 Page 1.

73 Marine Parade, Avalon

Geotechnical Comments for Section 4.55

We have reviewed the existing geotechnical report, the original plans, and the 8 amended plans by Gartner Trovato Architects, Project number 2105, drawings numbered A-01 to A-08, Revision C, dated 3/7/23.

The changes are as follows:

- Add a storage room to the garage floor of the proposed house.
- Alter the internal and external layout of the works.
- Various other minor modifications to the house and external areas.

The proposed storage room will increase the volume of excavated material but does not change the maximum depth of the excavation of its setbacks to the side boundaries. As such, the changes are considered minor from a geotechnical perspective and do not alter the recommendations or the risk assessment in the original report carried out by this firm numbered J3808 and dated the 14th January, 2022.

White Geotechnical Group Pty Ltd.

Nathan Gardner

B.Sc. (Geol. & Geophys. & Env. Stud.)

Hlandner

Engineering Geologist and Environmental Scientist.

Reviewed By:

Ben White M.Sc. Geol., AusIMM., CP GEOL.

No. 222757

Engineering Geologist.

GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER FORM NO. 1 – To be submitted with Development Application

Develo	pment Application	on for	Name of Applicant
			Name of Applicant
Addres	s of site	73 Marine Parade	e, Avalon
The follow geotechr	ving checklist cov nical engineer or	ers the minimum require engineering geologist	ements to be addressed in a Geotechnical Risk Declaration made by t or coastal engineer (where applicable) as part of a geotechnical report
,	Ben White (Insert Name)	on behalf of <u>W</u>	/hite Geotechnical Group Pty Ltd (Trading or Company Name)
rganisati	ngineer as define	sue this document and	certify that I am a geotechnical engineer or engineering geologist or isk Management Policy for Pittwater - 2009 and I am authorised by the above to certify that the organisation/company has a current professional indemnity
: Please m	nark appropriate	box	
\boxtimes			al Report referenced below in accordance with the Australia Geomechanics Guidelines (AGS 2007) and the Geotechnical Risk Management Policy for
	am willing to te	, ,	ne detailed Geotechnical Report referenced below has been prepared in hanics Society's Landslide Risk Management Guidelines (AGS 2007) and the
	have examined t with Section 6.0 assessment for	he site and the proposed of the Geotechnical Risk the proposed developm	of Fittwater - 2009 did development in detail and have carried out a risk assessment in accordance k Management Policy for Pittwater - 2009. I confirm that the results of the risk nent are in compliance with the Geotechnical Risk Management Policy for technical reporting is not required for the subject site.
	Application only	involves Minor Devel	d development/alteration in detail and I am of the opinion that the Development lopment/Alteration that does not require a Geotechnical Report or Risk accordance with the Geotechnical Risk Management Policy for Pittwater - 2009
	Hazard and does the Geotechnica	s not require a Geotechr I Risk Management Polic	development/alteration is separate from and is not affected by a Geotechnical nical Report or Risk Assessment and hence my Report is in accordance with cy for Pittwater - 2009 requirements. soastal forces analysis for inclusion in the Geotechnical Report
Geotechi	nical Report Deta	ails:	
		technical Report 73 Ma	rine Parade, Avalon
	Author: BEN WH	HITE	
	Author's Compan	y/Organisation: WHITE	GEOTECHNICAL GROUP PTY LTD
Documer	ntation which rel	ate to or are relied upo	on in report preparation:
			iety Landslide Risk Management March 2007.
	White Geote	chnical Group co	mpany archives.
			, prepared for the abovementioned site is to be submitted in support of a elied on by Pittwater Council as the basis for ensuring that the Geotechnica

I am aware that the above Geotechnical Report, prepared for the abovementioned site is to be submitted in support of a Development Application for this site and will be relied on by Pittwater Council as the basis for ensuring that the Geotechnical Risk Management aspects of the proposed development have been adequately addressed to achieve an "Acceptable Risk Management" level for the life of the structure, taken as at least 100 years unless otherwise stated and justified in the Report and that reasonable and practical measures have been identified to remove foreseeable risk.

Signature	Bellet
Name	Ben White
Chartered Professional Sta	tus MScGEOLAusIMM CP GEOL
Membership No.	222757
Company	White Geotechnical Group Pty Ltd

GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER FORM NO. 1(a) - Checklist of Requirements for Geotechnical Risk Management Report for Development Application

Develo	pment Application		Name of Applicant	
Addres	s of site	73 Marine Parade, A	• •	
Report. 1		company the Geotechnical	s to be addressed in a Geotechnical Risk Man Report and its certification (Form No. 1).	nagement Geotechnical
		eport 73 Marine Parade	, Avalon	
	Date: 14/1/22	•	,	
	BEN WHITE			
Author	's Company/Organi	sation: WHITE GEOTECH	NICAL GROUP PTY LTD	
Please m	nark appropriate bo	x		
\boxtimes	Comprehensive site	mapping conducted 18/10/21	-	
\boxtimes	Mapping details pres Subsurface investiga ☐ No ☒ Yes	tion required Justification	with geomorphic mapping to a minimum scale of	f 1:200 (as appropriate)
		s identified the site site the site	n inferred subsurface type-section	
	Geotechnical hazard Risk assessment cor ⊠ Conse	s described and reported	e Geotechnical Risk Management Policy for Pitt	water - 2009
	Risk calculation Risk assessment for Risk assessment for Assessed risks have Management Policy	property conducted in accord loss of life conducted in accord been compared to "Acceptab for Pittwater - 2009 ovided that the design can ac are achieved.	lance with the Geotechnical Risk Management P rdance with the Geotechnical Risk Management ble Risk Management" criteria as defined in the G hieve the "Acceptable Risk Management" criteria	Policy for Pittwater - 2009 Seotechnical Risk
	⊠ 100 ye □ Other _			
	Pittwater - 2009 have Additional action to re	e been specified	hases as described in the Geotechnical Risk Ma and practical have been identified and included Zone.	
that the g Managen	eotechnical risk man nent" level for the life	agement aspects of the pro e of the structure, taken as	hnical Report, to which this checklist applies, posal have been adequately addressed to act at least 100 years unless otherwise stated, a dentified to remove foreseeable risk.	nieve an "Acceptable Risk
		Signature	Belit	
		Name	Ben White	
		Chartered Professional Sta	tus MScGEOLAusIMM CP GEOL	
		Membership No.	222757	

Company White Geotechnical Group Pty Ltd



J3808. 14th January, 2022. Page 1.

GEOTECHNICAL INVESTIGATION:

New House and Pool at 73 Marine Parade, Avalon

1. Proposed Development

- **1.1** Demolish the existing house and construct a new part four-storey house by excavating to a maximum depth of ~5.0m.
- 1.2 Install a new pool on the uphill side of the property by excavating to a maximum depth of ~1.5m.
- **1.3** Various other minor alterations.
- 1.4 Details of the proposed development are shown on 10 drawings prepared by Gartner Trovato Architects, Project number 2105, drawings numbered A-00 to A-09, Revision A, dated 13/1/22.

2. Site Description

- **2.1** The site was inspected on the 18th October, 2021.
- 2.2 This residential property is on the high side of the road and has a predominantly W aspect. The block is located on the gentle to moderately graded upper reaches and crest of a hillslope that rises to the top of a ~50m high sea cliff. The slope rises across the site at an average angle of ~12°. The slope below the property (to the W) continues at gradually easing angles
- 2.3 At the road frontage, a concrete driveway runs up the slope to a gravel parking area on the downhill side of the property (Photo 1) and to a garage on the lower ground floor of the house (Photo 2). The cut for the driveway is supported by stable mortared stack rock retaining walls that will be demolished as part of the proposed works (Photo 3). Between the road frontage and the house is a gently sloping lawn and garden area (Photo 4). The part two-storey brick house was observed to be



J3808. 14th January, 2022. Page 2.

supported directly onto outcropping sandstone bedrock and will be demolished as part of the proposed works (Photos 5 & 6). A gentle to moderately-sloping garden area extends off the uphill side of the house (Photo 7). Sandstone bedrock was observed to be outcropping through the slope in multiple places (Photo 8). A near-level brick-paved fill has been placed at the top of the property (Photo 9). The fill is battered to stable angles and the fill batter is lined with large sandstone boulders (Photo 10). A ~50m high sea cliff falls from the top of the property. The sea cliff was observed from the rock platform below (Photo 11). It consists mainly of massive competent Medium Strength Sandstone with some, alternating thinly bedded shale/laminite layers. The cliff face below the property displays no significant undercutting or other significant geological defects that could affect its stability. The rock platform has a covering of dislodged sandstone boulders at the cliff base.

3. Geology

The Sydney 1:100 000 Geological sheet indicates the site is underlain by the Newport Formation of the Narrabeen Group. There is a band of sandstone underlying the entire uphill side of the property that extends through the otherwise shale-dominated profile.

4. Subsurface Investigation

Nine Dynamic Cone Penetrometer (DCP) tests were put down to determine the relative density of the overlying soil and the depth to bedrock. The locations of the tests are shown on the site plan attached. It should be noted that a level of caution should be applied when interpreting DCP test results. The test will not pass through hard buried objects so in some instances it can be difficult to determine whether refusal has occurred on an obstruction in the profile or on the natural rock surface. This is not expected to be an issue for the testing on this site. However, excavation and foundation budgets should always allow for the possibility that the interpreted ground conditions in this report vary from those encountered during excavations. See the appended "Important information about your report" for a more comprehensive explanation. The results are as follows:



J3808. 14th January, 2022. Page 3.

DCP TEST RESULTS – Dynamic Cone Penetrometer									
Equipment:	Equipment: 9kg hammer, 510mm drop, conical tip. Standard: AS1289.6.3.2 - 1997							.2 - 1997	
Depth(m) Blows/0.3 m	DCP 1 (~RL48.5)	DCP 2 (~RL47.9)	DCP 3 (~RL47.5)	DCP 4 (~RL46.6)	DCP 5 (~RL45.2)	DCP 6 (~RL44.3)	DCP 7 (~RL44.6)	DCP 8 (~RL41.0)	DCP 9 (~RL41.0)
0.0 to 0.3	9	4	ω E	ω E	ω m	ω ×	lmr	ω E	m m
0.3 to 0.6	#	12	Rock Exposed Surface	Rock Exposed at Surface	Rock Exposed at Surface	Rock Exposed at Surface	Rock Immediately Below	Rock Exposed at Surface	Rock Exposed at Surface
0.6 to 0.9		9	e dat	e dat	e dat	d at	tely	e dat	dat
0.9 to 1.2		#							
	Refusal on Rock @ 0.3m	Refusal on Rock @ 0.9m							

#refusal/end of test. F = DCP fell after being struck showing little resistance through all or part of the interval.

DCP Notes:

DCP1 – Refusal on rock @ 0.3m, DCP bouncing off rock surface, white, brown, and orange sandstone fragments on dry tip.

DCP2 – Refusal on rock @ 0.9m, DCP bouncing off rock surface, brown clay on dry tip.

DCP3 - Medium Strength Sandstone exposed at the surface.

DCP4 – Medium Strength Sandstone exposed at the surface.

DCP5 – Medium Strength Sandstone exposed at the surface.

DCP6 – Medium Strength Sandstone exposed at the surface.

DCP7 – Medium Strength Sandstone immediately below surface (~0.1m).

DCP8 – Medium Strength Sandstone exposed at the surface.

DCP9 – Medium Strength Sandstone exposed at the surface.

5. Geological Observations/Interpretation

The surface features of the block are controlled by the outcropping and underlying sandstone bedrock that steps up the property forming sub-horizontal benches between the steps. Where the grade is steeper, the steps are larger, and the benches narrower. Where the slope eases, the opposite is true. We note this is a relatively thick band of sandstone within the shale-dominated Narrabeen Group. These bands of sandstone are common immediately



J3808. 14th January, 2022.

Page 4.

adjacent to the sea cliffs. The vertical extent of the band is not known; however, the sandstone was observed to be outcropping and was encountered in the ground testing across the entire footprint of the proposed house. Where the rock is not exposed, it is overlain by natural sandy soils and firm to very stiff sandy clays that fill the bench step formation. In the test locations, where it was not exposed, rock was encountered at depths of between 0.3 to 0.9m below the current surface. The exposed sandstone across the site is estimated to be Medium Strength and a similar strength rock is expected to underly the entire site. See Type

6. Groundwater

Normal ground water seepage is expected to move over the buried surface of the rock and through the cracks.

Section attached for a diagrammatical representation of the expected ground materials.

Due to the slope and elevation of the block, the water table is expected to be many metres below the base of the proposed excavations.

7. Surface Water

No evidence of surface flows were observed on the property during the inspection. As the property encompasses the crest of the hill, any surface flows will be generated on the property and will flow away from the property.

8. Geotechnical Hazards and Risk Analysis

No geotechnical hazards were observed above or beside the property. The gentle to moderately graded slope that rises across the property and continues below is a potential hazard (Hazard One). The vibrations from the proposed excavations are a potential hazard (Hazard Two). A loose boulder, wedge, or similar geological defect toppling onto the work site during the excavation process is a potential hazard (Hazard Three). The sea cliff face that falls from the top of the property is a potential hazard (Hazard Four).



J3808. 14th January, 2022. Page 5.

Risk Analysis Summary

HAZARDS	Hazard One	Hazard Two		
ТҮРЕ	The gentle to moderate slope that rises across the site and continues below failing and impacting on the proposed works.	The vibrations produced during the proposed excavations impacting on the sea cliff and supporting walls of the neighbouring houses.		
LIKELIHOOD	'Unlikely' (10 ⁻⁴)	'Possible' (10 ⁻³)		
CONSEQUENCES TO PROPERTY	'Medium' (12%)	'Medium' (15%)		
RISK TO PROPERTY	'Low' (2 x 10 ⁻⁵)	'Moderate' (2 x 10 ⁻⁴)		
RISK TO LIFE	5.5 x 10 ⁻⁷ /annum	5.3 x 10 ⁻⁷ /annum		
COMMENTS	This level of risk is 'ACCEPTABLE'.	This level of risk to property is 'UNACCEPTABLE'. To move risk to 'ACCEPTABLE' levels, the recommendations in Section 12 are to be followed.		

RISK ANALYSIS SUMMARY CONTINUED ON NEXT PAGE



J3808. 14th January, 2022. Page 6.

HAZARDS	Hazard Three	Hazard Four		
		The long-term stability of the sea cliff on the		
	A loose boulder, wedge, or	property impacting the property taking into		
	similar geological defect	consideration the allowance for		
TYPE	toppling onto the work site	erosion/weathering of the cliff and of St		
	during the excavation	Michael's Cave as calculated by Horton		
	process.	Coastal Engineering in the next 100 years		
		(Photo 11).		
LIKELIHOOD	'Possible' (10 ⁻³)	'Rare' (10 ⁻⁵)		
CONSEQUENCES TO PROPERTY	'Medium' (20%)	'Major' (40%)		
RISK TO PROPERTY	'Moderate' (2 x 10 ⁻⁴)	'Low' (6 x 10 ⁻⁵)		
RISK TO LIFE	6.2 x 10 ⁻⁴ /annum	9.96 x 10 ⁻⁶ /annum		
		The base of the cliff is ~10m seaward of the		
	This level of risk to life and	proposed house. However, the rock platform		
	property is	continues seaward at the base of the cliff over		
	'UNACCEPTABLE'. To move	a distance of ~15m and Horton Coastal		
COMMENTS	risk to 'ACCEPTABLE' levels,	Engineering has provided a 7 to 12mm/year		
	the recommendations in	allowance for erosion of the cliff. As such, the		
	Section 13 are to be	cliff is not a significant risk to the property for		
	followed.	well over 100 years. This level of risk is		
		'ACCEPTABLE'.		

(See Aust. Geomech. Jnl. Mar 2007 Vol. 42 No 1, for full explanation of terms)

9. Suitability of the Proposed Development for the Site

The proposed development is suitable for the site. No geotechnical hazards will be created by the completion of the proposed development provided it is carried out in accordance with the requirements of this report and good engineering and building practice.

10. Stormwater

The fall is to Marine Parade. Roof water from the development is to be piped to the street drainage system through any tanks that may be required by the regulating authorities.



J3808.

14th January, 2022.

Page 7.

11. Excavations

An excavation to a maximum depth of ~5.0m is required to construct the proposed house.

Another excavation to a maximum depth of ~1.5m is required to construct the proposed pool.

The excavations are expected to be through a thin sandy soil with Medium Strength

Sandstone expected to be encountered at depths of between 0.3 to 0.9m below the current

surface where it is not exposed at the surface. We note the vertical extent of the band is not

known; however, the sandstone was observed to be outcropping and was encountered in the

ground testing across the entire footprint of the proposed house. As such, Medium Strength

Sandstone is expected to be encountered through the entirety of the excavation through

bedrock.

It is envisaged that excavations through sandy soil can be carried out with a bucket and

excavations through rock will require grinding or rock sawing and breaking.

12. Vibrations

Possible vibrations generated during excavations through sandy soils will be below the

threshold limit for building damage.

Excavations through Medium Strength Rock or better should be carried out to minimise the

potential to cause vibration damage to the neighbouring structures and to the sea cliff.

Allowing for backwall-drainage, the excavation will be set back ~1.4m from the N

neighbouring garage, ~3.4m from the N neighbouring house, and ~2.7m from the S

neighbouring house. The excavation for the pool will be set back ~10m from the edge of the

sea cliff.

Dilapidation reporting carried out on the N and S neighbouring properties is recommended

prior to the excavation works commencing.

Excavation methods are to be used that limit peak particle velocity to 5mm/sec at the sea cliff

and property boundaries. Vibration monitoring will be required to verify this is achieved. The

vibration monitoring equipment must include a light/alarm so the operator knows if vibration



J3808. 14th January, 2022. Page 8.

limits have been exceeded. It also must log and record vibrations throughout the excavation works.

In Medium Strength Rock or better, techniques to minimise vibration transmission will be required. These include:

- Rock sawing the excavation perimeter to at least 1.0m deep prior to any rock breaking with hammers, keeping the saw cuts below the rock to be broken throughout the excavation process.
- Limiting rock hammer size.
- Rock hammering in short bursts so vibrations do not amplify.
- Rock breaking with the hammer angled away from the nearby sensitive structures.
- Creating additional saw breaks in the rock where vibration limits are exceeded.

Following these recommendations, no adverse impacts to the neighbouring properties and to the sea cliff are expected. It is worth noting that vibrations that are below thresholds for building damage may still be felt by the occupants of the neighbouring houses.

13. Excavation Support Requirements

Bulk Excavation for Proposed House

The excavation is expected to reach a maximum depth of ~5.0m. The majority of the excavation is sufficiently set back from the common boundaries. However, a small portion of the N and S sides of the proposed excavation will be taken close to flush with the N and S common boundaries. The N neighbouring garage is set back ~1.4m from the common boundary in this location. As such, due to the exposed/shallow depth to Medium Strength Sandstone encountered in this location, only the N and S common boundaries will be within the zone of influence of the proposed excavation. In this instance, the zone of influence is the area above a theoretical 30° line through soil from the top of Medium Strength Sandstone towards the surrounding structures and boundaries.



J3808. 14th January, 2022.

Page 9.

Where the excavation depth through soil exceeds 0.6m, the cut through soil is to be permanently or temporarily supported along the N and S sides before the excavation through

rock commences. The support is to be installed systematically as the excavation progresses

to ensure the integrity of the neighbouring properties into the future. If the support is

temporary, it is to remain in place until the retaining wall is built as a sacrificial-type system.

Where the excavation depth through soil tapers to less than 0.6m, and along all other sides,

the soil portions of the cut batters are to be battered temporarily at 1.0 Vertical to 2.0

Horizontal (30°) until the retaining walls are in place. We note due to the depth of the

excavation, the soil is to be scraped back from the footprint of the excavation at least 0.5m

and then battered. Medium Strength Sandstone or better will stand at vertical angles

unsupported subject to approval by the geotechnical consultant. All excavation boundaries

are to be cut with a rock saw prior to any breaking with pneumatic hammers.

During the excavation process, the geotechnical consultant is to inspect the cut faces in 1.5m

intervals as they are lowered or after encountering softer sections of rock, while the machine

is on site to ensure the ground materials are as expected and no wedges or other geological

defects are present that could require additional support. Should any weak sections of rock

or adverse jointing be encountered, works are to stop until temporary or permanent support

such as rock anchors, bolts, sprayed concrete, or similar support designed by the structural

engineer in consultation with the geotechnical consultant, is installed.

Upon completion of the excavations, it is recommended all cut faces be supported with

retaining walls to prevent any potential future movement of joint blocks in the cut faces that

can occur over time, when unfavourable jointing is obscured behind the excavation faces.

Additionally, retaining walls will help control seepage and to prevent minor erosion and

sediment movement.



J3808.

14th January, 2022.

Page 10.

Bulk Excavation for Proposed Pool

No structures or boundaries will be within the zone of influence of the excavation. In the

location of the proposed pool, rock is expected at shallow depths of ~0.9m or less.

The soil portions of the cut for the pool are expected to stand at near-vertical angles for short

periods of time until the pool structure is installed, provided the cut batters are kept from

becoming saturated. If the cut batters remain unsupported for more than a day before the

pool construction commences, they are to be supported with typical pool shoring such as

braced form ply, until the pool structure is in place. Excavations through Medium Strength

Sandstone or better will stand at vertical angles unsupported subject to approval by the

geotechnical consultant.

Advice Applying to Both Excavations

Upslope runoff is to be diverted from the cut faces by sandbag mounds or other diversion

works. Unsupported cut batters through soil are to be covered to prevent access of water in

wet weather and loss of moisture in dry weather. The covers are to be tied down with metal

pegs or other suitable fixtures so they can't blow off in a storm. The materials and labour to

construct the retaining walls/pool structure are to be organised so on completion of the

excavations they can be constructed as soon as possible. The excavations are to be carried

out during a dry period. No excavations are to commence if heavy or prolonged rainfall is

forecast.

All excavation spoil is to be removed from site following the current Environmental Protection

Agency (EPA) waste classification guidelines.

14. Retaining Structures

For cantilever or singly-propped retaining structures, it is suggested the design be based on a

triangular pressure distribution of lateral pressures using the parameters shown in Table 1.



J3808. 14th January, 2022. Page 11.

Table 1 – Likely Earth Pressures for Retaining Structures

	Earth Pressure Coefficients				
Unit	Unit weight (kN/m³)	'Active' K _a	'At Rest' K₀		
Sandy Soil	20	0.40	0.55		
Medium Strength Sandstone	24	0.00	0.10		

For rock classes refer to Pells et al "Design Loadings for Foundations on Shale and Sandstone in the Sydney Region". Australian Geomechanics Journal 1978.

It is to be noted that the earth pressures in Table 1 assume a level surface above the structure, do not account for any surcharge loads, and assume retaining structures are fully drained. Rock strength and relevant earth pressure coefficients are to be confirmed on site by the geotechnical consultant.

All retaining structures are to have sufficient back-wall drainage and be backfilled immediately behind the structure with free-draining material (such as gravel). This material is to be wrapped in a non-woven Geotextile fabric (i.e., Bidim A34 or similar), to prevent the drainage from becoming clogged with silt and clay. If no back-wall drainage is installed in retaining structures, the likely hydrostatic pressures are to be accounted for in the structural design.

15. Foundations

Concrete slabs supported directly off Medium Strength Sandstone are suitable footings for the proposed house. This material is expected to be exposed across most of the base of the excavations. Where it is not exposed, and where the footprint of the proposed house does not fall over the excavation, piers will be required to maintain a uniform bearing material.



J3808.

14th January, 2022.

Page 12.

The proposed pool is expected to be partially seated in Medium Strength Sandstone. Where

sandstone is not exposed at the base of the excavation, the pool is to be supported on shallow

piers taken to the underlying Medium Strength Sandstone.

As the area around the pool will periodically become saturated with pool use, to prevent

excessive settlement it is recommended any paving be laid on a concrete slab supported on

Medium Strength Sandstone.

A maximum allowable bearing pressure of 600kPa can be assumed for footings on Medium

Strength Sandstone.

Naturally occurring vertical cracks known as joints commonly occur in sandstone. These are

generally filled with soil and are the natural seepage paths through the rock. They can extend

to depths of several metres and are usually relatively narrow but can range between 0.1 to

0.8m wide. If a pad footing falls over a joint in the rock, the construction process is simplified

if with the approval of the structural engineer the joint can be spanned or, alternatively, the

footing can be repositioned so it does not fall over the joint.

NOTE: If the contractor is unsure of the footing material required, it is more cost-effective to

get the geotechnical consultant on site at the start of the footing excavation to advise on

footing depth and material. This mostly prevents unnecessary over-excavation in clay-like

shaly rock but can be valuable in all types of geology.

16. Geotechnical Review

The structural plans are to be checked and certified by the geotechnical consultant as being

in accordance with the geotechnical recommendations. On completion, a Form 2B will be

issued. This form is required for the Construction Certificate to proceed.

17. Inspections

The client and builder are to familiarise themselves with the following required inspections

as well as council geotechnical policy. We cannot provide geotechnical certification for the



J3808. 14th January, 2022. Page 13.

owner or the regulating authorities if the following inspections have not been carried out during the construction process.

- During the excavation process, the geotechnical consultant is to inspect the cut faces
 as they are lowered in 1.5m intervals to ensure ground materials are as expected and
 that there are no wedges or other defects present in the rock that may require
 additional support.
- All footings are to be inspected and approved by the geotechnical consultant while the excavation equipment and contractors are still onsite and before steel reinforcing is placed or concrete is poured.

White Geotechnical Group Pty Ltd.

Ben White M.Sc. Geol., AuslMM., CP GEOL.

No. 222757

Engineering Geologist



Photo 1



J3808. 14th January, 2022. Page 14.




Photo 2



Photo 3



J3808. 14th January, 2022. Page 15.



Photo 4



Photo 5



J3808. 14th January, 2022. Page 16.



Photo 6



Photo 7



J3808. 14th January, 2022. Page 17.



Photo 8



Photo 9



J3808. 14th January, 2022. Page 18.



Photo 10



Photo 11




J3808. 14th January, 2022. Page 19.


Important Information about Your Report

It should be noted that Geotechnical Reports are documents that build a picture of the subsurface conditions from the observation of surface features and testing carried out at specific points on the site. The spacing and location of the test points can be limited by the location of existing structures on the site or by budget and time constraints of the client. Additionally, the test themselves, although chosen for their suitability for the particular project, have their own limiting factors. The testing gives accurate information at the location of the test, within the confines of the test's capability. A geological interpretation or model is developed by joining these test points using all available data and drawing on previous experience of the geotechnical consultant. Even the most experienced practitioners cannot determine every possible feature or change that may lie below the earth. All of the subsurface features can only be known when they are revealed by excavation. As such, a Geotechnical report can be considered an interpretive document. It is based on factual data but also on opinion and judgement that comes with a level of uncertainty. This information is provided to help explain the nature and limitations of your report.


With this in mind, the following points are to be noted:

- If upon the commencement of the works the subsurface ground or ground water conditions prove different from those described in this report, it is advisable to contact White Geotechnical Group immediately, as problems relating to the ground works phase of construction are far easier and less costly to overcome if they are addressed early.
- If this report is used by other professionals during the design or construction process, any questions should be directed to White Geotechnical Group as only we understand the full methodology behind the report's conclusions.
- The report addresses issues relating to your specific design and site. If the proposed project design changes, aspects of the report may no longer apply. Contact White Geotechnical if this occurs.
- This report should not be applied to any other project other than that outlined in section 1.0.
- This report is to be read in full and should not have sections removed or included in other documents as this can result in misinterpretation of the data by others.
- It is common for the design and construction process to be adapted as it progresses (sometimes
 to suit the previous experience of the contractors involved). If alternative design and construction
 processes are required to those described in this report, contact White Geotechnical Group. We
 are familiar with a variety of techniques to reduce risk and can advise if your proposed methods
 are suitable for the site conditions.





EXAMPLES OF GOOD HILLSIDE PRACTICE



EXAMPLES OF POOR HILLSIDE PRACTICE

