



ENERGY EFFICIENCY REPORT

BASIX[®] Thermal Comfort Simulation Assessment

SITE ADDRESS

Lot 9 (#53B) Warriewood Road WARRIEWOOD 2102

LOCAL GOVERNMENT AUTHORITY

Northern Beaches Council

DEPOSITED PLAN

1115877

CLIENT

Rise Projects

DWELLING TYPE

Double Storey

COMMISSIONED BY

Rise Projects

REFERENCE NUMBER

RP 225_Lot 9 v2.0

ASSESSMENT DATE

28/06/2022

While care has been taken to ensure that information contained in this report is true and correct at the time of publication, changes in circumstances after the time of publication may impact on the accuracy of this information. Energy Advance Australia Pty. Ltd. (A.C.N. 60 933 2014) gives no warranty or assurance and make no representation as to the accuracy of any information or advice contained, or that it is suitable for your intended use.

Energy Advance and its employees and agents shall have no liability (including but not limited to liability by reason of negligence) to any person using this report, for any loss, damage, cost or expense whether direct, indirect consequential or special, incurred by, or arising by reason of, any person using or relying on the report and whether caused by reason of any error, omission or misrepresentation in the report or otherwise.

This report is not to be distributed, copied or modified in any way with the intention to disclose to any other party other than those involved in the project's specific approval process.

PROJECT CERTIFICATION SUMMARY



DESIGN AND APPROVED SOFTWARE INFORMATION

SIMULATION ENGINE Chenath Engine v3.21
 EXPOSURE Suburban
 ORIENTATION: 41
 NatHERS CLIMATE ZONE: 56
 BCA (NCC) CLIMATE ZONE: 5


Dwelling Areas (m ²)	
INTERNAL AREAS (m ²)	190.00
OUTDOOR AREAS (m ²)	26.00
GARAGE/CARPORT (m ²)	29.00
TOTAL:	245.00

ASSESSMENT CALCULATIONS & SOFTWARE RESULTS

TARGET	(MJ/m ² .pa)	PROPOSED	(MJ/m ² .pa)	BUILD EFFICIENCY BENCHMARK	
Heating:	40.0	Heating:	32.8	PASS:	19.8%
Cooling:	26.0	Cooling:	25.5	PASS:	1.9%
Total:	66.0	Total:	58.3		

DWELLING THERMAL PERFORMANCE PER ZONED AREAS

The heating and cooling loads indicated are the simulated annual energy usages (MJ) for this home. The higher the load, the more energy needed to achieve thermal comfort.



STATEMENT OF COMPLIANCE

I / We certify that we are specialists in the relevant discipline and the following design documents comply with the relevant requirements of the National Construction Code (NCC Volume One/Two as applicable) in relation to thermal performance and the relevant Australian Standards specified in this report.

ASSESSOR NAME:

SIGNATURE:

C Soakloll
Soakloll

RELEVANT QUALIFICATION STATEMENT

Certificate IV in NatHERS Assessment (Credential Number: TRF0002560)

Residential Building Thermal Performance Assessment (91318NSW) Course

Assessor Accrediting Organisation (AAO) Accreditation Number: **VIC/BDV/14/1662 | ABSA/61846**



BUILDING SPECIFICATION SUMMARY



EXTERNAL WALLS

	CONSTRUCTION TYPE	INSULATION	NOTES
EXTERNAL WALLS	Brick Masonry	None	To the Front Elevation Garage wall (as per drawings)
	Brick Veneer Framed	None	To the remainder of Garage external walls
	Brick Veneer	R2.0 Batts	Specified external walls (as per drawings)
	Framed	R2.0 Batts	Throughout remainder of the external walls (as per drawings)

ADDITIONAL NOTES Location of Construction Materials as per drawings

INTERNAL WALLS

	CONSTRUCTION TYPE	INSULATION	NOTES
INTERNAL WALLS	Framed	R2.0 Batts	To the Garage internal walls only
	Framed	None	Throughout the remaining internal walls

ADDITIONAL NOTES None

ROOF AND CEILING

	CONSTRUCTION TYPE	INSULATION	NOTES
ROOF	Colorbond (un-ventilated)	R1.3 Roof Blanket	Approx. 22°5' Roof Pitch (location as per drawings)
CEILING	Plasterboard	None	Garage Ceiling Area
	Plasterboard	R4.0 Insulation	Main House Area Only

ADDITIONAL NOTES Location of ceiling insulation as per drawings

FLOOR


	CONSTRUCTION TYPE	INSULATION	NOTES
FLOOR	225mm Waffle 85mm Slab	Integrated	Throughout the Ground Floor
	Timber Suspended	R4.0 Batts	Throughout the Upper Floor

ADDITIONAL NOTES Floor Coverings modelled as per Drawings & NATHERS Protocols

GLASS TYPE	COLOUR	FRAME	U _w VALUE	SHGC	NOTES
Standard	Clear	Aluminium	6.38	0.75	Casement Windows
Standard	Clear	Aluminium	6.38	0.75	Sliding Windows
Standard	Clear	Aluminium	6.36	0.65	Awning Windows
Standard	Clear	Aluminium	6.16	0.71	Sliding Doors

Note: Only a +/-5% SHGC tolerance is allowed with this rating. NB: This tolerance ONLY applies to SHGC, the U-value can always be lower but not higher than the values stated in the report. If any of the windows selected are outside the 5% tolerance then this certificate is no longer valid and the dwelling will need to be rerated to confirm compliance.

GLAZING AREA DIRECTIONS



The chart above indicates the direction of all glazed doors and windows on the external envelope of the dwelling. To increase the thermal performance of the dwelling:

1. Maximise unsheltered northern-aspect glazing.
2. Keep west-facing glazing as small as possible: total window area should be less than 5% of the home's total floor area.
3. Keep south-facing glazing reasonably small: total window area should be less than 5% of the home's total floor area. Maximise the openable area if possible.
4. Keep east-facing glazing to a modest size: total window area should be less than 8% of the home's total floor area

Refer to the floor and elevation plans for shading location

LIGHTING/PENETRATION CALCULATIONS

ARTIFICIAL LIGHTING CALCULATION ALLOWANCES

AREA WITHIN THE CLASS 1 BUILDING	190.00 m²		
Development Total	950.0 Watts	Area Wattage Allowance	5.0 W/m ²
AREA WITHIN THE CLASS 10 BUILDING	29.00 m²		
Development Total	87.0 Watts	Area Wattage Allowance	3.0 W/m ²
AREA WITHIN THE OUTDOOR AREAS	26.00 m²		
Development Total	104.0 Watts	Area Wattage Allowance	4.0 W/m ²

CEILING INSULATION PENETRATION ALLOWANCE

CLASS 1 MAXIMUM PENETRATION ALLOWANCE

0.5% TOTAL INSULATED CEILING AREA

CLASS 1 MAXIMUM PENETRATION AREA (m²)

0.95

The clearance required around downlights by "Australian Standard AS/NZS 3000 – 2007 Electrical Installations" (AS/NZS 3000), introduces a significant area of uninsulated ceiling and therefore increases heat loss and gain through the ceiling.

If approved fireproof downlight covers, which can be fully covered by insulation, are specified and noted on the electrical plan by the building designer or architect, then there is no need to allow for the ceiling penetration

NSW ADDITIONS: BUILDING FABRIC THERMAL INSULATION

NSW 3.12.1 APPLICATION OF NSW PART 3.12.1

- (a) Compliance with NSW 3.12.1.1 satisfies NSW P2.6.1(a) for thermal insulation and thermal breaks.
- (b) NSW PART 3.12.1 only applies to thermal insulation in a Class 1 or 10 building where a development consent specifies that the insulation is to be provided as part of the development.
- (c) In (b), the term development consent has the meaning given by the Environmental Planning and Assessment Act 1979.
- (d) The Deemed-to-Satisfy Provisions of this Part for thermal breaks apply to all Class 1 buildings and Class 10a buildings with a conditioned space.

NSW 3.12.1.1 COMPLIANCE WITH BCA PROVISIONS

- (a) Thermal insulation in a building must comply with the national BCA provisions of 3.12.1.1.
- (b) A thermal break must be provided between the external cladding and framing in accordance with national BCA provisions of—
 - (i) 3.12.1.2(c) for a metal framed roof; and
 - (ii) 3.12.1.4(b) for a metal framed wall.
- (c) Compensation for reduction in ceiling insulation must comply with the national BCA provisions of 3.12.1.2(e).
- (d) A floor with an in-slab or in-screed heating or cooling system must comply with the national BCA provisions of—
 - (i) 3.12.1.5(a)(ii), (iii) and (e) for a suspended floor; or
 - (ii) 3.12.1.5(c), (d) and (e) for a concrete slab-on-ground.

BUILDING SEALING & SERVICES

NSW 3.12.3 APPLICATION OF NSW PART 3.12.3

- (a) Compliance with NSW 3.12.3.1 satisfies NSW P2.6.1(b) for building sealing.
- (b) NSW Part 3.12.3 is not applicable to—
 - (i) existing buildings being relocated; or
 - (ii) Class 10a buildings—
 - (A) without a conditioned space; or
 - (B) for the accommodation of vehicles; or
 - (iii) parts of buildings that cannot be fully enclosed; or
 - (iv) a permanent building opening, in a space where a gas appliance is located, that is necessary for the safe operation of a gas appliance; or
 - (v) a building in climate zones 2 and 5 where the only means of air-conditioning is by using an evaporative cooler.

NSW 3.12.3.1 COMPLIANCE WITH BCA PROVISIONS

The sealing of a building must comply with the national BCA provisions 3.12.3.1 to 3.12.3.6.

NSW 3.12.5 SERVICES: APPLICATION OF NSW PART 3.12.5

- (a) Compliance with NSW 3.12.5.1 satisfies NSW P2.6.2 for services.
- (b) NSW Part 3.12.5 is not applicable to existing services associated with existing buildings being relocated.

NSW 3.12.5.1 COMPLIANCE WITH BCA PROVISIONS

Services must comply with the national BCA provisions 3.12.5.0 to 3.12.5.3.



Nationwide House Energy Rating Scheme

NatHERS Certificate No. BT647CX2KL-03

Generated on 28 Jun 2022 using FirstRate5: 5.3.2a (3.21)

Property

Address Lot 9 (#53B) Warriewood Road WARRIEWOOD, Northern Beaches Council, NSW, 2102
Lot/DP 9|1115877
NCC Class* Class 1a
Type New Home

Plans

Main plan RP 225_Lot 9 v2.0 | 28/06/2022
Prepared by Rise Projects

Construction and environment

Assessed floor area (m²)*		Exposure type
Conditioned*	166.3	suburban
Unconditioned*	42.5	NatHERS climate zone
Total	208.8	56 Mascot AMO
Garage	29.9	



Accredited assessor

Name Claude-Francois Sookloll
Business name Energy Advance
Email energy@energyadvance.com.au
Phone 1300 850 228
Accreditation No. DMN/14/1662
Assessor Accrediting Organisation Design Matters National
Declaration of interest Declaration completed: no conflicts

National Construction Code (NCC) requirements

The NCC's requirements for NatHERS-rated houses are detailed in 3.12.0(a)(i) and 3.12.5 of the NCC Volume Two. For apartments the requirements are detailed in J0.2 and J5 to J8 of the NCC Volume One.

In NCC 2019, these requirements include minimum star ratings and separate heating and cooling load limits that need to be met by buildings and apartments through the NatHERS assessment. Requirements additional to the NatHERS assessment that must also be satisfied include, but are not limited to: insulation installation methods, thermal breaks, building sealing, water heating and pumping, and artificial lighting requirements.

The NCC and NatHERS Heating and Cooling Load Limits (Australian Building Codes Board Standard) are available at www.abcb.gov.au.

State and territory variations and additions to the NCC may also apply.

5.4
The more stars
the more energy efficient

NATIONWIDE HOUSE
ENERGY RATING SCHEME

58.3 MJ/m²
Predicted annual energy load for heating and cooling based on standard occupancy assumptions.

For more information on your dwelling's rating see:
www.nathers.gov.au

Thermal performance

Heating	Cooling
32.8	25.5
MJ/m ²	MJ/m ²

About the rating

NatHERS software models the expected thermal energy loads using information about the design and construction, climate and common patterns of household use. The software does not take into account appliances, apart from the airflow impacts from ceiling fans.

Verification

To verify this certificate, scan the QR code or visit <https://www.fr5.com.au/QRCodeLanding?PublicId=BT647CX2KL-03> When using either link, ensure you are visiting www.FR5.com.au.



Certificate Check

Ensure the dwelling is designed and then built as per the NatHERS Certificate. While you need to check the accuracy of the whole Certificate, the following spot check covers some important items impacting the dwelling's rating.

Genuine certificate

Does this Certificate match the one available at the web address or QR code in the verification box on the front page?
Does the set of NatHERS-stamped plans for the dwelling have a Certificate number on the stamp that matches this Certificate?

Ceiling penetrations*

Does the 'number' and 'type' of ceiling penetrations (e.g. downlights, exhaust fans, etc) shown on the stamped plans or installed, match what is shown in this Certificate?

Windows

Does the installed window meet the substitution tolerances (SHGC and U-value) and window type, of the window shown on this Certificate? Substituted values must be based on the Australian Fenestration Rating Council (AFRC) protocol.

Apartment entrance doors

Does the 'External Door Schedule' show apartment entrance doors? Please note that an "external door" between the modelled dwelling and a shared space, such as an enclosed corridor or foyer, should not be included in the assessment (because it overstates the possible ventilation) and would invalidate the Certificate.

Exposure*

Has the appropriate exposure level (terrain) been applied? For example, it is unlikely that a ground-floor apartment is "exposed" or a top floor high-rise apartment is "protected".

Provisional* values

Have provisional values been used in the assessment and, if so, noted in "additional notes" below?

Additional Notes

BCA Climate Zone: 5

Perimeter Insulation has not been included in the modelling of this dwelling

Please note, restricted window openings (%) have been modelled as per NCC 2019 requirements

Eaves indicated by the 'Horizontal shading feature* maximum projection (mm)' may not be directly opposing the respective wall (i.e. some eaves may be horizontally offset)

Where applicable, an additional 150mm has been added to the projection of all 'Horizontal shading features & eaves' to account for the Gutter & Fascia Board

Window and glazed door *type and performance*

Default* windows

Window ID	Window description	Maximum U-value*	SHGC*	Substitution tolerance ranges	
				SHGC lower limit	SHGC upper limit
No Data Available					

Custom* windows

Window ID	Window description	Maximum U-value*	SHGC*	Substitution tolerance ranges	
				SHGC lower limit	SHGC upper limit
DOW-001-01 A	Al Sliding Window SG 3Clr	6.38	0.75	0.71	0.79
DOW-006-01 A	Al Sliding Door SG 5Clr	6.16	0.71	0.67	0.75
DOW-002-01 A	Elite Al Awning Window SG 3Clr	6.36	0.65	0.62	0.68

* Refer to glossary.

Window and glazed door *Schedule*

Location	Window ID	Window no.	Height (mm)	Width (mm)	Window type	Opening %	Orientation	Window shading device*
Garage	DOW-001-01 A	W23	600	1800	sliding	45.0	NE	No
Garage	DOW-001-01 A	W22	600	1800	sliding	45.0	NE	No
Study/Bedroom	DOW-006-01 A	SD19	2370	2100	sliding	45.0	SE	No
Kitchen/Living	DOW-002-01 A	W3	1400	2000	awning	90.0	NW	No
Kitchen/Living	DOW-006-01 A	SD20	2400	3600	other	60.0	NW	No
Bedroom 2	DOW-001-01 A	W4	1400	2400	casement	10.0	SE	No
Bedroom 2	DOW-001-01 A	W16	500	1800	sliding	45.0	NE	No
Master Bedroom	DOW-001-01 A	W11	1400	2400	casement	10.0	SE	No
Master Bedroom	DOW-001-01 A	W21	1400	1600	casement	10.0	NE	No
Master Bedroom	DOW-001-01 A	W13	500	1800	sliding	45.0	SW	No
Rumpus	DOW-001-01 A	W27	500	1400	sliding	45.0	NE	No
Rumpus	DOW-001-01 A	W14	500	1400	sliding	45.0	NE	No
Rumpus	DOW-001-01 A	W26	1500	1800	sliding	30.0	NW	No
Rumpus	DOW-001-01 A	W20	1500	1800	sliding	30.0	NW	No
Bedroom 3	DOW-001-01 A	W12	500	1800	sliding	45.0	SW	No
Bedroom 3	DOW-001-01 A	W5	1500	1800	sliding	30.0	NW	No
Ensuite	DOW-001-01 A	Ensuite Window	500	1800	sliding	45.0	SW	No
Bathroom 2	DOW-001-01 A	W15	500	1800	sliding	45.0	NE	No

Roof window *type and performance value*

Default* roof windows

Window ID	Window description	Maximum U-value*	SHGC*	Substitution tolerance ranges	
				SHGC lower limit	SHGC upper limit
No Data Available					

Custom* roof windows

Window ID	Window description	Maximum U-value*	SHGC*	Substitution tolerance ranges	
				SHGC lower limit	SHGC upper limit
No Data Available					

Roof window *schedule*

Location	Window ID	Window no.	Opening %	Area (m ²)	Orientation	Outdoor shade	Indoor shade
No Data Available							

Skylight *type and performance*

Skylight ID	Skylight description
No Data Available	

Skylight *schedule*

Location	Skylight ID	Skylight No.	Skylight shaft length (mm)	Area (m ²)	Orient-ation	Outdoor shade	Diffuser	Skylight shaft reflectance
No Data Available								

External door *schedule*

Location	Height (mm)	Width (mm)	Opening %	Orientation
Garage	2200	4800	100.0	SE
Kitchen/Living	2340	920	100.0	SE
Laundry	2340	820	100.0	NW

External wall *type*

Wall ID	Wall type	Solar absorptance	Wall shade (colour)	Bulk insulation (R-value)	Reflective wall wrap*
1	STANDARD - Brick Veneer	0.5	Medium		No
2	STANDARD - Double Brick	0.5	Medium		No
3	STANDARD - Framed - Uninsulated (Generic)	0.5	Medium		No
4	STANDARD - Framed Slim (Generic) - R2.0 Batts	0.5	Medium	Glass fibre batt: R2.0 (R2.0)	No
5	STANDARD - Brick Veneer - R2.0 Batts	0.5	Medium	Glass fibre batt: R2.0 (R2.0)	No

External wall *schedule*

Location	Wall ID	Height (mm)	Width (mm)	Orientation	Horizontal shading feature* maximum projection (mm)	Vertical shading feature (yes/no)
Garage	1	2700	143	SW	1117	Yes
Garage	2	2700	5436	SE	1500	Yes
Garage	3	2700	5508	NE	0	Yes
Study/Bedroom	4	2700	3000	SW	0	Yes
Study/Bedroom	4	2700	4000	SE	1050	Yes
Study/Bedroom	4	2700	2771	NE	1845	Yes
Study/Bedroom	4	2700	223	NE	1400	Yes
Kitchen/Living	4	2700	8017	SW	0	Yes
Kitchen/Living	5	2700	1377	SE	4300	Yes
Kitchen/Living	4	2700	1898	NE	0	Yes
Kitchen/Living	4	2700	4372	NW	1505	Yes
Kitchen/Living	4	2700	4238	NW	2800	Yes
Bathroom 1	4	2700	1653	SW	0	Yes
Laundry	4	2700	2271	NE	0	Yes
Laundry	4	2700	2203	NW	0	Yes
Bedroom 2	4	2700	3768	SE	600	Yes
Bedroom 2	4	2700	3661	NE	600	No
Master Bedroom	4	2700	3931	SE	480	No
Master Bedroom	4	2700	2444	NE	479	Yes

* Refer to glossary.

Master Bedroom	4	2700	1185	SE	600	Yes
Master Bedroom	4	2700	4384	SW	600	No
WIR	4	2700	2145	SW	608	No
Rumpus	4	2700	4536	NE	600	No
Rumpus	4	2700	5064	NW	0	No
Bedroom 3	4	2700	3592	SW	600	No
Bedroom 3	4	2700	3846	NW	0	No
Ensuite	4	2700	2415	SW	600	No
Bathroom 2	4	2700	1996	NE	600	No

Internal wall type

Wall ID	Wall type	Area (m ²)	Bulk insulation
1	STANDARD - Internal Stud Walls	121.8	
2	STANDARD - Internal Stud Walls -R2.0 Batts	27.5	Glass fibre batt: R2.0 (R2.0)

Floor type

Location	Construction	Area (m ²)	Sub-floor ventilation	Added insulation (R-value)	Covering
Garage	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	1.8	Enclosed	R0.0	none
Garage	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	28.1	Enclosed	R0.0	none
Study/Bedroom	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	8	Enclosed	R0.0	Carpet
Study/Bedroom	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	4	Enclosed	R0.0	Carpet
Kitchen/Living	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	54.3	Enclosed	R0.0	Tiles
Kitchen/Living	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	0.6	Enclosed	R0.0	Tiles
Kitchen/Living	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	10.7	Enclosed	R0.0	Tiles
Bathroom 1	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	2.4	Enclosed	R0.0	Tiles
Bathroom 1	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	2.2	Enclosed	R0.0	Tiles
Laundry	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	0.8	Enclosed	R0.0	Tiles
Laundry	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	4.2	Enclosed	R0.0	Tiles
Bedroom 2	FLOOR - Framed External Suspended Floor (R4.0 Insulation)	1.1	Elevated	R4.0	Carpet
Bedroom 2	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	12.7	Enclosed	R4.0	Carpet
Master Bedroom	FLOOR - Framed External Suspended Floor (R4.0 Insulation)	4.1	Elevated	R4.0	Carpet
Master Bedroom	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	15.4	Enclosed	R4.0	Carpet
WIR	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	5.8	Enclosed	R4.0	Carpet
Rumpus	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	33.4	Enclosed	R4.0	Timber
Bedroom 3	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	13.1	Enclosed	R4.0	Carpet
Ensuite	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	6.6	Enclosed	R4.0	Tiles

Bathroom 2	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	7.5	Enclosed	R4.0	Tiles
------------	-----------------------------------------------------------	-----	----------	------	-------

Ceiling type

Location	Construction material/type	Bulk insulation R-value (may include edge batt values)	Reflective wrap*
Garage	Plasterboard	R0.0	Yes
Garage	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	R4.0	No
Study/Bedroom	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	R4.0	No
Study/Bedroom	Plasterboard	R4.0	Yes
Kitchen/Living	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	R4.0	No
Kitchen/Living	Plasterboard	R4.0	Yes
Kitchen/Living	Plasterboard	R4.0	Yes
Bathroom 1	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	R4.0	No
Bathroom 1	Plasterboard	R4.0	Yes
Laundry	Plasterboard	R4.0	Yes
Laundry	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	R4.0	No
Bedroom 2	Plasterboard	R4.0	Yes
Bedroom 2	Plasterboard	R4.0	Yes
Master Bedroom	Plasterboard	R4.0	Yes
Master Bedroom	Plasterboard	R4.0	Yes
WIR	Plasterboard	R4.0	Yes
Rumpus	Plasterboard	R4.0	Yes
Bedroom 3	Plasterboard	R4.0	Yes
Ensuite	Plasterboard	R4.0	Yes
Bathroom 2	Plasterboard	R4.0	Yes

Ceiling penetrations*

Location	Quantity	Type	Diameter (mm)	Sealed/unsealed
Kitchen/Living	1	Exhaust Fans	185	Sealed
Bathroom 1	1	Exhaust Fans	250	Sealed
Ensuite	1	Exhaust Fans	250	Sealed
Bathroom 2	1	Exhaust Fans	250	Sealed

Ceiling fans

Location	Quantity	Diameter (mm)
No Data Available		

Roof type

Construction	Added insulation (R-value)	Solar absorptance	Roof shade
--------------	----------------------------	-------------------	------------

* Refer to glossary.



Cont:Attic-Continuous

1.3

0.32

Light

Explanatory Notes

About this report

A NatHERS rating is a comprehensive, dynamic computer modelling evaluation of a home, using the floorplans, elevations and specifications to estimate an energy load. It addresses the building layout, orientation and fabric (i.e. walls, windows, floors, roofs and ceilings), but does not cover the water or energy use of appliances or energy production of solar panels.

Ratings are based on a unique climate zone where the home is located and are generated using standard assumptions, including occupancy patterns and thermostat settings. The actual energy consumption of a home may vary significantly from the predicted energy load, as the assumptions used in the rating will not match actual usage patterns. For example, the number of occupants and personal heating or cooling preferences will vary.

While the figures are an indicative guide to energy use, they can be used as a reliable guide for comparing different dwelling designs and to demonstrate that the design meets the energy efficiency requirements in the National Construction Code. Homes that are energy efficient use less energy, are warmer on cool days, cooler on hot days and cost less to run. The higher the star rating the more thermally efficient the dwelling is.

Accredited assessors

To ensure the NatHERS Certificate is of a high quality, always use an accredited or licenced assessor. NatHERS accredited assessors are members of a professional body called an Assessor Accrediting Organisation (AAO).

Australian Capital Territory (ACT) licensed assessors may only produce assessments for regulatory purposes using software for which they have a licence endorsement. Licence endorsements can be confirmed on the ACT licensing register

Glossary

Annual energy load	the predicted amount of energy required for heating and cooling, based on standard occupancy assumptions.
Assessed floor area	the floor area modelled in the software for the purpose of the NatHERS assessment. Note, this may not be consistent with the floor area in the design documents.
Ceiling penetrations	features that require a penetration to the ceiling, including downlights, vents, exhaust fans, rangehoods, chimneys and flues. Excludes fixtures attached to the ceiling with small holes through the ceiling for wiring, e.g. ceiling fans; pendant lights, and heating and cooling ducts.
Conditioned	a zone within a dwelling that is expected to require heating and cooling based on standard occupancy assumptions. In some circumstances it will include garages.
Custom windows	windows listed in NatHERS software that are available on the market in Australia and have a WERS (Window Energy Rating Scheme) rating.
Default windows	windows that are representative of a specific type of window product and whose properties have been derived by statistical methods.
Entrance door	these signify ventilation benefits in the modelling software and must not be modelled as a door when opening to a minimally ventilated corridor in a Class 2 building.
Exposure category - exposed	terrain with no obstructions e.g. flat grazing land, ocean-frontage, desert, exposed high-rise unit (usually above 10 floors).
Exposure category - open	terrain with few obstructions at a similar height e.g. grasslands with few well scattered obstructions below 10m, farmland with scattered sheds, lightly vegetated bush blocks, elevated units (e.g. above 3 floors).
Exposure category - suburban	terrain with numerous, closely spaced obstructions below 10m e.g. suburban housing, heavily vegetated bushland areas.
Exposure category - protected	terrain with numerous, closely spaced obstructions over 10 m e.g. city and industrial areas.
Horizontal shading feature	provides shading to the building in the horizontal plane, e.g. eaves, verandahs, pergolas, carports, or overhangs or balconies from upper levels.

* Refer to glossary.

AAOs have specific quality assurance processes in place, and continuing professional development requirements, to maintain a high and consistent standard of assessments across the country. Non-accredited assessors do not have this level of quality assurance or any ongoing training requirements.

Any questions or concerns about this report should be directed to the assessor in the first instance. If the assessor is unable to address these questions or concerns, the AAO specified on the front of this certificate should be contacted.



Disclaimer

The format of the NatHERS Certificate was developed by the NatHERS Administrator. However the content of each individual certificate is entered and created by the assessor to create a NatHERS Certificate. It is the responsibility of the assessor who prepared this certificate to use NatHERS accredited software correctly and follow the NatHERS Technical Notes to produce a NatHERS Certificate.

The predicted annual energy load in this NatHERS Certificate is an estimate based on an assessment of the building by the assessor. It is not a prediction of actual energy use, but may be used to compare how other buildings are likely to perform when used in a similar way. Information presented in this report relies on a range of standard assumptions (both embedded in NatHERS accredited software and made by the assessor who prepared this report), including assumptions about occupancy, indoor air temperature and local climate.

Not all assumptions that may have been made by the assessor while using the NatHERS accredited software tool are presented in this report and further details or data files may be available from the assessor.

National Construction Code (NCC) Class	the NCC groups buildings by their function and use, and assigns a classification code. NatHERS software models NCC Class 1, 2 or 4 buildings and attached Class 10a buildings. Definitions can be found at www.abcb.gov.au .
Opening Percentage	the openability percentage or operable (moveable) area of doors or windows that is used in ventilation calculations.
Provisional value	an assumed value that does not represent an actual value. For example, if the wall colour is unspecified in the documentation, a provisional value of 'medium' must be modelled. Acceptable provisional values are outlined in the NatHERS Technical Note and can be found at www.nathers.gov.au
Reflective wrap (also known as foil)	can be applied to walls, roofs and ceilings. When combined with an appropriate airgap and emissivity value, it provides insulative properties.
Roof window	for NatHERS this is typically an operable window (i.e. can be opened), will have a plaster or similar light well if there is an attic space, and generally does not have a diffuser.
Shading device	a device fixed to windows that provides shading e.g. window awnings or screens but excludes eaves.
Shading features	includes neighbouring buildings, fences, and wing walls, but excludes eaves.
Solar heat gain coefficient (SHGC)	the fraction of incident solar radiation admitted through a window, both directly transmitted as well as absorbed and subsequently released inward. SHGC is expressed as a number between 0 and 1. The lower a window's SHGC, the less solar heat it transmits.
Skylight (also known as roof lights)	for NatHERS this is typically a moulded unit with flexible reflective tubing (light well) and a diffuser at ceiling level.
U-value	the rate of heat transfer through a window. The lower the U-value, the better the insulating ability.
Unconditioned	a zone within a dwelling that is assumed to not require heating and cooling based on standard occupancy assumptions.
Vertical shading features	provides shading to the building in the vertical plane and can be parallel or perpendicular to the subject wall/window. Includes privacy screens, other walls in the building (wing walls), fences, other buildings, vegetation (protected or listed heritage trees).



Date	RV	Description
27/06/22	A	FOR DA LODGEMENT

All plans and drawings are copyright of RISE PROJECTS Pty Ltd. Any attempt in using or reproducing or copying the same, wholly or in part, without prior written permission from RISE will result in legal proceeding.




ADDRESS:
576-8 Herbert Street, St Leonards NSW 2065
PH: (02) 8094 1209
ABN: 79 160 683 929
WEBSITE: www.riseprojects.com.au

DRAWN BY: A.D. CHECKED: A.S.
ADDRESS:
**LOT 09 - 53B
WARRIEWOOD ROAD,
WARRIEWOOD**

VIEW:
SITE ANALYSIS

JOB No: **RP 225** NORTH:
SCALE: A1/As indicated
DATE: 27/06/22
DW No: **DA09.01** REV: **A**



Date	RV	Description
27/06/22	A	FOR DA LODGEMENT

All plans and drawings are copyright of RISE PROJECTS Pty Ltd. Any attempt in using or reproducing or copying the same, wholly or in part, without prior written permission from RISE will result in legal proceeding.



ADDRESS:
57/6-8 Herbert Street, St Leonards NSW 2065
PH: (02) 8094 1209
ABN: 79 160 683 929
WEBSITE: www.riseprojects.com.au

DRAWN BY: Author CHECKED: Checker

ADDRESS:
**LOT 09 - 53B
WARRIEWOOD ROAD,
WARRIEWOOD**

VIEW:
SITE PLAN



JOB No: **RP 225** NORTH:

SCALE: A1/ 1 : 50

DATE: 27/06/22

DW No. **DA09.02** REV: **A**

BM 300/Warriewood - 53B Warriewood ROAD, CENTRAL



AREA SCHEDULE TYPE 4	
Name	Area
GROUND FLOOR	86 m ²
FIRST FLOOR	104 m ²
	190 m ²
GARAGE	30 m ²
	30 m ²
LANDSCAPE	78 m ²
	78 m ²



Date	RV	Description
27/06/22	A	FOR DA LODGEMENT

All plans and drawings are copyright of RISE PROJECTS Pty Ltd. Any attempt in using or reproducing or copying the same, wholly or in part, without prior written permission from RISE will result in legal proceeding.



ADDRESS:
57/6-8 Herbert Street, St Leonards NSW 2065
PH: (02) 8094 1209
ABN: 79 160 683 929
WEBSITE: www.riseprojects.com.au

DRAWN BY: A.D | CHECKED: A.S

ADDRESS:
**LOT 09 - 53B
WARRIEWOOD ROAD,
WARRIEWOOD**

VIEW:
FLOOR PLANS

JOB No: RP 225	NORTH:
SCALE: A1/1:50	
DATE: 27/06/22	
DW No. DA09.03.1	REV: A


BM 300/Warriewood - 53B Warriewood ROAD, CENTRAL LOT



1 LOT 09 ELEVATION SE
1 : 50



2 LOT 09 ELEVATION NE
1 : 50



3 LOT 09 ELEVATION SW
1 : 50



4 LOT 09 ELEVATION NW
1 : 50

- 1 - WARM COLOUR WEATHERBOARD CLADDING
- 2 - STONE CLADDING
- 3 - WARM COLOUR RENDER WALL
- 4 - PAINTED TIMBER POST
- 5 - METAL ROOF
- 6 - PANEL LIFT GARAGE DOOR
- 7 - METAL ROOF - LIGHT COLOUR
- 8 - LOUVRED PERGOLA



Date	RV	Description
27/06/22	A	FOR DA LODGEMENT

All plans and drawings are copyright of RISE PROJECTS Pty Ltd. Any attempt in using or reproducing or copying the same, wholly or in part, without prior written permission from RISE will result in legal proceeding.



ADDRESS:
576-8 Herbert Street, St Leonards NSW 2065
PH: (02) 8094 1209
ABN: 79 160 683 929
WEBSITE: www.riseprojects.com.au


DRAWN BY: Author CHECKED: Checker

ADDRESS:
**LOT 09 - 53B
WARRIEWOOD ROAD,
WARRIEWOOD**


VIEW:
ELEVATIONS

JOB No:	RP 225	NORTH:	
SCALE:	A1/1:50		
DATE:	27/06/22		
DW No.	DA09.03.2	REV:	A


B:\00\Warriewood - 53B Warriewood Blvd - CENTRAL.rvt



1 LOT 09 SECTION 1
1 : 50



2 LOT 09 SECTION 2
1 : 50



Date	RV	Description
27/06/22	A	FOR DA LODGEMENT

All plans and drawings are copyright of RISE PROJECTS Pty Ltd. Any attempt in using or reproducing or copying the same, wholly or in part, without prior written permission from RISE will result in legal proceeding.



ADDRESS:
576-8 Herbert Street, St Leonards NSW 2065
PH: (02) 8094 1209
ABN: 79 160 683 929
WEBSITE: www.riseprojects.com.au


DRAWN BY: A.D. CHECKED: A.S.

ADDRESS:
**LOT 09 - 53B
WARRIEWOOD ROAD,
WARRIEWOOD**


VIEW:
SECTIONS

JOB No:	RP 225	NORTH:	
SCALE:	A1/As indicated	DATE:	27/06/22
DW No.:	DA09.03.3	REV:	A


BM 300/Warriewood - 53B Warriewood ROAD, CENTRAL.PLT




1 FF 21/JUN 9AM




2 FF 21/JUN 10AM




3 FF 21/JUN 11AM




4 FF 21/JUN 12PM



5 FF 21/JUN 1PM



6 FF 21/JUN 2PM



7 FF 21/JUN 3PM



Date	RV	Description
27/06/22	A	FOR DA LODGEMENT

All plans and drawings are copyright of RISE PROJECTS Pty Ltd. Any attempt in using or reproducing or copying the same, wholly or in part, without prior written permission from RISE will result in legal proceeding.



ADDRESS:
576-8 Herbert Street, St Leonards NSW 2065
PH: (02) 8094 1209
ABN: 79 160 683 929
WEBSITE: www.riseprojects.com.au

DRAWN BY: A.D. CHECKED: A.S.

ADDRESS:
**LOT 09 - 53B
WARRIEWOOD ROAD,
WARRIEWOOD**

VIEW:
**SHADOW STUDY
FIRST FLOOR**

JOB No:	RP 225	NORTH:	
SCALE:	A/1		
DATE:	27/06/22		
DW No.	DA09.05.2	REV:	A

BM 300/Warriewood - 53B Warriewood ROAD, CENTRAL PT