

Natural Environment Referral Response - Riparian

Application Number:	DA2025/0570
Proposed Development:	Demolition works and construction of a dwelling house including a swimming pool, cabana and sport court
Date:	25/07/2025
To:	Olivia Ramage
Land to be developed (Address):	Lot 59 DP 14682 , 1005 Barrenjoey Road PALM BEACH NSW 2108 Lot 57 DP 14682 , 1007 Barrenjoey Road PALM BEACH NSW 2108 Lot 58 DP 14682 , 1007 Barrenjoey Road PALM BEACH NSW 2108

Reasons for referral

This application seeks consent for the following:

- All Development Applications on land, and located within 40 metres of land, containing a watercourse, or
- All Development Applications on land containing a wetland, or located within 100m of land containing a wetland,
- All Development Applications on land that is mapped as "DCP Map Waterways and Riparian Land".

And as such, Council's Natural Environment Unit officers are required to consider the likely impacts on drainage regimes.

Officer comments

Supported.

This application has been assessed against relevant legislation and policy relating to waterways, riparian areas, and groundwater.

The site is close to Pittwater and as such the development must not significantly impact on the biophysical, hydrological or ecological integrity of Pittwater, or the quantity and quality of surface and ground water flows that it receives.

Subject to conditions, the proposal is unlikely to have an adverse effect on the integrity and resilience of the biophysical, ecological and hydrological environment of Pittwater.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

Recommended Natural Environment Conditions:

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

Installation and Maintenance of Sediment and Erosion Controls

Council proactively regulates construction sites for sediment management.

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) and the Erosion and Sediment Control Plan prepared by Kennon prior to commencement of any other works on site.

Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and vegetation cover has been re-established across 70 percent of the site, and the remaining areas have been stabilised with ongoing measures such as jute mesh or matting.

Reason: To protect the receiving environment.