

Landscape Referral Response

| | |
|--|--|
| Application Number: | DA2025/1428 |
| Date: | 17/10/2025 |
| Proposed Development: | Demolition works, construction of a dual occupancy (attached) including swimming pools and torrens title subdivision |
| Responsible Officer: | Anne-Marie Young |
| Land to be developed (Address): | Lot 37 DP 7236 , 21 Bassett Street MONA VALE NSW 2103 |

Reasons for referral

This application seeks consent for the following:

- Construction / development works within 5 metres of a tree or
- New residential works with three or more dwellings. (RFB's, townhouses, seniors living, guesthouses, etc). or
- Mixed use developments containing three or more residential dwellings.
- New Dwellings or

Officer comments

The proposal is supported with regard to landscape issues.

Council's Landscape Referral section have assessed the application against the Pittwater Local Environment Plan (PLEP), and the following Pittwater 21 DCP controls (but not limited to):

- B4.22 Preservation of Trees and Bushland Vegetation
- C1.1 Landscaping
- D9 Mona Vale Locality

One palm in the front setback will be removed and is exempt, therefore it may be managed or removed at the discretion of the applicant without consent. Three trees are proposed for retention in the front setback. The driveway works are in close proximity to the closest tree to the west of the proposed driveway. The letterbox blade wall for lot 37A is in close proximity to the tree to the east of the proposed driveway, and this tree is exempt by height. No arboricultural information has been provided; however, no concerns are raised with the removal of these two trees to facilitate the works. An additional native tree shall be installed in the front setback of the proposed lot 37B to help satisfy C1.1 of the PDCP.

The landscape proposal is generally supported and all proposed planting shall be installed in accordance with the requirements outlined in the conditions of consent. The side setback areas have been included in the landscaped area calculations but do not include any planting. At minimum, groundcover planting shall be installed in the side setbacks of both lots around the stepping stones to satisfy the definition of landscaped area under PLEP.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

Recommended Landscape Conditions:

CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

Tree Removal Within the Property

- a) This consent approves the removal of existing trees on the subject site as listed below:
- i) the closest tree to the west of the proposed driveway in the front setback of lot 37B,
 - ii) the exempt tree adjacent to the letterbox blade wall in the front setback of lot 37A.

Reason: To enable authorised development works.

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

Tree and Vegetation Protection

- a) Existing trees and vegetation shall be retained and protected, including:
- i) all trees within the site not approved for removal,
 - ii) all trees and vegetation located on adjoining properties,
 - iii) all trees and vegetation within the road reserve.
- b) Tree protection shall be undertaken as follows:
- i) tree protection shall be in accordance with AS 4970-2025 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment,
 - ii) existing ground levels shall be maintained within the tree protection zone of trees to be retained, unless authorised by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture,
 - iii) removal of existing tree roots at or >25mm (Ø) diameter is not permitted without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture,
 - iv) no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,
 - v) structures are to bridge tree roots at or >25mm (Ø) diameter unless directed by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture on site,
 - vi) excavation for stormwater lines and all other utility services is not permitted within the tree protection zone, without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture including advice on root protection measures,
 - vii) should either or all of v) or vi) occur during site establishment and construction works, an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture shall provide recommendations for tree protection measures. Details including photographic evidence of works undertaken shall be submitted by the Arborist/Project Arborist to the Principal Certifier,
 - viii) any temporary access to, or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of AS 4970-2025 Protection of trees on development sites,
 - ix) the activities listed in section 4.2 of AS 4970-2025 Protection of trees on development sites, shall not occur within the tree protection zone of any tree on the lot or any tree on an adjoining site,
 - x) tree pruning from within the site to enable approved works shall not exceed 10% of any tree canopy, and shall be in accordance with AS 4373-2007 Pruning of amenity trees,
 - xi) the tree protection measures specified in this clause must: be in place before work commences on the site, be maintained in good condition during the construction period, and remain in place for the duration of the construction works.
- c) The Principal Certifier must ensure that:
- i) If activated, the arboricultural works listed in a) and b) are undertaken and certified by an

Arborist/Project Arborist as complaint to AS 4970-2025 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment.

Reason: Tree and vegetation protection.

Condition of Trees

a) During the construction period the applicant is responsible for ensuring all existing trees required to be retained are maintained in a healthy and vigorous condition. This is to be done by ensuring that all identified tree protection measures are adhered to, or by seeking arboricultural advice from an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture during the works. In this regard all protected trees shall not exhibit:

- i) a general decline in health and vigour,
- ii) damaged, crushed or dying roots due to poor pruning techniques,
- iii) more than 10% loss or dieback of roots, branches and foliage,
- iv) mechanical damage or bruising of bark and timber of roots, trunk and branches,
- v) yellowing of foliage or a thinning of the canopy untypical of its species,
- vi) an increase in the amount of deadwood not associated with normal growth,
- vii) an increase in kino or gum exudation,
- viii) inappropriate increases in epicormic growth that may indicate that the plants are in a stressed condition,
- ix) branch drop, torn branches and stripped bark not associated with natural climatic conditions.

b) Any mitigating measures and recommendations required by the Arborist/Project Arborist are to be implemented.

c) The owner of the adjoining allotment of land is not liable for the cost of work carried out for the purpose of this clause.

Reason: Protection of trees.

CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

Landscape Completion

a) Landscape works are to be implemented in accordance with the approved Landscape Plan(s) (drawings C5 and C7 by Contour Landscape Architecture dated 29/08/25 revision C), and inclusive of the following conditions:

- i) landscape works are to be contained within the legal property boundaries,
- ii) planting shall be installed as indicated on the approved Landscape Plan(s) unless otherwise imposed by any conditions,
- iii) one additional native tree shall be installed in the front setback of lot 37B; species generally selected from Northern Beaches Council's Native Planting Guide, or Council's Tree Guide; and to achieve at least 6 metres height at maturity,
- iv) all tree planting shall be a minimum pre-ordered planting size of 75 litres or as otherwise scheduled if greater in size; meet the requirements of AS2303 – Tree Stock for Landscape Use; planted into a prepared planting hole 1m x 1m x 600mm depth generally, backfilled with a sandy loam mix or approved similar, mulched to 75mm depth minimum and maintained, and watered until established; and shall be located at least 3.0 metres from buildings and other trees or more, at least 1.5 metres from common boundaries; and located either within garden bed or within a prepared bed within lawn,
- v) groundcover planting shall be installed at minimum 4 plants per metre square in the side setback landscaped areas of both lots around the proposed stepping stones,
- vi) mass planting shall be installed in a garden bed prepared with a suitable free draining soil mix and

minimum 75mm depth of mulch,

vii) all proposed tree planting shall be positioned in locations to minimise significant impacts on neighbours in terms of blocking winter sunlight to living rooms, private open space and where the proposed location of trees may otherwise be positioned to minimise any significant loss of views from neighbouring and nearby dwellings and from public spaces,

viii) where swimming pools are part of the development works, selected planting shall comply with the planting and care requirements of AS1926.1 for a non-climbable zone.

b) Prior to the issue of an Occupation Certificate, details (from a landscape architect, landscape designer or qualified horticulturalist) shall be submitted to the Principal Certifier, certifying that the landscape works have been completed in accordance with any conditions of consent.

Reason: Environmental amenity.

ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

Landscape Maintenance

a) If any landscape materials/components or planting under this consent fails, they are to be replaced with similar materials/components.

b) Trees, shrubs and groundcovers required to be planted under this consent are to be mulched, watered and fertilised as required at the time of planting.

c) If any tree, shrub or groundcover required to be planted under this consent fails, they are to be replaced with similar species to maintain the landscape theme and be generally in accordance with the approved Landscape Plan(s) and any conditions of consent.

d) The approved landscape planted areas, whether containing lawn, gardens or planters shall in perpetuity remain as planting under the development consent, and shall not be replaced with any hard paved surfaces or structures.

Reason: To maintain local environmental amenity.