



# ENERGY EFFICIENCY REPORT

## BASIX® Thermal Comfort Simulation Assessment

**SITE ADDRESS**

**Lot 14 (#53B) Warriewood Road WARRIEWOOD 2102**

**LOCAL GOVERNMENT AUTHORITY**

**Northern Beaches Council**

**CLIENT**

**Rise Projects**

**COMMISSIONED BY**

**Rise Projects**

**ASSESSMENT DATE**

**22/06/2022**

**DEPOSITED PLAN**

**1115877**

**DWELLING TYPE**

**Double Storey**

**REFERENCE NUMBER**

**RP 225\_Lot 14**

While care has been taken to ensure that information contained in this report is true and correct at the time of publication, changes in circumstances after the time of publication may impact on the accuracy of this information. Energy Advance Australia Pty. Ltd. (A.C.N. 60 933 2014) gives no warranty or assurance and make no representation as to the accuracy of any information or advice contained, or that it is suitable for your intended use.


Energy Advance and its employees and agents shall have no liability (including but not limited to liability by reason of negligence) to any person using this report, for any loss, damage, cost or expense whether direct, indirect consequential or special, incurred by, or arising by reason of, any person using or relying on the report and whether caused by reason of any error, omission or misrepresentation in the report or otherwise.

This report is not to be distributed, copied or modified in any way with the intention to disclose to any other party other than those involved in the project's specific approval process.

PROJECT CERTIFICATION SUMMARY

DESIGN AND APPROVED SOFTWARE INFORMATION


SIMULATION ENGINE	Chenath Engine v3.21	Dwelling Areas (m <sup>2</sup> )	
EXPOSURE	Suburban	INTERNAL AREAS (m <sup>2</sup> )	192.00
ORIENTATION:	309	OUTDOOR AREAS (m <sup>2</sup> )	20.00
NatHERS CLIMATE ZONE:	56	GARAGE/CARPORT (m <sup>2</sup> )	30.00
BCA (NCC) CLIMATE ZONE:	5	TOTAL:	242.00



ASSESSMENT CALCULATIONS & SOFTWARE RESULTS

TARGET	(MJ/m <sup>2</sup> .pa)	PROPOSED	(MJ/m <sup>2</sup> .pa)	BUILD EFFICIENCY BENCHMARK
Heating:	40.0	Heating:	38.8	PASS: 3.0%
Cooling:	26.0	Cooling:	25.2	PASS: 3.1%
Total:	66.0	Total:	64.0	

DWELLING THERMAL PERFORMANCE PER ZONED AREAS



STATEMENT OF COMPLIANCE

I / We certify that we are specialists in the relevant discipline and the following design documents comply with the relevant requirements of the National Construction Code (NCC Volume One/Two as applicable) in relation to thermal performance and the relevant Australian Standards specified in this report.

ASSESSOR NAME: C Sookloll

SIGNATURE:

RELEVANT QUALIFICATION STATEMENT

Certificate IV in NatHERS Assessment (Credential Number: TRF0002560)  
Residential Building Thermal Performance Assessment (91318NSW) Course  
Assessor Accrediting Organisation (AAO) Accreditation Number: **VIC/BDVAV/14/1662 | ABSA/61846**



BUILDING SPECIFICATION SUMMARY



EXTERNAL WALLS

	CONSTRUCTION TYPE	INSULATION	NOTES
EXTERNAL WALLS	Framed	R2.5 Batts	Throughout the external walls
ADDITIONAL NOTES	Location of Construction Materials as per drawings		

INTERNAL WALLS

	CONSTRUCTION TYPE	INSULATION	NOTES
INTERNAL WALLS	Framed	R2.5 Batts	Throughout the internal walls
ADDITIONAL NOTES	None		

ROOF AND CEILING

	CONSTRUCTION TYPE	INSULATION	NOTES
ROOF	Colorbond (un-ventilated)	R1.3 Roof Blanket	Approx. 22"5' Roof Pitch (location as per drawings)
CEILING	Plasterboard Plasterboard	None R6.0 Insulation	Garage Ceiling Area Main House Area Only
ADDITIONAL NOTES	Location of ceiling insulation as per drawings		

FLOOR


	CONSTRUCTION TYPE	INSULATION	NOTES
FLOOR	225mm Waffle   85mm Slab Timber Suspended	Integrated R4.0 Batts	Throughout the Ground Floor Throughout the Upper Floor
ADDITIONAL NOTES	Floor Coverings modelled as per Drawings & NatHERS Protocols		

GLASS TYPE	COLOUR	FRAME	U <sub>w</sub> VALUE	SHGC	NOTES
Standard	Clear	Aluminium	6.38	0.75	Casement Windows
Standard	Clear	Aluminium	6.38	0.75	Sliding Windows
Standard	Clear	Aluminium	6.16	0.71	Sliding Doors

Note: Only a +/-5% SHGC tolerance is allowed with this rating. NB: This tolerance ONLY applies to SHGC, the U-value can always be lower but not higher than the values stated in the report. If any of the windows selected are outside the 5% tolerance then this certificate is no longer valid and the dwelling will need to be rerated to confirm compliance.



## GLAZING AREA DIRECTIONS



The chart above indicates the direction of all glazed doors and windows on the external envelope of the dwelling. To increase the thermal performance of the dwelling:

1. Maximise unsheltered northern-aspect glazing.
2. Keep west-facing glazing as small as possible: total window area should be less than 5% of the home's total floor area.
3. Keep south-facing glazing reasonably small: total window area should be less than 5% of the home's total floor area. Maximise the openable area if possible.
4. Keep east-facing glazing to a modest size: total window area should be less than 8% of the home's total floor area

Refer to the floor and elevation plans for shading location

## LIGHTING/PENETRATION CALCULATIONS

### ARTIFICIAL LIGHTING CALCULATION ALLOWANCES

AREA WITHIN THE CLASS 1 BUILDING	192.00 m <sup>2</sup>		
Development Total	960.0 Watts	Area Wattage Allowance	5.0 W/m <sup>2</sup>
AREA WITHIN THE CLASS 10 BUILDING	30.00 m <sup>2</sup>		
Development Total	90.0 Watts	Area Wattage Allowance	3.0 W/m <sup>2</sup>
AREA WITHIN THE OUTDOOR AREAS	20.00 m <sup>2</sup>		
Development Total	80.0 Watts	Area Wattage Allowance	4.0 W/m <sup>2</sup>

### CEILING INSULATION PENETRATION ALLOWANCE

CLASS 1 MAXIMUM PENETRATION ALLOWANCE	CLASS 1 MAXIMUM PENETRATION AREA (m <sup>2</sup> )
0.5% TOTAL INSULATED CEILING AREA	0.96

The clearance required around downlights by "Australian Standard AS/NZS 3000 – 2007 Electrical Installations" (AS/NZS 3000), introduces a significant area of uninsulated ceiling and therefore increases heat loss and gain through the ceiling.

If approved fireproof downlight covers, which can be fully covered by insulation, are specified and noted on the electrical plan by the building designer or architect, then there is no need to allow for the ceiling penetration

## NSW ADDITIONS: BUILDING FABRIC THERMAL INSULATION

### NSW 3.12.1 APPLICATION OF NSW PART 3.12.1

- (a) Compliance with NSW 3.12.1.1 satisfies NSW P2.6.1(a) for thermal insulation and thermal breaks.
- (b) NSW PART 3.12.1 only applies to thermal insulation in a Class 1 or 10 building where a development consent specifies that the insulation is to be provided as part of the development.
- (c) In (b), the term development consent has the meaning given by the Environmental Planning and Assessment Act 1979.
- (d) The Deemed-to-Satisfy Provisions of this Part for thermal breaks apply to all Class 1 buildings and Class 10a buildings with a conditioned space.

### NSW 3.12.1.1 COMPLIANCE WITH BCA PROVISIONS

- (a) Thermal insulation in a building must comply with the national BCA provisions of 3.12.1.1.
- (b) A thermal break must be provided between the external cladding and framing in accordance with national BCA provisions of—
  - (i) 3.12.1.2(c) for a metal framed roof; and
  - (ii) 3.12.1.4(b) for a metal framed wall.
- (c) Compensation for reduction in ceiling insulation must comply with the national BCA provisions of 3.12.1.2(e).
- (d) A floor with an in-slab or in-screed heating or cooling system must comply with the national BCA provisions of—
  - (i) 3.12.1.5(a)(ii), (iii) and (e) for a suspended floor; or
  - (ii) 3.12.1.5(c), (d) and (e) for a concrete slab-on-ground.

## BUILDING SEALING & SERVICES

### NSW 3.12.3 APPLICATION OF NSW PART 3.12.3

- (a) Compliance with NSW 3.12.3.1 satisfies NSW P2.6.1(b) for building sealing.
- (b) NSW Part 3.12.3 is not applicable to—
  - (i) existing buildings being relocated; or
  - (ii) Class 10a buildings—
    - (A) without a conditioned space; or
    - (B) for the accommodation of vehicles; or
  - (iii) parts of buildings that cannot be fully enclosed; or
  - (iv) a permanent building opening, in a space where a gas appliance is located, that is necessary for the safe operation of a gas appliance; or
  - (v) a building in climate zones 2 and 5 where the only means of air-conditioning is by using an evaporative cooler.

### NSW 3.12.3.1 COMPLIANCE WITH BCA PROVISIONS


The sealing of a building must comply with the national BCA provisions 3.12.3.1 to 3.12.3.6.

### NSW 3.12.5 SERVICES: APPLICATION OF NSW PART 3.12.5

- (a) Compliance with NSW 3.12.5.1 satisfies NSW P2.6.2 for services.
- (b) NSW Part 3.12.5 is not applicable to existing services associated with existing buildings being relocated.

### NSW 3.12.5.1 COMPLIANCE WITH BCA PROVISIONS

Services must comply with the national BCA provisions 3.12.5.0 to 3.12.5.3.





# Nationwide House Energy Rating Scheme

## NatHERS Certificate No. NX147388RR

Generated on 22 Jun 2022 using FirstRate5: 5.3.2a (3.21)

### Property

**Address** Lot 14 (#53B) Warriewood Road WARRIEWOOD, Northern Beaches Council, NSW, 2102  
**Lot/DP** 14|1115877  
**NCC Class\*** Class 1a  
**Type** New Home

### Plans

**Main plan** RP 225\_Lot 14 | 22/06/2022  
**Prepared by** Rise Projects

### Construction and environment

Assessed floor area (m <sup>2</sup> )*	Exposure type
Conditioned* 166.5	suburban
Unconditioned* 41.6	<b>NatHERS climate zone</b>
Total 208.1	56 Mascot AMO
Garage 30.2	



### Accredited assessor


**Name** Claude-Francois Sookloll  
**Business name** Energy Advance  
**Email** energy@energyadvance.com.au  
**Phone** 1300 850 228  
**Accreditation No.** DMN/14/1662  
**Assessor Accrediting Organisation** Design Matters National  
**Declaration of interest** Declaration completed: no conflicts

### National Construction Code (NCC) requirements

The NCC's requirements for NatHERS-rated houses are detailed in 3.12.0(a)(i) and 3.12.5 of the NCC Volume Two. For apartments the requirements are detailed in J0.2 and J5 to J8 of the NCC Volume One.

In NCC 2019, these requirements include minimum star ratings and separate heating and cooling load limits that need to be met by buildings and apartments through the NatHERS assessment. Requirements additional to the NatHERS assessment that must also be satisfied include, but are not limited to: insulation installation methods, thermal breaks, building sealing, water heating and pumping, and artificial lighting requirements. The NCC and NatHERS Heating and Cooling Load Limits (Australian Building Codes Board Standard) are available at [www.abcb.gov.au](http://www.abcb.gov.au).

State and territory variations and additions to the NCC may also apply.



### Thermal performance

Heating	Cooling
<b>38.8</b>	<b>25.2</b>
MJ/m <sup>2</sup>	MJ/m <sup>2</sup>

### About the rating

NatHERS software models the expected thermal energy loads using information about the design and construction, climate and common patterns of household use. The software does not take into account appliances, apart from the airflow impacts from ceiling fans.

### Verification

To verify this certificate, scan the QR code or visit <https://www.fr5.com.au/QRCodeLanding?PublicId=NX147388RR> When using either link, ensure you are visiting [www.FR5.com.au](http://www.FR5.com.au).



## Certificate Check

Ensure the dwelling is designed and then built as per the NatHERS Certificate. While you need to check the accuracy of the whole Certificate, the following spot check covers some important items impacting the dwelling's rating.

### Genuine certificate

Does this Certificate match the one available at the web address or QR code in the verification box on the front page?  
Does the set of NatHERS-stamped plans for the dwelling have a Certificate number on the stamp that matches this Certificate?

### Ceiling penetrations\*

Does the 'number' and 'type' of ceiling penetrations (e.g. downlights, exhaust fans, etc) shown on the stamped plans or installed, match what is shown in this Certificate?

### Windows

Does the installed window meet the substitution tolerances (SHGC and U-value) and window type, of the window shown on this Certificate? Substituted values must be based on the Australian Fenestration Rating Council (AFRC) protocol.

### Apartment entrance doors

Does the 'External Door Schedule' show apartment entrance doors? Please note that an "external door" between the modelled dwelling and a shared space, such as an enclosed corridor or foyer, should not be included in the assessment (because it overstates the possible ventilation) and would invalidate the Certificate.

### Exposure\*

Has the appropriate exposure level (terrain) been applied? For example, it is unlikely that a ground-floor apartment is "exposed" or a top floor high-rise apartment is "protected".

### Provisional\* values

Have provisional values been used in the assessment and, if so, noted in "additional notes" below?

## Additional Notes

BCA Climate Zone: 5

Perimeter Insulation has not been included in the modelling of this dwelling

Please note, restricted window openings (%) have been modelled as per NCC 2019 requirements

Eaves indicated by the 'Horizontal shading feature\* maximum projection (mm)' may not be directly opposing the respective wall (i.e. some eaves may be horizontally offset)

Where applicable, an additional 150mm has been added to the projection of all 'Horizontal shading features & eaves' to account for the Gutter & Fascia Board

## Window and glazed door *type and performance*

### Default\* windows

Window ID	Window description	Maximum U-value*	SHGC*	Substitution tolerance ranges	
				SHGC lower limit	SHGC upper limit
No Data Available					

### Custom\* windows

Window ID	Window description	Maximum U-value*	SHGC*	Substitution tolerance ranges	
				SHGC lower limit	SHGC upper limit
DOW-001-01 A	Al Sliding Window SG 3Clr	6.38	0.75	0.71	0.79
DOW-006-01 A	Al Sliding Door SG 5Clr	6.16	0.71	0.67	0.75

## Window and glazed door *Schedule*

\* Refer to glossary.

Location	Window ID	Window no.	Height (mm)	Width (mm)	Window type	Opening %	Orientation	Window shading device*
Bedroom 5/Study	DOW-001-01 A	W6	1400	1800	sliding	45.0	NW	No
Bedroom 5/Study	DOW-006-01 A	D5	2400	1800	sliding	45.0	SW	No
Kitchen/Living/-Dining	DOW-001-01 A	W23	1400	2700	sliding	60.0	NE	No
Kitchen/Living/-Dining	DOW-006-01 A	D2	2400	1780	sliding	45.0	NW	No
Kitchen/Living/-Dining	DOW-006-01 A	D10	2400	3150	other	60.0	NE	No
Kitchen/Living/-Dining	DOW-006-01 A	D3	2400	1780	sliding	45.0	SE	No
Kitchen/Living/-Dining	DOW-001-01 A	W22	1400	2700	sliding	60.0	NE	No
Kitchen/Living/-Dining	DOW-001-01 A	W2	1400	1000	sliding	45.0	NW	No
Kitchen/Living/-Dining	DOW-001-01 A	W3	1400	1000	sliding	45.0	NW	No
Bathroom 1	DOW-001-01 A	W5	1400	1000	sliding	45.0	NW	No
Bedroom 3	DOW-001-01 A	W20	500	1800	sliding	45.0	NW	No
Bedroom 3	DOW-001-01 A	W7	1400	2100	casement	10.0	SW	No
Bedroom 2	DOW-001-01 A	W31	1400	1600	casement	10.0	SW	No
Bedroom 4	DOW-001-01 A	W9	1400	1600	casement	10.0	SW	No
Bedroom 4	DOW-001-01 A	W10	500	1800	sliding	45.0	SE	No
Master Bedroom	DOW-001-01 A	W14	1400	2100	casement	60.0	NE	No
Rumpus	DOW-001-01 A	W17	500	1800	sliding	45.0	NW	No
Rumpus	DOW-001-01 A	W26	1700	1400	sliding	45.0	NW	No
Rumpus	DOW-001-01 A	W16	1400	2700	sliding	60.0	NE	No
Bathroom 2	DOW-001-01 A	W11	500	700	sliding	45.0	SE	No
Bathroom 2	DOW-001-01 A	W12	500	700	sliding	45.0	SE	No
Ensuite	DOW-001-01 A	W13	500	1250	sliding	45.0	NE	No

## Roof window type and performance value

### Default\* roof windows

Window ID	Window description	Maximum U-value*	SHGC*	Substitution tolerance ranges	
				SHGC lower limit	SHGC upper limit
No Data Available					

### Custom\* roof windows

				Substitution tolerance ranges	
Window ID	Window description	Maximum U-value*	SHGC*	SHGC lower limit	SHGC upper limit
No Data Available					



## Roof window *schedule*

Location	Window ID	Window no.	Opening %	Area (m <sup>2</sup> )	Orientation	Outdoor shade	Indoor shade
No Data Available							

## Skylight *type and performance*

Skylight ID	Skylight description
No Data Available	

## Skylight *schedule*

Location	Skylight ID	Skylight No.	Skylight shaft length (mm)	Area (m <sup>2</sup> )	Orient-ation	Outdoor shade	Diffuser	Skylight shaft reflectance
No Data Available								

## External door *schedule*

Location	Height (mm)	Width (mm)	Opening %	Orientation
Garage	2400	4800	100.0	SW
Entry	2340	920	100.0	SW

## External wall *type*

Wall ID	Wall type	Solar absorbance	Wall shade (colour)	Bulk insulation (R-value)	Reflective wall wrap*
1	STANDARD - Framed Slim (Render) - R2.5 Batts	0.5	Medium	Glass fibre batt: R2.5 (R2.5)	No
2	STANDARD - Framed Slim (Generic) - R2.5 Batts	0.5	Medium	Glass fibre batt: R2.5 (R2.5)	No

## External wall *schedule*

Location	Wall ID	Height (mm)	Width (mm)	Orientation	Horizontal shading feature* maximum projection (mm)	Vertical shading feature (yes/no)
Garage	1	2700	158	SW	1400	Yes
Garage	1	2700	5398	SW	1400	Yes
Garage	1	2700	123	SW	1400	Yes
Garage	1	2700	5485	SE	0	Yes
Bedroom 5/Study	2	2700	3499	NW	0	Yes
Bedroom 5/Study	2	2700	3194	SW	1341	Yes
Bedroom 5/Study	2	2700	1115	SE	7651	Yes
Entry	1	2700	1716	SW	2465	Yes
Kitchen/Living/Dining	2	2700	3693	NE	1035	Yes
Kitchen/Living/Dining	2	2700	1994	NW	3270	Yes
Kitchen/Living/Dining	2	2700	3516	NE	3030	Yes
Kitchen/Living/Dining	2	2700	1994	SE	3270	Yes
Kitchen/Living/Dining	2	2700	3600	NE	1035	Yes
Kitchen/Living/Dining	2	2700	5290	NW	0	Yes

Kitchen/Living/Dining	2	2700	279	SW	0	Yes
Kitchen/Living/Dining	1	2700	2295	NW	0	Yes
Kitchen/Living/Dining	2	2700	6389	SE	0	Yes
Bathroom 1	2	2700	1792	NW	0	Yes
Bathroom 1	2	2700	279	NE	0	Yes
Bedroom 3	2	2700	4242	NW	0	Yes
Bedroom 3	2	2700	2992	SW	0	No
Bedroom 3	2	2700	651	SE	0	Yes
Bedroom 2	1	2700	2358	SW	0	Yes
Bedroom 2	2	2700	397	NW	0	Yes
Bedroom 2	2	2700	634	SW	0	No
Bedroom 4	2	2700	2958	SW	0	No
Bedroom 4	2	2700	3989	SE	0	Yes
Master Bedroom	2	2700	3000	NE	0	Yes
Rumpus	2	2700	3287	NW	0	Yes
Rumpus	1	2700	2307	NW	0	Yes
Rumpus	2	2700	4175	NE	0	Yes
Store	2	2700	1048	NW	0	Yes
Bathroom 2	2	2700	3194	SE	0	Yes
Ensuite	2	2700	1766	NE	0	Yes
Ensuite	2	2700	3448	SE	0	Yes

## Internal wall type

Wall ID	Wall type	Area (m <sup>2</sup> )	Bulk insulation
1	STANDARD - Internal Stud Walls -R2.5 Batts	174.1	Glass fibre batt: R2.5 (R2.5)

## Floor type

Location	Construction	Area (m <sup>2</sup> )	Sub-floor ventilation	Added insulation (R-value)	Covering
Garage	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	7.3	Enclosed	R0.0	none
Garage	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	22.9	Enclosed	R0.0	none
Bedroom 5/Study	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	11.2	Enclosed	R0.0	Timber
Entry	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	10.8	Enclosed	R0.0	Timber
Kitchen/Living/Dining	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	45.4	Enclosed	R0.0	Timber
Kitchen/Living/Dining	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	6.5	Enclosed	R0.0	Timber
Kitchen/Living/Dining	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	12.8	Enclosed	R0.0	Timber
Bathroom 1	FR5 - 225mm waffle pod, 85mm concrete (R0.60)	5.7	Enclosed	R0.0	Tiles
Bedroom 3	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	12.7	Enclosed	R4.0	Carpet
Bedroom 2	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	9.7	Enclosed	R4.0	Carpet

Bedroom 2	FLOOR - Framed External Suspended Floor (R4.0 Insulation)	1.3	Elevated	R4.0	Carpet
Bedroom 4	FLOOR - Framed External Suspended Floor (R4.0 Insulation)	2.2	Elevated	R4.0	Carpet
Bedroom 4	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	9.6	Enclosed	R4.0	Carpet
Master Bedroom	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	12.2	Enclosed	R4.0	Carpet
WIR	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	3.9	Enclosed	R4.0	Carpet
Rumpus	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	29.2	Enclosed	R4.0	Timber
Store	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	1.9	Enclosed	R4.0	Timber
Bathroom 2	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	5.6	Enclosed	R4.0	Tiles
Ensuite	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	6.1	Enclosed	R4.0	Tiles

## Ceiling type

Location	Construction material/type	Bulk insulation R-value (may include edge batt values)	Reflective wrap*
Garage	Plasterboard	R0.0	Yes
Garage	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	R4.0	No
Bedroom 5/Study	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	R4.0	No
Entry	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	R4.0	No
Kitchen/Living/Dining	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	R4.0	No
Kitchen/Living/Dining	Plasterboard	R6.0	Yes
Kitchen/Living/Dining	Plasterboard	R6.0	Yes
Bathroom 1	FLOOR - Framed Internal Suspended Floor (R4.0 Insulation)	R4.0	No
Bedroom 3	Plasterboard	R6.0	Yes
Bedroom 2	Plasterboard	R6.0	Yes
Bedroom 2	Plasterboard	R6.0	Yes
Bedroom 4	Plasterboard	R6.0	Yes
Bedroom 4	Plasterboard	R6.0	Yes
Master Bedroom	Plasterboard	R6.0	Yes
WIR	Plasterboard	R6.0	Yes
Rumpus	Plasterboard	R6.0	Yes
Store	Plasterboard	R6.0	Yes
Bathroom 2	Plasterboard	R6.0	Yes

Ensuite	Plasterboard	R6.0	Yes
---------	--------------	------	-----

### Ceiling penetrations\*

Location	Quantity	Type	Diameter (mm)	Sealed/unsealed
Kitchen/Living/Dining	1	Exhaust Fans	185	Sealed
Bathroom 1	1	Exhaust Fans	250	Sealed
Bathroom 2	1	Exhaust Fans	250	Sealed
Ensuite	1	Exhaust Fans	250	Sealed

### Ceiling fans

Location	Quantity	Diameter (mm)
Bedroom 5/Study	1	1400
Bedroom 3	1	1400
Bedroom 2	1	1400
Bedroom 4	1	1400
Master Bedroom	1	1400
Rumpus	1	1400

### Roof type

Construction	Added insulation (R-value)	Solar absorptance	Roof shade
Cont:Attic-Continuous	1.3	0.32	Light

## Explanatory Notes

### About this report

A NatHERS rating is a comprehensive, dynamic computer modelling evaluation of a home, using the floorplans, elevations and specifications to estimate an energy load. It addresses the building layout, orientation and fabric (i.e. walls, windows, floors, roofs and ceilings), but does not cover the water or energy use of appliances or energy production of solar panels.

Ratings are based on a unique climate zone where the home is located and are generated using standard assumptions, including occupancy patterns and thermostat settings. The actual energy consumption of a home may vary significantly from the predicted energy load, as the assumptions used in the rating will not match actual usage patterns. For example, the number of occupants and personal heating or cooling preferences will vary.

While the figures are an indicative guide to energy use, they can be used as a reliable guide for comparing different dwelling designs and to demonstrate that the design meets the energy efficiency requirements in the National Construction Code. Homes that are energy efficient use less energy, are warmer on cool days, cooler on hot days and cost less to run. The higher the star rating the more thermally efficient the dwelling is.

### Accredited assessors

To ensure the NatHERS Certificate is of a high quality, always use an accredited or licenced assessor. NatHERS accredited assessors are members of a professional body called an Assessor Accrediting Organisation (AAO).

Australian Capital Territory (ACT) licensed assessors may only produce assessments for regulatory purposes using software for which they have a licence endorsement. Licence endorsements can be confirmed on the ACT licensing register

AAOs have specific quality assurance processes in place, and continuing professional development requirements, to maintain a high and consistent standard of assessments across the country. Non-accredited assessors do not have this level of quality assurance or any ongoing training requirements.

Any questions or concerns about this report should be directed to the assessor in the first instance. If the assessor is unable to address these questions or concerns, the AAO specified on the front of this certificate should be contacted.

### Disclaimer

The format of the NatHERS Certificate was developed by the NatHERS Administrator. However the content of each individual certificate is entered and created by the assessor to create a NatHERS Certificate. It is the responsibility of the assessor who prepared this certificate to use NatHERS accredited software correctly and follow the NatHERS Technical Notes to produce a NatHERS Certificate.

The predicted annual energy load in this NatHERS Certificate is an estimate based on an assessment of the building by the assessor. It is not a prediction of actual energy use, but may be used to compare how other buildings are likely to perform when used in a similar way. Information presented in this report relies on a range of standard assumptions (both embedded in NatHERS accredited software and made by the assessor who prepared this report), including assumptions about occupancy, indoor air temperature and local climate.

Not all assumptions that may have been made by the assessor while using the NatHERS accredited software tool are presented in this report and further details or data files may be available from the assessor.

## Glossary

<b>Annual energy load</b>	the predicted amount of energy required for heating and cooling, based on standard occupancy assumptions.
<b>Assessed floor area</b>	the floor area modelled in the software for the purpose of the NatHERS assessment. Note, this may not be consistent with the floor area in the design documents.
<b>Ceiling penetrations</b>	features that require a penetration to the ceiling, including downlights, vents, exhaust fans, rangehoods, chimneys and flues. Excludes fixtures attached to the ceiling with small holes through the ceiling for wiring, e.g. ceiling fans; pendant lights, and heating and cooling ducts.
<b>Conditioned</b>	a zone within a dwelling that is expected to require heating and cooling based on standard occupancy assumptions. In some circumstances it will include garages.
<b>Custom windows</b>	windows listed in NatHERS software that are available on the market in Australia and have a WERS (Window Energy Rating Scheme) rating.
<b>Default windows</b>	windows that are representative of a specific type of window product and whose properties have been derived by statistical methods.
<b>Entrance door</b>	these signify ventilation benefits in the modelling software and must not be modelled as a door when opening to a minimally ventilated corridor in a Class 2 building.
<b>Exposure category - exposed</b>	terrain with no obstructions e.g. flat grazing land, ocean-frontage, desert, exposed high-rise unit (usually above 10 floors).
<b>Exposure category - open</b>	terrain with few obstructions at a similar height e.g. grasslands with few well scattered obstructions below 10m, farmland with scattered sheds, lightly vegetated bush blocks, elevated units (e.g. above 3 floors).
<b>Exposure category - suburban</b>	terrain with numerous, closely spaced obstructions below 10m e.g. suburban housing, heavily vegetated bushland areas.
<b>Exposure category - protected</b>	terrain with numerous, closely spaced obstructions over 10 m e.g. city and industrial areas.
<b>Horizontal shading feature</b>	provides shading to the building in the horizontal plane, e.g. eaves, verandahs, pergolas, carports, or overhangs or balconies from upper levels.



<b>National Construction Code (NCC) Class</b>	the NCC groups buildings by their function and use, and assigns a classification code. NatHERS software models NCC Class 1, 2 or 4 buildings and attached Class 10a buildings. Definitions can be found at <a href="http://www.abcb.gov.au">www.abcb.gov.au</a> .
<b>Opening Percentage</b>	the openability percentage or operable (moveable) area of doors or windows that is used in ventilation calculations.
<b>Provisional value</b>	an assumed value that does not represent an actual value. For example, if the wall colour is unspecified in the documentation, a provisional value of 'medium' must be modelled. Acceptable provisional values are outlined in the NatHERS Technical Note and can be found at <a href="http://www.nathers.gov.au">www.nathers.gov.au</a>
<b>Reflective wrap</b> (also known as foil)	can be applied to walls, roofs and ceilings. When combined with an appropriate airgap and emissivity value, it provides insulative properties.
<b>Roof window</b>	for NatHERS this is typically an operable window (i.e. can be opened), will have a plaster or similar light well if there is an attic space, and generally does not have a diffuser.
<b>Shading device</b>	a device fixed to windows that provides shading e.g. window awnings or screens but excludes eaves.
<b>Shading features</b>	includes neighbouring buildings, fences, and wing walls, but excludes eaves.
<b>Solar heat gain coefficient (SHGC)</b>	the fraction of incident solar radiation admitted through a window, both directly transmitted as well as absorbed and subsequently released inward. SHGC is expressed as a number between 0 and 1. The lower a window's SHGC, the less solar heat it transmits.
<b>Skylight</b> (also known as roof lights)	for NatHERS this is typically a moulded unit with flexible reflective tubing (light well) and a diffuser at ceiling level.
<b>U-value</b>	the rate of heat transfer through a window. The lower the U-value, the better the insulating ability.
<b>Unconditioned</b>	a zone within a dwelling that is assumed to not require heating and cooling based on standard occupancy assumptions.
<b>Vertical shading features</b>	provides shading to the building in the vertical plane and can be parallel or perpendicular to the subject wall/window. Includes privacy screens, other walls in the building (wing walls), fences, other buildings, vegetation (protected or listed heritage trees).


# DEVELOPMENT APPLICATION

## TWO STORY DWELLING

LOT14 - 53B WARRIEWOOD ROAD, WARRIEWOOD 2102 NSW

Sheet List LOT 14			Sheet List LOT 14		
Sheet No.	Sheet Name	Rev.	Sheet No.	Sheet Name	Rev.
DA14.00	COVER PAGE	A	DA14.05.1	SHADOW STUDY GROUND FLOOR	A
DA14.01	SITE ANALYSIS	A	DA14.05.2	SHADOW STUDY FIRST FLOOR	A
DA14.02	SITE PLAN	A	DA14.05.4	LANDSCAPE PLAN	A
DA14.03.1	FLOOR PLANS	A	DA14.05.5	STORMWATER MANAGEMENT PLANS	A
DA14.03.2	ELEVATIONS	A			
DA14.03.3	SECTIONS	A			
DA14.04	MATERIAL BOARD	A			

[illegible]



08/06/22	A	FOR DA LODGEMEN
<b>Date</b>	<b>RV</b>	<b>Description</b>



**RISE PROJECTS**

DRAWN BY: A.D | CHECKED: A

VIEW:

JOB No : <b>RP 225</b>	NORTH:
---------------------------	--------

SCALE :


DATE: \_\_\_\_\_

08/06/22	
----------	--

DW No.	REV:
--------	------


DA14.01	A
---------	---






ADDRESS:  
LOT 14 - 53B  
WARRIEWOOD ROAD,  
WARRIEWOOD

JOB No.: <b>RP 225</b>	NORTH: 
SCALE: A1/1:50	
DATE: 08/06/22	
DW No. <b>DA14.02</b>	REV: <b>A</b>



**1 GROUND FLOOR**  
1 : 50



## 2 FIRST FLOOR

AREA SCHEDULE TYPE 8	
Name	Area
GROUND FLOOR	92 m <sup>2</sup>
FIRST FLOOR	100 m <sup>2</sup>
	192 m <sup>2</sup>
GARAGE	30 m <sup>2</sup>
	30 m <sup>2</sup>
Grand total	222 m <sup>2</sup>

[illegible]

3/06/22	A	FOR DA LODGEMENT
<b>Date</b>	<b>RV</b>	<b>Description</b>

All plans and drawing are copyright of RISE PROJECTS Pty Ltd.  
Any attempt in using or reproducing or copying the same, wholly or in part, without prior written permission from RISE will result in legal proceeding.




**ADDRESS:**  
7/6-8 Herbert Street, St Leonards NSW 2065  
**H:** (02) 8094 1209  
**BN:** 79 160 683 929  
**WEBSITE:** [www.riseprojects.com.au](http://www.riseprojects.com.au)

DRAWN BY: A.D | CHECKED: A.S

ADDRESS:  
LOT 14 - 53B  
WARRIEWOOD ROAD,  
WARRIEWOOD


VIEW:

## FLOOR PLANS

JOB No.: <b>RP 225</b> SCALE: A1/1:50 DATE: 08/06/22	NORTH: 
W No. <b>DA14.03.1</b>	REV: <b>A</b>

BIM 360://Warlewod - 538 Warlewod Rd,DA\_CENTRAL.MT





- 1 - WARM COLOUR WEATHERBOARD CLADDING
- 2 - EXTERNAL STONE WALL
- 3 - WARM COLOUR RENDER WALL
- 4 - PAINTED TIMBER POST
- 5 - METAL ROOF
- 6 - PANEL LIFT GARAGE DOOR
- 7 - METAL ROOF - LIGHT COLOUR
- 8 - WHITE BATTEN GABLE CLADDING

[illegible]

06/22	A	FOR DA LODGEMENT
Date	RV	Description

Plans and drawing are copyright of RISE PROJECTS Pty Ltd.

Any attempt in using or reproducing or copying the same, wholly or in part, without prior written permission from RISE will result in legal proceeding.






**ADDRESS:**  
16/6-8 Herbert Street, St Leonards NSW 2065  
T: (02) 8094 1209  
F: 79 160 683 929  
WEBSITE: [www.riseprojects.com.au](http://www.riseprojects.com.au)

AWN BY: A.D CHECKED: A.S

ADDRESS:  
LOT 14 - 53B  
WARRIEWOOD ROAD,  
WARRIEWOOD

VIEW:

DB No : <b>RP 225</b>	NORTH:
SCALE : A1/ 1 : 50	
DATE: 08/06/22	
DW No. <b>A14.03.2</b>	REV: <b>A</b>

[illegible]

Date	RV	Description
3/06/22	A	FOR DA LODGEMENT

All plans and drawings are copyright of RISE  
 ROJECTS Pty Ltd.  
 Any attempt in using or reproducing or copying the  
 same, wholly or in part, without prior written  
 permission from RISE will result in legal proceedings.



**DDRESS:**  
7/6-8 Herbert Street, St Leonards NSW 2065  
**H:** (02) 8094 1209  
**BN:** 79 160 683 929  
**WEBSITE:** [www.riseprojects.com.au](http://www.riseprojects.com.au)

DRAWN BY: A.D. CHECKED: A

ADDRESS:  
LOT 14 - 53B  
WARRIEWOOD ROAD,  
WARRIEWOOD

## VIEW:








### SECTIONS

JOB No : <b>RP 225</b>	NORTH:
SCALE : A1/As indicated	
DATE: 08/06/22	
DW No. <b>DA14.03.3</b>	REV: <b>A</b>







[illegible]

06/22	A	FOR DA LODGEMENT
<b>Date</b>	<b>RV</b>	<b>Description</b>

Plans and drawing are copyright of RISE PROJECTS Pty Ltd.  
Any attempt in using or reproducing or copying the same, wholly or in part, without prior written permission from RISE will result in legal proceeding.




**ADDRESS:**  
/6-8 Herbert Street, St Leonards NSW 2065  
**T:** (02) 8094 1209  
**F:** 79 160 683 929  
**WEBSITE:** [www.riseprojects.com.au](http://www.riseprojects.com.au)


AWN BY: A.D | CHECKED: A

ADDRESS:  
LOT 14 - 53B  
WARRIEWOOD ROAD,  
WARRIEWOOD


## VIEW:

### SHADOW STUDY GROUND FLOOR


DB No : <b>RP 225</b> SCALE : <b>A1/</b> DATE : <b>08/06/22</b>	NORTH: 
W No. <b>A14.05.1</b>	REV: <b>A</b>




1 FF 21/JUN 9AM




2 FF 21/JUN 10AM




3 FF 21/JUN 11AM




4 FF 21/JUN 12PM



5 FF 21/JUN 1PM



6 FF 21/JUN 2PM



7 FF 21/JUN 3PM

[illegible]

8/06/22	A	FOR DA LODGEMENT
<b>Date</b>	<b>RV</b>	<b>Description</b>

All plans and drawing are copyright of RISE PROJECTS Pty Ltd.  
Any attempt in using or reproducing or copying the same, wholly or in part, without prior written permission from RISE will result in legal proceedings.



**ADDRESS:**  
57/6-8 Herbert Street, St Leonards NSW 2065  
**PH:** (02) 8094 1209  
**ABN:** 79 160 683 929  
**WEBSITE:** [www.riseprojects.com.au](http://www.riseprojects.com.au)

DRAWN BY: A.D. CHECKED: A

ADDRESS: \_\_\_\_\_

LOT 14 53B

LOT 4 - 33B  
WARRIEWOOD ROAD,  
WARRIEWOOD

---


VIEW:

## SHADOW STUDY FIRST FLOOR

TABLE 1. Continued


IOB No :	NORTH:
----------	--------

RP 225

SCALE : A1/ 







08/06/22	A	FOR DA LODGEMEN
<b>Date</b>	<b>RV</b>	<b>Description</b>




DRAWN BY: A.D CHECKED: A

VIEW:

JOB No : <b>BB 225</b>	NORTH:
---------------------------	--------

SCALE :  $A1/1:50$


DATE: 

08/06/22	
DW No.	REV:


DA14.05.4 A

BLM 360 // Warlewod - 538 Warlewod Rd/DA\_CENTRAL.mt

LANDSCAPE SCHEDULE - LOT 14			
LOT NO.	LANDSCAPE	LOT AREA	%
LOT 14	83 m <sup>2</sup>	255 m <sup>2</sup>	32.61%



## 1 GROUND FLOOR



**2 FIRST FLOOR**  
1 : 50

[illegible]

8/06/22	A	FOR DA LODGEMEN
<b>Date</b>	<b>RV</b>	<b>Description</b>

All plans and drawing are copyright of RISE PROJECTS Pty Ltd.  
Any attempt in using or reproducing or copying the same, wholly or in part, without prior written permission from RISE will result in legal proceedings.



**ADDRESS:**  
676-8 Herbert Street, St Leonards NSW 2065  
**PH:** (02) 8094 1209  
**FAX:** (02) 8094 1209  
**ABN:** 79 160 683 929  
**WEBSITE:** [www.riseprojects.com.au](http://www.riseprojects.com.au)

DRAWN BY: A.D. CHECKED: A


ADDRESS:  
**Designer**


VIEW:  
**STORMWATER  
MANAGEMENT  
PLANS**

JOB No : <b>RP 225</b>	NORTH:
---------------------------	--------

SCALE : A1/1 : 50

DATE: \_\_\_\_\_



08/06/22	
OW No	REV: