

# TREE PROTECTION SPECIFICATION

REF: L&Co25006 | 3 September 2025 | v3.1 SITE ADDRESS | 154 Plateau Rd, Bilgola Plateau PREPARED FOR | Asri Halis c/o ERA PREPARED BY | Ms Emma Clark Dr Matthew Laurence BSc. (Hons) BA (Hons) PhD (Plant Pathology) Grad Cert (Arboriculture)

info@laurenceco.com.au

0404 282 825

ABN: 61 625 300 530

1.0	EXECUTIVE SUMMARY	2
2.0	INTRODUCTION	3
3.0	RESULTS	3
4.0	ARBORICULTURAL IMPACT ASSESSMENT	4
5.0	REFERENCES	8
6.0	APPENDIX 1   METHODOLOGY	9
7.0	APPENDIX 2   TREE ASSESSMENT SCHEDULE	13
8.0	APPENDIX 3   TREE LOCATION PLAN	18
9.0	APPENDIX 4   PROPOSED DEVELOPMENT PLANS	19
10.0	APPENDIX 5   ARBORICULTURAL IMPACT ASSESSMENT PLANS	
11.0	APPENDIX 6   TREE PROTECTION PLAN	32
12.0	APPENDIX 7   TYPICAL TREE PROTECTION DETAIL	
13.0	APPENDIX 8   TREE PROTECTION SPECIFICATION	37
14.0	APPENDIX 9   PLATES	40
15.0	APPENDIX 10 I LIMITATIONS & DISCLAIMERS	



# 1.0 EXECUTIVE SUMMARY |

- The proposal, outlined in the supplied plans, shows the demolition of some existing structures and alterations and additions to the existing residential dwelling including construction of a deck, retaining walls, pool, shed, cabana and associated landscaping at 154 Plateau Rd, Bilgola Plateau. The plans also include a garage and demolition of existing structures at the front of the property.
- 1.2 A total of thirty (30) trees were assessed that were a mix of Australian native and exotic species. Trees 16, 22, 27, 28, 29 & 30 were located on adjacent properties and were assigned Retention Values of Priority for Retention.
- 1.3 The supplied plans show no works are proposed within the TPZs of Trees 8, 10, 11, 13, 16, 23, 24, 25, 27, 28, 29 & 30. However, the tree protection measures outlined in this report should be implemented to avoid indirect impacts.
- 1.4 The proposed works are within the TPZ's Trees 9, 15 & 26 and represent and *Minor* Encroachment as defined by AS4970 and is considered acceptable by the standard when it is compensated for elsewhere and contiguous within the TPZ, as in the current case. Trees 9, 15 & 26 can be retained under the current proposal if the tree protection measures are implemented under the supervision of the Project Arborist.
- 1.5 The proposed works are within the SRZs & TPZ's of Trees 1, 2, 5, 7, 14, 17, 18, 19, 20, & 21 and represent a *Major Encroachment* (as defined by AS4970). Trees 1, 2, 5, 7, 14, 17, 18, 19, 20 & 21 will need to be removed as the TPZ encroachment is too large for their long-term viability, based on a consideration of their health, structure and the size of the encroachment. These trees were all assigned Low to Moderate Landscape Significance Values except for Tree 7, which was assigned a High Landscape Significance Values
- 1.6 Trees 3, 4, 6 & 12 are within the footprint of demolition and construction of the proposed front deck, driveway, planter and pool respectively and will need to be removed. Tree 12 was assigned High Landscape Significance Value.
- 1.7 The location of the underground services was not detailed in the supplied plans. The installation of underground services should be located outside of the TPZs detailed in this report. Where this is not possible, they should be installed around or below roots (>25mmØ) using either hydrovac or hand excavation and supervised by the Project Arborist.



## 2.0 INTRODUCTION |

# 2.1 **Background**

- 2.1.1 This Arboricultural Impact Assessment and Tree Protection Specification Report was prepared for Asri Halis c/o ERA in relation to the proposed development of 154 Plateau Rd, Bilgola Plateau. This report has determined the impact of the proposed works on the trees at 154 Plateau Rd, Bilgola Plateau and neighbouring properties and where appropriate, has provided tree sensitive construction methods to minimise negative impacts to the trees.
- 2.1.2 In preparing this report, the author is aware of and has considered the objectives of the Northern Beaches Council (Pittwater)'s Pittwater 21 Development Plan Part B4.22 Preservation of Trees and Bushland Vegetation (2004), Pittwater Local Environment Plan (2014), Australian Standard 4970 Protection of Trees on Development Sites (2009), Australian Standard 4373 Pruning of Amenity Trees (2007) and Safe Work Australia Guide for Managing Risks of Tree Trimming and Removal Work (2016).
- 2.1.3 Further methodology used in the preparation of this report is detailed in Appendix 1.
- 2.1.4 This Arboricultural Impact Assessment was based on an assessment of the following supplied documentation/plans only (Appendix 4):
  - Demolition Plan Prepared by ERA Architects Dated 28.08.2025
  - Site and Roof Plan Main Dwelling Prepared by ERA Architects. Dated 28.08.2025
  - Site and Roof Plan Detached Cabana Prepared by ERA Architects. Dated 28.08.2025
  - Landscape Plan Prepared by ERA Architects. Dated 28.082025
  - Erosion and Sediment Control Plan Prepared by ERA architects. Dated 28.08.2025
  - Siteworks Cut/Fill Plan Prepared by ERA architects. Dated 28.08.2025
  - E/04 North Eastern Elevation (Main Dwelling) Prepared by ERA architects. Dated 28.08.2025
  - Sections S/01 (Main Dwelling + Detached Cabana/Shed) Prepared by ERA architects. Dated 28.08.2025
  - Southeast/West Elevations (Detached Cabana/Shed) Prepared by ERA architects. Dated 28.08.2025
  - North/South Elevations (Detached Garage) Prepared by ERA architects. Dated 28.08.2025
  - Detail Survey. Prepared by Metropolis City Surveyors. Dated 22.08.2024.

## 2.2 The Proposal

2.2.1 The supplied plans show the shows the demolition of some existing structures and alterations and additions to the existing residential dwelling including construction of a deck, retaining walls, pool, shed, cabana and associated landscaping at 154 Plateau Rd, Bilgola Plateau. The plans also include a garage and demolition of existing structures at the front of the property.

## 3.0 RESULTS I

- 3.1 The Site
- 3.1.1 The site is a rectangular block with a total area stated in the plans as 899.4m<sup>2</sup>. The site has a fall from east to west.
- 3.1.2 The site is bounded by residential properties to the north, south and west with Plateau Road to the east.
- 3.2 The Trees
- 3.2.1 A Visual Tree Assessment (VTA) (Mattheck & Breloer, 2003) has been undertaken on trees growing within the site to determine their health and structural condition (Appendix 2). A full VTA of trees located outside of the site boundaries was not undertaken due to limited access. The species and trunk diameter were recorded for the purposes of determining Tree Protection Zone (TPZ) and Structural Root Zone (SRZ) calculations only. The distance of each tree from the site boundary is an approximation due to limited access.



- 3.2.2 The Australian Standard 4970: *Protection of Trees on Development Sites* (2009) Clause 2.3.2, requires the allocation of a Tree Retention Value. This value is based on the Useful Life Expectancy (ULE) and Landscape Significance, which considers the tree's health, structural condition and site suitability. The Retention Value does not consider any proposed development works and is not a schedule for tree retention or removal. The trees have been allocated one of the following Retention Values:
  - Priority for Retention
  - Consider for Retention
  - Consider for Removal
  - Priority for Removal
- 3.2.3 The Australian Standard 4970: *Protection of Trees on Development Sites* (2009) also requires the calculation of the Tree Protection Zone (TPZ) and Structural Root Zone (SRZ) for each tree (Appendix 1).
- 3.2.4 A total of thirty (30) trees were assessed which were a mix of Australian native and exotic species.
- 3.2.5 A search of the BioNet Atlas of NSW Wildlife Database was undertaken during May 2025. No individual threatened tree species that were listed within this database for the area were identified during the current field investigations of the site. The ecological significance and habitat value of the trees has not been assessed and is beyond the scope of this report.
- 3.2.6 Trees 1, 2, 3, 4, 7, 9, 10, 11, 12, 13, 14, 17 & 25 were within the site boundary and covered by the council's tree management controls.
- 3.2.7 Trees 5, 6, 8, 15, 18, 19, 20, 21, 23, 24 & 26 are exempt from the Council's tree management controls.
- 3.2.8 Trees 16, 22, 27, 28, 29 & 30 were located on adjacent properties. All trees on adjacent properties were allocated a Retention Value of *Priority for Retention*.
- 4.0 ARBORICULTURAL IMPACT ASSESSMENT |
- 4.1 Trees 1, 3 & 4
- 4.1.1 Trees 1, 3 & 4 were identified as *Eucalyptus racemosa* (Scribbly Gum), *Eucalyptus robusta* (Swamp Mahogany), *Callistemon viminalis* (Weeping Bottlebrush), *Acacia* sp. (Wattle), respectively and were allocated Low Landscape Significance Values and Retention Values of *Consider for Removal*, excepting Tree 1 which was assigned a Moderate Landscape Significance Value, and Retention Value of *Priority for Removal*.
- 4.1.2 Tree 1 was allocated a poor structural rating due to a large cavity at the base of the trunk. The column of decay associated with the cavity is likely to extend above and below the opening. However, internal investigations on the extent of the decay column were beyond the scope of this report. The main trunk cavity represents a point of structural weakness and given the size of the cavity, poor tree vigour, the species and the likelihood of decay progression, the tree is considered to be structurally compromised and tree removal should be considered from a tree stability and short ULE perspective.
- 4.1.3 The supplied pans show Trees 3 & 4 are in the footprint of garage and associated work at the front of the property and will need to be removed.
- 4.1.4 The supplied plans show the proposed demolition of the existing driveway is within the TPZ and SRZ of Tree 1. Works within the SRZ represent a *Major Encroachment* as defined by AS-4970 as root severance within the SRZ can lead to the destabilisation of the tree. The overall TPZ encroachments were estimated to be 23.1% and also represent *Major Encroachments* as defined by AS-4970.
- 4.1.5 Given the size and location of the encroachment, the long term structural and physiological viability of Tree 1 is highly likely to be compromised by the proposed encroachment, and the tree will need to be removed to accommodate the works.
- 4.1.6 Removal and replacement with healthy advanced size specimens would replace the loss of amenity within a short to medium, timeframe.
- 4.1.7 Refer to Appendix 5 for further detail.
- 4.2 Tree 2
- 4.2.1 Tree 2 was identified as a Eucalyptus robusta (Swamp Mahogany) and was allocated a Low Landscape Significance Value and Retention Value of Consider for Removal.
- 4.2.2 The supplied plans show the proposed carport works is within the SRZ of Tree 2. The overall TPZ encroachment was estimated to be 24.1% and also represent *Major Encroachments* as defined by AS-4970.
- 4.2.3 Given the size and location of the encroachments, the long term structural and physiological viability of Tree 2 is highly likely to be compromised by the proposed encroachment, and the tree will need to be removed to accommodate the works.
- 4.2.4 Removal and replacement with healthy advanced size specimens would replace the loss of amenity within a short to medium timeframe.
  - Refer to Appendix 5 for further detail



## 4.3 Trees 5, 6 & 7

- 4.3.1 Trees 5, 6 & 7 were identified as *Archontophoenix cunninghamiana* (Bangalow Palm), *Syzygium paniculatum* (Brush Cherry) and *Angophora floribunda* (Rough Barked Apple) respectively, and were allocated Low Landscape Significance Values and Retention Values of *Consider for Removal or Priority for removal*, excepting Tree 7 which was assigned a High Landscape Significance Value and a Retention Value of *Priority for Retention*.
- 4.3.2 Tree 5 is exempt from the Council's Tree Management controls based on species and can be removed without Council consent.
- 4.3.3 The supplied plans show the proposed planter and residential dwelling are within the TPZs and SRZs of Trees 5, 6 & 7. Works within the SRZ represent a *Major Encroachment* as defined by AS-4970 as root severance within the SRZ can lead to the destabilisation of the tree. The overall TPZ encroachments were estimated to be 56.3%, 61.4% and 25.9% and also represent *Major Encroachments* as defined by AS-4970.
- 4.3.4 Given the size and location of the encroachments, the long term structural and physiological viability of Trees 5, 6 & 7 are highly likely to be compromised by the proposed encroachment, and the trees will need to be removed to accommodate the works.
- 4.3.5 Removal and replacement with healthy advanced size specimens would replace the loss of amenity within a short to medium, timeframe.
- 4.3.6 Refer to Appendix 5 for further detail.
- 4.4 Trees 8, 10, 11, 13, 16, 23, 24, 25, 27, 28, 29 & 30
- 4.4.1 Trees 8, 10, 11, 13, 16, 23, 24, 25, 27, 28, 29 & 30 are mature to senescent trees and were allocated a low Landscape Significance Value and a Retention Value of Consider for Removal and Consider for Retention. Refer to Appendix 2 for species identifications and further detail.
- 4.4.2 Trees 8, 23, 24, 27, 28 & 29 are exempt from the Council's Tree Management controls based on species and can be removed without Council consent.
- 4.4.3 The supplied plans show no works are proposed within the TPZ of Trees 8, 10, 11, 13, 16, 23, 24, 25, 27, 28, 29 & 30. However, the following tree protection should be installed to avoid indirect impacts.
- 4.4.4 TPZ fencing should be installed prior to any site works (including demolition) and remain in place for the duration of the demolition and construction processes.
- 4.4.5 The area within the TPZ fencing should be mulched to a depth of 50mm with a non-toxic product (i.e. woodchips) with no fines.
- 4.4.6 Coir logs should be installed on the perimeter of the TPZ fencing to prevent runoff from the building works into the TPZ.
- 4.4.7 Materials, waste storage and temporary services should not be located within the TPZ fenced area. If works are required within the TPZ fenced area, then they should be supervised by the Project Arborist.
- 4.4.8 The tree protection measures must be inspected by the Project Arborist prior to the start prior of site works, including demolition.
- 4.4.9 Refer to AS4970 and Appendices 5, 6, 7 & 8 for further details for further details
- 4.5 **Tree 9**
- 4.5.1 Tree 9 was identified as *Angophora floribunda* (Rough Barked Apple) and were allocated High Landscape Significance Values and Retention Values of *Priority for Retention*.
- 4.5.2 The supplied plans show the proposed cabana works is within the TPZ of Tree 9 which represents a *Minor Encroachment*. The overall TPZ encroachment is approximately 2.2%. However, Clause 3.3.4 of AS-4970 does allow for major encroachments if design factors (e.g. tree sensitive construction methods) are used to minimise negative impacts.
- 4.5.3 Refer to Appendix 5 for further detail.
- 4.5.4 Given the good physiological condition and species of the tree the proposed development can be accommodated. However, given the size of encroachment the proposal represents a significant risk to the tree's long term structural and physiological viability and therefore the following tree sensitive construction methods and protection measures are carefully implemented under the supervision of the Project Arborist. Significant departures from the detailed tree sensitive construction methods and protection measures are likely to result in a shortened ULE and/or tree removal
- 4.5.5 TPZ fencing should be installed prior to any site works (including demolition) and remain in place for the duration of the demolition and construction processes.
- 4.5.6 The area within the TPZ fencing should be mulched to a depth of 50mm with a non-toxic product (i.e. woodchips) with no fines.
- 4.5.7 Coir logs should be installed on the perimeter of the TPZ fencing to prevent runoff from the building works into the TPZ.
- 4.5.8 Materials, waste storage and temporary services should not be located within the TPZ fenced area. If works are required within the TPZ fenced area, then they should be supervised by the Project Arborist.



- 4.5.9 The tree protection measures must be inspected by the Project Arborist prior to the start prior of site works, including demolition.
- 4.5.10 Refer to AS4970 and Appendices 5, 6, 7 & 8 for further details for further details.
- 4.6 Tree 12
- 4.6.1 Tree 12 was identified as *Angophora costata* (Sydney Red Gum) and was allocated a High Landscape Significance Value and a Retention Value of *Consider for Retention*.
- 4.6.2 The supplied plans show that Tree 12 is within the footprint of the proposed pool and will need to be removed.
- 4.6.1 The Tree was allocated a poor structural rating due to a large cavity on the main trunk (Appendix 9). The column of decay associated with the cavity is likely to extend above and below the opening. However, internal investigations on the extent of the decay column were beyond the scope of this Report.
- 4.6.2 A cavity of this size is unlikely to fully occlude, and the prognosis is for further decay over the medium term
- 4.6.3 Removal and replacement with a healthy advanced size specimen would replace the loss of amenity within a long timeframe.
- 4.6.4 Refer to Appendix 5 for further detail.
- 4.7 Trees 15 & 22
- 4.7.1 Trees 15 & 22 were identified as *Syzygium australe* (Brush Cherry Lilly Pilly) and *Cyathea australis* (Rough Tree Fern) and were allocated Moderate Landscape Significance Values and Retention Values of *Consider for Retention*.
- 4.7.2 The supplied plans show the proposed cabana works is within the TPZs of Trees 15 & 22 which represents a *Minor Encroachment*. The overall TPZ encroachment is approximately 4.8% and 0.8% respectively. However, Clause 3.3.4 of AS-4970 does allow for major encroachments if design factors (e.g. tree sensitive construction methods) are used to minimise negative impacts.
- 4.7.3 Refer to Appendix 5 for further detail.
- 4.7.4 However, TPZ fencing should be installed prior to any site works (including demolition) and remain in place for the duration of the construction. Materials, waste storage and temporary services should not be located within the TPZ fenced area. If works are required within the TPZ fenced area, then they should be supervised by the Project Arborist.
- 4.7.5 The tree protection measures must be inspected by the Project Arborist prior to the start of site works, including demolition.
- 4.7.6 Refer to AS4970 and Appendices 5, 6 & 7 for further details.
- 4.8 Trees 14, 17, 18, 19, 20 & 21
- 4.9 Trees 14, 17, 18, 19, 20 & 21 are semi-mature to mature trees and were allocated a Low to Moderate Landscape Significance Value and a Retention Value of Consider for Removal and Consider for Retention. Refer to Appendix 2 for species identifications and further detail. Trees 18, 19, 20 & 21 are exempt from the Council's Tree Management controls based on species and can be removed without Council consent.
- 4.9.1 The supplied plans show the proposed cabana works is within the SRZs of Trees 14, 17, 18, 19, 20 & 21. The demolition of the existing shed is also within the SRZ of Tree 17. The overall TPZ encroachments were estimated to be 10.7%, 19.6%, 17.2%, 32.9%, 66.6% and 35.0% respectively and also represent *Major Encroachments* as defined by AS-4970.
- 4.9.2 Given the size and location of the encroachments, the long term structural and physiological viability of Trees 14, 17, 18, 19, 20 & 21 are highly likely to be compromised by the proposed encroachment, and the trees will need to be removed to accommodate the works.
- 4.9.3 Removal and replacement with healthy advanced size specimens would replace the loss of amenity within a short to medium timeframe.
- 4.9.4 Refer to Appendix 5 for further detail.
- 4.10 **Tree 26**
- 4.10.1 Tree 26 was identified as an *Archontophoenix alexandrae* (Alexander Palm) and was allocated a Low Landscape Significance Value and a Retention Value of Consider for Removal. Tree 26 is exempt from the Council's Tree Management controls based on species and can be removed without council consent.
- 4.10.2 The supplied plans show the proposed development is within the TPZ of Tree 26. The overall TPZ encroachment is approximately 8.8%. However, Clause 3.3.4 of AS-4970 does allow for major encroachments if design factors (e.g. tree sensitive construction methods) are used to minimise negative impacts.
- 4.10.3 Refer to Appendix 5 for further detail.
- 4.10.4 Given the good physiological condition and species of the tree the proposed development can be accommodated. However, given the size of encroachment the proposal represents a significant risk to



- the tree's long term structural and physiological viability and therefore the following tree sensitive construction methods and protection measures are carefully implemented under the supervision of the Project Arborist. Significant departures from the detailed tree sensitive construction methods and protection measures are likely to result in a shortened ULE and/or tree removal
- 4.10.5 TPZ fencing should be installed prior to any site works (including demolition) and remain in place for the duration of the demolition and construction processes.
- 4.10.6 The area within the TPZ fencing should be mulched to a depth of 50mm with a non-toxic product (i.e. woodchips) with no fines.
- 4.10.7 Coir logs should be installed on the perimeter of the TPZ fencing to prevent runoff from the building works into the TPZ.
- 4.10.8 Materials, waste storage and temporary services should not be located within the TPZ fenced area. If works are required within the TPZ fenced area, then they should be supervised by the Project Arborist.
- 4.10.9 The tree protection measures must be inspected by the Project Arborist prior to the start prior of site works, including demolition.
- 4.10.10 Refer to AS4970 and Appendices 5, 6, 7 & 8 for further details for further details.



# 4.11 Removal & Replacement Planting

- 4.11.1 Removal works should be carried out by a practising arborist. The practising arborist should hold a minimum qualification equivalent (using Australian Qualifications Framework) of Level 3 or above in arboriculture or its recognised equivalent. The practising arborist should have a minimum of 3 years of practical experience. Pruning/removal works should be undertaken in accordance with the Australian Standard 4373: Pruning of Amenity Trees (2007), Safe Work Australia Guide for Managing Risks of Tree Trimming and Removal Work (2016) and other applicable legislation and codes.
- 4.11.2 Replacement tree planting should be provided when trees are removed. Replacement trees should be supplied as advanced size stock to help offset the loss of amenity resultant from the tree removals.
- 4.11.3 Replacement planting should be supplied in accordance with Australian Standard 2303: Tree Stock for Landscape Use (2015).

Dr Matthew Laurence

ma

Director

BSc. (Hons), PhD (Plant Pathology), GradCert (Arboriculture)

Institute of Australian Consulting Arboriculturists (Accredited Member – ACM0502016)

Australasian Plant Pathology Society

ResearchGate Profile - https://www.researchgate.net/profile/Matthew Laurence



# 5.0 REFERENCES |

Mattheck & Breloer (2003), The Body Language of Trees – A Handbook for Failure Analysis.

NSW Office of Environment and Heritage's Atlas of NSW Wildlife (2011), BioNet Atlas of NSW Wildlife.

Standards Australia (2009) Protection of Trees on Development Sites AS4970.

Standards Australia (2007) Pruning of Amenity Trees AS4373.

Standards Australia (2015) Tree Stock for Landscape Use AS2303.



## 6.0 APPENDIX 1 | METHODOLOGY

- 6.1 This report was based on data from a site inspection conducted on the 23.10.24. The recommendations in this report are based on and limited to observations from these site inspections.
- The subject tree(s) was assessed using the Visual Tree Assessment methodology described in *The Body Language of Trees A Handbook for Failure Analysis* (Mattheck et al., 2003). Subject trees were assessed from the ground only to provide an Arboricultural Impact Assessment and Tree Protection Specification report. No internal diagnostic testing was undertaken as part of this assessment. Trees outside the subject site were assessed from the property boundaries only.
- 6.3 The dimensions of the subject tree(s) are an approximation only.
- The location of the subject tree(s) was determined from the location plan provided. Trees not shown on this plan have been plotted in their approximate location only.
- Tree Protection Zones & Structural Root Zones for the subject tree(s) was based on methods outlined in Australian Standard 4970: *Protection of Trees on Development Sites* (2009).
- 6.6 The health of the subject tree(s) was determined by assessing:
  - Foliage size and colour
  - Pest and disease infestation
  - Extension growth
  - Crown density
  - Deadwood size and volume
  - Presence of epicormic growth
- 6.7 The structural condition of the subject tree(s) was assessed by:
  - Visible evidence of structural defects or instability
  - Evidence of previous pruning or physical damage
- The Useful Life Expectancy (ULE) is used to estimate a tree's longevity in its growing environment. The ULE is based on a tree's species, health, structural condition and site suitability. The tree(s) has been allocated one of the following ULE categories (modified from Barrell, 2001):
  - 40 years +
  - 15-40 years
  - 5-15 years
  - Less than 5 years
- 6.9 The Landscape Significance is based on a qualitative assessment of a tree's cultural, environmental and aesthetic value. This provides a relative measure of a tree's Landscape Significance and can be used to determine its Retention Value. Trees are rated under the following categories:
  - Very High
  - High
  - Moderate
  - Low
  - Insignificant



VERY HIGH	The subject tree is listed as a Heritage Item under the Local Environmental Plan with a local or state level of significance.
	The subject tree is listed on Council's Significant Tree Register.
	The subject tree is a remnant tree.
HIGH	The subject tree creates a 'sense of place' or is considered 'landmark' tree.
	The subject tree is of local, cultural or historical importance or is widely known.
•••	The subject tree has been identified by a suitably qualified professional as a species scheduled as a Threatened or Vulnerable Species or forms part of an Endangered Ecological Community associated with the subject site, as defined under the provisions of the Threatened Species Conservation Act 1995 (NSW) or the Environmental Protection and Biodiversity Conservation Act 1999.
***	The subject tree is known to provide habitat to a threatened species.
	The subject tree is an excellent representative of the species in terms of aesthetic value.
	The subject tree is of significant size, scale or makes a significant contribution to the canopy cover of the locality.
•••	The subject tree forms part of the curtilage of a heritage item with a known or documented association with that item.
MODERATE	The subject tree makes a positive contribution to the visual character or amenity of the area.
•••	The subject tree provides a specific function such as screening or minimising the scale of a building.
	The subject tree has a known habitat value.
	The subject tree is a good representative of the species in terms of aesthetic value.
LOW	The subject tree is an environmental pest species or is exempt under the provisions of the local Council's Tree Management Controls.
	The subject tree makes little or no contribution to the amenity of the locality.
	The subject tree is a poor representative of the species in terms of aesthetic value.
INSIGNIFICA NT	The subject tree is declared a Noxious Weed under the Noxious Weeds Act.
	No was provided by Appa Hanwood of TracIOTM and was madified from the Carthogons

The above table was provided by Anna Hopwood of TreelQ<sup>™</sup> and was modified from the Earthscape Criteria for Assessment of Landscape Significance.



- The Retention Value is based on a tree's ULE and Landscape Significance. The subject tree(s) has been allocated one of the following Retention Values:
  - Priority for Retention
  - Consider for Retention
  - Consider for Removal
  - Priority for Removal

	VERY HIGH	HIGH	MODERAT E	LOW	INSIGNIFICAN T	
40 years +	Priority for Retention	Priority fo	or Retention	Conside r for	Priority for Removal	
15-40 years	reconsorr	Priority for Retention	Consider for Retention	Remova I	, tomoval	
5-15 years	Co	nsider for Rete	ntion			
Less than 5 years	Consider for Removal					

The above table was provided by Anna Hopwood of TreelQ™

- 6.11 The Tree Protection Zone (TPZ) is the area above and below ground required to preserve the vigour and long-term viability of the tree. The TPZ is based on scientific research and is generally considered by the arboricultural industry as the area required to provide adequate tree protection during construction. The TPZ is the primary means of protecting trees on development sites (Australian Standard 4970:*Protection of Trees on Development Sites*, 2009).
- Works within the TPZ should be avoided. However, *Minor Encroachments*, defined in AS4970 as less than 10% of the TPZ area, are considered acceptable when it is compensated for elsewhere and contiguous within the TPZ. A *Major Encroachment*, defined in AS4970 as greater than 10% of the TPZ area or within the Structural Root Zone (SRZ), may require root investigations by non-destructive methods and tree sensitive construction methods.
- 6.13 The TPZ is the area within a circle that is centred on the trunk. The radius of the TPZ is calculated by the following formula:

TPZ= DBH x 12

where

DBH= Diameter at Breast Height (1.4m)



- The SRZ is the minimum area around the base of the tree required for the tree's stability. The SRZ only relates to tree stability and not the vigour and long-term viability of the tree.
- 6.15 The SRZ is the area within a circle that is centred on the trunk. The radius of the SRZ is calculated by the following formula:

SRZ= (Dx50)0.42 x 0.64

where

D= Trunk diameter (m) above the root buttress

- 6.16 Encroachment into SRZ (i.e. severance of structural roots >25mmØ) may lead to the destabilisation of the tree and the long-term viability must be demonstrated in such cases. This may require root investigations by non-destructive methods.
- 6.17 For further details on the TPZ and SRZ please refer to Australian Standard 4970: *Protection of Trees on Development Sites* (2009).



# 7.0 APPENDIX 2 | TREE ASSESSMENT SCHEDULE

Tree No.	Species	Height (m)	Radial Crown Spread (m)	DBH comb. (mm)	Radial TPZ (m)	TPZ Area (m²)	Radial SRZ (m)	Health Rating	Structural Rating	Age Class	ULE (years)	L/Sign	Retention Value	Comments	TPZ Encroachment (%)
1	Eucalyptus racemosa (Scribbly Gum)	12	8	600	7	163	2.8	Fair	Poor	Senescent	<5	Moderate	Priority for Removal	Crown density 50-75%. Small (<25mmø) epicormic growth in moderate volumes. Trunk cavity(s), major. Structures within SRZ.	23.1% (Within SRZ)
2	Eucalyptus robusta (Swamp Mahogany)	14	5	300	4	41	2.1	Good	No access to base. No rating.	Semi- mature	5-15	Low	Consider for Removal		24.1% (Within SRZ)
3	Callistemon viminalis (Weeping Bottlebrush)	6	4	71	2	13	1.5	Good	Good	Semi- mature	5-15	Low	Consider for Removal		Within Development Footprint
4	Acacia sp. (Wattle)	5	3	75	2	13	1.5	Fair	Fair	Late Mature	5-15	Low	Consider for Removal	Localised crown death. Crown density 50-75%. Wound(s), early signs of decay. Trunk cavity(s), minor. Borer.	Within Development Footprint
5	Archontophoenix cunninghamiana (Bangalow Palm)	8	4	246	3	27	1.9	Good	Fair	Semi- mature	5-15	Low	Consider for Removal	Co-dominant inclusions, major. Structures within SRZ.	61.8% (Within SRZ)
6	Syzygium paniculatum (Brush Cherry)	4	3	50	2	13	1.5	Good	Good	Semi- mature	5-15	Low	Consider for Removal	Crown density 75- 95%. Lopped.	Within Development Footprint
7	Angophora floribunda (Rough Barked Apple)	20	8	600	7	163	2.8	Fair	Good	Mature	15-40	High	Priority for Retention	Crown density 75- 95%. Small (<25mmø) epicormic growth in low volumes.	26.3% (Within SRZ)



Tree No.	Species	Height (m)	Radial Crown Spread (m)	DBH comb. (mm)	Radial TPZ (m)	TPZ Area (m²)	Radial SRZ (m)	Health Rating	Structural Rating	Age Class	ULE (years)	L/Sign	Retention Value	Comments	TPZ Encroachment (%)
														Previously crown lifted. Wound(s), no visible sign of decay. Trunk conflict with adjacent structures. Structures within SRZ.	
8	Archontophoenix cunninghamiana (Bangalow Palm)	6	3	125	2	13	1.5	Good	Good	Semi- mature	5-15	Low	Consider for Removal		No Encroachment
9	Angophora floribunda (Rough Barked Apple)	22	8	550	7	137	2.7	Fair	Fair	Mature	15-40	High	Priority for Retention	Trunk competition Crown density 75- 95%. Small (<25mmø) deadwood in moderate volumes. Previously crown lifted. Co-dominant inclusions, major.	2.2% (Minor Encroachment)
10	Syzygium australe (Brush Cherry Lilly Pilly)	6	3	160	2	13	1.6	Good	Fair	Mature	5-15	Moderate	Consider for Retention	Crown density 75- 95%. Co-dominant inclusions, major.	No Encroachment
11	<i>Syzygium</i> australe (Brush Cherry Lilly Pilly)	6	3	325	4	48	2.1	Poor	Fair	Senescent	<5	Low	Priority for Removal	Crown density 0- 25%. Crown consists mainly of epicormic growth. Co-dominant inclusions, major. Wound(s), no visible sign of decay.	No Encroachment



Tree No.	Species	Height (m)	Radial Crown Spread (m)	DBH comb. (mm)	Radial TPZ (m)	TPZ Area (m²)	Radial SRZ (m)	Health Rating	Structural Rating	Age Class	ULE (years)	L/Sign	Retention Value	Comments	TPZ Encroachment (%)
12	<i>Angophora</i> <i>costata</i> (Sydney Red Gum)	23	10	675	8	206	2.9	Fair	Poor	Late Mature	5-15	High	Consider for Retention	Localised crown death. Crown density 50-75%. Small (<25mmø), medium (25- 75mmø) & large (>75mmø) deadwood in moderate volumes. Wound(s), advanced stages of decay. Trunk cavity(s), major.	Within Development Footprint
13	<i>Syzygium</i> <i>australe</i> (Brush Cherry Lilly Pilly)	6	4	100	2	13	1.5	Good	Good	Mature	5-15	Moderate	Consider for Retention	Crown density 75- 95%. Structures within SRZ.	No Encroachment
14	<i>Syzygium</i> <i>australe</i> (Brush Cherry Lilly Pilly)	6	4	100	2	13	1.5	Good	Good	Mature	5-15	Moderate	Consider for Retention		10.7% (Within SRZ)
15	Syzygium australe (Brush Cherry Lilly Pilly)	4	3	50	2	13	1.5	Good	Good	Mature	5-15	Moderate	Consider for Retention	Group of two trees	13.4% (Within SRZ)
16	Casuarina glauca (Swamp She Oak)	16	6	325	4	48	2.1							Set back 2 m	No Encroachment
17	<i>Syzygium</i> <i>australe</i> (Brush Cherry Lilly Pilly)	6	4	100	2	13	1.5	Good	Good	Mature	5-15	Moderate	Consider for Retention		19.6% (Within SRZ)
18	Jubaea chilensis (Chilean wine palm)	5	3	300	4	41	2.1	Good	Good	Semi- mature	5-15	Low	Consider for Removal		17.2% (Within SRZ)



Tree No.	Species	Height (m)	Radial Crown Spread (m)	DBH comb. (mm)	Radial TPZ (m)	TPZ Area (m²)	Radial SRZ (m)	Health Rating	Structural Rating	Age Class	ULE (years)	L/Sign	Retention Value	Comments	TPZ Encroachment (%)
19	Jubaea chilensis (Chilean wine palm)	5	3	300	4	41	2.1	Good	Good	Semi- mature	5-15	Low	Consider for Removal		32.9% (Within SRZ)
20	Jubaea chilensis (Chilean wine palm)	5	3	300	4	41	2.1	Good	Good	Semi- mature	5-15	Low	Consider for Removal		66.6% (Within SRZ)
21	Persea americana (Avocado)	4	3	71	2	13	1.5	Good	Fair	Semi- mature	5-15	Low	Consider for Removal	Lopped with resultant epicormics. Wound(s), early signs of decay.	35.0% (Within SRZ)
22	Cyathea australis (Rough Tree Fern)	3	1	50	2	13	1.5								0.8% (Minor Encroachment)
23	Syagrus romanzoffianum (Cocos Palm)	10	4	150	2	13	1.6	Good	Good	Mature	5-15	Low	Consider for Removal		No Encroachment
24	Syagrus romanzoffianum (Cocos Palm)	10	4	150	2	13	1.6	Good	Good	Mature	5-15	Low	Consider for Removal		No Encroachment
25	Syzygium australe (Brush Cherry Lilly Pilly)	5	4	125	2	13	1.5	Good	Good	Mature	5-15	Low	Consider for Removal	Small (<25mmø) epicormic growth in moderate volumes. Structures within SRZ.	No Encroachmen
26	Archontophoenix alexandrae (Alexander Palm)	6	3	75	2	13	1.5	Fair	Good	Semi- mature	5-15	Low	Consider for Removal	Chlorotic foliage.	8.8% (Within SRZ)
27	Archontophoenix cunninghamiana (Bangalow Palm)	7	4	150	2	13	1.6								No Encroachment




Tree No.	Species		Radial Crown Spread (m)	COMP	Radial TPZ (m)	TPZ Area (m²)	Radial SRZ (m)	Health Rating	Structural Rating	ULE (years)	L/Sign	Retention Value	Comments	TPZ Encroachment (%)
28	Archontophoenix cunninghamiana (Bangalow Palm)		4	150	2	13	1.6							No Encroachment
29	Archontophoenix cunninghamiana (Bangalow Palm)	7	4	150	2	13	1.6							No Encroachment
30	Syncarpia glomulifera (Turpentine)	18	6	400	5	72	2.3						Set back 6 m	No Encroachment



# 8.0 APPENDIX 3 | TREE LOCATION PLAN

PLANT



PO Box 2169, Clovelly, NSW 2031 Ifo@laurenceco.com.au 0404 282 825

# 9.0 APPENDIX 4 | PROPOSED DEVELOPMENT PLANS



LEGEND:

EXISTING STRUCTURES TO REMAIN

EXISTING STRUCTURES TO BE DEMILOSHIED

EXISTING FLOOR STRUCTURE TO BE DEMOLISHED

DEMOLITION WORKS TO BE CARRIED OUT IN ACCORDANCE WITH AS 2601-2001, The Demoliton of Structures)Part 7.2(1)(a) ALL SERVICES ARE TO BE DISCONNECTED IN ACCORDANCE WITH THE REQUIREMENTS OF THE RELEVANT AUTHORITIES

## ASBESTOS NOTE:

THE BUILDER SHALL GIVE NOTICE MANEDIATELY F ASBESTOS IS FOUND ON SITE ASBESTOS REMOVAL MUST ONLY BE IMPORTANT BY SUTTAIN YOU, HE BUILDER SHALL GIVE ASSESSED AS ACCORDANCE WITH THE AUSTRALAM WORK, HEALTH AND SAFETY BUILDER ASSESSED AS ACCOUNTED AS AS AC

ANY LEAD PAINT REMOVAL REQUIRED: SHOULD IMPLEMENT SAFE PAINT AND ASSESTIGS WORK PRACTICES. PAINT REMOVE HAS A DUTY OF THE COMMAINT CHEMT EARLY BASED THE MEMBER OF THE THE CAMMAINT CHEMT EARLY BASED THE MEMBER OF THE REPORT THE RECORD FAINT MANAGEMENT AND THE ADDITIONAL REQUIREMENTS OF LOCAL AGENCIES WITH RESPONSIBILITIES FOR THE EMPROMENT HAS THE REPORT AND THE ALL THAT AND WORKPACE HEALTH AND SAFETY.



### WASTE MANAGEMENT:

## OBJECTIVES

TO ENSURE THAT NECESSARY MEASURES ARE EMPLOYED ON THE SITE THAT PROTECT BOTH THE NEIGHBOURHOOD AMENITY AND THE SURROUNDING ENVIRONMENT AND MINIMISE SITE DEGRADATION. THE RECYCLING OF MATERIALS WILL REDUCE TIPPING COSTS.

REFER TO WASTE MANAGEMENT PLAN REPORT.

### RESPONSIBILITY

THE CONTRACTOR WILL BE RESPONSIBLE AND LIABLE FOR ALL WORKS CARRIED OUT ON THE SITE. THIS INCLUDES ASSUMING RESPONSIBILITY FOR THE ACTIONS OF ALL THE SUBCONTRACTORS AS WELL AS ADVISING THEM OF COUNCIL'S REQUIREMENTS WHEN CARRYING OUT THE WORK.

IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO HAVE VIEWED A
APPROVED PLANS PRIOR TO THE COMMENCEMENT OF DEMOLITION,
EARTHWORKS AND CONSTRUCTION MODES.

#### CONTAINMENT OF SITE WASTE

BUILDING MATERIALS MUST NOT BE BURIED ON SITE. DEMOLITION WASTE RESULTING FROM THE WORKS IS NOT TO BE STORED ON FOOTPATHS, STREET GUTTERS OR ROADWAYS ETC. ALL WASTE TO BE PLACED IN RUBBISH SKIPS, OR CONTAINERS FOR COLLECTION.

#### COUNCIL PROPERTY

COUNCIL PROPERTY IS NOT TO BE USED FOR CONSTRUCTION OR STORAGE ACTIVITIES UNLESS PRIOR WRITTEN APPROVAL HAS BEEN OBTAINED. COUNCIL PROPERTY IS NOT TO BE DAMAGED AND IS TO BE KEPT IN A CLEAN, SAFE AND FUNCTIONAL CONDITION BEFORE, DURING AND ON COMPLETION OF THE WORKS.

SHOULD ANY COUNCIL PROPERTY INCLUDING FOOTPATHS BE INADVERTENTLY DAMAGED AS A RESULT OF THE WORKS, COUNCIL MUST BE NOTIFIED IMMEDIATELY.

#### **BUILDING MATERIAL STOCKPILE**

AT NO TIME MAY BUILDING MATERIALS OR STOCKPILES BE SITUATED ON A PUBLIC RESERVE, ROAD GUTTER OR FOOTPATH, THIS INCLUDES BUILDING OR DEMOLITION MATERIAL, WASTE CONTAINERS, PROTABLE SHEDS, PORTABLE TOILETS AND THE LIKE.

ALL BUILDING MATERAILS ARE TO BE STORED WITHIN THE SUBJECT SITE.
ALL LOOSE MATERIAL TO BE COVERED WITH TARPAULINS.

A SUFFICIENT AREA MUST BE ALLOCATED WITHIN THE SITE FOR SUCH STORAGE OF BUILDING MATERIALS, DEMOLITION WASTE, WASTE CONTAINERS ETC. AS REQUIRED, THE FEASIBILITY OF THE NOMINATED SITE FOR THE STOCKPILE MUST BE CONFIRMED PRIOR TO COMMENCEMENT.

## VEHICLE MOVEMENTS

ALL VEHICLES VISITING THE SITE ARE TO COMPLY WITH THE PARKING REGULATIONS IN THE AREA.

ALL TRUCKS AND UTILITIES MUST COVER THEIR LOADS. NO VEHICLE VISITING THE SITE IS TO IMPEDE LOCAL AREA TRAFFIC FLOWS.

## DUST CONTROL

APPROPRIATE METHODS ARE TO BE USED TO PREVENT WIND BLOWN DUST CREATING AN UNACCEPTABLE HAZARD OR NUISANCE ON THE SITE OR ADJOINING PROPERTIES. WHERE DUST IS CREATED AS A RESULT OF THE WORKS. MINIMISE DUST & KEEP THE AREA TIDY AT ALL TIMES.

#### VEMENTS HAZARDOUS MATERIALS

ASBESTOS CEMENT SHEETING IF ENCOUNTERED IS TO BE WRAPPED TIGHTLY IN PLASTIC TO COMPLY WITH THE AUSTRALIAN STANDARD AND WORK COVER AUTHORITIES REQUIREMENTS AND TAKEN TO AN APPROVED LANDFILL TIP.



## **DEMOLITION / WASTE MANAGEMENT PLAN**

1:200

Figured dimensions to be used in preference to scaling this drawing. Do not assume - if in doubt ASK.



Level 1 . 2 Epsom Road, Zetland, Sydney, NSW, 2017 office | 0421 813 873 e | hello@erarchitect.com.au licence No 7530



ISSUE FOR COUNCIL RFI	

REV	DATE	AMENDMENT	Copyright. ©	DF
			THE COLLECT IS SHOULD AND THE MAIN THE MEDICAL COLLECTION OF THE MEDIC	_
A	14.04.25	ISSUE FOR DA - AHUK	CONTRACTOR TO VORIEV DISCUSSIONS PRICE	
В	28.08.25	ISSUE AS COUNCIL RFI - AH	CONSTRUCTION, DO NOT SCAUE OFF DRAWING.	

	DRAWING:	
OTHE PRETARTY RECEIPT USE THE	DEMOLITION PLAN	
USE THE IS PARTY, OUT PRIOR ROSON (THIS	LOT:52 DP:12838	3
UEST.	154 PLATEAU RD	
PROF	BILGOLA PLATEAU, NSV	V

CLIENT: JENNY & JANNIS KEARNEY BOTT

LGA: NORTHERN BEACHES COUNCIL


DESIGN: ALTS & ADDS TO EX SINGLE STOREY DWELLING

JOB No:1982024 SHEET SIZE: A3 SHEET No:8 of 31

Plot Date: Friday, 29 August 2025




www.laurenceco.com.au





www.laurenceco.com.au



ARBORICULTURE PLANT PATHOLOGY Level 1 . 2 Epsom Road,

office | 0421 813 873

licence No.7530

www.erarchitect.com.au

Zetland, Sydney, NSW, 2017

e | hello@erarchitect.com.au


Plot Date: Friday, 29 August 2025

SITE & ROOF PLAN (Detached REV DATE AMENDMENT Copyright. © ISSUE FOR COUNCIL RFI Cabana/Shed) LOT:52 DP:12838 154 PLATEAU RD **BILGOLA PLATEAU, NSW 2107** B 28.08.25 ISSUE AS COUNCIL REL-AF

NORTHERN BEACHES COUNCIL LGA: DESIGN: ALTS & ADDS TO EX SINGLE STOREY DWELLING JOB No:1962024 SHEET SIZE: A3 SHEET No:3 of 31


JENNY & JANNIS KEARNEY BOTT

ox 2169, Clovelly, NSW 2031 info@laurenceco.com.au 0404 282 825





ox 2169, Clovelly, NSW 2031 info@laurenceco.com.au 0404 282 825



Figured dimensions to be used in preference to scaling this drawing. Do not assume - if in doubt ASK. Plot Date: Friday, 29 August 2025 REV DATE AMENDMENT DRAWING: ERROSION & SEDIMENT CONTROL CLIENT: JENNY & JANNIS KEARNEY BOTT Copyright. © Level 1 . 2 Epsom Road, ISSUE FOR COUNCIL RFI PLAN Zetland, Sydney, NSW, 2017 NORTHERN BEACHES COUNCIL LGA: office | 0421 813 873 LOT:52 DP:12838 DESIGN: ALTS & ADDS TO EX SINGLE STOREY DWELLING e | hello@erarchitect.com.au 154 PLATEAU RD www.erarchitect.com.au licence No.7530


**BILGOLA PLATEAU, NSW 2107** 



ox 2169, Clovelly, NSW 2031 info@laurenceco.com.au 0404 282 825 ACN: 625 300 530

JOB No:1962024 SHEET SIZE: A3 SHEET No:7 of 31

B 28.08.25 ISSUE AS COUNCIL REL-AF



SITE WORKS CUT & FILL PLAN 1:200

Figured dimensions to be used in preference to scaling this drawing. Do not assume - if in doubt ASK. Plot Date: Friday, 29 August 2025 REV DATE AMENDMENT CLIENT: JENNY & JANNIS KEARNEY BOTT DRAWING: Copyright. © Level 1 . 2 Epsom Road, SITE WORKS CUT/FILL PLAN ISSUE FOR COUNCIL RFI Zetland, Sydney, NSW, 2017 NORTHERN BEACHES COUNCIL office | 0421 813 873 LOT:52 DP:12838 e | hello@erarchitect.com.au **DESIGN:** ALTS & ADDS TO EX SINGLE STOREY DWELLING 154 PLATEAU RD www.erarchitect.com.au licence No.7530 **BILGOLA PLATEAU, NSW 2107** JOB No:1962024 SHEET SIZE: A3 SHEET No:9 of 31 B 28.08.25 ISSUE AS COUNCIL RFI - AH



ox 2169, Clovelly, NSW 2031

PROTECTION OF OPENABLE WINDOWS AS PER BCA PARTS 3.9.2.6 & 3.9.2.7: (First Floor Bedrooms) A window opening must be provided with protection if the floor below the window in a bedroom is 2m or more above the surface beneath. where the lowest level of a window opening is less than 1.7m above the floor, a keyed lock must be fitted so as to restrict the window opening to a max 125mm





Figured dimensions to be used in preference to scaling this drawing. Do not assume - if in doubt ASK. Level 1 . 2 Epsom Road, Zetland, Sydney, NSW, 2017 office | 0421 813 873 e | hello@erarchitect.com.au

licence No.7530

www.erarchitect.com.au



NORTH EASTERN ELEVATION (Main Dwelling) LOT:52 DP:12838

154 PLATEAU RD


**BILGOLA PLATEAU, NSW 2107** 


LGA: **DESIGN:** ALTS & ADDS TO EX SINGLE STOREY DWELLING JOB No:1962024 SHEET SIZE: A3 SHEET No:18 of 31

Plot Date: Friday, 29 August 2025 CLIENT: JENNY & JANNIS KEARNEY BOTT NORTHERN BEACHES COUNCIL



ox 2169, Clovelly, NSW 2031 info@laurenceco.com.au





Plot Date: Friday, 29 August 2025

www.erarchitect.com.au

Level 1 . 2 Epsom Road, Zetland, Sydney, NSW, 2017 office | 0421 813 873 e | hello@erarchitect.com.au licence No.7530

Figured dimensions to be used in preference to scaling this drawing. Do not assume - if in doubt ASK.

REV DATE AMENDMENT Copyright. © ISSUE FOR COUNCIL RFI B 28.08.25 ISSUE AS COUNCIL REL-AH

DRAWING: SECTIONS S/01 (Main Dwelling + Detached Cabana/Shed) LOT:52 DP:12838 154 PLATEAU RD


**BILGOLA PLATEAU, NSW 2107** 

JENNY & JANNIS KEARNEY BOTT

NORTHERN BEACHES COUNCIL **DESIGN:** ALTS & ADDS TO EX SINGLE STOREY DWELLING JOB No:1962024 SHEET SIZE: A3 SHEET No:19 of 31

ARBORICULTURE PLANT PATHOLOGY











ox 2169, Clovelly, NSW 2031 info@laurenceco.com.au 0404 282 825





E/10 SOUTH WESTERN ELEVATION

1:100

Figured dimensions to be used in preference to scaling this drawing. Do not assume - if in doubt ASK.

ERA

Level 1 . 2 Epsom Road, Zetland, Sydney, NSW, 2017 office | 0421 813 873 e | hello@erarchitect.com.au licence No.7530





DRAWING:
NORTH/SOUTH ELEVATIONS
(Detached Garage)

LOT:52 DP:12838 154 PLATEAU RD BILGOLA PLATEAU, NSW 2107 Plot Date: Friday, 29 August 2025

CLIENT: JENNY & JANNIS KEARNEY BOTT


LGA: NORTHERN BEACHES COUNCIL

DESIGN: ALTS & ADDS TO EX SINGLE STOREY DWELLING


JOB No:1962024 SHEET SIZE: A3 SHEET No:23 of 31



# 10.0 APPENDIX 5 | ARBORICULTURAL IMPACT ASSESSMENT PLANS







www.laurenceco.com.au

PO Box 2169, Clovelly, NSW 2031 info@laurenceco.com.au 0404 282 825 ACN: 625 300 530

CONSULTANCY

ARBORICULTURE

PLANT PATHOLOGY

# **Impact Assessment Plan**



□ SRZ

■ TPZ

Tree number



DEMOLITION WORKS TO BE CARRIED OUT IN ACCORDANCE WITH AS 2601-2001, The Demoliton of Structures)Part 7.2(1)(a) ALL SERVICES ARE TO BE DISCONNECTED IN ACCORDANCE WITH THE REQUIREMENTS OF THE RELEVANT AUTHORITIES

ASBESTOS NOTE:

THE BUILDER SHALL GIVE NOTICE MINEDIATELY IF ASBESTOS IS FOUND ON SITE ASBESTOS. EMOVAL MUST ONLY BE UNDERTRAKEN BY SUITABLY QUALIFIED BUILDERS IN ACCORDANCE WITH THE AUSTRALAN WORK, HEALTHAND SAFETY STRATECY 201-202 ANTIONAL COUNTIONAL HEALTHAND SAFETY STRATECY 201-202 ANTIONAL COUNTIONAL HEALTHAND SAFETY STRATECY 201-202 ANTIONAL COUNTIONAL HEALTHAND SAFETY STRATECY 201-202 ANTIONAL OF THE MOST CUPRENT COUNCIL SASBESTOS POLICY; IF ASBESTOS IS FOUND AN "ASBESTOS REMOVAL" SKOMAGE MUST BE DISPLAYED AND INCREMENTATION SONTIED IN ACCORDANCE TO DA CONDITIONS. ASSESTORS SKOMAGE MUST BE ERECTED AND DISPLAYED IN A MISGRIPH COUNTIES ASSESTORS SKOMAGE MUST BE ERECTED AND DISPLAYED IN A

ANY I FAD PAINT REMOVAL RECLIBED. SHOULD IMPLEMENT SAFE PAINT AND SESTOS WORK PRACTICES, PAINT REMOVES ANY LEAD PAINT REMOVAL REQUIRES SHOULD INVICENTED ANY AND ASSESSION WORK PROTICES SHOULD HAVE AS A DUTY TO THE COMMONIVE CLEEN, THE PLOYEES AND THEMSELVES TO FAITHFULLY INMILEMENT THE REGOGREMENTS OF LOCAL AGENCIES WITH RESPONSIBILITIES FOR THE ENVIRONMENT, WASTE DISPOSAL, PUBLIC HEALTH AND WORKPA ACE HEALTH AND AFETY.



## WASTE MANAGEMENT:

#### OB JECTIVES

TO ENSURE THAT NECESSARY MEASURES ARE EMPLOYED ON THE SITE THAT PROTECT BOTH THE NEIGHBOURHOOD AMENITY AND THE SURROUNDING ENVIRONMENT AND MINIMISE SITE DEGRADATION. THE RECYCLING OF MATERIALS WILL REDUCE TIPPING COSTS.

REFER TO WASTE MANAGEMENT PLAN REPORT.

## RESPONSIBILITY

THE CONTRACTOR WILL BE RESPONSIBLE AND LIABLE FOR ALL WORKS CARRIED OUT ON THE SITE. THIS INCLUDES ASSUMING RESPONSIBILITY FOR THE ACTIONS OF ALL THE SUBCONTRACTORS AS WELL AS ADVISING THEM OF COUNCIL'S REQUIREMENTS WHEN CARRYING OUT THE WORK.

IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO HAVE VIEWED ALL APPROVED PLANS PRIOR TO THE COMMENCEMENT OF DEMOLITION, EARTHWORKS AND CONSTRUCTION WORKS.

#### CONTAINMENT OF SITE WASTE

BUILDING MATERIALS MUST NOT BE BURIED ON SITE. DEMOLITION WASTE RESULTING FROM THE WORKS IS NOT TO BE STORED ON FOOTPATHS, STREET GUTTERS OR ROADWAYS ETC. ALL WASTE TO BE FLACED IN RUBBISH SKIPS, OR CONTAINERS FOR COLLECTION.

#### COUNCIL PROPERTY

COUNCIL PROPERTY IS NOT TO BE USED FOR CONSTRUCTION OR STORAGE ACTIVITIES UNLESS PRIOR WITTEN APPROVAL HAS BEEN OBTAINED. COUNCIL PROPERTY IS NOT TO BE DAMAGED AND IS TO BE KEPT IN A CLEAN, SAFE AND FUNCTIONAL CONDITION BEFORE, DURING AND ON COMPLETION OF THE WORKS.

SHOULD ANY COUNCIL PROPERTY INCLUDING FOOTPATHS BE INADVERTENTLY DAMAGED AS A RESULT OF THE WORKS, COUNCIL MUST BE NOTIFIED IMMEDIATELY.

## **BUILDING MATERIAL STOCKPILE**

AT NO TIME MAY BUILDING MATERIALS OR STOCKPILES BE SITUATED ON A PUBLIC RESERVE, ROAD GUTTER OR FOOTPATH, THIS INCLUDES BUILDING OR DEMOLITION MATERIAL, WASTE CONTAINERS, PROTABLE SHEDS, PORTABLE TOILETS AND THE LIKE.

ALL BUILDING MATERAILS ARE TO BE STORED WITHIN THE SUBJECT SITE.
ALL LOOSE MATERIAL TO BE COVERED WITH TARPAULINS.

A SUFFICIENT AREA MUST BE ALLOCATED WITHIN THE SITE FOR SUCH STORAGE OF BUILDING MATERIALS, DEMOLITION WASTE, WASTE CONTAINERS ETC. AS REQUIRED. THE FASIBILITY OF THE NOMINATED SITE FOR THE STOCKPILE MUST BE CONFIRMED PRIOR TO COMMENCEMENT.

## VEHICLE MOVEMENTS

ALL VEHICLES VISITING THE SITE ARE TO COMPLY WITH THE PARKING REGULATIONS IN THE AREA.

ALL TRUCKS AND UTILITIES MUST COVER THEIR LOADS. NO VEHICLE VISITING THE SITE IS TO IMPEDE LOCAL AREA TRAFFIC FLOWS.

#### DUST CONTROL

APPROPRIATE METHODS ARE TO BE USED TO PREVENT WIND BLOWN DUST CREATING AN UNACCEPTABLE HAZARD OR NUISANCE ON THE SITE OR ADJOINING PROPERTIES. WHERE DUST IS CREATED AS A RESULT OF THE WORKS. MINIMISE DUST & KEEP THE AREA TIDY AT ALL TIMES.

## HAZARDOUS MATERIALS

ASBESTOS CEMENT SHEETING IF ENCOUNTERED IS TO BE WRAPPED TIGHTLY IN PLASTIC TO COMPLY WITH THE AUSTRALIAN STANDARD AND WORK COVER AUTHORITIES REQUIREMENTS AND TAKEN TO AN APPROVED LANDFILL TIP.

CONSULTANCY

ARBORICULTURE

PLANT PATHOLOGY

## **DEMOLITION / WASTE MANAGEMENT PLAN** 1:200

www.erarchitect.com.au

Level 1 . 2 Epsom Road, Zetland, Sydney, NSW, 2017 office | 0421 813 873 e | hello@erarchitect.com.au licence No.7530



ISSUE FOR COUNCIL RFI

REV	DATE	AMENDMENT	Copyright, ©
			THE COLORANT COMES AND THE STREET WITH THE COLORANT COMES AND THE COLORANT COMES AND THE COLORANT THE COLORANT
A	14.04.25	ISSUE FOR DA - AHUK	CONTRACTOR TO VERIFY CHECKHOMS PRICE
В	28.08.25	ISSUE AS COUNCIL RFI - AH	CONSTRUCTION, DO NOT SCALE OFF DRAWING.

	DRAWING:				
E SWRTY SWPT	DEMOLITION PLAN				
THE WITY, PRIOR ON	LOT:52 DP:12838				
8	154 PLATEAU RD				
ICA ANG	BILGOLA PLATEAU, NSW 2107				

CLIENT: JENN	IY & JANNIS KEA	RNEY BOTT				
LGA:	COUNCIL					
DESIGN: ALTS & ADDS TO EX SINGLE STOREY DWELLING						
JOB No:1962024	SHEET SIZE: A3 SI	HEET No:8 of 31				


Plot Date: Friday, 29 August 2025

www.laurenceco.com.au


PO Box 2169, Clovelly, NSW 2031 info@laurenceco.com.au 0404 282 825 ACN: 625 300 530

32 | 44

# 11.0 APPENDIX 6 | TREE PROTECTION PLAN







Figured dimensions to be used in preference to scaling this drawing. Do not assume - if in doubt ASK.

Plot Date: Friday, 29 August 2025



Level 1 . 2 Epsom Road, Zetland, Sydney, NSW, 2017 office | 0421 813 873 e | hello@erarchitect.com.au licence No.7530



	REV	DATE	AMENDMENT	Copyright. ©
SSUE FOR COUNCIL RFI				THE DOCAMENT IS OWNED BY AND INFORMATION CONTINUED BY A THE REPORT OF A THE ATTEMPT OF ATTEMPT OF A THE ATTE
	A	14.04.25	ISSUE FOR DA - AHUK	CONTRACTOR TO VERIEV CHICAGONS O
	В	28.08.25	ISSUE AS COUNCIL RFI - AH	CONSTRUCTION, DO NOT SCALE OFF DRA


DRAWING: ERROSION & SEDIMENT CONTROL PLAN LOT:52 DP:12838 154 PLATEAU RD **BILGOLA PLATEAU, NSW 2107** 

CLIENT: JENNY & JANNIS KEARNEY BOTT NORTHERN BEACHES COUNCIL DESIGN: ALTS & ADDS TO EX SINGLE STOREY DWELLING JOB No:1962024 SHEET SIZE: A3 SHEET No:7 of 31



# 12.0 APPENDIX 7 | TYPICAL TREE PROTECTION DETAIL

# Tree Protection Detail - TPZ Fencing






PO Box 2169,

# Tree Protection Detail - Ground Protection

and soil moisture levels monitored by

the Project Arborist.


Required if temporary access for machinery is required within the TPZ to protect roots and prevent soil compaction.





PO Box 2169,

# Tree Protection Detail - Scaffolding within TPZ





## 13.0 APPENDIX 8 | TREE PROTECTION SPECIFICATION

# 13.1 Appointment of Project Arborist

13.1.1 Prior to commencement of works a Project Arborist should be engaged to monitor compliance with the protection measures. The Project Arborist will inspect tree protection measures and prepare a compliance certification for the principal certifying authority prior to the release of compliance certification. Contractors and site workers are to receive these specifications at least 3 days prior to commencing works. Contractors and site workers working within the TPZ should sign the site log confirming they have read and understood these specifications prior to commencing works.

## 13.2 Compliance

13.2.1 The Project Arborist will conduct regular site visits to certify the works are compliant with this specification. A compliance document will be prepared by the Project Arborist following each site inspection. The compliance document will include evidence of compliance with the tree protection measures detailed in this specification.

## 13.3 Tree & Vegetation Removal

- 13.3.1 Tree and vegetation removal will be undertaken prior to installation of tree protection measures. Tree removal works should be undertaken in accordance with the *Safe Work Australia Guide for Managing Risks of Tree Trimming and Removal Work* (2016).
- 13.3.2 Tree and vegetation removal must not damage trees to be retained.

## 13.4 Tree Protection Zone

- 13.4.1 Trees that are to be retained must be protected prior to and during construction from works that could negatively impact their health and structural integrity. The following works should not occur within the TPZ unless authorised by the Project Arborist:
  - Modification of existing soil levels, excavations and trenching
  - Mechanical removal of vegetation
  - Movement of naturally occurring rock
  - Storage of materials, plant/equipment and building of sheds
  - No signage or hoarding shall be fixed to the trees
  - · Preparation of building materials, refuelling or disposal of waste materials and chemicals
  - No lighting of fires
  - No pedestrian or vehicular traffic
  - Temporary or permanent location of services, or works required for their installation
  - Any other activities that may damage the tree



## 13.6 Tree Protection Fencing

- 13.6.1 The TPZ fencing must be positioned at the perimeter of the TPZ and may be combined to form a single area where the TPZs of multiple trees overlap. The approximate location of the TPZ fencing is outlined in the Arboricultural Impact Assessment with the exact location determined by consultation between the Principal Contractor/Project Manager and the Project Arborist prior to the commencement of works. Fencing may be setback to allow for demolition/construction access and for the installation of pavements only where appropriate ground protection is installed and approved by the Project Arborist. The TPZ fencing must be at least 1.8m above grade and made of wire mesh panels that are supported by concrete feet and fastened together to prevent sideways movement. Tree damage, including any low branches, must be avoided during the installation of the tree protection fencing. The TPZ fencing must include signage to identify the TPZ fencing and include the Project Arborist contact details.
- 13.7 Site Management
- 13.7.1 Materials, waste storage and temporary services should not be located within the TPZ.
- 13.8 Works within the Tree Protection Zones
- 13.8.1 In certain situations, works within the TPZ may be authorised by the determining authority. These works must be supervised by the Project Arborist. When working within the TPZ, special care should be taken to avoid damage to the tree's root system, trunks and lower branches.
- 13.8.2 If roots (>25mmØ) are encountered during excavation, demolition and construction works, these roots must be retained undamaged and advice sought from the Project Arborist. The design and final levels must remain flexible to enable the retention of roots >25mmØ where deemed necessary by the Project Arborist.
- 13.9 **Ground Protection**
- 13.9.1 The movement of machinery should be restricted to existing paved areas or in areas with temporary ground protection (i.e. steel road plates, ground mats) when deemed necessary by the Project Arborist.
- 13.9.2 Ground protection should be installed as per AS4970 and Appendix 7- Typical Tree Protection Detail.
- 13.9.3 If irrigation is considered necessary, it should be installed first and by a licensed irrigator under the supervision of the Project Arborist with no trenching.
- 13.9.4 The irrigation should be covered with a layer of geotextile and mulched to a depth of 100mm with a non-toxic product (i.e. woodchips) with no fines.
- 13.9.5 Once the irrigation, geotextile and mulch are in place then the ground protection boards (steel plates or rumble boards) can in be installed.
- 13.9.6 Boards should remain in place for the entire build.
- 13.10 Trunk & Branch Protection
- 13.10.1 If trunk protection is required it should be installed by wrapping the trunk and first order branching with padding (i.e. carpet underlay or 10mm thick geotextile) to a minimum height of 2m. Timber battens (90 x 45mm), spaced at 150mm centres should be strapped together and placed over the padding (Refer to AS4970 for further details).
- 13.10.2 Branch protection should be installed when considered necessary by the Project Arborist.
- 13.10.3 Branches should be wrapped with padding (i.e. Ableflex) to provide protection. Where possible, branches should be tied back and construction works to take place around branches (with appropriate branch protection installed as required). If pruning is unavoidable it should be in accordance with AS4373 and supervised by the Project Arborist.
- 13.11 Structure & Pavement Demolition
- 13.11.1 The Project Arborist should supervise the demolition of existing structures/pavement within the TPZ. Machinery is to be excluded from the TPZ unless operating from existing slabs, pavements or areas of ground protection. Machinery should not contact the tree's roots, trunks, branches and crown.
- 13.11.2 Existing pavement should be hand lifted to minimise disturbance to the existing sub-base and to prevent damage to tree roots. Wherever possible, the existing sub-base material should remain in situ.
- 13.11.3 When removing slab sections within the TPZ, machinery must work from the tree outwards to ensure the machinery always remains on the un-demolished section of slab. Wherever possible, footings or elements below grade should be retained to minimise disturbance to the tree's roots.
- 13.11.4 Structures must be shattered with hand-operated pneumatic/electric breaker before removal when considered necessary by the Project Arborist.
- 13.11.5 If roots (>25mm∅) are encountered during excavation, demolition and construction works these roots must be retained undamaged and advice sought from the Project Arborist. Exposed roots must be protected from direct sunlight, drying out and extremes of temperature by using 10mm thick jute geotextile fabric. This fabric should be kept moist at all times.
- 13.11.6 Where the Project Arborist determines that the tree is using underground elements (i.e. footings, pipes, rocks etc.) for support, these elements should be left *in situ*.
- 13.12 Pavement/Kerb Installation

CONSULTANCY

ARBORICULTURE

PLANT PATHOLOGY

13.12.1 Installation of pavements and sub-base within the TPZ must be supervised by the Project Arborist. New surfaces and sub-base materials should be placed above grade to minimise excavations and retain roots (unless prior root mapping has determined that there are no roots within the area of construction).

www.laurenceco.com.au

- 13.12.2 If roots (>25mm∅) are encountered during the installation of the new sub-base and surfaces these roots must be retained undamaged and advice sought from the Project Arborist. The design and final levels must remain flexible to enable the retention of roots >25mm∅ where deemed necessary by the Project Arborist.
- 13.12.3 Compaction of the ground prior to the installation of fill is not permitted.
- 13.12.4 New sub-base material should be a 20mm no-fines road base (i.e. Benedict Sand & Gravel- Product Code 20NF/RB or similar). Recycled concrete aggregates should not be used to avoid raising soil pH levels.
- 13.12.5 If required, bedding sand should be washed river sand (no crushed paving blends). The bedding sand should be consolidated with a pedestrian operated plate compactor only. If possible, pavement material should be permeable.
- 13.12.6 Kerbs within the TPZ should be modified to bridge roots (>25mm∅) unless root pruning is approved and undertaken by the Project Arborist.
- 13.13 Underground Services
- 13.13.1 The installation of underground services should be located outside of the TPZ. Where this is not possible they should be installed around or below roots (>25mm∅) using either hydrovac or hand excavation and supervised by the Project Arborist.
- 13.13.2 Boring methods may be used for the installation of services 800mm below grade. Excavations for starting and receiving pits for the boring equipment should be located outside of the TPZ or located to avoid roots (>25mmØ, or determined by the Project Arborist).
- 13.13.3 Excavations, Root Protection & Root Pruning
- 13.13.4 Excavations and root pruning within the TPZ must be supervised by the Project Arborist and should be avoided where possible.
- 13.13.5 No over-excavation, battering, or benching should be undertaken beyond the footprint of any structure unless approved by the Project Arborist. Hand excavation and root pruning along the excavation line should be completed prior to the commencement of mechanical excavation to prevent tearing and shattering damage to the roots.
- 13.13.6 Roots >25mmØ should be pruned by the Project Arborist only. Roots <25mmØ may be pruned by the Principal Contractor. Root pruning should be undertaken with clean, sharp secateurs or a pruning saw to ensure a smooth wound face, free from tears.
- 13.13.7 Damaged roots should be pruned behind the damaged tissues with the final cut made to the undamaged part of the root.



# 14.0 APPENDIX 9 | PLATES



a) Showing site from Plateau Road. b) Showing rear garden with Trees 9, 10 & 20. c) Showing Trees 25 and 12 with large trunk cavity. d) Showing localised crown death on Tree 12. e) Showing Trees 9 & 10. f) Showing Trees 13-15.



# 15.0 APPENDIX 10 | LIMITATIONS & DISCLAIMERS

- 15.1 Subject trees were assessed from the ground only and for providing an Arboricultural Impact Assessment and Tree Protection Specification.
- All recommendations in this Arboricultural Impact Assessment and Tree Protection Specification report are based on the observations made on the day of inspection (23.10.24). There is no warranty, expressed or implied, that problems or deficiencies relating to the subject trees, or the subject site may not arise in the future.
- Laurence & Co Consultancy takes care to obtain information from reliable sources. However, Laurence & Co Consultancy can neither guarantee nor be responsible for the accuracy of information provided by others. Plans, diagrams, graphs and photographs in this Arboricultural Impact Assessment and Tree Protection Specification report are visual aids only and are not necessarily to scale. This report provides recommendations relating to tree management only. Advice should be sought from appropriately qualified consultants regarding design/construction/ecological/heritage etc. issues
- This report has been prepared for exclusive use by the client. This report should not be viewed by others or for any other reason outside its intended target or without the prior written consent of Laurence & Co Consultancy. Unauthorised alteration or separate use of any section of the report invalidates the report.
- Many factors may contribute to tree failure and cannot always be predicted. Laurence & Co Consultancy takes care to accurately assess tree health and structural condition. However, a tree's internal structural condition may not always correlate to visible external indicators.
- Limitation of Liability. Laurence & Co Consultancy shall be liable only for direct damages that result from negligence or wilful misconduct in the performance of its services. Under no circumstances shall Laurence & Co Consultancy be liable for indirect, consequential, special, or punitive damages, or for damages caused by the client's failure to perform its obligations under law or contract. Laurence & Co Consultancy shall not be liable for and Client shall indemnify Laurence & Co Consultancy from and against all claims, demands, liabilities and costs (including attorneys' and expert fees) arising out of or in any way related to our performance or non-performance of services, including all on-site activities except to the extent caused by Laurence & Co Consultancy's negligence or wilful misconduct. In no event shall Laurence & Co Consultancy's liability exceed the amount paid to Laurence & Co Consultancy by the Client for our professional services (net of reimbursable expenses) and Client specifically releases Laurence & Co Consultancy for any damages, claims, liabilities and costs in excess of that amount.
- 15.7 Reference should be made to any relevant legislation including Tree Management Controls. All recommendations contained within this report are subject to approval from the relevant Consent Authority.

