### Notes

Notes:

Levels shown are approx. and should be verified on site
Figured dimensions are to be taken in preference to scaling
All measurements are in mm unless otherwise stated
Window sizes are nominal only. Final window sizes by builder
Dimensions are to be verified on site by builder before commencement of work
Centre line of downpipes to be 350mm from corner of face brickwork (unless specified on elevation)
Refer to the builders project specification for inclusions
Construction to be in accordance with the Relevant BCA and other relevant Australian standards
All service positions, air conditioning droppers, outlets, return air grills, manholes and bulkheads to be determined on site by supervisor
Termite protection to Australian standards
Refer to Basix page for energy requirements
Comm tolerance to be allowed for frames that are built to the low side of the slab
All upstairs windows with a sill beight less than 1700mm to have a max opening width of 125mm or fitted with a screen with secure fitti

14. All upstairs windows with a sill height less than 1700mm to have a max opening width of 125mm or fitted with a screen with secure fittings to comply with BCA

15. Final AJ's to engineers specifications

16. Plus or minus 200mm to floor level

## Copyright to plans remains at all times with Abeaut design t/a Accurate Design and Drafting.

THESE NOTES MUST BE READ AND UNDERSTOOD BY ALL INVOLVED IN THE 3. TRAFFIC MANAGEMENT PROJECT.

THIS INCLUDES (but is not limited): OWNER, BUILDER, SUBCONTRACTORS, CONSULTANTS, RENOVATORS, OPERATORS, MAINTAINERS, DEMOLISHERS.

#### 1 FAULS, SLIPS, TRIPS

a) WORKING AT HEIGHTS DURING CONSTRUCTION Wherever possible, components for this building should be prefabricated off-site or at ground level to minimize the risk of workers failing more than two meters. However, construction of this building will require workers to be working at heights where a fail in excess of two meters is possible and injury is likely to result from such a fail. The builder should provide such a barrier wherever a person is required to work in a situation where failing more than two meters is a possibility.

DURING OPERATION OR MAINTENANCE For houses or other low-rise buildings when scaffolding is appropriate: Cleaning and maintenance of windows, walls, coof or other components of this building will require persons to be situated where a fail from a height in excess of two meters is possible. Where this type of activity is required scaffolding, ladders or trestles should be used in accordance with relevant codes of practice, regulations or legislation. Cleaning and maintenance of windows, walls, roof or other components of this building will require persons to be in situations where a fail from a height in excess of two meters is possible. Where this type of activity is required, scaffolding fail barriers or Personal Protective Equipment (PPE) should be used in accordance with relevant codes of practice, regulations or legislations.

#### b) SUPPERY OR UNEVEN SURFACES

b) SUPPERY OR UNEVEN SURFACES FLOOR FINISHES Specified If finishes have been specified by the designer these have been selected to minimize the risk of floors and paved areas becoming silpoper when wet or when walked on with wet shoes/feet. Any changes to The specified finished should be made in consultation with the designer, or if this is not practical, surfaces with an equivalent or better silp resistance should be chosen. FLOOR FINISHES By Owner If a designer has not been involved in the selection of surface finishes in the pedestrian trafficable areas of this building then surfaces should be selected in accordance with AS HB 197:1999 and AS/NZ 458:FO04.

areas of this building then surfaces should be selected in accordance with AS HB 197:1999 and AS/NZ 458:004, STEPS, LOOSE OBJECTS AND UNEXEN SURFACES Due to design restrictions for building, steps and/or ramps are included in the building which may be a hazard to workers carrying objects or otherwise occupied. Steps should be clearly marked with both visual and tactile warning during construction, maintenance, demoition and at all times when the building operates as a workplace. Building owners and occupiers should monitor the pedestrian access ways and in particular access to areas where maintenance is routinely carried out to ensure that surfaces have not moved or cracked so that they become uneven and present a trip hazard. Spills, loose material, stray objects or any other matter that may cause a silp or trip hazard. Spills, loose material, stray objects or any other matter that may cause a silp or trip hazard. Spills, exonstruction, maintenance or demolition or enduce the risk of trips and fails in the workplace. Materialise. Advention assess ways. Contractors should be required to maintain a tdy work site during construction, maintenance should be sorted in designated areas away from access ways and work areas.

#### 2. FALLING OBJECTS

LOOSE MATERIALS OR SMALL OBJECTS Construction, maintenance or demolifon work on or around this building is likely to involve persons working above ground level or above floor levels. Where this occurs one or more of the following measures should be taken to avoid objects falling from the area where the works is being carried out onto persons below. 1. Prevent or restrict access to areas below where the works is being carried

out. Provide tie boards to scaffolding or work platforms. Provide protective structure below the work area. Ensure that all persons below the work area have Personal Protective

#### BUILDING COMPONENTS

SUBJING CONTRUMENTS During construction, renovation or demolition of this building, parts of the structure including fabricated steelwork, heavy panels and many other components will remain standing prior to or after the support parts are in place. Contractors should ensure that temporary bracing or other required support is in place at all times to avoid a collapse, which may injure persons in the area.

Mechanical lifting of materials and components during construction, maintenance or demolition presents a risk o failing objects. Contractors should ensure that appropriate lifting devices are used, that loads are properly secure and that access to areas below the load is prevented or restricted.

#### Amendments

Н

Electrical, Wet Areas

For building on a major, narrow or steeply sloping road: Parking of vehicles or loading/unloading of vehicles on this roadway may cause a traffic hazard. During construction, maintenance or demolition of this building designated parking for workers and loading areas should be provided. Trained traffic management personnel should be responsible for the supervision of these areas. For building where on-site loading/unloading is restricted: Construction of this buildin planned to avoid congestic n of this building will require loading and unloading of materials on the roadway. Deliveries should be avoid congestion of loading areas and trained traffic management personnel should be used to

r or an unnung: Busy construction and demolition sites present a risk of collision where deliveries and other traffic are moving within the site. A traffic management plan supervised by trained traffic management personnel should be adopted for the work site.

4. SERVICES

#### GENERAL

GENERAL Rapture of services during excavation or other activity creates a variety of risks including release of hazardous materials. Existing services are located on or around the site. Where known, these are identified on the plans but the exact location and extent of services may vary from that indicated. Services should be located using an appropriate service (such as Dial Before You Dig), appropriate excavation practice should be used and, where necessary, specialist contractors should be used. Locations with underground power lines: Underground power lines MAV be located near or on this site. These pose a risk of electrocution if struck or approached by lifting devices or other plant and persons working above ground level. Where there is a danger of this occurring power lines should be, where practical, discontexted. Where this is not practical adequate warning in the form of bright coloured tape or signage should be used or a protective barrier provided.

#### 5. MANUAL TASKS

# Components within this design with a mass in excess of 25kg should be lifted by two or more workers or by a mechanical lifting device. Where this is not practical, suppliers or fabricators should be required to limit the component mass. All material packaging, building and maintenance components should clearly show the total mass of packages and where practical all items should be sorted on site in a way which minimizes bending before lifting. Advice should be provided about unsafe lifting methods in areas where lifting may occur. Construction, maintenance and demolitor of this building will require the use of portable tools and equipment. These should be fully maintained in accordance with manufacturers specifications and not used when faulty or (in the case of electrical equipment) not carring a current electrical safety tag. All safety guards or devices should be requirarly checked and Personal Protective Equipment should be used in an accordance with the manufacturer's specification.

6. HAZARDOUS SUBSTANCES

ASSESTOS For alterations to a building constructed prior to: 1990 - It therefore may contain asbestos 1986 - It therefore is likely to contain asbestos Ethere in cladding material or in fire retariant insulation material. In either case, the builder should check and, if necessary, take appropriate action before demolishing, cutting, sanding drilling or otherwise disturbing the existi-

## POWDERED MATERIALS

POWDERED MATERIALS Many materials used in the construction of this building can cause harm if inhaled in a powder form. Persons working on or in the building during construction, operational maintenance or demolition should ensure food ventilation and wear Personal Protective Equipment including protection against inhalation while using powdered material or when sanding, drilling, cutting or otherwise disturbing or creating powdered material.

### TREATED TIMBER

10-08-18

The Asign of this building may include provision for the inclusion of treated timber within the structure. Dust or furnes from this material can be harmful. Persons working on or in the building during construction, operational maintenance or demolition should ensure good ventifation and wear Personal Protective Equipment including protection against inhalation of harmful materials when sanding, drilling, cutting or using treated timber in any way that may cause harmful material to be released. Do not burn treated timber.

## VOLATILE ORGANIC COMPOUNDS

V.B.

18006-7

VOLATILE ORGANIC COMPOUNDS Man typed of glue, solvents, spray back, paints, vanishes, and some cleaning materials and disinfectants have dangerous emissions. Areas where these are used should be kept well ventilated while the material is being used and for a period after installation. Personal Protective Equipment may also be required. The manufacturer's recommendations for use must be carefully considered at all times.

#### SYNTHETIC MINERAL FIBRE

There is a second secon

#### TIMBER FLOORS

TIMBER FLOORS This building may contain timber floors which have an applied finish. Areas where finishes are applied should be kept well ventilated during sanding and application and for a period after installation. Personal Protective Equipment may also be required. The manufacturer's recommendation for use must be carefully considered at all

#### 7. CONFINED SPACES

EXCAVATIONS Construction of this building and some maintenance of the building will require excavation and installation of items within excavation. Where practical, installation should be carried out using methods which do not require workers to enter the excavations. Where this is not practical, adequate support for the excavated area should be provided to prevent a collapse. Warning signs and barriers to prevent accidental or unauthorized access to all excavations

#### ENCLOSED SPACES

Enclosed spaces with enclosed spaces where maintenance or other access may be required: Enclosed spaces within this building may be present a risk to persons entering for construction, maintenance or any other purpose. The design documentation calls for warning signs and barriers to unauthorized access. These should be maintained throughout the life of the building. Where workers are required to enter enclosed spaces, air testing equipment and Personal Protective Equipment should be provided.

SMALL SPACES For buildings with small spaces where maintenance or other access may be required: some small spaces within this building will require access by construction or maintenance workers. The design documentation calls for warning signs and barriers to unauthorized access. These should be maintained throughout the life of the building. Where workers are required to enter small spaces they should be scheduled so that access is for short periods. Manual lifting and other manual activity should be restricted in small spaces.

#### 8. PUBLIC ACCESS

Public access to construction and demoiltion sites and to areas under maintenance causes risk to workers and public. Warning signs and secure barriers to unauthorized access should be provided. Where electrical installations, excavations, plant or loose materials are present they should be secure when not guily supervised.

#### 9. OPERATIONAL USE OF BUILDING RESIDENTIAL BUIDLINGS

This building has been designed as a residential building. If it, at a later date, is used or intended to be used as a workplace, the provisions of the Work Health and Safety Act 2011 or subsequent replacement Act should be applied to the new use.

#### **10. OTHER HIGH RISK ACTIVITY**

All electrical work should be carried out in accordance with the Code of Practice: Managing Electrical Risks at the Workplace, AS/NZ 3012 and all licensing requirements. All work using Plant should be carried out in accordance with the Code of Practice: Managing Risks of Plant at the Workplace. Managing Risks of Plant at the Workplace. All work should be carried out in accordance with the Code of Practice: Managing Noise and Preventing Hearing Loss at Work. Due to the history of serious incidents it is recommended that particular care be exercised when undertaking work involving steel construction and concrete placement

				Sheet Number	Sheet Name
				01	Cover Page
				02	Perspective View
				03	Ground Floor Plan
	Date	Signed/Requested	Drawing Number	04	Upper Floor Plan
	15-08-18	S.G.	18006-8	05	Elevations
				06	Elevation, Section & Details
	20-08-18	S.G.	18006-9	07	Site Plan
	06-09-18	S.G.	18006-10	08	Landscape Plan & Drainage Diagram
				09	Slab Detail
				10	Electrical Plan
				11	Shadow Diagrams 21st June
				12	Wet Area Details
				L	
_					
					Client Approval:









Karinya Lot Number: 20 **DP Number: UNREG** 

# design and drafting

Office: 1a/10 Exchange Parade Narellan NSW 2567 Phone : 0246472552 Email: info@accuratedesign.com.au

# Icon Job Number: J/0343



Job:								
Proposed B/V Residence								
Perspective View								
Scale:	Date:							
-	06-09-18							
Drawing No:	Sheet:	Issue:						
18006-10	2/12	K						
© abeaut designs t/a Accurate Design and Drafting 2018								





















# **EXTERNAL COLOUR SCHEDULE**

Client Name: Andrew Colin & Sharon Clark Job Address: Lot 20, Karinya Estate, Warriewood

ROOF TILE	GUTTER & DOWNPIPE	FRONT DOOR	RENDER/CLADDING	GARAGE D
BRISTILE COAL	COLORBOND SURFMIST	COLORBOND NIGHT SKY	TAUBMANS TAX TIME	TAUBMA BRIGHT V
PAINTED HINGED DOORS	FASCIA	ALUMINIUM WINDOWS & DOORS	BALCONY POST/BALUSTRADE	DRIVEWAY
TAUBMANS BRILLIANT WHITE	<b>COLORBOND</b> SURFMIST	STEGBAR PEARL WHITE	TAUBMANS BRIGHT WHITE	
		CLIENT 2 SIGNATURE	ANDREW COLIN Andrew C SHARON CLARK Allow Rebecca Cleary	DATE: :

NOTE: This external colour schedule is final. No changes will be permitted unless required by the developer/council. Changes outside of this will incur an administration fee. Please note images are an indication only and may not be a true representation of the final product/colour. Please refer to your Product Selection Document for further details.





