SECT 4.56 L A N D S C A P E PLAN

8 FOREST ROAD, WARRIEWOOD



Drawing L	ist				
Sheet No.	Sheet Name	Sheet Size	Rev. No.	Rev. Date	Project No.
L-00	TITLE PAGE	A1	U	01/07/24	15-826
L-01	LANDSCAPE MASTER PLAN	PLAN A1 U		01/07/24	15-826
L-02	EXISTING TREES PLAN		U	01/07/24	15-826
L-03	GROUND FLOOR EAST LANDSCAPE PLAN - 1	A1	U	01/07/24	15-826
L-04	GROUND FLOOR EAST LANDSCAPE PLAN - 2	JND FLOOR EAST LANDSCAPE PLAN - 2 A1 U		01/07/24	15-826
L-05	GROUND FLOOR WEST LANDSCAPE PLAN - 1	A1	U	01/07/24	15-826
L-06	GROUND FLOOR WEST LANDSCAPE PLAN - 2	A1	U	01/07/24	15-826
L-07	RIPARIAN PLANTING	A1	U	01/07/24	15-826
L-08	SOIL DEPTH ZONES PLAN	A1	U	01/07/24	15-826
L-09	LANDSCAPING/OPEN SPACE CALCULATION PLAN	A1	U	01/07/24	15-826
L-10	SECTIONS	A1	U	01/07/24	15-826
L-11	SECTIONS	A1	U	01/07/24	15-826
L-12	SECTIONS	A1	U	01/07/24	15-826
L-13	PLANTING SCHEDULE	A1	U	01/07/24	15-826
L-14	TYPICAL DETAILS & NOTES	A1	U	01/07/24	15-826
				1	I

+STUDIOS

SYDNEY NORTH STUDIO PO Box 265 **SEAFORTH NSW 2092** 0417685846 <u>p</u> 1300 22 44 55 info@sdstudios.com.au www.sdstudios.com.au

OCT

LANDSCAPE MAINTENANCE NOTES

(SEASOL) IRRIGATION WEED

REMOVAL

PRUNING WEED

SPARAYING IRRIGATION

N/A 2ND D

N/A 2ND D

N/A 2ND D

2ND D

MOWING FERTILISING CHECK HAND

EDGING

BLOWING

PLANTING ESTABLISHMENT PERIOD - 12 MONTHS LANDSCAPE MATERIAL ESTABLISHMENT - 12 MONTHS

KEY D-DAILY, W-WEEKLY, F-FORTNIGHT, M-MONTHLY, 2ND DAY,

Project	WARRIEWOOD VALE DEVELOPMENT	
Address	8 FOREST ROAD, WARRIEWOOD	
Drawing T	itle TITLE PAGE	
Client	WARRIEWOOD VALE P/L Scale N.T.S @A1	Drawing No. 15-82

WATERING/ PLANT REPLACEMENT IF REQUIRED

W

W

W

W

W

W

W

W

W

01/07/24 ISSUE SECT 4.56 FOR APPROVAL 13/03/24 ISSUE SECT 4.56 FOR **APPROVAL** 09/01/24 ISSUE SECT 4.56 FOR APPROVAL 29/11/23 ISSUE SECT 4.56 FOR APPROVAL 17/11/23 ISSUE SECT 4.56 FOR APPROVAL

ISSUE DATE COMMENT

AMENDMENTS

GENERAL NOTES All work to be carried out in accordance with the Building Code of Australia, all Local and State Government Ordinances, relevant Australian Standards, Local Authorities Regulations and all other relevant Authorities concerned. All structural work and site drainage to be subject to Engineer's details or certification where required by Council. This shall include r.c. slabs and footings, r.c. and steel beams & columns, wind bracing to AS 1170 and AS4055, anchor rods or bolts, tie downs, fixings etc., driveway slabs and drainage to Council's satisfaction. All timbers to be in accordance with SAA Timber Structure Code AS1720 and SAA Timber Framing Code AS 1684. All work to be carried out in a professional and workman-shiplike manner according to the plans and specification.

Do not scale off the drawings unless otherwise stated and use figured dimensions in preference.

All dimensions are to be checked and verified on site before the commencement of any work, all dimensions and levels are subject to final survey and set-out

No responsibility will be accepted by Sitedesign for any variations in design, builder's method of construction or materials used, deviation from specification without permission or accepted work practices resulting in inferior construction. Locate and protect all services prior to construction.

This drawing and design is the property of Sitedesign and should not be reproduced either in part or whole without the written consent of this firm

MAINTENANCE GENERAL NOTES

SECTION C: LANDSCAPE MAINTENANCE SPECIFICATION 1.0 SCOPE

The 52 week Planting Establishment Period commences at the date of registration of the repective plan. The contractor is to also allow for maintenance from the date of Practical Completion to the start date of the 52 week Planting Establishment Period. The allowance shall be for a weekly rate which will then be implemented until the formal maintenance period commences. 1.2 PROGRAM

Furnish a proposed planting maintenance program with the tender.

1.3 MAINTENANCE LOGBOOK

Contractor to keep a maintenance record of works carried out on a monthly basis. Log should include but not

limited to: - Activities carried out during each attendance;

- Irregularities encountered and actions taken;

NB: Maintenance payments will be evaluated on submission of monthly logbooks.

1.4 RECURRENT WORKS

Throughout the Planting Establishment Period, continue to carry out recurrent works of a maintenance nature including, but not limited to, watering, mowing, weeding, rubbish removal, fertilising, pest and disease control, staking and tying, replanting, cultivating, pruning and keeping the site neat and tidy. All rubbish related to landscape works shall be removed by the landscape contractor before it is allowed to accumulate. 1.5 PLANTING

Commence recurrent planting maintenance works at the completion of planting. Ensure the stock arriving on site is protected and maintained for healthy growth.

1.6 REPLACEMENTS

Continue to replace failed, damaged or stolen plants for the extent of the Planting Establishment Period.

1.7 MULCHED SURFACES

Maintain the surface in a clean and tidy condition and reinstate the mulch as necessary.

1.8 GRASSED AREAS

Commence grass maintenance works at the completion of turfing, and continue to carry out grass maintenance throughout the contract and Planting Establishment Period, maintaining healthy weed free growth.

Adjust or replace as required. Remove those not required at the end of the Planting Establishment Period. 1.10 WATERING/ IRRIGATION

An irrigation system is to be installed to all mass planted beds and new tree planting, conntected to a pump and the rainwater tank /OSD tank. Install one tap near the front boundary (Wurrook Circuit) and one tap on the rear (eastern) boundary. This system shall be installed and maintained for the duration of the maintenance period (52 weeks) and in perpetuity of the development. All irrigation works shall be performed by a licensed irrigation contractor. Materials to be used are to be submitted to the site superintendent for approval. The contractor shall

provide design drawings and material specifications/samples prior to commencing work. All works are to be conducted to all current and relevant Australian Standards.

The contractor is to be completely responsible for the coordination of the installation of the irrigation system with other services throughout the site. Recommended flow rates: The system shall be set up on a trial basis and them adjusted to suit the local requirements and conditions. Once the system is satisfactorily adjusted the contractor shall make fortnightly visits within the establishment period to ensure satisfactory performance of the system and to adjust the watering periods as required. A minimum even coverage of 25mm of water per week is

recommended. 2.0 REPORTS

2.1 LANDSCAPE MAINTENANCE REPORT

'Landscape Maintenance Reports' shall be submitted to the Principle Certifying Authority by the contractor verifying that satisfactory maintenance of the landscape works has been undertaken and that any necessary rectification measures have been carried out to a high professional standard. This documentation is to be submitted through the plant establishment period.

Page

L-00

creating places to

live in and enjoy



APPROVAL 13/03/24 ISSUE SECT 4.56 FOR **APPROVAL** 09/01/24 ISSUE SECT 4.56 FOR APPROVAL 29/11/23 ISSUE SECT 4.56 FOR **APPROVAL** 17/11/23 ISSUE SECT 4.56 FOR **APPROVAL**

01/07/24 ISSUE SECT 4.56 FOR

ISSUE DATE COMMENT

AMENDMENTS

NOTES

GENERAL NOTES All work to be carried out in accordance with the Building Code of Australia, all Local and State Government Ordinances, relevant Australian Standards, Local Authorities Regulations and all other relevant Authorities concerned. All structural work and site drainage to be subject to Engineer's details or certification where required by Council. This shall include r.c. slabs and footings, r.c. and steel beams & columns, wind bracing to AS 1170 and AS4055, anchor rods or bolts, tie downs, fixings etc., driveway slabs and drainage to Council's satisfaction. All timbers to be in accordance with SAA Timber Structure Code AS1720 and SAA Timber Framing Code AS 1684. All work to be carried out in a professional and workman-shiplike manner according to the plans and specification.

Do not scale off the drawings unless otherwise stated and use figured dimensions in preference.

All dimensions are to be checked and verified on site before the commencement of any work, all dimensions and levels are subject to final survey and set-out

No responsibility will be accepted by Sitedesign for any variations in design, builder's method of construction or materials used, deviation from specification without permission or accepted work practices resulting in inferior construction. Locate and protect all services prior to construction. This drawing and design is the property of Sitedesign and should not be

reproduced either in part or whole without the written consent of this firm.

EXISTING TREE LEGEND:



LEGEND: **— —** BOUNDARY LINE --- BASEMENT LINE

RL 30.10 PROPOSED LEVELS TOW 30.93 PROPOSED TOP OF WALL

CONCRETE PATHWAY

ROAD - ASPHALT

DEEP SOIL GARDEN BEDS

PODIUM GARDEN BEDS

BIO-RETENTION BASIN

JREPAVE - TURF

PROPOSED BUILDING

SEALED FIRE ACCESS ROAD

AS SELECTED DECK

AS SELECTED PAVER

AS SELECTED PAVER

AS SELECTED PAVER

AS SELECTED PAVER

AS SELECTED PEBBLES

TILED AREA

RETAINING WALL

STORMWATER PIT REFER TO CIVIL DETAILS

creating places to live in and enjoy

+STUDIOS

SYDNEY NORTH STUDIO PO Box 265
SEAFORTH NSW 2092
0417685846
p 1300 22 44 55
info@sdstudios.com.au

WARRIEWOOD VALE DEVELOPMENT Project 8 FOREST ROAD, WARRIEWOOD Address Drawing Title LANDSCAPE MASTER PLAN Drawing No. **15-826** Client WARRIEWOOD VALE P/L Scale 1:500 @A1

Page



SITEDESIGN +STUDIOS

SYDNEY NORTH STUDIO
PO Box 265
SEAFORTH NSW 2092
0417685846
p 1300 22 44 55
info@sdstudios.com.au
www.sdstudios.com.au


Project WARRIEWOOD VALE DEVELOPMENT

Address 8 FOREST ROAD, WARRIEWOOD

Drawing Title EXISTING TREES PLAN

Client WARRIEWOOD VALE P/L Scale 1:500 @A1 Drawing No. 15-826

Page



1800mm High Lapped & Capped

Timber Boundary Fence

TREE PLANTING WITH SHRUBS & GROUNDCOVERS

creating places to live in and enjoy

+STUDIOS

SYDNEY NORTH STUDIO PO Box 265
SEAFORTH NSW 2092
0417685846
p 1300 22 44 55
info@sdstudios.com.au

8 FOREST ROAD, WARRIEWOOD Address

Drawing Title GROUND FLOOR EAST LANDSCAPE PLAN - 1 Drawing No. **15-826** Client WARRIEWOOD VALE P/L Scale 1:200 @A1



+STUDIOS

SYDNEY NORTH STUDIO
PO Box 265
SEAFORTH NSW 2092
0417685846
p 1300 22 44 55
info@sdstudios.com.au

WARRIEWOOD VALE DEVELOPMENT Project

8 FOREST ROAD, WARRIEWOOD Address

Drawing Title GROUND FLOOR EAST LANDSCAPE PLAN - 2

Client WARRIEWOOD VALE P/L Scale 1:200 @A1

L-04 Drawing No. **15-826**



LANDSCAPE ARCHITECTS // CONSTRUCTION // MAINTENANCE // IRRIGATION

+STUDIOS

SYDNEY NORTH STUDIO
PO Box 265
SEAFORTH NSW 2092
0417685846
p 1300 22 44 55
info@sdstudios.com.au

Drawing Title GROUND FLOOR WEST LANDSCAPE PLAN - 1

WARRIEWOOD VALE P/L Scale 1:200 @A1 Client

Drawing No. **15-826**



9


+STUDIOS

SYDNEY NORTH STUDIO PO Box 265
SEAFORTH NSW 2092
0417685846
p 1300 22 44 55
info@sdstudios.com.au

8 FOREST ROAD, WARRIEWOOD Address

Drawing Title GROUND FLOOR WEST LANDSCAPE PLAN - 2

Client WARRIEWOOD VALE P/L Scale 1:200 @A1 Drawing No. **15-826**





SYDNEY NORTH STUDIO
PO Box 265
SEAFORTH NSW 2092
0417685846
p 1300 22 44 55
info@sdstudios.com.au
www.sdstudios.com.au


Project WARRIEWOOD VALE DEVELOPMENT

Address 8 FOREST ROAD, WARRIEWOOD

Drawing Title RIPARIAN PLANTING

Client WARRIEWOOD VALE P/L Scale 1:500 @A1 Drawing No. 15-826

Page





SYDNEY NORTH STUDIO
PO Box 265
SEAFORTH NSW 2092
0417685846
p 1300 22 44 55
info@sdstudios.com.au
www.sdstudios.com.au

Project	WARRIEWOOD VALE DEVELOPMENT	
Address	8 FOREST ROAD, WARRIEWOOD	
Drawing Titl	e SOIL DEPTH ZONES PLAN	
Client	WARRIEWOOD VALE P/L Scale 1:500 @A1	Drawing No. 15-826

Page

01/07/24 ISSUE SECT 4.56 FOR APPROVAL
13/03/24 ISSUE SECT 4.56 FOR APPROVAL
09/01/24 ISSUE SECT 4.56 FOR APPROVAL
29/11/23 ISSUE SECT 4.56 FOR APPROVAL
17/11/23 ISSUE SECT 4.56 FOR APPROVAL

ZONE 2 - DEPTH VARIES DUE TO RAMP (BASEMENT LID)

ZONE 3 - 300mm STEP DOWN IN LANDSCAPE NATURAL GRASS

ISSUE DATE COMMENT

ZONE 1 - DEEP SOIL ZONE

ZONE 4 - DEEP PLANTER 800mm DEPTH TOTAL 400mm STEP DOWN + 400mm ABOVE SLAB


EXISTING TREE LEGEND:

EXISTING TREES TO BE RETAINED

TREES TO BE REMOVED

AMENDMENTS -

SOIL DEPTH ZONES:



+STUDIOS

PO Box 265
SEAFORTH NSW 2092
0417685846
p 1300 22 44 55
info@sdstudios.com.au

Drawing Title LANDSCAPING/OPEN SPACE CALCULATION PLAN Drawing No. **15-826** WARRIEWOOD VALE P/L Scale 1:500 @A1 Client



01/07/24 ISSUE SECT 4.56 FOR APPROVAL 13/03/24 ISSUE SECT 4.56 FOR APPROVAL 09/01/24 ISSUE SECT 4.56 FOR APPROVAL 29/11/23 ISSUE SECT 4.56 FOR APPROVAL

APPROVAL ISSUE DATE COMMENT

AMENDMENTS -

GENERAL NOTES All work to be carried out in accordance with the Building Code of Australia, all Local and State Government Ordinances, relevant Australian Standards, Local Authorities Regulations and all other relevant Authorities concerned.
All structural work and site drainage to be subject to Engineer's details or certification where required by Council. This shall include r.c. slabs and footings, r.c. and steel beams & columns, wind bracing to AS 1170 and AS4055, anchor rods or bolts, tie downs, fixings etc., driveway slabs and drainage to Council's satisfaction. All timbers to be in accordance with SAA Timber Structure Code AS1720 and SAA Timber Framing Code AS 1684. All work to be carried out in a professional and workman-shiplike manner according to the plans and specification.

17/11/23 ISSUE SECT 4.56 FOR

Do not scale off the drawings unless otherwise stated and use figured dimensions in preference.


All dimensions are to be checked and verified on site before the

commencement of any work, all dimensions and levels are subject to final survey and set-out

No responsibility will be accepted by Sitedesign for any variations in design, builder's method of construction or materials used, deviation from specification without permission or accepted work practices resulting in inferior construction. Locate and protect all services prior to construction.

This drawing and design is the property of Sitedesign and should not be reproduced either in part or whole without the written consent of this firm.

SECTION 1 (REFER TO CC-01) RIPARIAN ZONE




SECTION 2 (REFER TO CC-04) ROAD
Scale: 1:50


creating places to live in and enjoy

+STUDIOS

SYDNEY NORTH STUDIO
PO Box 265
SEAFORTH NSW 2092
0417685846
p 1300 22 44 55
info@sdstudios.com.au

Page WARRIEWOOD VALE DEVELOPMENT Project 8 FOREST ROAD, WARRIEWOOD Address Drawing Title **SECTIONS** Drawing No. **15-826** Client WARRIEWOOD VALE P/L Scale 1:50 @A1





ISSUE DATE COMMENT

AMENDMENTS -

NOTES

GENERAL NOTES

All work to be carried out in accordance with the Building Code of Australia, all Local and State Government Ordinances, relevant Australian Standards, Local Authorities Regulations and all other relevant Authorities concerned. All structural work and site drainage to be subject to Engineer's details or certification where required by Council. This shall include r.c. slabs and footings, r.c. and steel beams & columns, wind bracing to AS 1170 and AS4055, anchor rods or bolts, tie downs, fixings etc., driveway slabs and drainage to Council's satisfaction. All timbers to be in accordance with SAA Timber Structure Code AS1720 and SAA Timber Framing Code AS 1684. All work to be carried out in a professional and workman-shiplike manner according to the plans and specification.


Do not scale off the drawings unless otherwise stated and use figured dimensions in preference.

All dimensions are to be checked and verified on site before the commencement of any work, all dimensions and levels are subject to final survey and set-out

survey and set-out

No responsibility will be accepted by Sitedesign for any variations in design, builder's method of construction or materials used, deviation from specification without permission or accepted work practices resulting in inferior construction. Locate and protect all services prior to construction. COPYRIGHT CLAUSE

This drawing and design is the property of Sitedesign and should not be reproduced either in part or whole without the written consent of this firm.



SECTION 4 (REFER TO CC-06) COMMUNAL OPEN SPACE Scale: 1:50

creating places to live in and enjoy



SYDNEY NORTH STUDIO
PO Box 265
SEAFORTH NSW 2092
0417685846
p 1300 22 44 55
info@sdstudios.com.au
www.sdstudios.com.au

Project WARRIEWOOD VALE DEVELOPMENT


Address 8 FOREST ROAD, WARRIEWOOD

Drawing Title SECTIONS

Client WARRIEWOOD VALE P/L Scale 1:50 @A1 Drawing No. 15-826

Page

L-11





SYDNEY NORTH STUDIO
PO Box 265
SEAFORTH NSW 2092
0417685846
p 1300 22 44 55
info@sdstudios.com.au
www.sdstudios.com.au

Project	WARRIEWOOD VALE DEVELOPMENT			
Address	8 FOREST ROAD, WARRIEWOOD			
Drawing Ti	tle SECTIONS			
Client	WARRIEWOOD VALE P/L Scale 1:50 @A1	Drawing No. 15-826		

Page

01/07/24 ISSUE SECT 4.56 FOR APPROVAL
13/03/24 ISSUE SECT 4.56 FOR APPROVAL
09/01/24 ISSUE SECT 4.56 FOR APPROVAL
29/11/23 ISSUE SECT 4.56 FOR APPROVAL
17/11/23 ISSUE SECT 4.56 FOR APPROVAL

All work to be carried out in accordance with the Building Code of Australia, all Local and State Government Ordinances, relevant Australian Standards, Local Authorities Regulations and all other relevant Authorities concerned. All structural work and site drainage to be subject to Engineer's details or certification where required by Council. This shall include r.c. slabs and footings, r.c. and steel beams & columns, wind bracing to AS 1170 and AS4055, anchor rods or bolts, tie downs, fixings etc., driveway slabs and drainage to Council's satisfaction. All timbers to be in accordance with SAA Timber Structure Code AS1720 and SAA Timber Framing Code AS 1684. All work to be carried out in a professional and workman-shiplike manner

Do not scale off the drawings unless otherwise stated and use figured

commencement of any work, all dimensions and levels are subject to final

No responsibility will be accepted by Sitedesign for any variations in design, builder's method of construction or materials used, deviation from specification without permission or accepted work practices resulting in inferior construction. Locate and protect all services prior to construction. COPYRIGHT CLAUSE

This drawing and design is the property of Sitedesign and should not be reproduced either in part or whole without the written consent of this firm.

All dimensions are to be checked and verified on site before the

ISSUE DATE COMMENT

according to the plans and specification.

dimensions in preference.

survey and set-out

AMENDMENTS -

GENERAL NOTES

L-12

SECTION 5 (REFER TO CC-01) PRIVATE ACCESS ROAD
Scale: 1:50


Plant Schedule						
ID	Qty	Common Name	Botanical Name	Scheduled Size	Mature Height	Mature Spread
Trees						
AS	108	Lillypilly	Acmena smithii	45L	5 - 10m	6 - 10m
ACost	20	Sydney Red Gum, Smooth-barked Apple	Angophora costata	150L	15 - 20m	6 - 10m
AF	1	Rough-barked Apple	Angophora floribunda	150L	10 - 15m	6 - 10m
Ban-int	7	Coastal Banksia	Banksia integrifolia	45L	5 - 10m	3.5 - 6m
Euc-ra	1	Snappy gum	Eucalyptus racemosa	45L	8-15m	6 - 10m
Euc-ro	23	Swamp Mahogany	Eucalyptus robusta	75L	5m	3m
Hym-fl	3	Native frangipani	Hymenosporum flavum	400L	6-9m	6-8m
Lag-na	10	Natchez Crepe Myrtle	Lagerstroemia 'Natchez'	400L	6-8m	4-6m
LAust	5	Cabbage-tree Palm	Livistona australis	2m CT	15 - 20m	6 - 10m
mel-qui	10	Broad-leafed Paperbark	Melaleuca quinquenervia	45L	10 - 15m	3.5 - 6m
Plum-rub	31	Frangipani	Plumeria rubra	45L	3 - 5m	3.5 - 6m
syz-au're'	39	Lilly Pilly	Syzygium australe 'Resilience'	75L	4 - 6m	1.5m
TLaur-lus	26	Kanooka, Water Gum	Tristaniopsis laurina 'luscious'	400L	5 - 10m	3.5 - 6m
Shrubs						
Ban-eri	16	Heath-leaved Banksia	Banksia ericifolia	75L	3 - 5m	3.5 - 6m
Cor-alb	6	White Correa	Correa alba	200mm	0.9 - 1.5m	0.9 - 1.2m
Lav-ang-mun	498	Munstead Lavender	Lavandula angustifolia 'Munstead'	200mm	0.45 - 0.6m	0.6 - 0.9m
Іер-рс	35	Tea Tree	Leptospermum 'Pink Cascade'	200mm	1 - 3m	2m
Lep-pol	19	Jelly bush	Leptospermum polygalifolium	200mm	1.5 - 3m	2.0 - 3.5m
Mur-pan	156	Orange Jessamine	Murraya paniculata	200mm	1.5 - 3m	3.5 - 6m
Vib-odo	426	Viburnum	Viburnum odoratissmum	200mm	1500mm hedged	1000mm hedged
Wes-fru	585	Coastal Rosemary	Westringia fruticosa	200mm	0.6m	0.9m
Wes-wy	387	Wynyabbie Coast Rosemary	Westringia Wynyabbie Gem	300mm	1.6m	1.2m
Myo-par	6032	Carpet Spreading Myoporum	Myoporum parvifolium	150mm	0.45 - 0.6m	0.3m
Grasses						
Dia-cae	914	Paroo Lily, Blue Flax-lily	Dianella caerulea	150mm	0.6 - 0.75m	0.6 - 0.9m
Dor-exc	179	Gymea Lily	Doryanthes excelsa	300mm	1-2m	2-4m
gah-sie	189	Water Vine	Gahnia hypoglauca	150mm	2m	0.8m
jun-us	903	Rush	Juncus usitatus	150mm	1m	0.8m
Lom-lon	3656	Spiny-headed Mat-Rush	Lomandra longifolia	150mm	0.75 - 0.9m	0.9 - 1.2m
lom-ta	3621	Fine-leaved mat rush	Lomandra 'Tanika'	150mm	0.5m	0.6m
mic-sti	206	Weeping Grass	Microlaena stipoides	150mm	0.6 - 0.75m	0.6 - 0.9m
poa-la	3621	Tussock Grass	Poa labillardieri	150mm	0.6m	0.8m
Total	21733					

01/07/24 ISSUE SECT 4.56 FOR APPROVAL 13/03/24 ISSUE SECT 4.56 FOR APPROVAL 09/01/24 ISSUE SECT 4.56 FOR APPROVAL 29/11/23 ISSUE SECT 4.56 FOR 17/11/23 ISSUE SECT 4.56 FOR APPROVAL

ISSUE DATE COMMENT **AMENDMENTS** -



Lilly pilly









Myoporum parvifolium Yareena Creeping Boobiala



Angophora floribunda Rough Bark Apple



Flax Lilly

Banksia ericifolia Correa alba Heath-leaved banksia White correa



Doryanthes excelsa **Gymea Lilly**

Coastal Banksia




Eucalyptus racemosa
Narrow Leaved Scribbly Gum

















Client



Lagerstroemia Natchez Natchez Crepe Myrtle

Murraya paniculata Orange Jessamine

Lomandra tanika

Fine Leafed Mat Rush

WARRIEWOOD VALE P/L Scale N.T.S @A1



Livistona australis





Microlaena stipoides

Weeping grass



Westringia fruiticosa

Westringia

Melaleuca quinquenervia

Broad Leaf Paperbark

Poa labillardieri Tussock grass

Drawing No. **15-826**

creating places to live in and enjoy

SITEDESIGN +STUDIOS

SYDNEY NORTH STUDIO www.sdstudios.com.au

PO Box 265
SEAFORTH NSW 2092
0417685846
p 1300 22 44 55
info@sdstudios.com.au

WARRIEWOOD VALE DEVELOPMENT Project

8 FOREST ROAD, WARRIEWOOD Address


Drawing Title **PLANTING SCHEDULE**


Page


L-13


Plumeria rubra


Red Frangipani




















TYPICAL PLANTING/ PODIUM DETAIL
Scale: 1:20

SYDNEY NORTH STUDIO PO Box 265 **SEAFORTH NSW 2092** 0417685846 <u>р</u> 1300 22 44 55 info@sdstudios.com.au www.sdstudios.com.au

Client

Project WARRIEWOOD VALE DEVELOPMENT 8 FOREST ROAD, WARRIEWOOD Address

Drawing Title TYPICAL DETAILS & NOTES

Drawing No. **15-826**

01/07/24 ISSUE SECT 4.56 FOR APPROVAL ISSUE SECT 4.56 FOR **APPROVAL** ISSUE SECT 4.56 FOR **APPROVAL** 29/11/23 ISSUE SECT 4.56 FOR APPROVAL 17/11/23 ISSUE SECT 4.56 FOR **APPROVAL**

ISSUE DATE COMMENT

AMENDMENTS

All work to be carried out in accordance with the Building Code of Australia, all Local and State Government Ordinances, relevant Australian Standards, Local Authorities Regulations and all other relevant Authorities concerned All structural work and site drainage to be subject to Engineer's details or certification where required by Council. This shall include r.c. slabs and footings, r.c. and steel beams & columns, wind bracing to AS 1170 and AS4055, anchor rods or bolts, tie downs, fixings etc., driveway slabs and drainage to Council's satisfaction. All timbers to be in accordance with SAA Timber Structure Code AS1720 and SAA Timber Framing Code AS 1684. All work to be carried out in a professional and workman-shiplike manner according to the plans and specification.

Do not scale off the drawings unless otherwise stated and use figured

All dimensions are to be checked and verified on site before the commencement of any work, all dimensions and levels are subject to final survey and set-out No responsibility will be accepted by Sitedesign for any variations in design,

builder's method of construction or materials used, deviation from specification without permission or accepted work practices resulting in inferior construction. Locate and protect all services prior to construction.

This drawing and design is the property of Sitedesign and should not be reproduced either in part or whole without the written consent of this firm

LANDSCAPE MAINTENANCE

THE CONTRACTOR SHALL CONTINUOUSLY MAINTAIN ALL AREAS OF THE CONTRACT DURING THE PROGRESS OF THE WORKS. THE CONTRACTOR SHALL COMMENCE AND FULLY IMPLEMENT THE SHORT-TERM MAINTENANCE AND ESTABLISHMENT AFTER PRACTICAL COMPLETION HAS BEEN CONFIRMED.

SITE CONTROL: REPORT TO THE PRINCIPAL'S DESIGNATED REPRESENTATIVE ON ARRIVING AT AND BEFORE LEAVING THE SITE.

PLANT ESTABLISHMENT PERIOD: THE PERIOD BETWEEN THE DATE OF PRACTICAL COMPLETION AND THE DATE OF FINAL COMPLETION. MAINTENANCE/ ESTABLISHMENT PERIOD: 12 MONTHS.

PLANT ESTABLISHMENT: MAINTAIN THE CONTRACT AREA DURING THE PLANT ESTABLISHMENT PERIOD. ENSURE THE GENERAL APPEARANCE AND PRESENTATION OF THE LANDSCAPE AND THE QUALITY OF PLANT MATERIAL AT DATE OF PRACTICAL COMPLETION IS MAINTAINED FOR THE FULL PLANTING ESTABLISHMENT PERIOD. EXISTING PLANT MATERIAL: MAINTAIN EXISTING PLANTING WITHIN THE LANDSCAPE CONTRACT AREA AS SPECIFIED FOR NEW PLANTING. REPLACEMENTS: REPLACE FAILED, DEAD AND/OR DAMAGED PLANTS AT MINIMUM 3 WEEK

INTERVALS AS NECESSARY THROUGHOUT THE FULL PLANT ESTABLISHMENT PERIOD. REPORTING: SUBMIT REGULAR REPORTS BY THE LAST FRIDAY OF EACH MONTH SUMMARISING THE GENERAL STATUS OF WORKS. INCLUDE A MAINTENANCE SCHEDULE, A LOG BOOK OF MAINTENANCE ACTIVITY, SOIL TEST RESULTS AS REQUIRED FOR ANY FERTILISING PROGRAMS, AND PLANT REPLACEMENT REQUIREMENTS.

WATER RESTRICTIONS: COORDINATE THE WATER SUPPLY AND CONFIRM THE WATERING REGIME AGAINST RELEVANT GOVERNMENT LEGISLATION AND RESTRICTIONS AT THE TIME STAKES AND TIES: REMOVE AT THE END OF THE PLANTING ESTABLISHMENT PERIOD. TEMPORARY FENCES: REMOVE TEMPORARY PROTECTIVE FENCES AT THE END OF THE PLANTING ESTABLISHMENT PERIOD.

COMPLIANCE: PLANT ESTABLISHMENT SHALL BE DEEMED COMPLETE, SUBJECT TO THE FOLLOWING:

* REPAIRS TO PLANTING MEDIA COMPLETED.

* PESTS, DISEASE, OR NUTRIENT DEFICIENCIES OR TOXICITIES ARE NOT EVIDENT.

* MULCHED SURFACES HAVE BEEN MAINTAINED IN A WEED FREE AND TIDY

CONDITION AND TO THE SPECIFIED DEPTH.

* VEGETATION IS ESTABLISHED AND WELL FORMED. * PLANTS HAVE HEALTHY ROOT SYSTEMS.

* VEGETATION IS NOT RESTRICTING ESSENTIAL SIGHT LINES AND SIGNAGE.

DRIP IRRIGATION PERFORMANCE SPECIFICATION

All Garden Beds and Planter Boxes are to be provided with a drip irrigation system connected to a pump and the rainwater tank. Water Taps to be provided.

Design, supply and install a permanent, fully automated drip irrigation system. The system is to cover all new garden areas to the extent shown on the drawings. Water is to be delivered via sub surface drippers and/or drip lines. The system is to be capable of supplying 32mm of water/week over all irrigated areas. It is to be designed to operate for a minimum of 10 years. All lines are to be buried below the finished ground level. Pits are to be set on a 200mm deep bed of gravel. Pit covers are to be level with the soil surface. Avoid seepage onto pavement, buildings or other structures. Include plumbing connection to main, main valve and backflow prevention. Central controller/programmer to be located in a lockable box in nominated location to be approved prior to installation. A dedicated GPO is to be provided for the controller to be plugged into. All work is to be approved by the local regulatory authority. Prepare as installed drawings and commission the system. The Contractor is to submit documents of the design and specification for the irrigation system for approval prior to commencement of work. Equipment is to comply with AS 2698.1 & as 2698.3.

Connect to pumps connect to the rainwater tanks.

Page

creating places to live in and enjoy

+STUDIOS

WARRIEWOOD VALE P/L Scale N.T.S @A1