




100mm DEPTH OF MULCH AS SPECIFIED 125x5mm HOT DIPPED GALVANISED M.S. STRAP TO FORM EDGE BETWEEN TURF & PLANTER BED. TOP OF STEEL EDGE TO BE FLUSH WITH GRASS SHRUBS & GROUNDCOVERS LAWN AS SPECIFIED IMPORTED TOPSOIL AS SPECIFIED 450x10mm DIA, HOT DIPPED GALVANISED 450XTOTIM DIA. HOT DIFFED GALVANISED M.S. METAL STAKE TO BE HAMMERED INTO PLACE & SPOT WELDED ONTO STEEL EDGE AT 1200mm CENTRES 300mm MIN DEPTH IMPORTED TOPSOIL AS SPECIFIED (REFER TO SHRUB BED DETAIL) CULTIVATED SUBGRADE EDGE TYPE 1 - STEEL EDGE

SCALE 1:20@ A3 1:10@A1

SCALE 1:20@ A3 1:10@A









LANDSCAPE SPECIFICATION NOTES

Locate any underground and overground services & ensure no damage occurs. Levels on plan are nominal only & all dimensions to be checked on site prior to commencement, final structural integrity of all items shall be the sole responsibility of landscape contractor.

PROTECTION OF EXISTING TREES:

Prior to commencement of work, a continuous Tree Protection Fence shall be erected around the perimeter of the Tree Protection Zone (TPZ) in Prior to commencement of work, a continuous free Protection Fence shall be efected around the perimeter of the free Protection Fence shall be a minimum of 1800mm high chain link fabric on 2400mm star picket or 50 Ømm GWI pipe anchor posts driven 600mm into the ground. Take necessary precautions to protect the Structural Root Zone (SRZ) as per AS 4970-2009 Australian Standard for Protection of Trees on Development Sites. Tree protection measures shall remain intact until the completion of all construction works. A 600mm x 450mm prohibition sign complying with ASB319 stating "NO ENTRY - TREE PROTECTION ZONE" and including contact details of the site foreman is to be attached to the

tence
Prohibited Works or material storage within the TPZ as per AS 4970-2009 except with approval of council:
- entry of machinery or storage of building materials
- parking of any kind of vehicle
- erection or placement of site facilities
- removal or stockpiling of soil or site debtis

- disposal of liquid waste including paint & concrete wash

- disposal of liquid waste including paint & concrete wash
 excavation or frenching of any kind (including irrigation or electrical connections).
 attaching any signs or any other objects to the tree
 placement of waste disposal or skip bins
 pruning and removal of branches, other than those by a qualified Arborist
 Compacted Ground/Caring: Avoid compaction of the ground under trees. If compaction nevertheless occurs loosen the soil by Coring, Coring to be carried out by a qualified Arborist.

ELIMINATE WEEDS

Remove all existing weeds by hand, wiping or spraying with a glyphosate based herbicide. Weed control shall never be performed by mechanical cultivation or by scraping. Herbicide spraying is to be used to eliminate all existing weeds 30 days prior to planting.

EXCAVATION & SUB SOIL PREPARATION

EXCAVATION & SUB SOIL PREPARATION

Excavate garden beds to the depth required and rip or scarify base & sides of pit to a minimum depth of 150mm SUB SOIL DRAINAGE

Install drainage layer where there is surface water runoff draining into garden bed areas & where the existing sub-soil has more than 50% clay

Install ardinage layer where there is surface water funds ardining into garden bed areas & where the existing sub-soil has more than 50% circomposition 8, there is a risk of subsurface water ponding, Install perforated corrugated ag, line 75-100mm Dia, with geotextile filter sock & backfill to a minimum 200mm using free draining material, reclaimed/recycled where available. Direct flows at a minimum 0.5% fall to sw system. In areas isolated from stormwater system excavate & backfill an appropriate water dispersion pit.

REUSE EXISTING TOPSOIL

Existing site topsoil should be salvaged & appropriately stockpiled where possible. IMPORTED TOPSOIL

IMPORTED TOPSOIL

Quality System: AS 4419 or as specified below.

Turf Areas: Turf Underlay' as supplied by, ANL p: 02 9450 1444 or approved alternative.

Tree Pit and Shrub Planting: 'Premium Garden Mix' as supplied by, ANL p: 02 9450 1444 or approved alternative

PLANTING

Hadth & March Control of the Planting of t Health & Vigour: Supply plants with foilage size, texture & colour consistent with that shown in healthy specimens of the species.

Balance of Crown: Supply plants with max, variation in crown bulk on opposite sides of stem axis, +/- 20%

Stock selection should be based on NATSPEC Guide Specifying Trees: a Guide to Assessment of Tree Quality STAKING

Install 2 x 1800mm 40x40 hardwood timber stakes with hessian ties to all trees. Provide appropriate support considering exposure to prevailing winds. Stakes and hessian ties to be removed as soon as the tree is self supporting.

MULCHING

Quality system: AS 4454 All planting area to be mulched with 50mm depth of river pebbles unless otherwise specified. Keep mulch 100mm away from plant stem & form a

well to stop excessive water runoff. Finish flush with adjacent surfaces. **TURFING**

Tokring

As specified.

Excavate / grade all areas to be turfed to 120mm below finished levels. Ensure that all surface runoff is directed away from buildings. Ensure that no pooling or ponding will occur. Further rip the subgrade to 150mm. Install 100mm of imported turf underlay. Rolls to be closely butted and laid in a brickwork pattern. Fill any small gaps with topsoil and water thoroughly.

WATERING

Water in immediately after plant installation & allow for soil settlement. For the first 2 to 4 weeks after planting, the root zone & immediate surrounds

All services and infrastructure locations are indicative only. Contractor to confirm location of all services and infrastructure prior to initiating

ALL SERVICES AND INFRASTRUCTURE LOCATIONS ARE INDICATIVE ONLY, CONTRACTOR TO CONFIRM LOCATION OF ALL SERVICES AND INFRASTRUCTURE PRIOR TO INITIATING LANDSCAPE WORKS

ISSUE	REASON FOR ISSUE	DATE	DESIGN	CHECKED
Α	Draft for client review	13.09.2021	PG	PG
В	For DA Approval	14.09.2021	PG	PG



CONTACT DETAILS

AFFILIATED CONSULTANT
ARCHITECT: Walsh Architects

CLIENT

58 Forest Way
Frenchs Forest

DRAWING LANDSCAPE DETAILS - SHEET 4		SCALE VARIES	
PROJECT No 21-322	DRAW LS503.	ING No.	ISSUE B