

NOTES

- CONFIRM ALL DIMENSIONS, SERVICES AND LEVELS ON SITE PRIOR TO STARTING WORK.
- ALL BUILDING WORKS SHALL COMPLY WITH THE BUILDING CODE OF AUSTRALIA, THE RELEVANT AUSTRALIAN STANDARDS AND THE LOCAL GOVERNMENT AUTHORITY.
- TIMBER FRAMING AS PER AS1684 AND THE NSW TIMBER FRAMING CODE.
- BOUNDARY FENCING TO BE UPGRADED AS NECESSARY AND ALL POOL FENCING TO COMPLY WITH THE NSW SWIMMING POOL ACT 1992, AS1926.1-2012-SAFETY BARRIERS FOR SWIMMING POOLS AND AS1926.2-2012 LOCATION OF SAFETY BARRIERS FOR SWIMMING POOLS.
- THIS POOL IS NOT DESIGNED FOR DIVING.
- EL = EXISTING LEVEL
- FL = FLOOR LEVEL
- RL = REDUCED LEVEL
- COS = CHECK ON SITE
- UNO = UNLESS NOTED OTHERWISE


TOTAL POOL VOLUME = 63,000 LITRES

- BASIX REQUIREMENTS**
- RAINWATER TANK**
1. a rainwater tank of 2537 litres must be installed on the property in accordance with the applicable regulatory authorities.
 2. The rainwater tank must collect runoff from at least 50 square metres of roof area.
 3. The rainwater tank must be connected to a tap located within 10m of the edge of the pool and spa area.
- POOL**
4. the swimming pool must be located outdoors.
 5. the swimming pool must not have a capacity of greater than 63 kilolitres.
 6. the swimming pool must have a pool cover.
 7. a pool pump timer must be installed.
 8. the pool must have a gas heating system installed as part of this development.

SITE PLAN / SITE ANALYSIS PLAN


SYMBOL LEGEND

- NEIGHBOURING PRIVATE OPEN SPACE
- PREVAILING WINDS
- VIEWS
- NOISE SOURCE




POOL PLAN


+ 100 DENOTES TOP OF POOL RELATIVE TO NATURAL GROUND LEVEL



SECTION A-A



SECTION B-B



**RIGHT ANGLE DESIGN
& DRAFTING PTY LTD**


ROBYN GOOD
HORTICULTURE CERT II
ASSOC. DIPLOMA STRUCTURAL ENGINEERING
NZCO ARCHITECTURAL DRAFTING
P.O. Box 1049 SURRY HILLS 2010
PH: 8399-0072
EMAIL: info@rightangledesign.com.au
ABN: 70 150 745 556

REVISIONS:

PROPOSED POOL & ASSOCIATED WORKS
STEPHEN WOODS & KERRIE WILSON
LOT 37 SEC C DP6195
No. 45 HILLCREST AVENUE
MONA VALE 2103


DWG NAME
POOL PLAN AND SECTIONS

DATE	SCALE AT A3	JOB NUMBER	DWG NUMBER
OCT 2020	1:100	RADD20090	P3




SOUTH ELEVATION


NORTH ELEVATION




WEST ELEVATION




EAST ELEVATION




 <p>RIGHT ANGLE DESIGN & DRAFTING PTY LTD ROBYN GOOD HORTICULTURE CERT II ASSOC. DIPLOMA STRUCTURAL ENGINEERING NZQD ARCHITECTURAL DRAFTING P.O. Box 1049 SURRY HILLS 2010 PH: 8399-0072 EMAIL: info@rightangledesign.com.au ABN: 70 150 745 556</p>	REVISIONS:	PROPOSED POOL & ASSOCIATED WORKS STEPHEN WOODS & KERRIE WILSON LOT 37 SEC C DP6195 No. 45 HILLCREST AVENUE MONA VALE 2103	DWG NAME ELEVATIONS			
			DATE	SCALE AT A3	JOB NUMBER	DWG NUMBER
			OCT 2020	1:100	RADD20090	P4



- all works to be carried out in accordance with landcom publication -managing urban stormwater: soils and construction "the blue book".
- site works will not start until the erosion and sediment control works outlined in clauses 2 to 4 below are installed and functional.
- the entry to and departure of vehicles from the site will be confined to one stabilised point. sediment or barriers fencing will be used to restrict all vehicular movements to that point. stabilisation will be achieved by either:-
 - constructing a sealed driveway to the street,
 - constructing a stabilised site access or other suitable technique approved by council.
- sediment fences and barrier fences shall be installed as shown.
- topsoil from the work's area will be stripped and stockpiled for later use in landscaping the site if necessary. otherwise the excavation material is to be removed from site at the responsibility of the excavation contractor.
- all stockpiles will be placed at least 2m clear of possible areas of concentrated water flow including driveways.
- lands outside of the scope of works and on the footpath will not be disturbed during works except where essential eg. drainage works across footpath. where works are necessary they will be undertaken in such a way to minimise the occurrence of soil erosion, even for short periods. they will be rehabilitated (grassed) as soon as possible. stockpiles will not be placed on these lands and they will not be used as vehicle parking areas.
- approved bins for building waste, concrete and mortar slurries, paints, acid washings and letter will be provided and arrangements made for regular collection and disposal.
- guttering will be connected to the stormwater system or the rainwater tank as soon as possible.
- topsoil will be respread and all disturbed areas will be stabilised within 20 working days of the completion of works.
- all erosion and sediment controls will be checked at least weekly and after rain to ensure they are maintained in a fully functional condition.



POOL WASTE WATER
-SHALL BE COLLECTED BY 500 PVC PIPE FROM FILTER INTO SEWER GULLY TRAP SUPPLIED BY OTHERS AS SHOWN:



PLUMBING LAYOUT
DIAGRAMMATIC ONLY

<p>1. construct sediment fence as close as possible to the parallel contours of the site. 2. drive 1.5m long star pickets into ground, 2.5m apart max. 3. dig a 150mm deep trench along the upslope line of the fence for the bottom of the fabric to be entrenched. 4. fix self supporting geotextile to upslope side of posts with wire ties or as recommended by geotextile manufacturer. 5. join sections of fabric at support post with a 150mm overlap. 6. backfill the trench over the base of the fabric and compact it thoroughly over the geotextile.</p>	<p>1. construct with gradient of 1 percent to 5 percent. 2. avoid removing trees and shrubs if possible. 3. drains to be of circular, parabolic or trapezoidal cross section not v-shaped. 4. earth banks to be adequately compacted in order to prevent failure. 5. permanent or temporary stabilisation of the earth bank to be completed within 10 days of construction. 6. all outlets from disturbed lands are to feed into a sediment basin or similar. 7. discharge runoff collected from undisturbed lands onto either a stabilised or undisturbed disposal site with the same subcatchment area from which the water originated. 8. compact bank with a suitable implement in situations where they are required to function for more than five days. 9. earth banks to be free of projections or other irregularities that will impede normal flow.</p>	<p>1. where possible locate stockpile at least 5m from existing vegetation, concentrated water flows, roads and hazard areas. 2. construct on the contour as a low, flat elongated mound. 3. where there is sufficient area topsoil piles shall be less than 2m in height. 4. rehabilitate in accordance with the swmp/escp. 5. construct earth bank (see detail) on the upslope side to divert run off around the stockpile and a sediment fence 1-2m downslope of the stockpile.</p>	<p>1. strip topsoil and level site. 2. compact subgrade. 3. cover area with needle-punched geotextile. 4. construct 200mm thick pad over geotextile using roadbase or 30mm aggregate. minimum length 15m or to building alignment. min width 3 metres. 5. construct hump immediately within boundary to divert water to a sediment fence or other sediment trap.</p>
<p>sediment fence</p> <p>temp. drop inlet sediment trap</p>	<p>earth bank (low flow)</p> <p>diversion bank and channel</p>	<p>topsoil stockpile</p>	<p>stabilised site access</p>

RIGHT ANGLE DESIGN & DRAFTING PTY LTD
ROBYN GOOD
HORTICULTURE CERT II
ASSOC. DIPLOMA STRUCTURAL ENGINEERING
NZSO ARCHITECTURAL DRAFTING
P.O. Box 1049 SURRY HILLS 2010
PH: 8399-0072
EMAIL: info@rightangledesign.com.au
ABN: 70 150 745 556

PROPOSED POOL & ASSOCIATED WORKS
STEPHEN WOODS & KERRIE WILSON
LOT 37 SEC C DP6195
No. 45 HILLCREST AVENUE
MONA VALE 2103

DWG NAME	SEDIMENT CONTROL PLAN		
DATE	SCALE AT A3	JOB NUMBER	DWG NUMBER
OCT 2020	1:250	RADD20090	P6

MATERIALS AND FINISHES FOR 45 HILLCREST AVENUE, MONA VALE



TRAVERTINE TILE FOR THE SWIMMING POOL COPING AND SURROUNDS



SWIMMING POOL FENCING—TO COMPLY WITH POOL FENCING ACT



EXISTING RETAINING WALL TO CONTINUE ON NEW LOWER LEVEL RETAINING WALL



SANDSTONE FINISH FOR RETAINING WALL



REINFORCED BLOCK RETAINING WHERE NECESSARY