

# Geotechnical Site Investigation

Lot. 2 No. 40 Wellman Road, Forestville NSW 2087



Submitted To Metricon Homes Pty Ltd Building E, Level 4, 32 Lexington Drive BAULKHAM HILLS, NSW 2153

Site Number 117640

**Date** 20/09/2019 **Author** Raj Singh

Published 20/09/2019

Document Revision: 0 Template Version: ii Template Name: Master with Cover

Intrax Consulting Engineers Pty Ltd ABN: 31 106 481 252

Head Office Level 4, 469 Latrobe Street, Melbourne, Vic 3000 p: 1300 INTRAX w: www.intrax.com.au



# **Table of Contents**

1	Introduction	. 5
2	Project and Site Description	. 5
	2.1 Project Description	. 5
	2.2 Site Description	. 5
3	Method of Investigation	. 5
	3.1 Desktop Assessment	. 5
	3.2 Fieldwork	. 6
4	Results of Investigation	. 6
	4.1 Desktop Assessment	. 6
	4.2 Subsurface Conditions	. 6
5	Slope Instability	.7
	5.1 Proposed Development	. 7
	5.2 Previous Instability	. 7
	5.3 Site Features Relating to Slope Instability	. 7
	5.4 Possible Landslide Hazards	. 7
	5.5 Hazard Identification	. 7
	5.6 Risk Assessment	. 8
6	Discussion and Recommendations	. 9
	6.1 General	. 9
	6.2 Site Reactivity – AS 2870	. 9
	6.3 Building Foundations	. 9
	6.4 Excavation and Retention	10
	6.5 Drainage	11
	6.6 Further Assessment	11
	6.7 Inspections (Hold Points)	12
7	Limitations of Report	13

#### Confidentiality

All documents are subject to the 'Intrax Terms and Conditions' and 'Intrax Terms and Conditions -NAC' documents. These documents are available on our website for your perusal.

#### Conditions of Use

This report is not intended for use by any other person or third party other than the named client.

**Direct Contact** 

#### Copyright

©2019 Intrax Consulting Engineers Pty Ltd (ABN 31 106 481 252).

This geotechnical site inspection report has been prepared expressly for the client for the sole purpose of constructing the building described in the plans and specifications. This report is copyright to Intrax Consulting Engineers Pty Ltd.

No part of this report shall be used for any other purpose nor by any third party without the prior



Any questions or queries regarding this report should be directed to the Geotechnical Department, Engineering Team on 1300 or scott.emmett@intrax.com.au. written consent of Intrax Consulting Engineers Pty Ltd. The client is defined as the person or persons named in this report or the person or persons for whom the named building company is acting as agent.

#### **Document Revision History**

Date	Rev	Author	Approved by	Comments
20-Sep-19	0	Raj Singh	Scott Emmett	First Edition



# **List of Appendices**

**APPENDIX A:** Site Plan and Borehole Logs

**APPENDIX B:** Site Photography

**APPENDIX C:** CSIRO BTF "Foundation Maintenance and Footing Performance: A Homeowner's Guide" Practice Note Guidelines For Landslide Risk Management 2007, Australian Geoguide LR8 (Construction Practice)

#### **REFERENCED STANDARDS:**

AS 1726-2017, Geotechnical site investigations, Standards Australia, Sydney, Retrieved from SAI Global AS 2159-2009, Piling-Design and Installation, Standards Australia, Sydney, Retrieved from SAI Global AS 2870-2011, Residential slabs and footings, Standards Australia, Sydney, Retrieved from SAI Global AS 3798-2007, Guidelines on earthworks for commercial and residential developments, Standards Australia, Sydney, Retrieved from SAI Global

#### **REPORT AUTHOR/S:**

Mr Scott Emmett Geologist BSc (EarthScience) Hons, MAIG RPGeo 10246

hold Connell

Mr Raj Singh Senior Geotechnical Engineer BTech (Civil), ME (Geotechnical)

REPORT CONTACT: Scott Emmett 02 8355 1200 raj.singh@intrax.com.au

Intrax Consulting Engineers Pty Ltd Geotechnical Consultants C2.07/22-36 Mountain Street ULTIMO NSW 2007



# **1** Introduction

Intrax Consulting Engineers has completed a geotechnical investigation for the proposed double storey residential development at Lot. 2 No. 40 Wellman Road, Forestville NSW 2087.

The investigation was carried out in accordance with the email fee proposal commissioned by Metricon Homes Pty. Ltd.

This report outlines the geotechnical site investigation carried out on 13<sup>th</sup> September 2019. The report includes a site classification in accordance with AS2870-2011 and geotechnical recommendations and design parameters for foundations, retaining walls and site excavations.

The report also provides risk of Landslide Assessment in accordance with Northern beaches council E10 landslide Risk guidelines.

# 2 **Project and Site Description**

#### 2.1 **Project Description**

The proposed development is a new double storey dwelling as outlined in the architectural drawings provided by the client. Some excavation may be required to achieve the proposed design levels.

#### 2.2 Site Description

The site is situated to the north of Wellman Road and covers an area of about 830m<sup>2</sup>.

The site is bounded by:

- Fitzpatrick Avenue west (Unformed road) to the north
- Residential dwellings to the east and west.
- Wellman Road to the south.

Site was occupied with a double storey brick house. It was observed that existing residential dwelling is may be supported by timber beams which resting on brick piers. At the time of preparing this report, Intrax does not have any structural details about the existing residential dwelling. The site has an overall slope of about  $8^{\circ}$  -  $9^{\circ}$  towards the rear boundary as observed from the Wellman Road.

From the middle of property, the ground is sloping downwards for about 3 to 4m at 12° - 15°. The area contains several large trees and retaining walls. A 1.7m retaining wall is observed on the western side of the property. Another retaining is observed running between the boundary of two properties along the eastern side. Large sandstone boulders and large trees were observed throughout the area. The large sandstone boulders appeared to be in-situ rock.

Existing trees on the site do no exhibit and trunk curvature which is indicative of limited to no soil creep and downhill movement of the soil profile.

The surface soils generally comprise of FILL - Sandy SILT trace clay gravel overlying natural SAND trace clay gravel followed by SANDSTONE.

Site conditions on the date of inspection are visible in the attached photography in Appendix B with the site features indicated in the site plan, refer Appendix A.

# 3 Method of Investigation

#### 3.1 Desktop Assessment

Geological maps from the Geological Survey of New South Wales (NSW), aerial photography and our local experienced were used to assess the anticipated site conditions and the area geology.



#### 3.2 Fieldwork

The fieldwork consisted of visual inspection of the site. During the site classification investigation on 12/10/2018, three boreholes (BH1 to BH3) were drilled to a maximum depth of 0.7 meters using a hand auger. The approximate locations of the boreholes are shown on the attached site plan in Appendix A. The subsurface materials were visually classified in accordance with AS1726-2017: Geotechnical Site Investigation.

One (1) Dynamic Cone Penetrometer (DCP) tests were conducted adjacent to boreholes 1.

## 4 Results of Investigation

#### 4.1 Desktop Assessment

Investigation of geological maps from the Geological survey of NSW has identified the expected site geology is Middle Triassic aged Hawkesbury Sandstone (Rh) which comprises of medium to coarse-grained quartz, sandstone, very minor shale and laminite lenses. This geology was consistent with the visual identification of material on site. An extract of the local geological map is provided below.



Figure 1: Extract of local geology from 1:100,000 Sydney Map

#### 4.2 Subsurface Conditions

From previous study, the boreholes revealed the substrata typically consisted of the following soil profile. Variation from this profile existed across the site, refer to borehole logs in Appendix A for details.

FILL Sandy SILT trace clay gravel, m<sub>c</sub>>PL, low plasticity, firm – stiff, dark black grey brown

RESIDUAL SAND trace clay gravel, moist, medium dense, pale grey brown yellow

**TERMINATED on ROCK - SANDSTONE** 

#### 4.2.1 Ground Water

Groundwater was not intersected at a maximum depth of 0.70 metres during borehole drilling.

Substrata conditions encountered are such that infiltration and occurrence of perched water at the interface between different material layers should not be disregarded.



# **5** Slope Instability

A landslide hazard assessment of the existing slopes has been carried out in accordance with the Australian Geomechanics Society Landslide Risk Management Concepts and Guidelines, 2007.

A copy of this document can be found at www.australiangeomechanics.org. Appendix C of the document describes the terminology used.

#### 5.1 Proposed Development

As mentioned in section 2.1 of the report, the proposed development would comprise a double storey residential dwelling.

#### 5.2 Previous Instability

Indicators of instability within soil or rock beneath the site can include, but not be limited to:

Rock outcropping and boulders which including rock sliding/toppling.

The borehole encountered soil cover (fill and residual soils) may influence the risk of slope instability/creep.

#### 5.3 Site Features Relating to Slope Instability

The following site features are assessed to be relevant for assessment of risk of slope instability:

- Slope of the site 8<sup>°</sup> 9<sup>°</sup> downward towards the rear boundary as observed from the Wellman Road.
- Presence of several detached boulders.
- The slope of the site beyond the proposed new development was assessed to be about 12<sup>o</sup> to 15<sup>o</sup>.

#### 5.4 Possible Landslide Hazards

On the basis of the visual of the site, possible landslide hazards considered applicable to the existing slope are as follows:

Possible Failure Mechanisms Description	Description of Failure Mechanism				
Rotational/ Translational Landslide	This mode of failure is characterised by a curved or relatively flat failure surface. Should rotational/translational failure occur at this site, the plane of failure would likely be on the contact between natural soil and/or weathered rock depending on groundwater conditions prevailing at the time of the failure.				
Creep	Slow downhill movement of landmass due to steep slopes, groundwater conditions and other factors.				
Rock Fall/Sliding	Boulders may lose grip and could slide or roll down/slip down slope				

Table 2: General Possible Failure Mechanisms for Landslide

#### 5.5 Hazard Identification

Based on the site features noted above, the following instability mechanisms are considered relevant for the proposed work:

- Failure of natural hill slide slope.
- Failure of stone/rock retaining walls behind the existing residential dwelling and on the perimeter of the property.



- Rolling/sliding of detached boulders.
- Failure of unsupported cuttings during excavation.

#### 5.6 Risk Assessment

In accordance with Appendix – C Qualitative Measures of Consequences to property, the anticipated consequences of the identified landslide hazards are explained in the report from section 5.6.1 to 5.6.5.

The level of risk to property has been determined using the Qualitative Risk Analysis Matrix.

#### 5.6.1 Failure of natural hill slide slope

Based on the contour plans the overall slope of the site is about 8°-10°. Based on the subsurface profile encountered in the boreholes from the previous study (BH1 to BH3) the maximum depth of soil cover is 700mm.

Based on engineering judgement, the likelihood of a hillside failure within the overburden soils is assessed to be unlikely, with an annual probability of 0.0001. The consequence of this instability is assessed to be medium. Hence the risk to the property is assessed to be **low**.

# 5.6.2 Failure of stone/rock retaining walls behind the existing residential dwelling and on the perimeter of the property.

Intrax does not have any structural details about the existing stone/rock retaining walls behind the residential dwelling and on the perimeter of the property. A structural engineer should carry out an inspection to assess the structural integrity of these retaining walls.

#### 5.6.3 Rolling/sliding of detached boulders

Site at the rear contains several detached sandstone boulders. Mostly the boulders were greater than 0.70m in size. The rolling/sliding of these boulders is assessed to be possible with an annual probability of 0.001. The consequence of this failure on the subject site is more depends upon the size of the boulders. Boulders of less than 200mm will not impact on property. However, the consequences to property by rolling/sliding of boulders of about 1m is assessed to be medium. Hence the overall risk is moderate. This risk may be reduced to low by removal of all the boulders which are not in stable position or has the possibility of rolling/sliding.

#### 5.6.4 Failure of unsupported cuttings during excavation

Based on the supplied drawings, it is understood that excavation may require to achieve the proposed design levels.

Based on the subsurface profile encountered in the borehole, it is assessed that excavation material would comprise Sandy SILT fill and residual SAND.

Based on engineering judgement, probability of failure of unsupported cuttings during excavation is assessed to be possible with an indicative value of approximate annual probability 0.001. The consequences of this instability are assessed to be Medium. Hence, the risk to the property is assessed to be **moderate**. This risk may be reduced to **Low** by adopting the safe batter angles provided in *section 6.4 Excavation and Retention* of this report.

Based on the above, the overall risk of slope instability of this site is assessed to be **Moderate**. The risk level can be reduced to **Low** by the measures described in section 5.6.1 to 5.6.4 of this report.

The risk assessment is based on Australian Geomechanics Guidelines for Landslide Risk Assessment and Management. Risk levels are defined in the attached Appendix C and above (from the Guidelines) and the development should be carried out in accordance with sound engineering principles, guidelines for good hillside construction practice as outlined Australian Geoguide LR8 (from the Guidelines) attached and the specific recommendations given in this report.



# 6 Discussion and Recommendations

#### 6.1 General

The generalised subsurface profile within the boreholes may be represented by FILL – Sandy SILT and Residual SAND and then sandstone rock

#### 6.2 Site Reactivity – AS 2870

After considering the area geology, the soil profile encountered in the bores, and the climatic zone of the area, this site has been classified as CLASS S with respect to foundation construction (Australian Standard 2870-2011 Residential Slabs and Footings) due to the steep slope, presence of trees and existing structure.

Based on the findings of the previous investigation, the soil profile combined with this writer's local knowledge and experience, the characteristic surface movement (Ys) on this site, under normal condition, has been estimated to be in the range of 0mm to 20mm.

#### 6.3 **Building Foundations**

#### 6.3.1 Waffle and Raft Footings

It is recommended that the foundation system be designed by engineering principles. (AS 2870 - 2011 Cl 1.4). We recommend that the designing engineer refer to AS2870 - 2011 to ensure design compliance to this document, especially Sections 1.3 "Performance of Footing Systems" and "Design Considerations".

Allowable bearing pressures provided in section 6.3 for strip footings can be adopted for load bearing ribs on waffle/raft foundations.

#### 6.3.2 Pad and Strip Footings

Pad and strip footings are an appropriate footing arrangement for the proposed structure. Based on the site investigation, pad and strip footings founded at least 500mm into the naturally occurring sandstone rock as described in the logs of boring can be assumed to have an allowable bearing pressure of 500kPa.

As a guide, with regard to the above along with information obtained from the bores, the founding depths of shallow foundations at this site will be up to 1200mm below the existing surface.

The allowable bearing capacity values provided in this report are maximum values without further geotechnical investigation or detailed analysis of foundation design.

#### 6.3.3 Piled Foundations

If bored piers are used at this site, they should be founded not less than 1-15 times the pile diameters into the naturally occurring Sandstone rock soils as described in the logs of boring, where they can adopt an allowable end bearing value of 750kPa. The embedment depth provided above is only for compressive loading.

An allowable skin friction of 50kPa can be assumed to exist between piers and any of the naturally occurring sandstone rock. No skin friction should be adopted for FILL soils or soils within 600mm of surface level.

The allowable bearing capacity values provided in this report are maximum values without further geotechnical investigation or detailed analysis of foundation designs.



#### 6.3.4 General Conditions – Foundations

Where footings are founded in different soil groups (especially reactive and non-reactive soils), the designer should provide articulation for the structure to accommodate to for potential damages which could be caused by differential movement of the soil due to seasonal moisture variation.

Note it is our preference that the design engineer adopt the same founding material across the structure where possible.

After excavation for the footings has been completed if there is any doubt as to the bearing capacity of the founding soil, then Intrax should be contacted and an inspection of the sites founding conditions carried out.

Foundations proposed for founding in and on existing fill, if any, then the fill must be stripped and the surface of the natural soil must be compacted with the soil in a moist condition. Stripped or imported fill meeting the minimum suitability requirements of section 4 of AS3798 must be placed at minimum 150mm uncompacted layers and each layer shall be compacted to minimum 98% dry density ratio at moisture contents between 90% and 110% of the optimum moisture content. Following the above ground preparation, an allowable bearing pressure of 100kPa can be assumed at 200mm below the compacted surface. Should additional filling depths exceed 1.0m it is recommended that a specification for earthworks be prepared.

#### 6.4 Excavation and Retention

#### 6.4.1 Retention Design Parameters

The following parameters established from Rankine's theory would be valid in the design of a retention system. These values assume that the soil being retained/supported has horizontal surface.

Material Description	Unit weight (kN/m³)	Cu (kPa)	Friction angle (°)	Ka <sup>#</sup>	Kp <sup>#</sup>	Ko <sup>#</sup>	
SAND	18	-	32	0.31	3.25	0.47	
SANDSTONE rock	20	50	32	0.31	3.25	0.47	

Table 1: Geotechnical soil and retention design parameters

\*Approximate depth based on borehole logs completed during geotechnical investigation <sup>#</sup>K<sub>a</sub>, K<sub>p</sub> and K<sub>o</sub> are the active, passive and at-rest earth pressure coefficients.

Allowable bearing pressures given under 6.3 are relevant for foundation loading.

The above parameters assume that the level of the water table is below the bottom of the excavation by the use of adequate drainage and that any adjacent surcharge loads are superimposed.

It is suggested that design of permanent retaining structures be based on an average bulk unit weight for the retained material of 17kN/m<sup>3</sup> and on a triangular distribution. In order to maximise the rigidity of the retaining wall, 'at rest' Ko earth pressure conditions may be adopted.

#### 6.4.2 Site Excavation

During the excavation of the site following prolonged rain periods, seepage water may be present in the excavation. The zone of influence that the work has on the surface of the excavation during construction is at an angle of 30° from the vertical face of the excavation or at a distance of 0.58H horizontal from the surface of the excavation where H is the depth of the excavation.

It is recommended that where any footings are to be constructed next to the existing underground services (sewers, etc), then these footings should be founded and designed taking into account the above parameters.



This office recommends the following excavation methodology;

- 1. Any upper FILL, TOPSOIL and SILT layers should be temporarily retained or battered to not steeper than 35 degrees with the horizontal all around the excavation perimeter or temporarily retained.
- 2. Any vertical excavations are completed at the latest opportunity during construction. Vertical excavations can be assumed to remain stable for the period presented in the below table.
- 3. Steeper batter angles or extended vertical excavation periods may be adopted following approval from a suitability experienced geotechnical engineer/engineering geologist, and adoption of an inspection regime by a qualified geotechnical engineer/engineering geologist.
- 4. All vertical excavations to be avoided during periods of predicted heavy or prolonged rainfall
- 5. Inspections are to be completed by this office following any of the below events during construction:
  - Following rainfall events in excess of 30mm over a 24-hour period.
  - At any sign of instability including but not limited to:
    - Water seepage through the excavation face
      - Material observed at the base of the excavation
      - $\circ$   $\;$  Tension cracks observed at the surface  $\;$
- 6. Excavations adjacent to existing structures, property boundaries or services (were batters cannot be achieved during horizontal distance constraints) are to be retained prior to excavation via use of an insitu retaining wall system (e.g. non-contiguous pile wall).

Table 2: Safe batter angles

Material Description	Safe Batter (V:H)				
	Short Term				
SAND	1:1.5				
SANDSTONE rock	1:0.75				

#### 6.5 Drainage

The following drainage measures should be implemented to reduce the risk of slope instability:

- Subsoil drains should be provided behind all retaining walls.
- Roof drainage and drainage from hard stand areas should be collected and directed to site drainage system in a manner that does not reduce the site stability.
- Stormwater from other hardstand area may be discharged from the site via pipes into designated council drainage paths and not allowed to flow on to the ground.

The layout of drains should be designed by a qualified Civil Engineer.

#### 6.6 Further Assessment

It is recommended that the following review/inspections be undertaken to assess geotechnical conditions and to further reduce the risk of slope instability.

• Site drainage plans should be reviewed and approved by an experienced consultant.



#### 6.7 Inspections (Hold Points)

Intrax **must** be engaged at the following stages:

- 1. In the event soil conditions encountered differ significantly from those described within this report.
- 2. If project design is altered significantly from drawings reviewed and outlined or project described within this report

Intrax should be engaged at the following stages:

- 1. To confirm safe batter angles and excavation construction during construction.
- 2. To confirm founding materials and allowable bearing pressures.



# 7 Limitations of Report

- 1. The recommendations in this report are based on the following:
  - a. Information about the site & its history, proposed site treatment and building type conveyed to us by the client and or their agent
  - b. Professional judgements and opinions using the most recent information in soil testing practice that is available to us.
  - c. The location of our test sites and the information gained from this and other investigations.

Should the client or their agent neglect to supply us with correct or relevant information, including information about previous buildings, trees or past activities on the site, or should changes be made to the building type, size and or/position, this report may be made obsolete, irrelevant or unsuitable. In such cases, Intrax will not accept any liability for the consequences and Intrax reserves the right to make an additional charge if more testing or a change to the report is necessary.

- 2. The recommendations made in this report may need to be reviewed should any site works disturb any soil 200mm below the proposed founding depth.
- The descriptions of the soils encountered in the boreholes follow those outlined in AS1726-2017; Geotechnical Site Investigations. Colour descriptions can vary with soil moisture content and individual interpretation.
- 4. If the site conditions at the time of construction differ from those described in this report then Intrax must be contacted so a site inspection can be carried out prior to any footing being poured. The owner/builder will be responsible for any fees associated with this additional work.
- 5. This report assumes that the soil profile observed in the boreholes are representative of the entire site. If the soil profile and site conditions appear to differ substantially from those reported herein, then Intrax should be contacted immediately and this report may need to be reviewed and amended where appropriate. The owner/builder will be responsible for any fees associated with this additional work.
- 6. The user of this report must take into account the following limitations. Soil and drilling depths are given to a tolerance of +/- 200mm.

It must be understood and a condition of acceptance of this report is that whilst every effort is made to identify fill material across the site, difficulties exist in determining fill material, in particular, for example, well compacted site or area derived fill, when utilising a small diameter auger. Consequently Intrax emphasises that we will not be responsible for any financial losses, consequential or otherwise, that may occur as a result of not accurately determining the fill profile across the site.

7. Finally, no responsibility will be taken for this report if it is altered in any way or is not reproduced in full.



# **Appendix A**

Site Plan and Borehole Logs



Ę	Ø	In	Itr	<b>a</b> )	In C2 UI Pt	trax Consulting Engineers 2.07 / 22-36 Mountain Street timo NSW 2007 none: 02 8355 1200	BOREHOLE NUMBER BH1 PAGE 1 OF 1					
СГ	IEN	T Me	etricor	n Pty.	Ltd		PROJECT NAME Propos	sed Residenti	al Dwelling (Double Storey)			
PF	ROJE		UMBE	<b>R</b> _S	#1176	40	PROJECT LOCATION	ot. 2 No. 40 W	ellman Road, Forestville NSW 208			
DA	ATE :	STAR	TED _	12-10	D-18	COMPLETED <u>12-10-18</u> R	.L. SURFACE		DATUM			
DF	RILLI	NG C	ONTR	ACTO	R _In	trax S	LOPE _90°		BEARING			
EC	QUIP	MENT	<u>Ha</u>	nd Au	ger	Н	OLE LOCATION Refer to	o the site plan				
HC		SIZE	90m	m 	0.0		OGGED BY <u>AW</u>		CHECKED BY <u>AW</u>			
NC		<u>s le</u>	rmina	ted at	0.6 on	SANDSTONE						
Method	Water	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description		Samples Tests Remarks	Additional Observations			
			-		MLS	Sandy SILT trace clay gravel, dark black grey brown PL), firm to stiff SAND trace clay gravel, pale grey brown yellow, moi	, low plasticity, moist (mc >>	2	FILL			
	ed		-					2				
HA	Not Encounter		-					3				
			-					4				
			0 <u>.5</u>					8				
			-			Borehole BH1 terminated at 0.6m		20	DCP terminated N>20			

Ł	3	In	Itr	<b>a</b> )	Int C2 UI Pt	trax Consulting Engine 2.07 / 22-36 Mountain S timo NSW 2007 tone: 02 8355 1200	ers Street	BOREHOLE NUMBER BH2 PAGE 1 OF 1					
	ENT	<u>Ме</u>	etricor	n Pty.	Ltd	40		PROJECT NAME Proposed Residential Dwelling (Double Storey)					
DAT DRII EQU	DJE E S LLII JIPN	CT NI STAR <sup>®</sup> NG CI MENT	JMBE	<u>12-10</u> ACTO	<u>#1176</u> 0-18 0R _Int ger	40 COMPLETED trax	12-10-18	PROJECT LOCATION _L R.L. SURFACE SLOPE _90° HOLE LOCATION _ <u>Refer t</u>	ot. 2 No. 40 W	eliman Road, Forestville NSW 208         DATUM         BEARING			
HOL NOT	ES	SIZE Tei	90m minat	m ted at	0.4 on	SANDSTONE		_ LOGGED BY _AW		CHECKED BY AW			
Method	Water	RL (m)	Depth (m)	Graphic Log	Classification Symbol		Material Descripti	ion	Samples Tests Remarks	Additional Observations			
HA NA	Not Encountered M		(m) 		SP	Sandy SILT trace clay gravel PL), firm to stiff SAND trace clay gravel, particular descent of the stiff of the second sec	ale grey brown yellow, at 0.4m	own, low plasticity, moist (mc >> moist, medium dense		FILL         RESIDUAL			

REHOLE / TEST PIT S#117640.GPJ GINT STD AUSTRALIA.G

CLIENT Metrico PP, Lid     PROJECT MARE: Proposed Residential Dealing Contention Story)       PROJECT UNABLER: Sel1/2840     PROJECT LOCATION Lot 2 No. 40 Welliam Road, Foresholler NSW 200       DATE STARTED: 12:10:18     COMPLETED: 12:10:18     PRLUSTRACE       DRILLING CONTRACTOR: Inhox     SLOPE 90'     BEARING		Q	} <b>Ir</b>	ntr	<b>'</b> 8)	In C2 UI Pł	trax Consulting Engineers 2.07 / 22-36 Mountain Street Itimo NSW 2007 none: 02 8355 1200	BOREHOLE NUMBER BH3 PAGE 1 OF					
PROJECT NUMBER         SATURATION         PROJECT COLUMNON         Data or presiminal readin (Noticement Rest) 200           DATE STATETS         COMPLETED 12:10:15         R.L. SUPEACE         DATIM           BEAUNIS CONTRACTOR         Intrax         SUPEACT         DATIM           EQUIPARENT Hand Auger         HOLE LOCATION Refer to the site plan         LOCESDE 300 mm         LOCEEDE X           NOTES         Terminated at 0.7 on SANDSTONE         LOCEDE X         Samples         Additional Observators           NOTES         Terminated at 0.7 on SANDSTONE         Samples         Additional Observators         Researed Description         Samples         Additional Observators           1         1         1         Maser al Description         Samples         Additional Observators           1         1         1         Maser al Description         Samples         Additional Observators           1         1         1         1         Maser al Description         Samples         Additional Observators           1         1         1         1         Maser al Description         Samples         FEL           1         1         1         1         Maser al Description         Samples         FEL           1         1         1 <td< th=""><th></th><th></th><th></th><th>etrico</th><th>n Pty.</th><th>Ltd</th><th>40</th><th></th><th colspan="2">al Dwelling (Double Storey)</th></td<>				etrico	n Pty.	Ltd	40		al Dwelling (Double Storey)				
Darte StartED     12-10-18     COMPETED     12-10-18     R.L. SURFACE     Dartum       DRULING CONTRACTOR     Intrax     Hot E UCATION     Repairing and the site plan.     Hot E UCATION     Repairing and the site plan.       HOLE SUZE glomm     LOGGED BY _AW     CHECKED BY _AW     CHECKED BY _AW       MOTES     Terminated at 0.7 or SANDSTONE     CHECKED BY _AW     CHECKED BY _AW       MOTES     Terminated at 0.7 or SANDSTONE     Addtonal Observations       NOTES     Terminated at 0.7 or SANDSTONE     Plut       NOTES     Terminated at 0.7 or SANDSTONE     Addtonal Observations       Notes     Terminated at 0.7 or SANDSTONE     Plut       NOTES     Terminated at 0.7 or SANDSTONE     Addtonal Observations       Notes     Notes     Samples     Addtonal Observations       Notes     Notes     Samples     Plut       Notes     Notes     Notes     Samples     Plut       Notes     Notes     Notes     Notes     Notes     Plut       Notes     Notes     Notes     <	ľ	'ROJ	ECIN	UMBE	<b>-R</b> _S	#1176	40	$\underline{ PROJECT LOCATION  \underline{ }}$	eliman Road, Forestville NSW 208				
UnitLinks Contraction     Interact     SLOPE_g0     Beaking       EQUIPMENT     Includ Auger     HOLE LOCATION     Refer to the site plan       HOLE EXE     Stamption     COGGED BY _AW     CHECKED BY _AW       NOTES     Terminated at 0.7 on SANDSTONE     Check By _AW       Image: Stamption     Stamption     Stamption       Image: Stamption<			STAR	TED	12-10	<u>)-18</u>	COMPLETED <u>12-10-18</u>			DATUM			
CAUPERTEdit Auge:         Mode EVE         Cell CAUVING _ Receip to passe part           NOTE 5         Terminated at 0.7 on SANDSTONE         CHECKED BY _AW         CHECKED BY _AW           NOTE 5         Terminated at 0.7 on SANDSTONE         CHECKED BY _AW         CHECKED BY _AW           Note 5         Terminated at 0.7 on SANDSTONE         Samplas _ Remarks         Additional Observations           gag available         min book by gaged, dark black gray brown, two plasticity, molit (mc >>         Additional Observations           gag available         min book bits         Samplas _ Remarks         Additional Observations           gag available         min book dit         Samplas _ Remarks         Additional Observations           gag available         min book dit         Samplas _ Remarks         Additional Observations           gag available         min book dit         Fill frame clay gravet, dark gray brown, two plasticity, molit (mc >>         PIL           gag available         -         -         Borehook BH3 terminated at 0.7m         FIESDUAL         FIESDUAL						<b>)R</b> <u>In</u>	trax			BEARING			
TOLE 302       Constraints				I <u>Ha</u>	ind Au	ger			o the site plan				
Total colspan="4"       y <th></th> <th></th> <th>S Te</th> <th>rmina</th> <th>ited at</th> <th>0 7 on</th> <th>SANDSTONE</th> <th></th> <th></th> <th></th>			S Te	rmina	ited at	0 7 on	SANDSTONE						
Image: Properties         Semples: Remarks         Additional Observations           1	F												
Y     MLS     Sandy SLT frace day gravel, dark black grey brown, low plasticity, most (me >>     FLL       -     -     -     -       -     -     -     -       -     -     -     -       -     -     -     -       -     -     -     -       -     -     -     -       -     -     -     -       -     -     -     -       -     -     -     -       -     -     -     -       -     -     -     -		Water	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Descript	ion	Samples Tests Remarks	Additional Observations			
		Not Encountered		- - - - -		SP	SAND trace clay gravel, dark black grey bi SAND trace clay gravel, pale grey brown yellow. Borehole BH3 terminated at 0.7m	own, low plasticity, moist (mc >> , moist, medium dense		RESIDUAL			

REHOLE / TEST PIT S#117640.GPJ GINT STD AUSTRALIA.GD

		EXPLAN TEST PI	ATION F LOGS	OF NOTES, AE	BREVI	ATIONS &	TERM	S USED ON BOREHOLE AND		
DRILLIN	IG/EXC	AVATION METHOD								
HA	Hand /	Auger	W	Washbore			PT	Push Tube		
MA-	Mecha	inical Auger Drilling	HQ	Diamond Core - 6	3 mm		EX	Excavator		
-V	V-Bit		NMLC	Diamond Core - 5	2 mm		HAD	Hollow Auger Drilling		
-TC	TC-Bit,	e.g. ADT	NQ	Diamond Core - 4	7 mm					
PENETR	RATION	EXCAVATION RESISTANCE								
L	Low re	sistance. Rapid penetration possible	with little e	ffort from the equipr	ment used					
м	Mediu	m resistance. Excavation/possible at	an acceptab	ole rate with modera	ite effort fr	om the equipme	ent used			
н	High re	esistance. Further penetration is poss	ible at a slo	w rate and requires	significant	effort from the	equipme	nt		
R	Refusa	l or Practical Refusal. No further prog	gress possib	le without the risk of	f damage c	or unacceptable	wear to t	he digging implement or machine.		
These as	sessmer	its are subjective and are dependent	on many fa	ctors including the e	quipment	power, weight, d	condition	or excavation or drilling tools, and experience of		
the oper	ator.									
WATER										
$\nabla$	Water	level at date shown	$\Leftarrow$	Partial water loss						
$\Rightarrow$	Water	inflow	$ \Leftarrow $	Complete water lo	DSS					
NO	Ground Water Not Observed: Ground water obersvation not possible. Ground water may or may not be present									
NE	Groun less pe	d Water Not Encountered: Ground w rmeable strata. Inflow may have bee	ater was no n observed	t evident during exca had the borehole/te	avation or est pit beer	a short time aften I left open for a	er comple longer pe	tion. However, groundwater could be present in riod.		
SAMPL	ING AN	D TESTING								
SPT		Standard Penetration Test to AS128	89.6.3.1 - 20	004	DS	Disturbed sam	ple			
3,6,9	9 N=15	3,6,9 = blows per 150mm. N = blow penetration	vs per final 3	300mm	BDS	S Bulk disturbed sample				
30/80mi	m	Practical refusal, with blows and de refusal occurred	pth of pene	tration before	U63	3 Undisturbed thin wall push tube sample, nominal sample diameter denoted in millimetres				
RV	V	Penetration caused under rod weig	ht only		W	W Water sample				
ни	V	Penetration caused under hammer	and rod we	ight only	G	Gas sample				
н	В	Hammer bounce without penetration	on		V	V pilcon shear vane (kPa)				
1	R	Refusal to test			PP	PP Pocket penetrometer (kPa)				
					FP	Field permeab	ility test o	over section noted		
DCP		Dynamic Cone Penetrometer Test t	o AS1289.6	.3.2 - 1997	ES	Environmenta	l sample			
DCP (p)		Dynamic Cone Penetrometer Test t	o AS1289.6	.3.3 - 1997 Perth	PI	Plastic Index (9	%)			
		Sand Penetrometer			PL	Plastic Limit (%	6)			
	6	6 = blows per 100mm of penetratio	n		LL	Liquid Limit (%	5)			
				MC	MC Moisture Content (%)					
					CBR	Californian Bea	aring Rati	ion (%)		
ROCK CO	ROCK CORE RECOVERY									
TCR = Tc	TCR = Total Core Recovery (%)RQD = Rock Quality Designation (%)									
$=\frac{L}{2}$	ength o Leng	$\frac{f \ core \ recovered}{th \ of \ core \ run} \times 100$		$=\frac{\sum Axial la}{L}$	engths of ength of	core > 100 m core run	$\frac{n}{2} \times 100$	)		



#### **EXPLANATION OF NOTES, ABBREVIATIONS & TERMS USED ON BOREHOLE AND TEST PIT LOGS - SOIL DESCRIPTION (AS1726 - 2017)**

#### SOIL CLASSIFICATION SYSTEM

#### **Coarse Grained Soil**

- GW Well graded gravels, gravel-sand mixtures, little or no fines
- Poorly-graded gravels, gravel-sand mixtures, little or no fines, uniform GP gravels GM Silty gravels, gravel-sand-silt mixtures
- GC Clayey gravels, gravel-sand-clay mixtures
- sw
- Well-graded sands, gravelly sands, little or no fines
- Poorly-graded sands, gravelly sand, little or no fines SP
- SM Silty sands, sand-silt mixtures
- SC Clayey sands, sand-clay mixtures

#### **Fine Grained Soils**

- Inorganic silts and very fine sands, rock flour, silty or clayey fine sands ML or silts with low plasticity
- CL, CI Inorganic clays of low to medium plasticity, gravelly clays, sandy clays
- OL Organic silts and organic silty clays of low plasticity
- Inorganic silts, micaceous or diatomaceous fine sand for silty soils мн
- СН Inorganic clays of high plasticity
- ОН Organic clays of medium to high plasticity, organic silts
- РТ Peat, humus, swamp soils with high organic contents

First Letter: G = Gravel, S = Sand, M = Silt, C = Clay; Second Letter: W = Well-graded, P = Poorly-graded, M = Mixture, O = Organic, L = Low plasticity, H = High plasticity Soils may be a combination of multiple soil classifications where borderline

	PARTI	CLE SIZE		PLASTICITY CHART									
Soil	Major Division	Sub-Division	Particle Size (mm)										
	Boulders		>200										
	Cobbles		63 - 200	50									
		Coarse	20 - 63										
arse	Gravel	Medium	6 - 20	х 40 х СН ог ОН 50 <sup>3</sup> СИ -									
Соа		Fine	2.36 - 6	2 30									
		Coarse	0.6 - 2.36										
	Sand	Medium	0.2 - 0.6	MH or OH									
		Fine	0.075 - 0.2										
э	Silt		0.002 - 0.075										
Ë	Clay		< 0.002	0 10 20 30 40 50 60 70 80 90 100									
0.075mm	is the approximate minimum	particle size disc	ernible by eye										
MOISTU	RE CONDITION												
a)	D Dry	Sands and grav	els are free flowing.										
oars	M Moist	Soils are darker	than in the dry conditio	n and may feel cool. Sands and gravels tend to cohere.									
Ŭ	W Wet	Soils exude free	e water. Sands and grave	els tend to cohere.									
ē	PL Plastic Limit	Moisture conte	nt of fine grain soils are	described; as below plastic limit ( <pl), (="PL)," above="" limit="" limit<="" near="" plastic="" td="" to=""></pl),>									
Fir	LL Liquid Limit	(>PL), near to t	ne liquid limit (=LL), or al	bove the liquid limit (>LL)									
CONSIST													

Fine	e Grained Soils			Poc	ket Pentror	neter Coarse	Grained Soil		
					Reading (kP	'a)		Density Index %	'N' Value
VS	Very Soft	Exudes betwee	en fingers when squeezed	l	<25	VL	Very Loose	≤15	0 - 4
S	Soft	Can be mould	ed by light finger pressure	2	20 - 50	L	Loose	15 - 35	4 - 10
F	Firm	Can be mould	ed by strong finger pressu	ire	50 - 100	MD	Medium Dense	35 - 65	10 - 30
St	Stiff	Cannot be mo	ulded by fingers. Can be i	ndented by thumb	100 - 200	D	Dense	65 - 85	30 - 50
VSt	Very Stiff	Can be indent	ed by thumb nail		200 - 400 VD		Very Dense	>85	>50
н	Hard	Can be indent	ed by thumb nail with diff	iculty	>400				
SEC	ONDARY OR MIN	IOR SOIL COM	PONENTS						
	Designation of		In c		In	fine grained soils			
	components	%Fines	Terminology	%Accessory Coars	e Fraction	Terminology	%Sand/gravel	%Sand/gravel Terminolo	
		≤5	'trace' clay/silt	≤15		'trace' sand/gravel	≤15	'trace' sand/gravel	
	Minor 5 - 12 'with' clay/silt 15 - 3		15 - 30		'with' sand/gravel	15 - 30	'with' sand/gravel		
	Secondary	> 15	Prefix silty or clayey	>30		Prefix sandy or gravelly	>30	Prefix sandy or gravelly	



#### EXPLANATION OF NOTES, ABBREVIATIONS & TERMS USED ON BOREHOLE AND TEST PIT LOGS - ROCK DESCRIPTION (AS1726 - 2017)

STRENG	RENGTH OF INTACT ROCK									
Symbol	ol Term Point Load Index, (I		50) MPa			Field Gu	uide to Strength			
VL	Very Low	0.03	≤ I <sub>s50</sub> < 0.	1	Material crumbles thick can be broker	under firr n by finge	n blows with sharp end r pressure	d of pick; can be peeled	with knife; pieces up to 30mm	
L	Low	0.1	≤ I <sub>s50</sub> < 0.3	1	Easily scored with k 50mm diameter ca	knife; ind n be brok	entations 1mm to 3mn en by hand; sharp edg	n after firm blow with pie es of core friable	ck point; core 150mm long and	
м	Medium	0.3	≤ I <sub>s50</sub> < 1.0		Readily scored with	n knife; co	re 150mm long and 50	)mm diameter can be br	oken by hand with difficulty	
н	High	1.0	≤ I <sub>s50</sub> < 3		Core 150mm long and 50mm diameter cannot be broken by hand but can be broken by single firm blow c pick; rock rings under hammer					
VH	Very High	3 ≤	۲ I <sub>s50</sub> < 10		Hand held specimen breaks with pick after more than one blow; rock rings under hammer					
EH	Extremely High	1	$0 \le I_{s50}$		Specimen requires many pick blows to break intact rock, rock rings under hammer					
Material	with rock strength	less than 'Ver	y Low' are	described	d using soil propertie	S				
DEGREE	OF ROCK WEA	THERING								
	Term Syr			nbol			C	Definition		
Residual S	Soil		1	RS	Soil derived from th has not been signif	ne weath icantly tra	ering of rock; the mass ansported.	structure and material f	abric are no longer evident the soil	
Extremely	/ Weathered		х	W	Material is weather remoulded, in wate	red to suc er. Fabric	h an extent that it has of original rock still vis	soil properties, i.e. it eitl ible.	her disintegrates or can be	
Highly We	eathered	Distinctly Weathered	НW	DW	Rock strength is cha staining or bleachir decomposed to cla weathering produc	anged by ng to the y mineral ts in pore	weathering. The whole extent that the colour o s. Porosity may be incr s.	e of the rock material is o of the original rock is not eased by leach, or may l	discoloured, usually by iron t recognizable. Some minerals are be decreased due to deposition of	
Moderate	ely Weathered		MW	The whole of the rock material is discoloured, usually colour of the original rock is not recognisable, but sho		Ily by iron staining or ble shows little or no change	eaching to the extent that the of strength from fresh rock.			
Slightly W	/eathered		S	W	Rock is slightly disc	oloured b	out shows little or no cl	nange of strength from f	resh rock	
Fresh		FR			Rock shows no sign	Rock shows no sign of decomposition or staining				
Distinctly	Weathered is to l	oe used when i	t is not po	ssible to c	lifferentiate betweer	n highly a	nd moderately weathe	red.		
Extremely	/ Weathered mate	erial is to be de	scribed us	sing soil pr	roperties					
ROCK M	ASS PROPERTIE	S								
Term		Separation of Stratification	Planes		Term	Descri	otion			
Thinly lan	ninated	< 6mr	n		Fragmented	Primar	ly fragments < 20mm	length and mostly of wic	th < core diameter	
Laminate	d	6mm to 2	0 mm		Highly fractured	Core le	ngths generally less th	an 20mm to 40mm with	occasional fragments	
Very thinl	ly bedded	20mm to 6	50mm							
Thinly be	dded	60mm to 2	00mm		Fractured	Core le	ngths mainly 30mm to	100mm with occasiona	I shorter and longer pieces	
Medium I	bedded	0.2m to 0	0.6m		Slightly fractured	Core le	ngths generally 0.3m t	o 1.0m with occasional l	onger and shorter sections	
Thickly be	edded	0.6m to 2	2.0m				<b>6</b>			
Massive		< 2m	1		Unbroken	Core h	as no fractures			
DEFECT	TYPES AND DES	CRIPTIONS				Currentere	Developeration	Defect	<b>C</b> a at in an	
	Pedding parting			Defect Sr	Diapar	Surrace	Vorurough	Defect	Clean	
				PL	Fidildi	VK	Very rough	CL CT	Clean	
ср 11	Shoarod surface			ы СР	Stepped	RU SN4	Rougn	51	Voncor	
эћ 67	SR Sheared surface				Irrogular		Dolishod	VIN	Conting	
3 <u>2</u> 55	SZ Sneared zone				rU SI	Slickenside	CI	coating		
55	Crushed coom				Giluliaulig	JL	SIICKEIISIUE			
				Vertical	artical Boreholes - The din of the defect is given from the horizontal					
NS NS	Extremely Most	arad Saam		Inclined			lefect is given from the			
xs Extremely Weathered Seam				inclined	burenoies - The angl	e or the (	lerect is given from the	e core axis		



# **Appendix B**

Site Photography











# Appendix C

CSIRO BTF "Foundation Maintenance and Footing Performance: A Homeowner's Guide"

Practice Note Guidelines For Landslide Risk Management 2007

Australian Geoguide LR8 (Construction Practice)

# Foundation Maintenance and Footing Performance: A Homeowner's Guide



BTF 18 replaces Information Sheet 10/91

Buildings can and often do move. This movement can be up, down, lateral or rotational. The fundamental cause of movement in buildings can usually be related to one or more problems in the foundation soil. It is important for the homeowner to identify the soil type in order to ascertain the measures that should be put in place in order to ensure that problems in the foundation soil can be prevented, thus protecting against building movement.

This Building Technology File is designed to identify causes of soil-related building movement, and to suggest methods of prevention of resultant cracking in buildings.

#### Soil Types

The types of soils usually present under the topsoil in land zoned for residential buildings can be split into two approximate groups – granular and clay. Quite often, foundation soil is a mixture of both types. The general problems associated with soils having granular content are usually caused by erosion. Clay soils are subject to saturation and swell/shrink problems.

Classifications for a given area can generally be obtained by application to the local authority, but these are sometimes unreliable and if there is doubt, a geotechnical report should be commissioned. As most buildings suffering movement problems are founded on clay soils, there is an emphasis on classification of soils according to the amount of swell and shrinkage they experience with variations of water content. The table below is Table 2.1 from AS 2870, the Residential Slab and Footing Code.

#### **Causes of Movement**

Settlement due to construction

There are two types of settlement that occur as a result of construction:

- Immediate settlement occurs when a building is first placed on its foundation soil, as a result of compaction of the soil under the weight of the structure. The cohesive quality of clay soil mitigates against this, but granular (particularly sandy) soil is susceptible.
- Consolidation settlement is a feature of clay soil and may take place because of the expulsion of moisture from the soil or because of the soil's lack of resistance to local compressive or shear stresses. This will usually take place during the first few months after construction, but has been known to take many years in exceptional cases.

These problems are the province of the builder and should be taken into consideration as part of the preparation of the site for construction. Building Technology File 19 (BTF 19) deals with these problems.

#### Erosion

All soils are prone to erosion, but sandy soil is particularly susceptible to being washed away. Even clay with a sand component of say 10% or more can suffer from erosion.

#### Saturation

This is particularly a problem in clay soils. Saturation creates a boglike suspension of the soil that causes it to lose virtually all of its bearing capacity. To a lesser degree, sand is affected by saturation because saturated sand may undergo a reduction in volume – particularly imported sand fill for bedding and blinding layers. However, this usually occurs as immediate settlement and should normally be the province of the builder.

#### Seasonal swelling and shrinkage of soil

All clays react to the presence of water by slowly absorbing it, making the soil increase in volume (see table below). The degree of increase varies considerably between different clays, as does the degree of decrease during the subsequent drying out caused by fair weather periods. Because of the low absorption and expulsion rate, this phenomenon will not usually be noticeable unless there are prolonged rainy or dry periods, usually of weeks or months, depending on the land and soil characteristics.

The swelling of soil creates an upward force on the footings of the building, and shrinkage creates subsidence that takes away the support needed by the footing to retain equilibrium.

#### Shear failure

This phenomenon occurs when the foundation soil does not have sufficient strength to support the weight of the footing. There are two major post-construction causes:

- Significant load increase.
- Reduction of lateral support of the soil under the footing due to erosion or excavation.
- In clay soil, shear failure can be caused by saturation of the soil adjacent to or under the footing.

	GENERAL DEFINITIONS OF SITE CLASSES						
Class	Foundation						
А	Most sand and rock sites with little or no ground movement from moisture changes						
S	Slightly reactive clay sites with only slight ground movement from moisture changes						
М	Moderately reactive clay or silt sites, which can experience moderate ground movement from moisture changes						
Н	Highly reactive clay sites, which can experience high ground movement from moisture changes						
E	E Extremely reactive sites, which can experience extreme ground movement from moisture changes						
A to P	A to P Filled sites						
Р	Sites which include soft soils, such as soft clay or silt or loose sands; landslip; mine subsidence; collapsing soils; soils subject to erosion; reactive sites subject to abnormal moisture conditions or sites which cannot be classified otherwise						

#### Tree root growth

Trees and shrubs that are allowed to grow in the vicinity of footings can cause foundation soil movement in two ways:

- Roots that grow under footings may increase in cross-sectional size, exerting upward pressure on footings.
- Roots in the vicinity of footings will absorb much of the moisture in the foundation soil, causing shrinkage or subsidence.

#### **Unevenness of Movement**

The types of ground movement described above usually occur unevenly throughout the building's foundation soil. Settlement due to construction tends to be uneven because of:

- Differing compaction of foundation soil prior to construction.
- Differing moisture content of foundation soil prior to construction.

Movement due to non-construction causes is usually more uneven still. Erosion can undermine a footing that traverses the flow or can create the conditions for shear failure by eroding soil adjacent to a footing that runs in the same direction as the flow.

Saturation of clay foundation soil may occur where subfloor walls create a dam that makes water pond. It can also occur wherever there is a source of water near footings in clay soil. This leads to a severe reduction in the strength of the soil which may create local shear failure.

Seasonal swelling and shrinkage of clay soil affects the perimeter of the building first, then gradually spreads to the interior. The swelling process will usually begin at the uphill extreme of the building, or on the weather side where the land is flat. Swelling gradually reaches the interior soil as absorption continues. Shrinkage usually begins where the sun's heat is greatest.

#### Effects of Uneven Soil Movement on Structures

#### Erosion and saturation

Erosion removes the support from under footings, tending to create subsidence of the part of the structure under which it occurs. Brickwork walls will resist the stress created by this removal of support by bridging the gap or cantilevering until the bricks or the mortar bedding fail. Older masonry has little resistance. Evidence of failure varies according to circumstances and symptoms may include:

- Step cracking in the mortar beds in the body of the wall or above/below openings such as doors or windows.
- Vertical cracking in the bricks (usually but not necessarily in line with the vertical beds or perpends).

Isolated piers affected by erosion or saturation of foundations will eventually lose contact with the bearers they support and may tilt or fall over. The floors that have lost this support will become bouncy, sometimes rattling ornaments etc.

#### Seasonal swelling/shrinkage in clay

Swelling foundation soil due to rainy periods first lifts the most exposed extremities of the footing system, then the remainder of the perimeter footings while gradually permeating inside the building footprint to lift internal footings. This swelling first tends to create a dish effect, because the external footings are pushed higher than the internal ones.

The first noticeable symptom may be that the floor appears slightly dished. This is often accompanied by some doors binding on the floor or the door head, together with some cracking of cornice mitres. In buildings with timber flooring supported by bearers and joists, the floor can be bouncy. Externally there may be visible dishing of the hip or ridge lines.

As the moisture absorption process completes its journey to the innermost areas of the building, the internal footings will rise. If the spread of moisture is roughly even, it may be that the symptoms will temporarily disappear, but it is more likely that swelling will be uneven, creating a difference rather than a disappearance in symptoms. In buildings with timber flooring supported by bearers and joists, the isolated piers will rise more easily than the strip footings or piers under walls, creating noticeable doming of flooring.



As the weather pattern changes and the soil begins to dry out, the external footings will be first affected, beginning with the locations where the sun's effect is strongest. This has the effect of lowering the external footings. The doming is accentuated and cracking reduces or disappears where it occurred because of dishing, but other cracks open up. The roof lines may become convex.

Doming and dishing are also affected by weather in other ways. In areas where warm, wet summers and cooler dry winters prevail, water migration tends to be toward the interior and doming will be accentuated, whereas where summers are dry and winters are cold and wet, migration tends to be toward the exterior and the underlying propensity is toward dishing.

#### Movement caused by tree roots

In general, growing roots will exert an upward pressure on footings, whereas soil subject to drying because of tree or shrub roots will tend to remove support from under footings by inducing shrinkage.

#### Complications caused by the structure itself

Most forces that the soil causes to be exerted on structures are vertical – i.e. either up or down. However, because these forces are seldom spread evenly around the footings, and because the building resists uneven movement because of its rigidity, forces are exerted from one part of the building to another. The net result of all these forces is usually rotational. This resultant force often complicates the diagnosis because the visible symptoms do not simply reflect the original cause. A common symptom is binding of doors on the vertical member of the frame.

#### Effects on full masonry structures

Brickwork will resist cracking where it can. It will attempt to span areas that lose support because of subsided foundations or raised points. It is therefore usual to see cracking at weak points, such as openings for windows or doors.

In the event of construction settlement, cracking will usually remain unchanged after the process of settlement has ceased.

With local shear or erosion, cracking will usually continue to develop until the original cause has been remedied, or until the subsidence has completely neutralised the affected portion of footing and the structure has stabilised on other footings that remain effective.

In the case of swell/shrink effects, the brickwork will in some cases return to its original position after completion of a cycle, however it is more likely that the rotational effect will not be exactly reversed, and it is also usual that brickwork will settle in its new position and will resist the forces trying to return it to its original position. This means that in a case where swelling takes place after construction and cracking occurs, the cracking is likely to at least partly remain after the shrink segment of the cycle is complete. Thus, each time the cycle is repeated, the likelihood is that the cracking will become wider until the sections of brickwork become virtually independent.

With repeated cycles, once the cracking is established, if there is no other complication, it is normal for the incidence of cracking to stabilise, as the building has the articulation it needs to cope with the problem. This is by no means always the case, however, and monitoring of cracks in walls and floors should always be treated seriously.

Upheaval caused by growth of tree roots under footings is not a simple vertical shear stress. There is a tendency for the root to also exert lateral forces that attempt to separate sections of brickwork after initial cracking has occurred.

The normal structural arrangement is that the inner leaf of brickwork in the external walls and at least some of the internal walls (depending on the roof type) comprise the load-bearing structure on which any upper floors, ceilings and the roof are supported. In these cases, it is internally visible cracking that should be the main focus of attention, however there are a few examples of dwellings whose external leaf of masonry plays some supporting role, so this should be checked if there is any doubt. In any case, externally visible cracking is important as a guide to stresses on the structure generally, and it should also be remembered that the external walls must be capable of supporting themselves.

#### Effects on framed structures

Timber or steel framed buildings are less likely to exhibit cracking due to swell/shrink than masonry buildings because of their flexibility. Also, the doming/dishing effects tend to be lower because of the lighter weight of walls. The main risks to framed buildings are encountered because of the isolated pier footings used under walls. Where erosion or saturation cause a footing to fall away, this can double the span which a wall must bridge. This additional stress can create cracking in wall linings, particularly where there is a weak point in the structure caused by a door or window opening. It is, however, unlikely that framed structures will be so stressed as to suffer serious damage without first exhibiting some or all of the above symptoms for a considerable period. The same warning period should apply in the case of upheaval. It should be noted, however, that where framed buildings are supported by strip footings there is only one leaf of brickwork and therefore the externally visible walls are the supporting structure for the building. In this case, the subfloor masonry walls can be expected to behave as full brickwork walls.

#### Effects on brick veneer structures

Because the load-bearing structure of a brick veneer building is the frame that makes up the interior leaf of the external walls plus perhaps the internal walls, depending on the type of roof, the building can be expected to behave as a framed structure, except that the external masonry will behave in a similar way to the external leaf of a full masonry structure.

#### Water Service and Drainage

Where a water service pipe, a sewer or stormwater drainage pipe is in the vicinity of a building, a water leak can cause erosion, swelling or saturation of susceptible soil. Even a minuscule leak can be enough to saturate a clay foundation. A leaking tap near a building can have the same effect. In addition, trenches containing pipes can become watercourses even though backfilled, particularly where broken rubble is used as fill. Water that runs along these trenches can be responsible for serious erosion, interstrata seepage into subfloor areas and saturation.

Pipe leakage and trench water flows also encourage tree and shrub roots to the source of water, complicating and exacerbating the problem.

Poor roof plumbing can result in large volumes of rainwater being concentrated in a small area of soil:

 Incorrect falls in roof guttering may result in overflows, as may gutters blocked with leaves etc.

- · Corroded guttering or downpipes can spill water to ground.
- Downpipes not positively connected to a proper stormwater collection system will direct a concentration of water to soil that is directly adjacent to footings, sometimes causing large-scale problems such as erosion, saturation and migration of water under the building.

#### Seriousness of Cracking

In general, most cracking found in masonry walls is a cosmetic nuisance only and can be kept in repair or even ignored. The table below is a reproduction of Table C1 of AS 2870.

AS 2870 also publishes figures relating to cracking in concrete floors, however because wall cracking will usually reach the critical point significantly earlier than cracking in slabs, this table is not reproduced here.

#### **Prevention/Cure**

#### Plumbing

Where building movement is caused by water service, roof plumbing, sewer or stormwater failure, the remedy is to repair the problem. It is prudent, however, to consider also rerouting pipes away from the building where possible, and relocating taps to positions where any leakage will not direct water to the building vicinity. Even where gully traps are present, there is sometimes sufficient spill to create erosion or saturation, particularly in modern installations using smaller diameter PVC fixtures. Indeed, some gully traps are not situated directly under the taps that are installed to charge them, with the result that water from the tap may enter the backfilled trench that houses the sewer piping. If the trench has been poorly backfilled, the water will either pond or flow along the bottom of the trench. As these trenches usually run alongside the footings and can be at a similar depth, it is not hard to see how any water that is thus directed into a trench can easily affect the foundation's ability to support footings or even gain entry to the subfloor area.

#### Ground drainage

In all soils there is the capacity for water to travel on the surface and below it. Surface water flows can be established by inspection during and after heavy or prolonged rain. If necessary, a grated drain system connected to the stormwater collection system is usually an easy solution.

It is, however, sometimes necessary when attempting to prevent water migration that testing be carried out to establish watertable height and subsoil water flows. This subject is referred to in BTF 19 and may properly be regarded as an area for an expert consultant.

#### Protection of the building perimeter

It is essential to remember that the soil that affects footings extends well beyond the actual building line. Watering of garden plants, shrubs and trees causes some of the most serious water problems.

For this reason, particularly where problems exist or are likely to occur, it is recommended that an apron of paving be installed around as much of the building perimeter as necessary. This paving

Description of typical damage and required repair	Approximate crack width limit (see Note 3)	Damage category
Hairline cracks	<0.1 mm	0
Fine cracks which do not need repair	<1 mm	1
Cracks noticeable but easily filled. Doors and windows stick slightly	<5 mm	2
Cracks can be repaired and possibly a small amount of wall will need to be replaced. Doors and windows stick. Service pipes can fracture. Weathertightness often impaired	5–15 mm (or a number of cracks 3 mm or more in one group)	3
Extensive repair work involving breaking-out and replacing sections of walls, especially over doors and windows. Window and door frames distort. Walls lean or bulge noticeably, some loss of bearing in beams. Service pipes disrupted	15–25 mm but also depend on number of cracks	4



should extend outwards a minimum of 900 mm (more in highly reactive soil) and should have a minimum fall away from the building of 1:60. The finished paving should be no less than 100 mm below brick vent bases.

It is prudent to relocate drainage pipes away from this paving, if possible, to avoid complications from future leakage. If this is not practical, earthenware pipes should be replaced by PVC and backfilling should be of the same soil type as the surrounding soil and compacted to the same density.

Except in areas where freezing of water is an issue, it is wise to remove taps in the building area and relocate them well away from the building – preferably not uphill from it (see BTF 19).

It may be desirable to install a grated drain at the outside edge of the paving on the uphill side of the building. If subsoil drainage is needed this can be installed under the surface drain.

#### Condensation

In buildings with a subfloor void such as where bearers and joists support flooring, insufficient ventilation creates ideal conditions for condensation, particularly where there is little clearance between the floor and the ground. Condensation adds to the moisture already present in the subfloor and significantly slows the process of drying out. Installation of an adequate subfloor ventilation system, either natural or mechanical, is desirable.

*Warning:* Although this Building Technology File deals with cracking in buildings, it should be said that subfloor moisture can result in the development of other problems, notably:

- Water that is transmitted into masonry, metal or timber building elements causes damage and/or decay to those elements.
- High subfloor humidity and moisture content create an ideal environment for various pests, including termites and spiders.
- Where high moisture levels are transmitted to the flooring and walls, an increase in the dust mite count can ensue within the living areas. Dust mites, as well as dampness in general, can be a health hazard to inhabitants, particularly those who are abnormally susceptible to respiratory ailments.

#### The garden

The ideal vegetation layout is to have lawn or plants that require only light watering immediately adjacent to the drainage or paving edge, then more demanding plants, shrubs and trees spread out in that order.

Overwatering due to misuse of automatic watering systems is a common cause of saturation and water migration under footings. If it is necessary to use these systems, it is important to remove garden beds to a completely safe distance from buildings.

#### Existing trees

Where a tree is causing a problem of soil drying or there is the existence or threat of upheaval of footings, if the offending roots are subsidiary and their removal will not significantly damage the tree, they should be severed and a concrete or metal barrier placed vertically in the soil to prevent future root growth in the direction of the building. If it is not possible to remove the relevant roots without damage to the tree, an application to remove the tree should be made to the local authority. A prudent plan is to transplant likely offenders before they become a problem.

#### Information on trees, plants and shrubs

State departments overseeing agriculture can give information regarding root patterns, volume of water needed and safe distance from buildings of most species. Botanic gardens are also sources of information. For information on plant roots and drains, see Building Technology File 17.

#### Excavation

Excavation around footings must be properly engineered. Soil supporting footings can only be safely excavated at an angle that allows the soil under the footing to remain stable. This angle is called the angle of repose (or friction) and varies significantly between soil types and conditions. Removal of soil within the angle of repose will cause subsidence.

#### Remediation

Where erosion has occurred that has washed away soil adjacent to footings, soil of the same classification should be introduced and compacted to the same density. Where footings have been undermined, augmentation or other specialist work may be required. Remediation of footings and foundations is generally the realm of a specialist consultant.

Where isolated footings rise and fall because of swell/shrink effect, the homeowner may be tempted to alleviate floor bounce by filling the gap that has appeared between the bearer and the pier with blocking. The danger here is that when the next swell segment of the cycle occurs, the extra blocking will push the floor up into an accentuated dome and may also cause local shear failure in the soil. If it is necessary to use blocking, it should be by a pair of fine wedges and monitoring should be carried out fortnightly.

### This BTF was prepared by John Lewer FAIB, MIAMA, Partner, Construction Diagnosis.

The Information in this and other issues in the series was derived from various sources and was believed to be correct when published.

The Information is advisory. It is provided in good faith and not claimed to be an exhaustive treatment of the relevant subject.

Further professional advice needs to be obtained before taking any action based on the information provided.

Distributed by

CSIRO PUBLISHING PO Box 1139, Collingwood 3066, Australia

Freecall 1800 645 051 Tel (03) 9662 7666 Fax (03) 9662 7555 www.publish.csiro.au Email: publishing.sales@csiro.au

© CSIRO 2003. Unauthorised copying of this Building Technology file is prohibited

QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007 APPENDIX C: LANDSLIDE RISK ASSESSMENT

# QUALITATIVE MEASURES OF LIKELIHOOD

Approximate A	nnual Probability	Imulied Indicativ	ve Landslide		Decemination	0110
Indicative	Notional	Recurrence	Interval	Description	Indines	
Value	Boundary				AT MOST CEDTAIN	~
10 <sup>-1</sup>		10 years		The event is expected to occur over the design life.	ALMUST CENTAIN	V
10 <sup>-2</sup>	- 01XC	100 years	20 years	The event will probably occur under adverse conditions over the design life.	LIKELY	В
10-3	$5 \times 10^{-3}$	1000 vears	200 years	The event could occur under adverse conditions over the design life.	POSSIBLE	c
10-4	5x10 <sup>-4</sup>	10,000 years	2()()() vears	The event might occur under very adverse circumstances over the design life.	UNLIKELY	D
10-5	5x10 <sup>-5</sup>	100,000 years	20,000 years	The event is conceivable but only under exceptional circumstances	RARE	ш
10-6	- 5x10 <sup>-6</sup>	1.000.000 vears	200,000 years	The event is inconceivable or fanciful over the design life.	BARELY CREDIBLE	н
10		6				

The table should be used from left to right; use Approximate Annual Probability or Description to assign Descriptor, not vice versa. Note: (1)

# QUALITATIVE MEASURES OF CONSEQUENCES TO PROPERTY

Approximate (	Cost of Damage	Description	Descriptor	Level
Indicative	Notional			
200%	f imminor	Structure(s) completely destroyed and/or large scale damage requiring major engineering works for	CATASTROPHIC	1
60%	100%	extension course of structure, and/or extending beyond site boundaries requiring significant Extension damage to most of structure, and/or extending beyond site boundaries requiring significant modulisation works. Could cause at least one adjacent monerty medium consequence damage.	MAJOR	2
20%	40%	nationation works, court where we and/or significant part of site requiring large stabilisation works. Moderate damage to some of structure, and/or significant part of site requiring large stabilisation works.	MEDIUM	3
20/2	10%	Louid cause at least one adjacent property minor supervise access and set of site requiring some reinstatement stabilisation works.	MINOR	4
0.5%	1%	Little damage. (Note for high probability event (Almost Certain), this category may be subdivided at a notional boundary of 0.1%. See Risk Matrix.)	INSIGNIFICANT	5
Notes: (2)	The Approximate C	ost of Damage is expressed as a percentage of market value, being the cost of the improved value of the unaffected I	property which includes the la	and plus the

à unaffected structures. I he Appr (7)

The Approximate Cost is to be an estimate of the direct cost of the damage, such as the cost of reinstatement of the damaged portion of the property (land plus structures), stabilisation works required to render the site to tolerable risk level for the landslide which has occurred and professional design fees, and consequential costs such as legal fees, temporary accommodation. It does not include additional stabilisation works to address other landslides which may affect the property. (3)

The table should be used from left to right, use Approximate Cost of Damage or Description to assign Descriptor, not vice versa (4)

Australian Geomechanics Vol 42 No 1 March 2007

APPENDIX C: - QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY (CONTINUED) PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

<b>LIKELIHO</b>	00	CONSEQU	ENCES TO PROPE	CRTY (With Indicati	ve Approximate Cost	of Damage)
	Indicative Value of Approximate Annual Probability	1: CATASTROPHIC 200%	2: MAJOR 60%	3: MEDIUM 20%	4: MINOR 5%	5: INSIGNIFICANT 0.5%
A – ALMOST CERTAIN	10 <sup>-1</sup>	HIA	HA	HIA	Н	M or L (5)
B - LIKELY	10 <sup>-2</sup>	HA	ΝΗ	Н	M	L
C - POSSIBLE	10-3	НИ	Н	M	M	٨L
D - UNLIKELY	10-4	Н	M	L	L	NL
E - RARE	10-5	M	L	L	٧L	NL
F - BARELY CREDIBLE	10-6	L	٨L	AL	٨L	NL

QUALITATIVE RISK ANALYSIS MATRIX – LEVEL OF RISK TO PROPERTY

Notes:

For Cell A5, may be subdivided such that a consequence of less than 0.1% is Low Risk. When considering a risk assessment it must be clearly stated whether it is for existing conditions or with risk control measures which may not be implemented at the current (5)

time.

**RISK LEVEL IMPLICATIONS** 

	Risk Level	Example Implications (7)
		Unacceptable without treatment. Extensive detailed investigation and research, planning and implementation of treatment
HA	VERY HIGH RISK	options essential to reduce risk to Low; may be too expensive and not practical. Work likely to cost more than value of the
		property.
:		Unacceptable without treatment. Detailed investigation, planning and implementation of treatment options required to reduce
Ľ	NCIN HUIH	risk to Low. Work would cost a substantial sum in relation to the value of the property.
		May be tolerated in certain circumstances (subject to regulator's approval) but requires investigation, planning and
M	MODERATE RISK	implementation of treatment options to reduce the risk to Low. Treatment options to reduce to Low risk should be
		implemented as soon as practicable.
	ASIG INO 1	Usually acceptable to regulators. Where treatment has been required to reduce the risk to this level, ongoing maintenance is
Г	LUW NIJA	required.
٨L	VERY LOW RISK	Acceptable. Manage by normal slope maintenance procedures.
(D) , 14	The implications for a motion for a motion	we to be determined by all norties to the risk assessment and may denend on the nature of the monetry at risk' these are only

g nature of the property an DEI O may uepenu ISK The implications for a particular situation are to be determined by all parties to the given as a general guide.  $\Xi$ Note:

#### AUSTRALIAN GEOGUIDE LR8 (CONSTRUCTION PRACTICE)

#### HILLSIDE CONSTRUCTION PRACTICE

Sensible development practices are required when building on hillsides, particularly if the hillside has more than a low risk of instability (GeoGuide LR7). Only building techniques intended to maintain, or reduce, the overall level of landslide risk should be considered. Examples of good hillside construction practice are illustrated below.



#### WHY ARE THESE PRACTICES GOOD?

Roadways and parking areas - are paved and incorporate kerbs which prevent water discharging straight into the hillside (GeoGuide LR5).

Cuttings - are supported by retaining walls (GeoGuide LR6).

**Retaining walls -** are engineer designed to withstand the lateral earth pressures and surcharges expected, and include drains to prevent water pressures developing in the backfill. Where the ground slopes steeply down towards the high side of a retaining wall, the disturbing force (see GeoGuide LR6) can be two or more times that in level ground. Retaining walls must be designed taking these forces into account.

Sewage - whether treated or not is either taken away in pipes or contained in properly founded tanks so it cannot soak into the ground.

**Surface water -** from roofs and other hard surfaces is piped away to a suitable discharge point rather than being allowed to infiltrate into the ground. Preferably, the discharge point will be in a natural creek where ground water exits, rather than enters, the ground. Shallow, lined, drains on the surface can fulfil the same purpose (GeoGuide LR5).

**Surface loads** - are minimised. No fill embankments have been built. The house is a lightweight structure. Foundation loads have been taken down below the level at which a landslide is likely to occur and, preferably, to rock. This sort of construction is probably not applicable to soil slopes (GeoGuide LR3). If you are uncertain whether your site has rock near the surface, or is essentially a soil slope, you should engage a geotechnical practitioner to find out.

Flexible structures - have been used because they can tolerate a certain amount of movement with minimal signs of distress and maintain their functionality.

**Vegetation clearance -** on soil slopes has been kept to a reasonable minimum. Trees, and to a lesser extent smaller vegetation, take large quantities of water out of the ground every day. This lowers the ground water table, which in turn helps to maintain the stability of the slope. Large scale clearing can result in a rise in water table with a consequent increase in the likelihood of a landslide (GeoGuide LR5). An exception may have to be made to this rule on steep rock slopes where trees have little effect on the water table, but their roots pose a landslide hazard by dislodging boulders.

Possible effects of ignoring good construction practices are illustrated on page 2. Unfortunately, these poor construction practices are not as unusual as you might think and are often chosen because, on the face of it, they will save the developer, or owner, money. You should not lose sight of the fact that the cost and anguish associated with any one of the disasters illustrated, is likely to more than wipe out any apparent savings at the outset.

#### ADOPT GOOD PRACTICE ON HILLSIDE SITES

Australian Geomechanics Vol 42 No 1 March 2007

#### AUSTRALIAN GEOGUIDE LR8 (CONSTRUCTION PRACTICE)

#### EXAMPLES OF POOR HILLSIDE CONSTRUCTION PRACTICE



#### WHY ARE THESE PRACTICES POOR?

Roadways and parking areas - are unsurfaced and lack proper table drains (gutters) causing surface water to pond and soak into the ground.

**Cut and fill -** has been used to balance earthworks quantities and level the site leaving unstable cut faces and added large surface loads to the ground. Failure to compact the fill properly has led to settlement, which will probably continue for several years after completion. The house and pool have been built on the fill and have settled with it and cracked. Leakage from the cracked pool and the applied surface loads from the fill have combined to cause landslides.

**Retaining walls -** have been avoided, to minimise cost, and hand placed rock walls used instead. Without applying engineering design principles, the walls have failed to provide the required support to the ground and have failed, creating a very dangerous situation.

A heavy, rigid, house - has been built on shallow, conventional, footings. Not only has the brickwork cracked because of the resulting ground movements, but it has also become involved in a man-made landslide.

**Soak-away drainage -** has been used for sewage and surface water run-off from roofs and pavements. This water soaks into the ground and raises the water table (GeoGuide LR5). Subsoil drains that run along the contours should be avoided for the same reason. If felt necessary, subsoil drains should run steeply downhill in a chevron, or herring bone, pattern. This may conflict with the requirements for effluent and surface water disposal (GeoGuide LR9) and if so, you will need to seek professional advice.

**Rock debris** - from landslides higher up on the slope seems likely to pass through the site. Such locations are often referred to by geotechnical practitioners as "debris flow paths". Rock is normally even denser than ordinary fill, so even quite modest boulders are likely to weigh many tonnes and do a lot of damage once they start to roll. Boulders have been known to travel hundreds of metres downhill leaving behind a trail of destruction.

Vegetation - has been completely cleared, leading to a possible rise in the water table and increased landslide risk (GeoGuide LR5).

#### DON'T CUT CORNERS ON HILLSIDE SITES - OBTAIN ADVICE FROM A GEOTECHNICAL PRACTITIONER

More information relevant to your particular situation may be found in other Australian GeoGuides:

•	GeoGuide LR1	- Introduction		GeoGuide LR6	- Retaining Walls
	GeoGuide LR2	- Landslides	•	GeoGuide LR7	- Landslide Risk
•	GeoGuide LR3	- Landslides in Soil		GeoGuide LR9	- Effluent & Surface Water Disposal
•	GeoGuide LR4	- Landslides in Rock		GeoGuide LR10	<ul> <li>Coastal Landslides</li> </ul>
•	GeoGuide LR5	- Water & Drainage	•	GeoGuide LR11	- Record Keeping

The Australian GeoGuides (LR series) are a set of publications intended for property owners; local councils; planning authorities; developers; insurers; lawyers and, in fact, anyone who lives with, or has an interest in, a natural or engineered slope, a cutting, or an excavation. They are intended to help you understand why slopes and retaining structures can be a hazard and what can be done with appropriate professional advice and local council approval (if required) to remove, reduce, or minimise the risk they represent. The GeoGuides have been prepared by the <u>Australian Geomechanics Society</u>, a specialist technical society within Engineers Australia, the national peak body for all engineering disciplines in Australia, whose members are professional geotechnical engineers and engineering geologists with a particular interest in ground engineering. The GeoGuides have been funded under the Australian governments' National Disaster Mitigation Program.

Australian Geomechanics Vol 42 No 1 March 2007