

Grade site to achieve proposed final grades. Cultivate sub grade to a depth of 300mm.


Stockpile soil if suitable for reuse or provide landscape soil that meets Australian Standards to replace site top soil. Install plant material as per plan. Keep planting areas moist, stake plants as required and 'water in'. Fertilise exotic plants with Osmocote 'Plus' 8-9 month slow release fertiliser and native plants with Osmocote zero Phosphorus 5-6 month slow release. Apply as per manufacturer's instructions.

Gardens are to be mulched to a 75mm depth using Native Leaf Litter Mulch or wood chip that meets Australian Standards. Keep mulch clear of all plant stems.

Level turf areas and spread lawn food as per manufacturers instructions. Lay turf, water well and roll with turf roller. Keep moist at all times.

Fill gaps and depressions with sand and allow 4 weeks before cutting.

Paving to be laid on compacted surface of 50mm sand bedding on 100mm compacted fine crushed rock. Ensure ground below is also compacted. Check paying and setout prior to laying. Retaining walls and concrete driveways / paths to engineers



TYPICAL SHRUB PLANTING DETAIL

TYPICAL PLANTING DETAIL



PROPOSED FRONT FENCE, BALCONY, DECK. **SWIMMING POOL & LANDSCAPING CLIFFORD & PENELOPE LEESON** LOT 2 DP581210 No. 52 SEAVIEW STREET BALGOWLAH 2093

LANDSCAPE PLAN

DWG NAME

DATE SCALE AT A3 JOB NUMBER DWG NUMBER FEB 2023 P6 RADD23003

200mm J 1:1