



# **JACKSONS NATURE WORKS**

34 CALOOLA CRESCENT, BEVERLY HILLS 2209

9 150 4430  
0 4 18) 414 502

## **ARBORICULTURAL IMPACT ASSESSMENT REPORT**

**At**

**54 Bardo Road, Newport**

**Prepared for**

**Built Projects**

**16<sup>th</sup> March 2021**

**Prepared by:** Ross Jackson

Graduate Certificate in Arboriculture (AQF L 8)  
Dip. Horticulture (Arboriculture – AQF L 5)  
Certificate III in Horticulture (Arboriculture)  
Certificate in Horticulture (Landscape)

Member of the Arboriculture Australia (MAA)  
Member of the Australian Institute of Horticulture  
Consulting Arborist Nos.1695

E: [jacksonsnatureworks@bigpond.com](mailto:jacksonsnatureworks@bigpond.com)

## DISCLAIMER

The Client acknowledges that this Report, and any opinions, advice or recommendations expressed or given in it, are the information supplied by the Client and on the data inspections, measurements and analysis carried out or obtained by Jacksons Nature Works (JNW) and referred to in the Report. The Client should rely on The Report, and on its contents, only to that extent.

Care has been taken to obtain all information from reliable sources. All data has been verified as far as possible. However, Ross Jackson – Consulting Arborist can neither guarantee nor be responsible for the accuracy of information provided by others.

Unless stated otherwise:

- Information contained in this report covers only the trees examined and reflects the health and structure of the trees at the time of inspection. The documented, observations, results, recommendations and conclusions given may vary after the site visit due to environmental conditions.
- The inspection was limited to visual examination from the base of the subject tree without dissection, probing or coring.
- There is no warranty or guarantee, expressed or implied, that problems or deficiencies of the subject trees may not arise in the future.
- Unauthorised use of this report in any form is prohibited and remains the intellectual property of Jacksons Nature Works until all costs are settled; &
- Unauthorised use of this report in any form is prohibited and remains the intellectual property of Jacksons Nature Works until all costs are settled.

Ross Jackson.

Consulting Arborist

## **Table of Contents**

<b>1. Background and Methodology.....</b>	<b>4</b>
<b>2. Observations.....</b>	<b>5</b>
<b>3. Discussions.....</b>	<b>5</b>
<b>4. Recommendations.....</b>	<b>19</b>
<b>Annexure A: Observations.....</b>	<b>21</b>
<b>Annexure B: Tree location plan.....</b>	<b>24</b>
<b>Annexure C: Tree impact plan.....</b>	<b>25</b>
<b>Annexure D: Typical trunk protection.....</b>	<b>28</b>

## 1. BACKGROUND and METHODOLOGY

- 1.1 The purpose of this Tree Report is to inform and accompany a reply to Council as part of DA 2020/1172 at 54 Bardo Road, Newport – The Site.
- 1.2 The report was commissioned by Built Projects to respond to Council's requirements to consider the development impacts on trees located on and around the Site.
- 1.3 This report outlines the health and condition of the subject trees, the remaining life expectancy of the trees, identifies any visible defects or other problems, describes which trees require pruning, removal, retention or represent a potential hazard and comments on the impact on these trees in relation to the works proposed. The report also provides recommended tree protection measures (Tree Management Plan) to ensure the long-term preservation of the trees to be retained where appropriate.
- 1.4 The Site is a residential site with gardens at Newport.
- 1.5 The trees were identified by ground level Visual Tree Assessment (VTA) <sup>1</sup> only in the data collection, taken on 11.3.2021 (review of details by Tree Survey). No aerial (climbing) was undertaken.
- 1.6 All site photographs were taken by the author at the site. All photographs were taken using a digital camera (Canon 7D) with no image enhancement either within the camera or on computer.
- 1.7 The subject trees were located on plans supplied. The trees have been plotted and can be found on Annexure B – Tree Location Plan.
- 1.8 The trees were identified and their genus species and common name used. The trees were identified by the use of data collected and compared to G Burnie, S Forrester et al (1997) **Botanica** Random House, Milsons Point, NSW, Australia.
- 1.9 DBH. The Trunk Diameter at Breast Height (1.4 metres above ground level) in centimetres was measured over bark using a metal tape which automatically converts to diameter and assumes a circular trunk cross section.
- 1.10 DRB. The trunk Diameter above Root Buttress in centimetres was measured over bark using a metal tape which automatically converts to diameter and assumes a circular trunk cross section.
- 1.11 Height. Estimated overall height in metres.
- 1.12 Spread. Measured with a metal tape measure and shown in metres.
- 1.13 Useful Life Expectancy (ULE)<sup>2</sup>.

---

<sup>1</sup> Mattheck, Dr. Clause & Breloer, Helge (1994) – Sixth Edition (2001) **The Body Language of Trees – A Handbook for Failure Analysis** The Stationery Office, London, England

<sup>2</sup> Barrell, Jeremy (1996, 2001) **Pre-development Tree Assessment** Proceedings of the International Conference on Trees and Building Sites (Chicago) International Society of Arboriculture, Illinois, USA

A systematic pre-development tree assessment procedure developed by Jeremy Barrell, Hampshire, England. It gives a length of time that the Arborist feels a particular tree can be retained with an acceptable level of risk based on the information available at the time of the inspection. SULE ratings are Long (retainable for 40 years or more with an acceptable level of risk), Medium, (retainable for 16 – 39 years), Short (retainable for 5 – 15 years) and Removal (tree requiring immediate removal due to imminent hazard or absolute unsuitability).

1.14 The Tree Protection Zone (TPZ) and Structural Root Zone (SRZ) have been calculated in terms of AS 4970 – 2009 Protection of trees on development site Section 3.

1.15 To prepare this report we have reviewed the following documents:

- Detail survey by C & A Surveyors NSW P/L dated 6.8.2020.
- Arboricultural Impact Assessment & Tree Protection Plan by Tree Survey dated 3.9.2020 (TS – 2020).
- Architectural plans by Giles Tribe dated 16.3.2021.
- Northern Beaches Council, B4.22 Preservation of Trees or Bushland Vegetation (TPO); &
- Australian Standard AS 4970 – 2009 Protection of trees on development sites.

## **2. OBSERVATIONS as seen on the days of inspection (11.3.2021)**

2.1 The tree observations can be found on Annexure A.

## **3. DISCUSSIONS**

3.1 We have been commissioned by Built Projects to examine the health and condition of the trees on and around this development site.

It is proposed to demolish the existing and the construction of a senior's residential development on Site (development works in DA 2020/1172).

3.2 We have examined the trees on site and can suggest the following considerations for the development works:

1. Tree *Fraxinus griffithii* is a mature tree with fair condition with sparse canopy density – refer plate 1.

The development has a major encroachment within this trees TPZ – exceeding 26%.

This tree is assessed to be of low retention value and can be easily replaced in the landscape works.

Due to the low retention value, sparse canopy density and the major level of impact, removal of this tree is recommended. Note for removal in the Tree Management Plan (TMP).



Plate 1: Tree 1

2. Tree 2 *Syncarpia glomulifera* is a street tree in Council's nature strip in front of the site – it has typical upper canopy pruning for the overhead power lines – refer plate 2.

The changes to the development works include:

- a. Light weight front fence on isolated posts.
- b. Entrance, letter box and walkway to units all an elevated structure.
- c. N.B: refer Annexure C.

These design considerations are tree sensitive and will ensure the long-term retention of this street tree. Tree protection to be installed during development works.

Note for retention and protection in the TMP.

3. Tree 3 *Eucalyptus crebra* is a street tree in Council's nature strip in front of the site – it has typical upper canopy pruning for the overhead power lines – refer plate 2.

The development works have less than 10% encroachment within this tree's TPZ, thus ensuring retention. Tree protection to be installed during development works.

Note for retention and protection in the TMP.



Plate 2: tree 2 & 3

4. Tree 4 *Eucalyptus punctata* shows good condition with minor deadwood scattered around the canopy – refer plate 3. This tree has a high retention value.

In consultation with Giles Tribe Architects the following changes to the design have been incorporated:

- a. Light weight front fence on isolated posts.
- b. Entrance, letter box and walkway to units all an elevated structure.
- c. Deletion of the impervious pathway to G01.
- d. POS to G01 on a suspended slab with an air gap.
- e. Basement adjusted away from TPZ.
- f. Refer Annexure C.

In view of these design changes the long-term retention of this tree will be achieved and is supported. Tree protection to be installed during development works.

Note for retention and protection in the TMP.



Plate 3: tree 4

5. Tree 5 *Syncarpia glomulifera* shows good vitality with previous lower branch pruning – refer Plate 4.

The location of the basement driveway has been located on the eastern side of the site to avoid impacting Trees 2, 3, 4 & 8 – refer Annexure C.

Consequently, this tree will need to be removed to excavate and construct the double width driveway / waiting bay to the basement – refer Annexure C.



It is acknowledged this tree is of high retention value and forms part of the streetscape. However, rather than merely cutting this tree down, a replacement tree of the same species can be replanted on site to ensure benefit of trees in this locality.

Note this tree for removal with replacement planting on site.



Plate 4: tree 5

6. Tree 6 *Acer palmatum* is showing suppression by Trees 8 & 9.

This deciduous tree is assessed to be of low retention value (exotic and deciduous) with a small form. It is within the proposed development works – refer Annexure C.

Removal is supported to allow the development to proceed. Note for removal in the TMP.

7. Tree 7 *Syncarpia glomulifera* shows good vitality with previous lower branch pruning – refer Plate 5.

It is acknowledged there is an existing concrete driveway beside this tree. It is proposed to install the basement driveway and standing bay within this tree's TPZ – refer Annexure C.

To reduce the potential impacts on this tree, the proposed driveway will incorporate the removal of the existing concrete driveway with rubber tract excavators (i.e. spreading the load), then providing an aggregated layer of 100mm (no fines), a 200Um Fordicon layer (prevent leeching of lime into the root plate) and a new concrete driveway – refer Annexure C, Driveway Detail.



It will be essential to install trunk protection around this tree before Site Establishment – refer Annexure D.

The above design considerations will ensure the longevity of this high retention tree. Note for retention and protection in the TMP.



Plate 5: tree 7 – note existing concrete driveway on site.

8. Tree 8 *Syncarpia glomulifera* shows good vitality with an elevated canopy form. This tree has a high retention value.

In consultation with Giles Tribe Architects the following changes to the design have been incorporated:

- a. Light weight front fence on isolated posts.
- b. Entrance, letter box and walkway to units all an elevated structure.
- c. Deletion of the impervious pathway to G01.
- d. POS to G01 on a suspended slab with an air gap.
- e. Basement adjusted away from TPZ.
- f. Refer Annexure C.
- g. N.B. No canopy pruning is required to undertake the development works.

To understand what root material is located between this tree and the basement a root mapping investigation has been undertaken. The findings of the root mapping can be found in Section 3.3.

The conclusion of the root mapping has determined the retention of this tree.

Note this tree for retention and protection in the TMP.

9. Tree 9 *Eucalyptus botryoides* shows fair to average condition with less than normal canopy density and suppressed development – refer plate 6. Medium retention value.

It is acknowledged this tree is an indigenous tree to this locality.

This tree is within the proposed development – refer Annexure C. In view of its fair - average condition and poor form, removal is supported.

It must be acknowledged the proposed design has been modified to ensure the retention of Trees 2, 3, 4, 7 & 8 in the front setback of this site, thus maintain the streetscape and a cluster of trees at the front of the site.

Note for removal in the TMP.



Plate 6: tree 9

10. Tree 10 *Banksia serrata* is a semi-mature specimen with a small canopy.

This tree is assessed to be of low retention value and is located in the proposed walkway to G04 – refer Annexure C.

In view of this trees small form and low retention value and being within the walkway, removal is supported.

There is ample space on site to replant replacement trees to compensate for the removal of this tree.

Note for removal in the TMP.

11. Trees 11, 13, 14 & 15 *Syncarpia glomulifera* and tree 12 *Eucalyptus botryoides* are a clump of trees behind the existing building.

Tree 11, 14 & 15 have suppressed form as a consequence of suppression by the dominant trees: 13 & 12 – refer plate 7.

To understand what root material is located between this tree and the basement a root mapping investigation has been undertaken. The findings of the root mapping can be found in Section 3.3.

In consultation with Giles Tribe Architects the following changes to the design have been incorporated:

- a. Basement adjusted away from the TPZ of these trees.
- b. Walkway to units all an elevated structure.
- c. Unit G04 incorporates a suspended slab over the TPZ of Tree 12 & 13 to ensure air and moisture exchange with the root system.
- d. No canopy pruning is required to undertake the development works.
- e. It is proposed to remove Tree 11, 14 & 15 to provide greater deep soil area for the roots of Trees 12 & 13 i.e. reduced competition for soil moisture and nutrients.
- f. The longevity of Trees 12 & 13 will be enhanced by the reduced competition with the removal of Trees 11, 14 & 15, including greater access to sunlight for their natural process of photosynthesis and nutrient uptake.
- g. An irrigation system can be added in the landscape works to augment the supply of water.

By incorporating the above design and management practices, the long-term retention of Trees 12 & 13 will be achieved, well beyond the early years of the post development works.

It has been our experience that the future residents will be pro-active in the care of the trees in and around their property.

Also, it is proposed to replant replacement trees in the landscape plans to compensate for the removal of Trees 11, 14 & 15 i.e. Turpentine.

Removal of Trees 11, 14 & 15 is supported. Retention of Trees 12 & 13 is justified.

Note Trees 11, 14 & 15 for removal and Trees 12 & 13 for retention in the TMP.





Plate 7: Tree 15, 14, 13, 12 & 11.

12. Trees 16 *Eucalyptus botryoides* & tree 17 *Eucalyptus crebra* are located in the adjoining property to the north of the Site.

The development works have less than 10% encroachment within these trees TPZ – refer Annexure C, thus ensuring retention.

Note for retention and protection in the TMP.

### 3.3 Root mapping

This report has been prepared to provide details regarding the size and location of any root material observed in 1 trench on site adjacent to Trees 6 & 8 and trench 2 adjacent to trees 11, 12, 13 – refer to Annexure 6.

Work carried out:

- a. One trench was excavated on site between Trees 6 & 8 – refer plate 8. The trench was dug by hand on 11.3.2021.
- b. One trench was excavated on site to the east of Trees 11, 12 & 13 – refer plate 9. The trench was dug by hand on 11.3.2021.
- c. Trench 1 was dug to a depth of 500mm +/- and was 8.2m long.
- d. Trench 2 was dug to a depth of 500mm (start of trench), 600mm at 3.8m and 550mm at end of trench.



Plate 8 – trench 1.



Plate 9 – trench 2.

Root Activity:

Trench No 1 was located between Trees 6 & 8 – at a distance of 2m centre line of Tree 8.

The root material is noted below & refer plates 10, 11 & 12:

Root No.	Distance from start of trench (m)	Depth (mm)	Root Diameter (mm) or other
1	0.25	400	40 (Turpentine – T)



2	0.8 – 1.4	0 - 150	180 (Not T)
3	1.5	150	60
4	1.6	150	40
5	1.7	200	50
6	1.9	150	120
7	2.1	150	80
8	2.5	300	120
9	2.6	150	120
10	3.5	surface	50 (Not T)
11	3.6	surface	50 (Not T)
12	3.8	surface	30 (Not T)
13	4.1	300	80
14	4.6	300	30 (Not T)
15	5.0	200	25, 25
16	5.1	300	70 (Not T)
17	5.6	50	50 (Not T)
18	5.5 – 5.7	250	70
19	8.0	250	20 (Not T)



Plate 10: Roots 1 – 7.





Plate 11: Roots 8 - 15.



Plate 12: Roots 15 – 19.

Trench No 2 was located on the east side of Trees 11, 13, 14 & 15 – at a distance of 1.8m centre line of Tree 13.

The root material is noted below & refer plates 13, 14 & 15:

Root No.	Distance from start of trench (m)	Depth (mm)	Root Diameter (mm) or other
1	0.1 – 0.3	150	30
2	0.35	300	70
3	0.5 – 0.6	100	45
4	0.6	400	40
5	1.0	400	25

6	1.1	100	25
7	1.1 – 1.3	150	25
8	1.5	surface	110
9	2.2	100	25, 25
10	2.4	150	50
11	2.5	150, 300	60, 20
12	2.6	400	40
13	2.65	200	40
14	2.9	400	50
15	3.0	300	50
16	3.2	400	30
17	3.5	300	25
18	3.6	200	40
19	3.8	150	160
20	4.6	400	150
21	4.7 – 5.0	400 - 100	160
22	5.7 – 6.0	300	30
23	6.5	200	150
24	6.6	100	5 x 30





Plate 13: Roots 1 – 13.



Plate 14: Roots 14 – 21.



Plate 15: Roots 22 – 24.

## Discussions on Root Mapping

In terms of AS 4970 – 2009 Section 3.3 the Project Arborist needs to demonstrate how a development can be built while ensuring the viability of the retained tree. The determining factor is a calculation of a tree's, Tree Protection Zone (TPZ) and Structural Root Zone (SRZ) – where:

$$\text{TPZ} = \text{DBH} \times 12 \ \& \ \text{SRZ} = (\text{DRB} \times 50)^{0.42} \times 0.64$$

Tree 8: DBH = 60cm & DRB = 120cm.

Tree 11: DBH = 85cm & DRB = 100cm.

Tree 12: DBH = 65cm & DRB = 75cm.

Tree 13: DBH = 70cm & DRB = 90cm.

Therefore, the calculations for the subject tree:

Tree 8: TPZ = 7.2m radius & SRZ = 3.6m radius.

Tree 11: TPZ = 10.2m radius & SRZ = 3.3m radius.

Tree 12: TPZ = 7.8m radius & SRZ = 2.9m radius.

Tree 13: TPZ = 8.4m radius & SRZ = 3.2m radius.

The proposed development works are within the TPZ of Tree 8, 11, 12 & 13 – Refer Annexure C, I.E. a major encroachment.

Therefore, where a “major encroachment” is proposed, i.e. greater than 10% of the TPZ or inside the SRZ. Where this is the case the Site Arborist should demonstrate how the tree/s will remain viable.

When determining the potential impacts of encroachments into the TPZ / SRZ, the consulting arborist should consider the following with answers supplied from site inspection, root mapping and analysis of the plans provided:

a. Location of & distribution of roots:

1. Trees 8, 11, 12 & 13:

*Trench 1 found 19 roots varying from 20mm to 120 mm all within the TPZ of these trees i.e. woody & non-woody roots<sup>3</sup>. Root 2, 10, 11, 12, 14, 16, 17 & 19 do not appear to be from Tree 8. The roots are scattered along the trench.*

*Roots 1, 4 & 15 are classified as “Non-Structural Roots” (Draper & Richards 2009).*

*Trench 2 found 24 roots varying in size from 25mm to 160mm. Roots 1, 5, 6, 7, 9, 12, 13, 16, 17, 18, 22 & 24 are non-woody roots. N.B. It was difficult to determine which roots were from these trees.*

b. The potential loss of root mass resulting from the encroachment:

1. Tree 8:

*Minor roots from tree 8 will be pruned to excavate for the basement i.e at a distance of 4.2m from this tree. The roots at this distance would have tapered to less than 10mm.*

2. Tree 11 – an unacceptable extent of root pruning.

3. Tree 12 & 13- minor roots to be pruned i.e at a distance of 4.5m from this tree. The roots at this distance would have tapered to less than 10mm.

---

<sup>3</sup> Draper, D. B. & Richards, P. A. (2009). **Dictionary for Managing Trees in Urban Environments**. CSIRO Publishing, Collingwood, Victoria.

- c. Tree species & tolerance to root disturbance:  
*Trees 8, 12 & 13 (Syncarpia glomulifera) will have a good tolerance to root disturbance due to the small number of roots affected by the construction activity (basement and pier excavations).*
- d. Age, vigour & size of tree – refer Annexure A.
- e. Lean and stability of tree:  
*Tree 8, 12 & 13 are stable with no leaning.*
- f. Soil characteristics and volume, topography and drainage: *Site soil is classified as Erina<sup>4</sup>- moderately deep (<100 - 200cm). The site slopes from front to rear with good surface drainage.*
- g. The presence of existing or past structures or obstacles affecting root growth: *“The existing structures have minimally affected these trees – existing residence near Trees 11 & 12.*
- h. Design factors: *The development can be located near Tree 8, 12 & 13. However, the impacts are considered excessive on Tree 11 and removal is recommended.*

#### Root Mapping Conclusions:

The following conclusions can be advised:

1. Trees 8, 11, 12 & 13 show good condition and are stable.
2. The retention of Trees 8, 12 & 13 will be achieved with very minor root pruning due to a rapid tapering of roots at the distances the buildings are located.
3. Tree 11 is unretainable due to the extent of encroachment within its TPZ.
4. The proposed building can be located and built as shown in Annexure C.
5. The pruning of roots from Tree 8, 12 & 13 will not have a long-term impact on the tree’s stability and longevity.

#### 4. RECOMMENDATIONS

The following recommendations are advised:

- a) Retain the following trees on site: Tree 4, 7, 8, 12 & 13.
- b) Remove the following trees on site: Tree 1, 5, 6, 9, 10, 11, 14 & 15.
- c) Retain the following street trees: Tree 2 & 3.
- d) Retain the following neighbour’s trees: Tree 16 & 17.
- e) That the proposed development works be constructed as shown in Annexure C in DA 2020/1172.
- f) Tree removal work shall be carried out by an experienced tree surgeon in accordance with *Safe Work Australia Guide for Managing Risks of Tree Trimming and Removal (2016)*.
- g) Trunk protection shall consist of a padding material such as hessian or thick carpet underlay wrapped around the trunk. Timber planks (50mm x 100mm or similar) shall be placed over the padding and around the trunk of the tree at 150mm centres. The planks shall be secured with 8-gauge wire or hoop steel at 300mm spacing. Trunk protection shall extend a minimum height of 2 metres – refer Annexure D on Trees 2, 4, 7, 8, 12 & 13.
- h) Install the following Tree Protection Measures around the retained trees: Tree 2, 3, 4, 7, 8, 12 & 13, protection measures shall be a temporary fence of chain

---

<sup>4</sup> Chapman. G. A. & Murphy. C. L. (1989). **Soil Landscapes of the Sydney 1:100,000 Sheet**. Soil Conservation Service of NSW. Sydney.



wire panels 1.8 metres in height (or equivalent), supported by steel stakes or concrete blocks as required and fastened together and supported to prevent sideways movement. A sign is to be erected on the tree protection fences of the trees to be retained that the trees are covered by Council's tree preservation orders and that "No Access" is permitted into the tree protection zone – refer Annexure D.

- i) That a Tree Management Plan be prepared as part of the Construction Certificate by a consulting arborist who holds the Diploma in Horticulture (Arboriculture), Level 5 or above under the Australian Qualification Framework.
- j) An AQF Level 5 Project Arborist shall be engaged to supervise the building works and certify compliance with all Tree Protection Measures.
- k) The tree location plans can be found on Annexure B; &
- l) The tree impact plans can be found on Annexure C.



Ross Jackson M.A.A. & M.A.I.H.  
Consulting Arborist 1695  
Graduate Certificate in Arboriculture AQF Level 8  
Diploma Horticulture (Arboriculture) – AQF Level 5  
Certificate III in Horticulture  
Certificate in Horticulture (Landscape – Honours)



## Annexure A: Observations as seen on the day of inspection of trees.

Tree No	Botanical Name	Age Class	Height (m)	Spread (m)	D.B.H. (cm)	D.R.B. (cm)	TPZ (radius m)	SRZ (radius m)	Condition comments as seen on site	ULE
1	<i>Fraxinus griffithii</i>	M	4	4	15	25	1.8	1.8	F vitality. Low retention.	3a
2	<i>Syncarpia glomulifera</i>	M	12	6	45	55	5.4	2.6	G vitality. OHPL pruning. Medium retention. ST.	2
3	<i>Eucalyptus crebra</i>	M	14	8	40	50	4.8	2.5	G vitality. Slight lean towards street. OHPL. Medium retention. ST.	2
4	<i>Eucalyptus punctata</i>	M	14	12	65	75	7.8	2.9	G vitality. High retention.	2
5	<i>Syncarpia glomulifera</i>	M	14	12	45, 75	100	10.5	3.3	G vitality	2
6	<i>Acer palmatum</i>	M	5	7	45	55	5.4	2.6	G vitality	3
7	<i>Syncarpia glomulifera</i>	M	16	16	40, 60	90	8.7	3.2	G vitality	2
8	<i>Syncarpia glomulifera</i>	M	16	14	40, 45, 60	120	7.2	3.6	G vitality	2
9	<i>Eucalyptus botryoides</i>	M	16	16	65	90	7.8	3.2	F - A vitality. Suppressed form. Thinning foliage density.	3b
10	<i>Banksia serrata</i>	SM	4	5	20	30	2.4	2.0	F vitality	5a
11	<i>Syncarpia glomulifera</i>	M	16	16	85	100	10.2	3.3	G vitality	2
12	<i>Eucalyptus botryoides</i>	M	16	10	65	75	7.8	2.9	G vitality	2
13	<i>Syncarpia glomulifera</i>	M	16	10	70	90	8.4	3.2	G vitality	2
14	<i>Syncarpia glomulifera</i>	M	10	7	35	45	4.2	2.4	F vitality	2
15	<i>Syncarpia glomulifera</i>	M	10	7	25	35	3.0	2.1	F vitality	3
16	<i>Eucalyptus botryoides</i>	M	18	12	50	60	6.0	2.7	G vitality	2
17	<i>Eucalyptus crebra</i>	M	18	16	80	90	9.6	3.2	G vitality	2

### Terms used in Tree Survey & Report:

#### Age Class

**(Y)** – **Young** refers to a well-established but juvenile tree. Less than 1/3 life expectancy

**(SM)** – **Semi-mature** refers to a tree at growth stages between immaturity and full size. A tree has reached First Adult Form i.e. displays adult characteristics. 1/3 to 2/3 life expectancy

**(M)**- **Mature** refers to a full size tree with some capacity for future growth. Older than 2/3 life expectancy

**(OM)** – **Over-mature** refers to a tree approaching decline or already declining. Older than 2/3 life expectancy and showing signs of irreversible decline.

**Health** refers to a tree's vigour, growth rate, disease and/or insects.

**Vitality** summarises observations about the health and structure of the tree on a scale of: **(G) Good, (F) Fair, (P) Poor, (P) Poor & (D) Dead.**

**Good:** Tree is generally healthy and free from obvious signs of structural weaknesses or significant effects of pests and diseases or infection;

**Fair:** Tree is generally vigorous although has some indication of being adversely affected by the early effects of disease or infection or environmental or mechanical damage. Appropriate tree maintenance can usually improve overall health and halt decline;

**Poor:** Tree in decline and is not likely to improve with reasonable maintenance practices or has a structural fault such as bark inclusion;

**Dead:** Tree no longer capable of sustained growth.

**Deadwood (DW)** – deadwood found in canopy as a percentage.

**Over Head Power Lines (OHPL)** – upper canopy pruned to accommodate power lines at a given height.

**Height** expressed in metres refers to estimated overall height of tree.

**Next Door tree (ND)** – tree located in the neighbour's property.

**Street Tree (ST)** – tree located in Councils footpath reserve.

**Spread** expressed in metres refers to estimated spread of crown at the drip line.

**(DBH) Diameter at Breast Height** expressed in millimetres refers to the trunk diameter at 1.4 metres above ground level. Where there are multiple trunks the combined diameter has been calculated in terms of Appendix A – AS 4970 – 2009, shown in brackets.

**(DRB) Diameter above Root Buttress** expressed in millimetres refers to the trunk diameter above root buttress.

**(TPZ) Tree Protection Zone & Structural Root Zone (SRZ)** as defined by AS 4970 – 2009 Section 3

**(ULE)** The various ULE categories indicate the useful life anticipated for an individual tree or trees assessed as a group. Factors such as the location, age, condition and vitality of the tree are significant to the determination of this rating. Other influences such as the tree's effect on better specimens and the economics of managing the tree successfully in its location are also relevant to ULE (Barrell 1993, 1995, 2001).

**ULE RATING (UPDATED 1/4/01) BARRELL**


<p><b>1.Long ULE:</b> Trees that appear to be retainable at the time of assessment for more than 40 years with an acceptable level of risk.</p>	<p><b>2.Medium ULE:</b> Trees that appear to be retainable at the time of assessment for more than 15-40 years with an acceptable level of risk.</p>	<p><b>3.Short ULE:</b> Trees that appear to be retainable at the time of assessment for more than 5-15 years with an acceptable level of risk.</p>	<p><b>4.Remove:</b> Trees that should be removed within the next 5 years.</p>	<p><b>5.Small, young or regularly pruned:</b> Trees that can be reliably moved or replaced.</p>
<p>(A) Structurally sound trees located in positions that can accommodate future growth</p>	<p>(A) Trees that may only live between 15 and 40 more years.</p>	<p>(A) Trees that may only live between 5 and 15 more years.</p>	<p>(A) Dead, dying, suppressed or declining trees because of disease or inhospitable conditions.</p>	<p>(A) Small trees less than 5 Metres in height.</p>
<p>(B) Trees that could be made suitable for retention in the long term by remedial tree care.</p>	<p>(B) Trees that could live for more than 40 years but may be removed for safety or nuisance reasons.</p>	<p>(B) Trees that could live for more than 15 years but may be removed for safety or nuisance reasons.</p>	<p>(B) Dangerous trees because of instability or recent loss of adjacent trees.</p>	<p>(B) Young trees less than 15 years old but over 5 metres in height.</p>
<p>(C) Trees of special significance for historical, commemorative or rarity reasons that would warrant extraordinary efforts to secure their long term retention.</p>	<p>(C) Trees that could live for more than 40 years but may be removed to prevent interference with more suitable individuals or to provide space for new planting.</p>	<p>(C) Trees that could live for more than 15 years but may be removed to prevent interference with more suitable individuals or to provide space for new planting.</p>	<p>(C) Dangerous trees because of structural defects including cavities, decay, included bark, wounds or poor form.</p>	<p>(C) Formal hedges and trees intended for regular pruning to artificially control growth.</p>
	<p>(D) Trees that could be made suitable for retention in the medium term by remedial tree care.</p>	<p>(D) Trees that require substantial remedial tree care and are only suitable for retention in the short term.</p>	<p>(D) Damaged trees that are clearly not safe to retain.</p>	
			<p>(E) Trees that could live for more than 5 years but may be removed to prevent interference with more suitable individuals or to provide space for new planting.</p>	
			<p>(F) Trees that are damaging or may cause damage to existing structures within 5 years.</p>	
			<p>(G) Trees that will become dangerous after removal of other trees for the reasons given in (A) to (F).</p>	
			<p>(H) Trees in categories (A) to (G) that have a high wildlife habitat value and, with appropriate treatment, could be retained subject to regular review.</p>	

# Annexure B: Tree location plan

A1



- LEGEND:**
- ALD AUSTRALIAN HEIGHT DATUM
  - AWM AWNING
  - BM BENCH MARK
  - CS CONC
  - D/M/S DIA/ETW/HEIGHT/SPREAD
  - EC EDGE OF CONCRETE
  - EG EAVE & GUTTER
  - EN EXISTING
  - GN GARAGE
  - HTD HYDRANT
  - LI LAMP HOLE
  - NS NATURAL SURFACE
  - PP POWER POLE
  - PL POND LEVEL
  - RS RUSTIC
  - S STEPS
  - SL SURFACE LEVEL
  - SV STOP VALVE
  - TE TELEPHONE
  - TOW TOP OF WALL
  - WC WATER CROSSING
  - WM WATER METER
  - W/O TOP OF WINDOW



LOT 1  
DP 331984

LOT 4  
SECTION 2  
DP 4689

LOT 6  
SECTION 2  
DP 4689

LOT 14  
SECTION 2  
DP 4689

LOT 11  
SECTION 2  
DP 4689

LOT 13  
SECTION 2  
DP 4689

BARDO ROAD

**NOTES:**

A) SERVICES SHOWN HAVE BEEN IDENTIFIED FROM VISUAL EVIDENCE APPEARING TO BE CORRECT. THE RELEVANT SERVICE AUTHORITY SHOULD BE CONTACTED TO CONFIRM THE LOCATION AND DEPTH OF ANY SERVICES PRIOR TO CONSTRUCTION OR EXCAVATION.

B) SURVEY POINTS AND SPREADS OF INTEREST ARE IDENTIFIED TO THE BEST OF OUR ABILITY AND SHOULD BE USED AS A GUIDE ONLY.

C) DIMENSIONS OF LEVELS: SEAM 2455, RL 7288 (AHD), CLASS LC.

D) THESE NOTES FORM PART OF THIS PLAN AND CANNOT BE REMOVED.

E) DISTANCES SHOWN ARE IN METRES, UNLESS OTHERWISE SPECIFIED.

F) NO CONSULTANT PROFESSIONAL OPINIONS HAVE BEEN INVESTIGATED.

**C & A SURVEYORS NSW PL**  
 Pty 9830 9299 Fax 9839 1199  
 Suite 3, Level 4, 480 CHURCH STREET,  
 NORTH PARARAMATTA NSW 2151  
 info@casurveyors.com.au  
 www.casurveyors.com.au


**DETAIL & IDENTIFICATION SURVEY OF  
 LOT 42 SECTION 2 IN DP 4689, LOCATED AT  
 No. 54, BARDO ROAD, NEWPORT.**

**INSTRUCTING PARTY: CHEYNE JAMES**

Revision No	Description	Date
01	DRAWN FOR ISSUE	24/04/2020
02	DRAWN FOR ISSUE	24/04/2020
03	ADD INFO	4/5/2020
04	ADD INFO	16/07/2020

<b>DATUM:</b>	AHD	<b>SURVEYED BY:</b>	HH
<b>SURVEY DATE:</b>	21/04/2020	<b>DRAWN BY:</b>	HA
<b>DATE DRAWN:</b>	24/04/2020	<b>SCALE:</b>	1:150@A1
<b>REFERENCE:</b>	13949-20 DET/D	<b>SHEET:</b>	1 OF 1

# Annexure C: Tree impact plan and root mapping locations



A1

- LEGEND:**
- AHD AUSTRALIAN HEIGHT DATUM
  - BM BENCH MARK
  - CONC CONCRETE
  - DIAM/DIAMETER
  - D/DIAMETER/HEIGHT/SPREAD
  - D DOOR
  - EG EAVE & GUTTER
  - FL FLOOR LEVEL
  - FLM FLOOR LINE
  - HND HANDRAIL
  - LD LAMP
  - LI LIGHTING
  - LS LANTERN
  - LS NATURAL SURFACE
  - LS POWER POLE
  - PL PLASTER
  - PL POOL LEVEL
  - PL STEPS
  - SL SURFACE LEVEL
  - SV STOP VALE
  - TEL TELEPHONE
  - TOW TOP OF WALL
  - WC WATER CROSSING
  - WC WATER METER
  - W/M WATER METER
  - W/M TOP OF WINDOW

**C & A SURVEYORS NSW P/L**  
 Ph: 9630 8289 Fax: 9633 1189  
 Suite 3, Level 4, 460 CHURCH STREET,  
 NORTH PARAMATTA NSW 2151  
 www.casurveyors.com.au

**DETAIL & IDENTIFICATION SURVEY OF**  
**LOT 42 SECTION 2 IN DP 4689, LOCATED AT**  
**No. 54, BARDO ROAD, NEWPORT.**

**INSTRUCTING PARTY: CHEVNE JAMIES**

Revision No.	Description	Date
01	DRAWN FROM ISSUE	23/04/2020
02	DRAWN FROM ISSUE	24/04/2020
03	ADD DATE	24/04/2020
04	ADD DATE	24/04/2020

**DATUM:**

Survey Date	Drawn By
21/04/2020	HA
24/04/2020	HA


**DATE DRAWN:** 24/04/2020 **SCALE:** 1:150@A1

**REFERENCE:** 19849-20 DET/D SHEET: 1 OF 1

**NOTES:**

1. ALL DIMENSIONS SHOWN HAVE BEEN OBTAINED FROM VISUAL SURVEY AND ARE APPROXIMATE AT THE TIME OF SURVEY. SERVICES MAY BE DEEPER THAN SHOWN WHICH ARE NOT SHOWN. THE RELEVANT SERVICES AUTHORITY SHOULD BE CONTACTED TO OBTAIN THE EXACT DIMENSIONS OF ANY SERVICES. DIMENSIONS SHOULD BE OBTAINED FROM THE AUTHORITY.
2. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
3. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
4. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
5. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
6. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
7. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
8. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
9. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
10. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
11. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
12. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
13. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
14. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
15. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
16. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
17. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
18. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
19. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.
20. DIMENSIONS SHOWN ARE OF AUSTRALIAN HEIGHT DATUM ONLY.





SRZ - STRUCTURAL ROOT ZONE  
 TZ - TREE PRESERVATION ZONE  
 TREES FOR REMOVAL  
 TREES 2, 3, 4, 7, 8, 12, 13 TO BE  
 RETAINED. REFER TO ARBORIST'S  
 REPORT.

NO.	DESCRIPTION	STATUS
1	EXISTING SITE	RETAINED
2	EXISTING TREE	RETAINED
3	EXISTING TREE	RETAINED
4	EXISTING TREE	RETAINED
7	EXISTING TREE	RETAINED
8	EXISTING TREE	RETAINED
12	EXISTING TREE	RETAINED
13	EXISTING TREE	RETAINED
14	EXISTING TREE	RETAINED
15	EXISTING TREE	RETAINED
16	EXISTING TREE	RETAINED
17	EXISTING TREE	RETAINED
18	EXISTING TREE	RETAINED
19	EXISTING TREE	RETAINED
20	EXISTING TREE	RETAINED
21	EXISTING TREE	RETAINED
22	EXISTING TREE	RETAINED
23	EXISTING TREE	RETAINED
24	EXISTING TREE	RETAINED
25	EXISTING TREE	RETAINED
26	EXISTING TREE	RETAINED
27	EXISTING TREE	RETAINED
28	EXISTING TREE	RETAINED
29	EXISTING TREE	RETAINED
30	EXISTING TREE	RETAINED
31	EXISTING TREE	RETAINED
32	EXISTING TREE	RETAINED
33	EXISTING TREE	RETAINED
34	EXISTING TREE	RETAINED
35	EXISTING TREE	RETAINED
36	EXISTING TREE	RETAINED
37	EXISTING TREE	RETAINED
38	EXISTING TREE	RETAINED
39	EXISTING TREE	RETAINED
40	EXISTING TREE	RETAINED
41	EXISTING TREE	RETAINED
42	EXISTING TREE	RETAINED
43	EXISTING TREE	RETAINED
44	EXISTING TREE	RETAINED
45	EXISTING TREE	RETAINED
46	EXISTING TREE	RETAINED
47	EXISTING TREE	RETAINED
48	EXISTING TREE	RETAINED
49	EXISTING TREE	RETAINED
50	EXISTING TREE	RETAINED
51	EXISTING TREE	RETAINED
52	EXISTING TREE	RETAINED
53	EXISTING TREE	RETAINED
54	EXISTING TREE	RETAINED
55	EXISTING TREE	RETAINED
56	EXISTING TREE	RETAINED
57	EXISTING TREE	RETAINED
58	EXISTING TREE	RETAINED
59	EXISTING TREE	RETAINED
60	EXISTING TREE	RETAINED
61	EXISTING TREE	RETAINED
62	EXISTING TREE	RETAINED
63	EXISTING TREE	RETAINED
64	EXISTING TREE	RETAINED
65	EXISTING TREE	RETAINED
66	EXISTING TREE	RETAINED
67	EXISTING TREE	RETAINED
68	EXISTING TREE	RETAINED
69	EXISTING TREE	RETAINED
70	EXISTING TREE	RETAINED
71	EXISTING TREE	RETAINED
72	EXISTING TREE	RETAINED
73	EXISTING TREE	RETAINED
74	EXISTING TREE	RETAINED
75	EXISTING TREE	RETAINED
76	EXISTING TREE	RETAINED
77	EXISTING TREE	RETAINED
78	EXISTING TREE	RETAINED
79	EXISTING TREE	RETAINED
80	EXISTING TREE	RETAINED
81	EXISTING TREE	RETAINED
82	EXISTING TREE	RETAINED
83	EXISTING TREE	RETAINED
84	EXISTING TREE	RETAINED
85	EXISTING TREE	RETAINED
86	EXISTING TREE	RETAINED
87	EXISTING TREE	RETAINED
88	EXISTING TREE	RETAINED
89	EXISTING TREE	RETAINED
90	EXISTING TREE	RETAINED
91	EXISTING TREE	RETAINED
92	EXISTING TREE	RETAINED
93	EXISTING TREE	RETAINED
94	EXISTING TREE	RETAINED
95	EXISTING TREE	RETAINED
96	EXISTING TREE	RETAINED
97	EXISTING TREE	RETAINED
98	EXISTING TREE	RETAINED
99	EXISTING TREE	RETAINED
100	EXISTING TREE	RETAINED



**GILES TRIBE**  
 34/35 Lisarong Street  
 Parramatta NSW 2150  
 Phone: (02) 9647 8888  
 Email: info@gilestribe.com.au

**Built Property**  
 64 BARDOL ROAD  
 BARDOL NSW  
 PROJECT 2106

**BASEMENT PLAN**

**FOR APPROVAL**  
 DATE: 20055 DA006 O





LANDSCAPING AREA (PRIVATE)  
 LANDSCAPING COMMON

602 - 50% CT 19A, 80% ZONE  
 192 - TREE MFD SECTION 2018  
 TREES SHOWN REMOVAL

PRESS 3, 4, 7, 8, 10, 11 TO BE REMOVED. REFER TO ARBORISTS REPORT.

REMOVAL OF TREES TO BE DETERMINED BY ARBORISTS REPORT. REFER TO ARBORISTS REPORT.

REMOVAL OF TREES TO BE DETERMINED BY ARBORISTS REPORT. REFER TO ARBORISTS REPORT.

NO.	DATE	DESCRIPTION	BY	CHECKED BY
1	15/06/2021	ISSUED FOR PERMIT	...	...
2	15/06/2021	REVISIONS TO PERMIT	...	...
3	15/06/2021	REVISIONS TO PERMIT	...	...
4	15/06/2021	REVISIONS TO PERMIT	...	...
5	15/06/2021	REVISIONS TO PERMIT	...	...
6	15/06/2021	REVISIONS TO PERMIT	...	...
7	15/06/2021	REVISIONS TO PERMIT	...	...
8	15/06/2021	REVISIONS TO PERMIT	...	...
9	15/06/2021	REVISIONS TO PERMIT	...	...
10	15/06/2021	REVISIONS TO PERMIT	...	...
11	15/06/2021	REVISIONS TO PERMIT	...	...
12	15/06/2021	REVISIONS TO PERMIT	...	...
13	15/06/2021	REVISIONS TO PERMIT	...	...
14	15/06/2021	REVISIONS TO PERMIT	...	...
15	15/06/2021	REVISIONS TO PERMIT	...	...
16	15/06/2021	REVISIONS TO PERMIT	...	...
17	15/06/2021	REVISIONS TO PERMIT	...	...
18	15/06/2021	REVISIONS TO PERMIT	...	...
19	15/06/2021	REVISIONS TO PERMIT	...	...
20	15/06/2021	REVISIONS TO PERMIT	...	...
21	15/06/2021	REVISIONS TO PERMIT	...	...
22	15/06/2021	REVISIONS TO PERMIT	...	...
23	15/06/2021	REVISIONS TO PERMIT	...	...
24	15/06/2021	REVISIONS TO PERMIT	...	...
25	15/06/2021	REVISIONS TO PERMIT	...	...
26	15/06/2021	REVISIONS TO PERMIT	...	...
27	15/06/2021	REVISIONS TO PERMIT	...	...
28	15/06/2021	REVISIONS TO PERMIT	...	...
29	15/06/2021	REVISIONS TO PERMIT	...	...
30	15/06/2021	REVISIONS TO PERMIT	...	...

**GILES TRIBE** ARCHITECTS  
 44 BARDO ROAD  
 SYDNEY NSW  
 20055 DA007P

**FOR APPROVAL**

Scale: 1:100


Project: 20055 DA007P

Drawn: [Name]

Checked: [Name]

Date: 15/06/2021


## Annexure D: Tree protection details



### LEGEND:

- 1 Chain wire mesh panels with shade cloth (if required) attached, held in place with concrete feet.
- 2 Alternative plywood or wooden paling fence panels. This fencing material also prevents building materials or soil entering the TPZ.
- 3 Mulch installation across surface of TPZ (at the discretion of the project arborist). No excavation, construction activity, grade changes, surface treatment or storage of materials of any kind is permitted within the TPZ.
- 4 Bracing is permissible within the TPZ. Installation of supports should avoid damaging roots.

FIGURE 3 PROTECTIVE FENCING



### NOTES:

- 1 For trunk and branch protection use boards and padding that will prevent damage to bark. Boards are to be strapped to trees, not nailed or screwed.
- 2 Rumble boards should be of a suitable thickness to prevent soil compaction and root damage.

FIGURE 4 EXAMPLES OF TRUNK, BRANCH AND GROUND PROTECTION