

SITE AREA - 923.2m²

LEGEND FOR WORKING WITHIN THE SYDNEY WATER MAIN SEWER LINE


INTERNAL SEWER LINE
RUNNING FROM THE EXISTING RESIDENCE INTO THE MAINS

SYDNEY WATER MAINS SEWER LINE
TAKEN FROM SEWER PEGOUT REPORT

ZONE OF INFLUENCE (ZOI)-
ANY WORKS WITHIN THE ZOI WILL REQUIRE ADDITIONAL PIERING OR ENCASING, AS WELL AS ADDITIONAL APPROVALS & INSPECTIONS BY A WATER SERVICES COORDINATOR

BOUNDARY LINE

FENCE LOCATION



IMPORTANT SURVEY NOTE:

PARCEL BOUNDARY DIMENSIONS, BEARINGS AND AREAS HAVE BEEN ADOPTED FROM THE SUBJECT DEPOSITED PLAN AND HAVE NOT BEEN INVESTIGATED. ANY BEARING, DISTANCE, AREA, SETBACK OR OTHER DIMENSION MAY BE SUBJECT TO CHANGE WITH FURTHER INVESTIGATION AND LODGEMENT OF A PLAN AT THE LAND TITLES OFFICE.

THEREFORE, AT TIME OF SITE PEGOUT BEFORE CONSTRUCTION WORKS COMMENCE, THERE MAY BE SOME MINOR DISCREPANCIES WITH THE SETBACKS BETWEEN BUILDINGS AS SHOWN ON THE SITE PLAN.

CONTOURS ARE INDICATIVE OF SURFACE TOPOGRAPHY ONLY. SURVEYED SPOT LEVELS ARE THE ONLY VALUES AT WHICH REDUCED LEVEL CAN BE RELIED UPON. CONTOURS ARE DISPLAYED AT 1 METRE MAJOR AND 0.25 METRE MINOR INTERVALS.

SERVICES SHOWN HAVE BEEN DERIVED FROM VISUAL EVIDENCE APPARENT AT THE TIME OF SURVEY. IT IS STRONGLY ADVISED TO VISIT 'DIAL BEFORE YOU DIG' PRIOR TO ANY EXCAVATION OR CONSTRUCTION AND VERIFY LOCATIONS WITH A SUITABLY QUALIFIED SERVICE LOCATOR PRIOR TO ANY WORKS OR CRITICAL DESIGN.

IT IS STRONGLY ADVISED TO REVIEW AN UP TO DATE TITLE SEARCH AND GIVE CAREFUL CONSIDERATION TO ALL ITEMS PRIOR TO ANY PLANNING OR CONSTRUCTION.

TREE AND ROOF PROFILE DETAILS ARE APPROXIMATE ONLY.

WHEN BUILDING ON A SITE WITH AN EXISTING INGROUND POOL, GRANNY FLAT SOLUTIONS WILL NOT BE RESPONSIBLE FOR ANY VIBRATION CAUSED TO THE POOL DURING EXCAVATION, PIERING AND CONSTRUCTION, OR TO FUTURE DAMAGE


SITE INDUCTION NOTE:

BEFORE ENTERING THE SITE, PLEASE REVIEW AND MAKE YOURSELF FAMILIAR WITH THE EMERGENCY CONTACTS, AND SITE INDUCTION INFORMATION.


IF YOU HAVE ANY TROUBLES UNDERSTANDING THE INSTRUCTIONS, PLEASE CONTACT YOUR SITE SUPERVISOR BEFORE ENTERING THE SITE.

GIBBS LANE

QUINLAN PARADE



www.dialbeforeyoudig.com.au



GENERAL NOTES				
THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF GRANNYFLAT SOLUTIONS PTY LTD				
DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS TO TAKE PRECEDENCE				
ANY DISCREPANCIES TO BE BROUGHT TO THE ATTENTION OF GRANNYFLAT SOLUTIONS, PRIOR TO WORKS COMMENCING.				
				JOB REF 193715
				SCALE A3 1:200
21/02/2020	NS	E	PRELIMINARY CONCEPT	SHEET CDC 02
DATE	DRAWN BY	REVISION	ISSUE	

CLIENT DETAILS	
32 Quinlan Parade, Manly Vale	
ANNE & GREG CHAIMANDOS	
LOT 17 - DP 7686	
SITE PLAN	


DESIGN BY

GrannyFlat solutions

20 / 7 SEFTON ROAD, THORNLEIGH NSW 2120
Ph: (02) 9481 7443

www.grannyflatsolutions.com.au

WINDOW SCHEDULE							
W#	HEIGHT	WIDTH	FRAME	GLAZING	TYPE	REVEAL	OFFSET
SK1	1,000	1,181	ALUMINIUM	CLEAR	SLIDING	138mm	0
SK2	1,000	1,181	ALUMINIUM	CLEAR	SLIDING	138mm	0
W1	1,200	2,050	ALUMINIUM	CLEAR	SLIDING	138mm	0
W2	1,029	1,210	ALUMINIUM	CLEAR	SLIDING	138mm	0
W3	600	1,810	ALUMINIUM	CLEAR	SLIDING	138mm	0
W4	600	1,810	ALUMINIUM	CLEAR	SLIDING	138mm	0
W5	2,100	1,810	ALUMINIUM	CLEAR	SLIDING DOOR	138mm	0
W6	1,200	2,050	ALUMINIUM	CLEAR	SLIDING	138mm	0
W7	600	850	ALUMINIUM	CLEAR	SLIDING	138mm	0



GROUND FLOOR

FLOOR FINISHES NOTES

PLEASE NOTE THAT THERE MAY BE A SMALL STEP WHEN THERE IS A CHANGE IN FLOOR FINISHES BETWEEN ROOMS

STUD OPENING SIZE

ADD 60mm TO HEIGHT AND 50mm TO WIDTH OF ALL WINDOWS

FLYSCREEN NOTES

ALL FLYSCREEN FOR SLIDING DOORS TO HAVE MID BARS

GLAZING NOTES

ALL GLAZING TO COMPLY WITH AS1288 & BASIX CERTIFICATE.
ALL WINDOWS WILL HAVE A FIXED PANEL ON THE RIGHT AND OPENING PANEL ON THE LEFT, WHEN VIEWED FROM THE OUTSIDE, UNLESS REQUESTED OTHERWISE. SLIDING DOORS WILL OPEN IN DIRECTION AS SHOWN ON PLAN.

EXTERNAL DOOR WARRANTY

GRANNY FLAT SOLUTIONS CANNOT PROVIDE WARRANTY ON ENTRANCE DOORS IF THE COLOUR CHOSEN HAS A LIGHT REFLECTIVE VALUE (LRV) OF 50 OR BELOW (THESE COLOURS REPRESENT THE DARKER COLOURS IN THE PAINT SPECTRUM). THE MANUFACTURERS DO NOT WARRANT DOORS PAINTED IN DARK COLOURS AS THEY ABSORB MORE HEAT THAN COLOURS GREATER THAN 50 LRV RATING, CAUSING THEM TO WARP OR BEND. FURTHERMORE, THE MANUFACTURER'S WARRANTY IS ALSO VOID IF THE EXTERNAL DOOR IS NOT COVERED BY AT LEAST 1 METER WIDE ROOF / EAVE OVERHANG / PATIO, DUE TO THE DOOR HAVING DIRECT EXPOSURE TO WEATHER ELEMENTS (WIND, RAIN, SUN ETC.) WHICH MAY CAUSE THE DOOR TO SWELL, WARP OR BEND.

BAL RATING ON PAGE 1



GENERAL NOTES

THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF GRANNYFLAT SOLUTIONS PTY LTD
DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS TO TAKE PRECEDENCE
ANY DISCREPANCIES TO BE BROUGHT TO THE ATTENTION OF GRANNYFLAT SOLUTIONS, PRIOR TO WORKS COMMENCING.

21/02/2020	NS	E	PRELIMINARY CONCEPT
DATE	DRAWN BY	REVISION	ISSUE

JOB REF	193715
SCALE A3	1:200
SHEET	CDC 03

CLIENT DETAILS

32 Quinlan Parade, Manly Vale
ANNE & GREG CHAIMANDOS

LOT 17 - DP 7686


FLOOR PLAN

DESIGN BY



20 / 7 SEFTON ROAD, THORNLEIGH NSW 2120
Ph: (02) 9481 7443

www.grannyflatsolutions.com.au



LANDSCAPING NOTE

UNLESS SPECIFIED IN YOUR CONTRACT, NO LANDSCAPING WORKS HAVE BEEN ALLOWED FOR AROUND THE BUILDING.

AT COMPLETION OF LANDSCAPE WORKS, THE SLAB HEIGHT MUST REMAIN A MIN. OF 75mm ABOVE THE FINISHED LANDSCAPED LEVEL.

GUTTERING AND VALLEY NOTE

WHEN BUILDING NEAR TREES, WE STRONGLY RECOMMEND YOU INSTALL GUTTER-GUARD OR A SIMILAR PRODUCT IN ALL GUTTERS AND VALLEYS, TO PREVENT LEAF BUILD-UP AND WATER OVERFLOW UNDER THE ROOF TILES OR SHEETING

FLOOR LEVEL NOTE

THE FLOOR LEVEL SHOWN ON THE ELEVATIONS MAY VARY SLIGHTLY ON SITE, DUE TO SITE CONDITIONS AND FINAL LEVELS AFTER EXCAVATION AND REMOVAL OF SOIL.

UNLESS SPECIFIED IN YOUR TENDER AND BUILDING CONTRACT, NO DIRT REMOVAL HAS BEEN ALLOWED FOR WHEN LEVELLING THE SITE FOR A CONCRETE SLAB. WHEN ACCESS IS TIGHT, A DECISION WOULD NEED TO BE MADE AS TO WHERE TO STOCKPILE ON SITE TO AVOID ACCESS INTERRUPTIONS OR A COST TO REMOVE THE SOIL CAN BE ARRANGED OR YOU.

FURTHERMORE, NO EXTERNAL STEPS TO PORCHES, DROP EDGE BEAMS OR RETAINING WALLS HAVE BEEN ALLOWED FOR, UNLESS SPECIFIED IN YOUR TENDER.

GENERAL NOTES

THIS DRAWING IS COPYRIGHT AND THE PROPERTY OF GRANNYFLAT SOLUTIONS PTY LTD

DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS TO TAKE PRECEDENCE

ANY DISCREPANCIES TO BE BROUGHT TO THE ATTENTION OF GRANNYFLAT SOLUTIONS, PRIOR TO WORKS COMMENCING.

4/03/2020	NS	E	PRELIMINARY CONCEPT
DATE	DRAWN BY	REVISION	ISSUE

JOB REF	193715
SCALE	A3
SHEET	CDC 04

CLIENT DETAILS

32 Quinlan Parade, Manly Vale
ANNE & GREG CHAIMANDOS

LOT 17 - DP 7686

ELEVATIONS & SECTION

DESIGN BY

GrannyFlat
solutions

20 / 7 SEFTON ROAD, THORNLEIGH NSW 2120
Ph: (02) 9481 7443

www.grannyflatsolutions.com.au