Barrenjoey Consulting Engineers pty ltd Stormwater Structural Civil abn 13124694917 acn 124694917

N Herman 60 - 62 Chisholm Rd Avalon Beach NSW 2107 <sup>C</sup>/o Andy Lehman Design 16<sup>th</sup> Nov 2022

## 60 – 62 CHISHOLM RD AVALON BEACH ALTERATIONS / ADDITIONS STORMWATER MANAGEMENT DESIGN Job No 201206

In reference to DA 2022/1399, Councils letter dated 8 November 2022 and the Stormwater Management Plan (SWMP 18 10 2022) issued by this office.

Water Management Referral -

- Runoff from the development retained at natural discharge rates with the implementation of onsite stormwater detention (as is Council policy).
- Sediment is controlled at the source with a conventional sediment trap /sump within the pit on the lower boundary collecting all development runoff.
- Stormwater quality is addressed, as per Table 4 ie temperature, salinity, chemical makeup and sediment loads, with the implementation of a *Oceanguard Pit Basket* by *Ocean Protect*. Noting there will be no variation in temperature, salinity, chemical makeup and sediment loads from this 'residential' development.

Development Engineer Referral -

- Calculations for pre and post development, details of the bypass flows and flows from the OSD as shown for all storms, as per DRAINS software analysis on SW3 of the plans issued by BCE.
- The rock gabion in the road reserve has been deleted.
- The discharge point is along the driveway to the dish drain in Chisholm Ave.

Should further information regarding this matter be required please contact our office as outlined below.

Regards BARRENJOEY CONSULTING ENGINEERS pty ltd NON' 2022 Per

Lucas Molloy (Director) BE CPEng NER

E: lucasbce@bigpond.com





# STORMWATER NOTES

- 1. All roof collection components (ie gutters / DPs etc)are to be located / sized by the Developments contracting Plumber for a 5% AEP event capacity.
- 2. Trunk lines shown on plan to be 150mm dia uPVC. 3. All pipes to be uPVC to AS 1254:2002.
- 4. All pipes to be laid at the grade required to match pit
- 5. All pipes to be installed and laid in accordance with AS
- 6. All roof guttering/ down pipes / valley gutters / box gutters etc are to be sized and installed in accordance with AS
- 7. All pits are to be proprietary uv resistant polypropylene or similar unless noted (approved by the Engineer )and are to include a min 50mm sediment trap in the base and a maximesh screen laid at 45' across the pit to protect the
- 8. All pits greater than 600mm in depth are to be proprietary precast concrete (approved by the Engineer).
- 9. All pits greater than 1000mm in depth are to have adequate access requirements in accordance with OH&S/Workcover requirements (ie; minimum dimensions 900x900mm with step irons).
- 10.All works are to be inspected and certified by the Principle Certifying Authority prioir to backfilling.
- 11.All works requiring certification by the Engineer will require a works as executed survey prepared by a registered Surveyor detailing all levels etc as on the Engineering plans.
- 12. The system is too be flushed and cleaned of all sediment and debris annually.
- 13. The system will require regular cleaning and maintenance to ensure its ability to function is maintained. 14.To ensure the system's ability to function is maintained it is to be inspected and certified as operating effectively
- by a licensed plumber every 5 years, and a engineer 15.All existing predevelopment catchment area run-off
- conditions exiting the site are to be maintained with no run-off flows being diverted from the predevelopment
- 16.Flows from upstream properties entering the site are to be monitored during construction and diverted about the OSD system / residence etc as required.

Barrenjoey Consulting Engineers pty ltd

LUCAS MOLOY MIEA CPEng NER Director

Drawing No

SW2

