









LEDGE HOUSE

No.2 WYADRA AVENUE, FRESHWATER

SITE STORMWATER MANAGEMENT

LEGEND

	RW		RAIN WATER
	SW		STORM WATER
	SS		SUBSOIL DRIANAGE
	ESW		EXISTING STORM WATER
I.O	INSPECTION OPENING		
EX.	EXISTING		
S.I.P	STORMWATER INLET PIT		
RWH	RAINWATER HEAD		
M/H	SEWER MANHOLE		
CAT.	CATCHMENT		
H/W	HEAD WALL		
HY.	DUAL FIRE HYDRANT		
RWO	RAINWATER OUTLET		
T.B.C	TO BE COORDINATED		
NB	NOMINAL BORE		
F.F.L	FINISHED FLOOR LEVEL		
L/s	LITRES PER SECOND		
G.D	GRATED DRAIN		
IV.L	INVERT LEVEL		
F.W	FLOOR WASTE		
EX.	EXISTING		
WT	WATER TANK		
DP	DOWNPIPE		
OSD	ONSITE STORMWATER DETENTION		

CONSENT AUTHORITIES

- NORTHERN BEACHES COUNCIL
- NSW WORKCOVER

CODES / INSTALLATION STANDARDS

- NCC 2019 VOL 1
- NCC 2019 VOL 3 PLUMBING CODE OF AUSTRALIA
- N.B.C D.C.P 21.

STORMWATER MANAGEMENT DESIGN PLAN

- DESIGN I.F.D - 5min EVENT.
 - 2 YR = 110mm/hr
 - 20 YR = 198mm/hr
 - 100 YR = 261mm/hr
- SEE ATTACHED DRAINS MODEL ANALYSIS OF SITE STORMWATER MANAGEMENT DESIGN.
 - DESIGN ANALYSIS INPUT DATA FILE.
 - DESIGN ANALYSIS RESULTS DATA FILE.

SPECIFICATION AND INSTALLATION NOTES:

- IT IS THE RESPONSIBILITY OF THE LICENSED PLUMBING CONTRACTOR TO ENSURE ALL WORKS ARE COMPLIANT WITH INSTALLATION CONTROL STANDARDS.
- THE DRAWINGS ARE A GUIDE ONLY FOR THE LOCATION AND LAYOUT OF SERVICES, DO NOT SCALE FROM DRAWINGS.
- VERIFY THAT ALL INVERT LEVELS, SURFACE LEVELS AND CLEARANCES ARE CORRECT AND OBTAINABLE PRIOR TO COMMENCING WORKS.
- ALL WORKS TO BE CONSTRUCTED IN ACCORDANCE WITH AS/NZS 3500, LOCAL AUTHORITY GUIDELINES AND NATIONAL CONSTRUCTION CODE 2016 AND PLUMBING CODE OF AUSTRALIA.
- ALL PLUMBING AND DRAINAGE MATERIALS SHALL BE IN ACCORDANCE WITH AS/NZS 3500, LOCAL AUTHORITY GUIDELINES AND NATIONAL CONSTRUCTION CODE 2016 AND PLUMBING CODE OF AUSTRALIA.
- WORKS SHALL BE CONSTRUCTED BY SUITABLY QUALIFIED, COMPETENT AND LICENSED TRADES PEOPLE.
- ALL TESTING AND INSPECTION REQUIREMENTS OUTLINED ON THESE DRAWINGS, CONTRACT DOCUMENTS AND REVEL ANT STANDARDS, CODES AND LEGISLATION TO BE UNDERTAKEN AND COMPLIANCE DOCUMENTED. ALL COST ASSOCIATED SHALL BE PAYABLE AS REQUIRED.
- ALL PIPEWORK SERVICE DIMENSIONS INDICATED ON DRAWINGS ARE TO BE TAKEN AS NOMINAL INTERNAL DIAMETER. FOR NOMINAL INTERNAL DIAMETER OF PIPEWORK UP TO DN50, REFER AS/NZS 3500.1 APPENDIX J.
- PROVIDE SERVICE MARKING TAPE TO CLEARLY IDENTIFY SERVICE BELOW IN ACCORDANCE WITH AS/NZS 2648.1. SERVICE MARKING TAPE TO BE PLASTIC WITH INTEGRATED WIRE TRACER LAID 350mm ABOVE BURIED SERVICE AND COVERED WITH 100mm OF SAND BACKFILL.
- COMPLETE A DIAL - BEFORE - YOU - DIG SURVEY PRIOR TO START OF WORKS.


MATERIAL SPECIFICATION


- NOTE: ALL MATERIALS ARE TO BE WATERMARK CERTIFIED.
- ALL SITE STORMWATER PIPE LINES TO BE INSTALLED IN DWV.
 - SITE SUB-SOIL LINES INSTALLED AS PER DETAIL.


PLAN SCHEDULE

- H01 - TITLE PAGE AND LEGEND
- H02 - LEVEL 1 STORM WATER MANAGEMENT PLAN
- H03 - LEVEL 2 STORM WATER MANAGEMENT PLAN
- H04 - LEVEL 3 STORM WATER MANAGEMENT PLAN
- H05 - ROOF PLAN
- H06 - DETAIL PLAN


 CONTINUES ON PLAN No.





1	DEVELOPMENT APPLICATION	23/03/22	Project: LEDGE HOUSE No.2 WYADRA AVENUE, FRESHWATER	Date: 23/03/22	Drawn By: L.OLIVE	Drawing No. 2021-X50/H01		14 Page Street Moruya N.S.W. 2537 Ph: (02) 4474 2401 Email: info@jclmoruya.com	North Point.
			Drawing Title: TITLEPAGE AND LEGEND	Scale: N/A A2	Design By: J.OLIVE				
Issue:	Description:	Date:		Plan No. 1	Checked By:	Issued For: DEVELOPMENT APPLICATION	1		



TOTAL POST DEVELOPMENT SITE
STORM RUNOFF
- 2YR = 14L/s
- 20YR = 25L/s
- 100YR = 33L/s
TOTAL PRE-DEVELOPED SITE
STORM RUNOFF
- 2YR = 13L/s
- 20YR = 25L/s
- 100YR = 37L/s
NOTE: SEE ATTACHED DRAINS MODEL INPUT
DATA AND RESULTS DATA FILE.







1	DEVELOPMENT APPLICATION	23/03/22
Issue:	Description:	Date:

Project: LEDGE HOUSE No.2 WYADRA AVENUE, FRESHWATER
Drawing Title: ROOF PLAN


Date: 23/03/22
Scale: 1:100
Plan No. 5





Drawn By: L.OLIVE
Design By: J.OLIVE
Checked By:

Drawing No. 2021-X50/H05
Issued For: DEVELOPMENT APPLICATION



14 Page Street Moruya N.S.W. 2537 Ph: (02) 4474 2401 Email: info@jclmoruya.com





JCL No 2 Wyadra Avenue, Freshwater DRAINS analysis result data file.

Note that this DRAINS analysis has been prepared to support the Stormwater Management design principle adopted in the preparation of system designs detailed on JCL plan set X50-H01 to H01 to H06.

Analysis modelling of pre-developed site and post-developed site adopts site ground description as detailed in the Crozier Geotechnical Consultants report that describes the site as general rock shelf, therefore no disposal of collected storm runoff from the site is proposed for disposal into the existing site soil profile.

All collected and controlled storm runoff from the site is to be discharged via the existing stormwater easement pipe line that currently services the block.

The following results are confirmed by the completed DRAINS analysis.

Pre-Developed total site discharge flows- uncontrolled	2 year-13 l/s	20 year-27 l/s	100 year-37 l/s
Post-Developed total site discharge flows-controlled/uncontrolled	2 year-14 l/s	20 year-25 l/s	100 year-33 l/s

DRAINS results prepared from Version 2020.061

PIT / NODE DETAILS			Version 8					
Name	Max HGL	Max Pond	Max Surface	Max Pond	Min	Overflow	Constraint	
	HGL	Flow Arriving	Volume Freeboard					
		(cu.m/s)	(cu.m) (m)					
Pit1	38.41	0.007	0.89 0.000	None				
N2	7.02	0.000						

SUB-CATCHMENT DETAILS

Name	Max Flow Q (cu.m/s)	Paved Max Q (cu.m/s)	Grassed Max Q (cu.m/s)	Paved Tc (min)	Grassed Tc (min)	Supp. Tc (min)	Due to Storm (min)
Cat1	0.016	0.016	0.000	5.00	3.00	2.00	x50 1%
Cat2	0.007	0.007	0.000	5.00	5.00	2.00	x50 1%
Cat3	0.013	0.013	0.000	7.00	10.00	2.00	x50 1%
Cat4	0.001	0.001	0.000	7.00	5.00	2.00	x50 1%
Cat5	0.001	0.001	0.000	7.00	5.00	2.00	x50 1%
Cat6	0.032	0.031	0.001	7.00	7.00	2.00	x50 1%

Outflow Volumes for Total Catchment (0.13 impervious + 0.00 pervious = 0.14 total ha)

Storm	Total Rainfall cu.m	Total Runoff cu.m (Runoff %)	Impervious Runoff cu.m (Runoff %)	Pervious Runoff cu.m (Runoff %)
x50 1%	29.84	26.96 (90.4%)	26.42 (90.8%)	0.54 (72.6%)
x50 5%	22.64	19.76 (87.3%)	19.40 (87.9%)	0.36 (63.9%)
X50 50%		12.58	9.70 (77.1%)	9.59 (78.2%) 0.11 (35.2%)

PIPE DETAILS

Name	Max Q	Max V	Max U/S	Max D/S	Due to Storm
	(cu.m/s)		(m/s) HGL (m)	HGL (m)	
Pipe1	0.007	0.89	38.357	38.257	x50 1%
Pipe2	0.001	0.83	7.223	7.023	x50 1%

CHANNEL DETAILS

Name	Max Q	Max V	Chainage	Max	Due to Storm
	(cu.m/s)		(m/s) (m)	HGL (m)	

OVERFLOW ROUTE DETAILS

Name	Max Q U/S	Max Q D/S	Safe Q	Max D	Max DxV	Max Width	Max V	Due to Storm
OF1	0	0	1.442	0	0	0	0	

DETENTION BASIN DETAILS

Name	Max WL	MaxVol	Max Q	Max Q	Max Q
		Total	Low Level	High Level	
Basin1	37.38	1.6	0.001	0.001	0.000

CONTINUITY CHECK for x50 1%

Node	Inflow	Outflow	Storage Change	Difference
	(cu.m)	(cu.m)	(cu.m)	%
N1	4.84	4.84	0.00	0.0
Pit1	2.09	2.09	0.00	0.0
Basin1	2.09	1.85	0.24	-0.1
N2	1.85	1.85	0.00	0.0
N3	5.63	5.63	0.00	0.0
N4	0.39	0.39	0.00	0.0
N5	0.59	0.59	0.00	0.0
N6	13.41	13.41	0.00	0.0

Run Log for X50 run at 10:23:30 on 22/3/2022 using version 2020.061

No water upwelling from any pit. Freeboard was adequate at all pits.

Flows were safe in all overflow routes.