PROPOSED DEVELOPMENT (No.116-120) FRENCHS FOREST RD, (No.11) GLADYS AVE, FRENCHS FOREST STORMWATER MANAGEMENT PLANS

LEGEND DENOTES ON-SITE DETENTION TANK DENOTES ON-SITE RETENTION TANK DENOTES DWELLING FOOTPRINT DENOTES 100mm DIA. STORMWATER/SURFACE WATER SYSTEM PIPE AT 1% MIN. GRADE U.N.O. DENOTES 100mm DIA. FULLY SEALED RAINWATER SYSTEM PIPE U.N.O. 150 DENOTES RAINWATER PIPE AND DIA. WHEN PIPE EXCEEDS 100mm DIA. 150 DENOTES STORMWATER/SURFACE WATER PIPE AND DIA. WHEN PIPE EXCEEDS 100mm DIA. DENOTES RISING MAIN AND _____ W/RM _____ PIPE DIA. U.N.O. 100 DENOTES SUBSOIL DRAINAGE LINE AND DIA. WRAPPED IN GEOFABRIC U.N.O. DP DENOTES DOWNPIPE 10 DENOTES INSPECTION OPENING WITH SCREW DOWN LID AT FINISHED SURFACE LEVEL CO DENOTES INSPECTION OPENING WITH SCREW DOWN LID AT FINISHED SURFACE LEVEL FOR SYSTEM FLUSHING PURPOSES \square STORMWATER PIT - SOLID COVER STORMWATER PIT - GRATED INLET DENOTES GRATED DRAIN panamana a DENOTES ABSORPTION TRENCH К NON RETURN VALVE \bigcirc PUMP \bowtie STOP VALVE (ISOLATION VALVE) 240v REQUIRED DENOTES LEVEL OF INLET /OUTLET OF STORMWATER PIPE. IL23.31 NOTE: UNLESS NOTED OTHERWISE, THE BASE OF THE PIT IS THE SAME AS THE PIPE INLET/OUTLET.

DIAL BEFORE YOU DIG



IMPORTANT: THE CONTRACTOR IS TO MAINTAIN A CURRENT SET OF "DIAL BEFORE YOU DIG" DRAWINGS ON SITE AT ALL TIMES.

C)COPYRIGHT of this design and plan is the property of HYDRACOR Consulting Engineers Pty Ltd, ACN 127 012 104 ATF HYDRACOR Unit Trust trading as HYDRACOR ABN 81 392 991 647, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from HYDRACOR Consulting Engineers Pty Ltd.

						Client
G	RE-ISSUED FOR DEVELOPMENT APPROVAL	23.04.25	IK	BK	North	
F	RE-ISSUED FOR DEVELOPMENT APPROVAL	23.04.25	IK	BK		
E	ISSUED TO SUIT NEW ARCHITECTURALS	25.02.25	LW	BK		ARCHITECTS
D	RE-ISSUED IN RESPONSE TO COUNCIL RFI	04.02.25	IK	BK		
Issue	Description	Date	Drawn	Approved		
-1 0	1cm at full size					

GENERAL NOTES

1.	THESE PLANS SHALL BE READ IN CONJU CONSULTANTS' PLANS, SPECIFICATIONS CONSENT AND CONSTRUCTION CERTIFIC DISCREPANCIES ARE FOUND HYDRACOF BE CONTACTED IMMEDIATELY FOR VERIF
2.	WHERE THESE PLANS ARE NOTED FOR D ONLY, THEY SHALL NOT BE USED FOR ON NOR USED FOR CONSTRUCTION PURPOS
3.	SUBSOIL DRAINAGE SHALL BE DESIGNED ENGINEER. SUBSOIL DRAINAGE SHALL N STORMWATER SYSTEM IDENTIFIED ON T HYDRACOR CONSULTING ENGINEERS P
	STORMWATER CONS
	STORWWATER CONT
1.	ALL WORK SHALL BE CARRIED OUT IN AC EDITION) AND THE REQUIREMENTS OF TH CODES
2.	THE MINIMUM SIZES OF THE STORMWAT DN90 FOR CLASS 1 BUILDINGS AND DN10 AS REQUIRED BY THE REGULATORY AUT
3.	THE MINIMUM GRADIENT OF STORMWAT OTHERWISE
4.	COUNCIL'S TREE PRESERVATION ORDER TREES SHALL BE REMOVED UNTIL PERM
5.	PUBLIC UTILITY SERVICES ARE TO BE AD EXPENSE
6.	ALL PITS TO BE BENCHED AND STREAML OVER 1.2m DEEP
7.	MAKE SMOOTH JUNCTION WITH ALL EXIS
8.	VEHICULAR ACCESS AND ALL SERVICES ADJOINING PROPERTIES AFFECTED BY C
9.	SERVICES SHOWN ON THESE PLANS HAV SUPPLIED BY THE RELEVANT AUTHORITI NOT GUARANTEED COMPLETE NOR COR RESPONSIBILITY TO LOCATE ALL PRIOR
10.	ANY VARIATION TO THE WORKS AS SHON TO BE CONFIRMED BY HYDRACOR CONS THEIR COMMENCEMENT

- JNCTION WITH OTHER RELEVANT S, CONDITIONS OF DEVELOPMENT ICATE REQUIREMENTS. WHERE R CONSULTING ENGINEERS PTY LTD MUST IFICATION
- DEVELOPMENT APPLICATION PURPOSES BTAINING A CONSTRUCTION CERTIFICATE SES
- ED AND DETAILED BY THE STRUCTURAL NOT BE CONNECTED INTO THE THESE PLANS UNLESS APPROVED BY PTY LTD.

STRUCTION NOTES

- CCORDANCE WITH AS/NZS 3500 (CURRENT THE LOCAL COUNCIL'S POLICIES AND
- TER DRAINS SHALL NOT BE LESS THAN 00 FOR OTHER CLASSES OF BUILDING OR THORITY
- TER DRAINS SHALL BE 1%, UNLESS NOTED
- R IS TO BE STRICTLY ADHERED TO. NO MIT IS OBTAINED
- DJUSTED AS NECESSARY AT THE CLIENT'S
- LINED. PROVIDE STEP IRONS FOR ALL PITS
- STING WORK
- S TO BE MAINTAINED AT ALL TIMES TO CONSTRUCTION
- VE BEEN LOCATED FROM INFORMATION IES AND FIELD INVESTIGATIONS AND ARE RRECT. IT IS THE CLIENT & CONTRACTOR'S TO CONSTRUCTION
- WN ON THE APPROVED DRAWINGS ARE SULTING ENGINEERS PTY LTD PRIOR TO

RAINWATER RE-USE SYSTEM NOTES

- 1. RAINWATER SUPPLY PLUMBING TO BE CONNECTED TO OUTLETS WHERE REQUIRED BY BASIX CERTIFICATE (BY OTHERS)
- 2. TOWN WATER CONNECTION TO RAINWATER TANK TO BE TO THE SATISFACTION OF THE REGULATORY AUTHORITY. THIS MAY REQUIRE PROVISION OF: 2.1. PERMANENT AIR GAP 2.2. BACKFLOW PREVENTION DEVICE
- 3. NO DIRECT CONNECTION BETWEEN TOWN WATER SUPPLY AND THE RAIN WATER SUPPLY
- 4. AN APPROVED STOP VALVE AND/OR PRESSURE LIMITING VALVE AT THE RAINWATER TANK
- PROVIDE APPROPRIATE FLOAT VALVES AND/OR SOLENOID VALVES TO CONTROL TOWN WATER SUPPLY INLET TO TANK IN ORDER TO ACHIEVE THE TOP-UP INDICATED ON THE TYPICAL DETAIL
- 6. ALL PLUMBING WORKS ARE TO BE CARRIED OUT BY LICENSED PLUMBERS IN ACCORDANCE WITH AS/NZS3500.1 NATIONAL PLUMBING AND DRAINAGE CODE
- 7. PRESSURE PUMP ELECTRICAL CONNECTION TO BE CARRIED OUT BY A LICENSED ELECTRICIAN
- 8. ONLY ROOF RUN-OFF IS TO BE DIRECTED TO THE RAINWATER TANK . SURFACE WATER INLETS ARE NOT TO BE CONNECTED
- PIPE MATERIALS FOR RAINWATER SUPPLY PLUMBING ARE TO BE APPROVED MATERIALS TO AS/NZS3500 PART 1 SECTION 2 AND TO BE CLEARLY AND PERMANENTLY IDENTIFIED AS 'RAINWATER'. THIS MAY BE ACHIEVED FOR BELOW GROUND PIPES USING IDENTIFICATION TAPE (MADE IN ACCORDANCE WITH AS2648) OR FOR ABOVE GROUND PIPES BY USING ADHESIVE PIPE MARKERS (MADE IN ACCORDANCE WITH AS1345)
- 10. EVERY RAINWATER SUPPLY OUTLET POINT AND THE RAINWATER TANK ARE TO BE LABELED 'RAINWATER' ON A METALLIC SIGN IN ACCORDANCE WITH AS1319
- 11. ALL INLETS AND OUTLETS TO THE RAINWATER TANK ARE TO HAVE SUITABLE MEASURES PROVIDED TO PREVENT MOSQUITO AND VERMIN ENTRY

SHEET INDEX

COVER SHEET & NOTES	SHEET SW1
STORMWATER MANAGEMENT PLAN - BASEMENT 2 SHEET No.1	SHEET SW2
STORMWATER MANAGEMENT PLAN - BASEMENT 2 SHEET No.2	SHEET SW3
STORMWATER MANAGEMENT PLAN - BASEMENT 2 SHEET No.3	SHEET SW4
STORMWATER MANAGEMENT PLAN - BASEMENT 1 SHEET No.1	SHEET SW5
STORMWATER MANAGEMENT PLAN - BASEMENT 1 SHEET No.2	SHEET SW6
STORMWATER MANAGEMENT PLAN - MEZZANINE	SHEET SW7
STORMWATER MANAGEMENT PLAN - GROUND FLOOR SHEET No.1	SHEET SW8
STORMWATER MANAGEMENT PLAN - GROUND FLOOR SHEET No.2	SHEET SW9
STORMWATER MANAGEMENT PLAN - GROUND FLOOR SHEET No.3	SHEET SW10
STORMWATER MANAGEMENT PLAN - ONSITE DETENTION LAYOUT	SHEET SW12
STORMWATER MANAGEMENT DETAILS SHEET No.1	SHEET SW12
STORMWATER MANAGEMENT DETAILS SHEET No.2	SHEET SW13
STORMWATER QUALITY REPORT SHEET No.1	SHEET SW14
STORMWATER QUALITY REPORT SHEET No.2	SHEET SW15
EROSION & SEDIMENT CONTROL NOTES	SHEET SW16
EROSION & SEDIMENT CONTROL PLAN	SHEET SW17
EROSION & SEDIMENT CONTROL DETAIL SHEET	SHEET SW18
ON-SITE DETENTION CHECK LIST	SHEET SW19
DRAINAGE LONG SECTION	SHEET SW20

SITE AREA SITE LOCAT PRE-DEVEL POST DEVE

1. FULL REFEF 2. DRAIN

SITE AREA IMPERVIOU

PRE-DEVEL

ARI (YEA

5 100

POST DEVE ROOF AREA DRIVEWAY MISC. IMP A TOTAL IMPE

FOR CALCU

OSD CATCH OSD BYPAS

STORAGE

MAXIMUM H TOP STORE C/L OF ORIF THEREFOR

DESIGN HAS COUNCIL'S

Project
PROPOSED RE
No.116 - 120 FRENCHS FC No.11 GLADYS AVENUE FRENCHS FOREST



T +61 2 4324 3499

ENGINEERS | CIVIL | FLOOD STUDIES | STORMWATER | HYDRAULIC

HYDRACOR Consulting Engineers Pty Ltd

Platinum Building, Suite 2.01, 4 Ilya Avenue

ERINA NSW 2250, Australia





Architect

ORT	HERN BEACH		NCII RFO		NTS
(m²) TION OPED II	MPERVIOUS AREA (n IMPERVIOUS AREA (n²)			
	TATIONAL METHOD A RAINS MODEL CC230 ⁻ MARY		NG DRAINS PR	OGRAM.	
(m²) S PRE-[DEVELOPED FOR CA	LCULATIONS			
OPED D	DISCHARGE FLOW R	ATES			
		PC	OST-DEVELOP	ED FLOW RAT	ES
ARS)	PRE-DEVELOPED FLOW RATE (L/sec)	OSD PIPED OUTFLOW (L/sec)	OVERFLOW (L/sec)	TOTAL OUTFLOW (L/sec)	OSD STORAGE VOMUME (m ³)
	190	164	0	164	35
	330	198	121	319	50
eadwa d wati ice = r e: adof	E REQUIRED = 50m ³ ATER = 1.35m ER LEVEL = RL 152.7 RL 151.35 PT = 297mm ORIFICE PREPARED IN ACCC			REACHES	
	MANAGEMENT POL				
	DEVELOPM	1ENT APF	PLICATIO	N ISSUE	


DRAWINGS MUST BE PRINTED IN COLOUR

SIDENTIAL	COVER SHEET & NOTES							
REST ROAD	Drawn LW	Date NOV 2024	Scale A1 AS NOTED	Q.A. Check	Date -			
	Designed BK	Project No. CC230	124	Dwg. No. SW1	lssue G			






HYDR∧€OR	HYDRACOR Consulting Engineers Pty Ltd Platinum Building, Suite 2.01, 4 Ilya Avenue ERINA NSW 2250, Australia	Project PROPOSED RESIDENTIAL DEVELOPMENT	Drawing Title STORMWATER MANAGEMENT BASEMENT 2 SHEET No.2				
CONSULTING ENGINEERS	T +61 2 4324 3499	No.116 - 120 FRENCHS FOREST ROAD	Drawn IK	Date NOV 2024	Scale A1 AS NOTED	Q.A. Check -	Date -
	ENGINEERS CIVIL FLOOD STUDIES STORMWATER HYDRAULIC	No.11 GLADYS AVENUE FRENCHS FOREST	Designed BK	Project No. CC230		Dwg. No. SW3	lssue G



AY

PROPOSED RESIDENTIAL DEVELOPMENT No.116 - 120 FRENCHS FOREST ROAD No.11 GLADYS AVENUE


ENGINEERS | CIVIL | FLOOD STUDIES | STORMWATER | HYDRAULIC





DENOTES TREE TO BE REMOVED


DENOTES TREE PROTECTION ZONE ON EXISTING TREES TO REMAIN, NOTE: PROVIDE APPROPRIATE PROTECTION MEASURES DURING CONSTRUCTION IN ACCORDANCE WITH ARBORISTS REQUIREMENTS


DENOTES STRUCTURAL ROOT ZONES ON EXISTING TREES TO REMAIN















SIDENTIAL	GROUND FLOOR SHEET No.1							
	Drawn	Date	Scale A1	Q.A. Check	Date			
OREST ROAD	IK	NOV 2024	AS NOTED	-	-			
	Designed	Project No.		Dwg. No.	Issue			
	ВК	CC230	SW8	G				






SIDENTIAL	Drawing Title STORM GROUN	EMENT PLAN T No.3			
	Drawn	Date	Scale A1	Q.A. Check	Date
OREST ROAD	IK	NOV 2024	AS NOTED	-	-
	Designed	Project No.		Dwg. No.	Issue
	ВК	CC230	124	SW10	G





	LEGEND
	LEGEND
	ROOFWATER INLET PIPE/S
2	SURFACE WATER INLET PIPE
3	375 DIA DISCHARGE PIPE
4	2 x 300 DIA HIGH LEVEL OVERFLOW PIPE/S
5	350 x 350 x 4 PL 316SS 4 HOLES 12 DIA FOR M10 CHEMSETS REFER TO DETAIL 2
6	TRASH SCREEN LYSAGHT RH3030 GALV. REMOVABLE WITH HANDLE REER TO DETAIL 1
7	900 x 900 SOLID COVER BOLTED DOWN
8	REFLUX FLAP. REFER TO DETAIL 3 150 DIA. VOID
9	PROVIDE GALVANISED STEP IRONS AT 300mm CENTRES WHERE DEPTH EXCEEDS 1100mm IN ACCORDANCE WITH THE AUST. STANDARDS AT ALL ACCESS POINTS OF THE TANK, TYP.
(10)	RISING MAIN FROM PUMP-OUT TANK
(11)	ATLAN CARTRIDGE FILTERS (6 FULL HEIGHT)
(12)	WATER QUALITY OVERFLOW WEIR
(13)	HIGH EARLY DISCHARGE OVERFLOW WEIR
(14)	TANK STRUCTURE TO STRUCTURAL ENGINEERS DETAILS

ESIDENTIAL	Drawing Title STORMWATER MANAGEMENT DETAILS SHEET No.1							
	Drawn	Date	Scale A1	Q.A. Check	Date			
FOREST ROAD	IK	NOV 2024	AS NOTED	-	-			
	Designed	Project No.		Dwg. No.	Issue			
	BK	CC230	124	SW12	G			



OUT DESIGN NOTES
L BE OPERATED IN THE FOLLOWING MANNER:-
L BE PROGRAMMED TO WORK ALTERNATELY TO ALLOW BOTH AN EQUAL OPERATION LOAD AND PUMP LIFE
E PROVIDED TO ENSURE THAT THE MINIMUM REQUIRED MAINTAINED WITHIN THE SUMP AREA OF THE BELOW GROUND GARD THIS FLOAT WILL FUNCTION AS AN OFF SWITCH FOR THE INIMUM WATER LEVEL. THE SAME FLOAT SHALL BE SET TO E PUMPS ON UPON WATER LEVEL IN THE TANK RISING TO 300mm ABOVE THE MINIMUM WATER LEVEL. THE PUMP SHALL THE TANK IS DRAINED TO THE MINIMUM WATER LEVEL.
SHALL BE PROVIDED AT A HIGH LEVEL, WHICH IS THE ROOF LEVEL OF THE BELOW GROUND TANK. THIS FLOAT OTHER PUMP THAT IS NOT OPERATING AND ACTIVATE THE
M SHALL BE PROVIDED WITH A FLASHING STROBE LIGHT AND A ARNING SIGN WHICH ARE TO BE LOCATED AT THE DRIVEWAY IE BASEMENT LEVEL. THE ALARM SYSTEM SHALL BE PROVIDED

5. A CONFINED SPACE DANGER SIGN SHALL BE PROVIDED AT ALL ACCESS POINTS

PUMP-OUT TANK MAINTENANCE SCHEDULE

NOTE: A 24 HOUR X 12 MONTHLY EMERGENCY AND MAINTENANCE CONTRACT SHALL BE OBTAINED FROM A COMPANY CAPABLE OF EXECUTING THE WORK AND SHALL BE KEPT IN FORCE BY THE PROPERTY OWNER(S) FOR THE LIFE OF THE BUILDING.

THE MAINTENANCE CONTRACT SHALL BE CARRIED OUT EVERY THREE (3) MONTHS AND

CLEAN OUT ALL PITS OF SILT AND DEBRIS. 2. CHECK AND CLEAN OUT, IF NECESSARY, ALL PIPELINES.

4. CARRY OUT ROUTINE MAINTENANCE TO PUMPS AS RECOMMENDED BY THE

5. CHECK OPERATIONAL SEQUENCE OF LEVEL SWITCHES, PUMPS AND CONTROL

6. THE EMERGENCY CONTRACT SHALL PROVIDE FOR A 24 HOUR X 7 DAY PER

THE CONTRACTOR SHALL PROVIDE A NAME PLATE STATING NAME, WORKING HOURS, TELEPHONE NUMBER AND OUT OF HOURS NUMBER AND SUCH NAME PLATE SHALL BE

ESIDENTIAL	_	IWATER .S SHEE	MANAGI T No.2	EMENT	
1	Drawn	Date	Scale A1	Q.A. Check	Date
FOREST ROAD	IK	NOV 2024	AS NOTED	-	-
	Designed	Project No.		Dwg. No.	Issue
	BK	CC230	124	SW13	G

STORMWATER QUALITY REPORT

1 INTRODUCTION

A CATCHMENT BASED WATER QUALITY MODEL WAS DEVELOPED TO ASSESS THE STORMWATER RUNOFF QUALITY IN ACCORDANCE WITH THE REQUIREMENTS OF TABLE 5 NORTHERN BEACHES WATER MANAGEMENT FOR DEVELOPMENT POLICY AND THE OBJECTIVES OUTLINED IN WARRINGAH DCP PART G SECTION G9.9 OBJECTIVE A AND B. IN THIS REGARD WE REFER TO THE PRESCRIBED TARGETS TABLED FOLLOWING:

TABLE 1 - STORMWATER POLUTANT REDUCTION TARGETS

STORMWATER POLLUTANT	REDUCTION TARGETS
GROSS POLLUTANT	90%
TOTAL SUSPENDED SOLIDS (TSS)	85%
TOTAL PHOSPHORUS (TP)	65%
TOTAL NITROGEN (TN)	45%

2 STUDY METHODOLOGY

THE OBJECTIVES OF THIS REPORT ARE TO:

- ASSESS THE RUNOFF QUALITY FOR THE UNTREATED POST DEVELOPED SCENARIO AND IDENTIFY STORMWATER QUALITY CONTROLS LIKELY TO IMPACT ON RUNOFF QUALITY.
- ASSESS THE STORMWATER QUALITY FOR THE POST DEVELOPED SCENARIO INCLUDING THE MEASURES PROPOSED TO MEET THE POLLUTANT REMOVAL TARGETS .

THE REPORT IS BASED ON THE APPLICATION OF MUSIC SOFTWARE (MODEL FOR URBAN STORMWATER IMPROVEMENT CONCEPTUALISATION). IN THIS REGARD THE MODEL IS DEFINED AS FOLLOWS:

A STORMWATER QUALITY MODEL TO CONVERT RAINFALL AND EVAPOTRANSPIRATION INTO RUNOFF.

 ESTIMATION OF STORMWATER FLOW AND POLLUTION GENERATION BY SIMULATING THE PERFORMANCE OF STORMWATER TREATMENT DEVICES INDIVIDUALLY AND AS PART OF A TREATMENT TRAIN.

THE MODEL DEFINES WATER QUALITY PROFILES TREATED SCENARIOS. THE TREATED POST DEVELOPED MODEL INCLUDES PARAMETERS WHICH REPRESENT THE WATER QUALITY MEASURES.

	DPYRIGHT of this design and plan is the property of HYDRACOR Consulting Engineers rights reserved. It must not be used, modified, reproduced or copied wholly or in pa					81 392 991 647,
						Client
G	RE-ISSUED FOR DEVELOPMENT APPROVAL	23.04.25	IK	BK	North	
F	RE-ISSUED FOR DEVELOPMENT APPROVAL	23.04.25	IK	BK		BREWS
Е	ISSUED TO SUIT NEW ARCHITECTURALS	25.02.25	LW	BK		

04.02.25 IK BK Date Drawn Approved

RE-ISSUED IN RESPONSE TO COUNCIL RFI

Issue Description

1cm at full size

VSTER MURRAY ITECTS

3 STORMWATER QUALITY MODELLING

3.1 GENERAL

THE FOLLOWING PARAMETERS WERE ASSESSED FOR THE HYDROLOGICAL MODELLING ASSOCIATED WITH THE CATCHMENT.

- RAINFALL/RUNOFF AND EVAPOTRANSPIRATION.
- SUB CATCHMENT DIVERSIONS.
- LAND USE (PERVIOUS AND IMPERVIOUS)

3.2 RAINFALL/RUNOFF AND EVAPOTRANSPIRATION

NORTHERN BEACHES COUNCIL'S WSUD & MUSIC MODELING GUIDELINES WERE UTILISED IN THIS STUDY. THEREFORE DAILY RAINFALL DATA WAS OBTAINED FROM THE SYDNEY OBSERVATORY HILL RAINFALL STATION WITH 6 min TIMESTEP, STATION NO. 066062. THE COUNCIL'S DEFAULT MONTHLY AVERAGE POTENTIAL EVAPOTRANSPIRATION DATA WAS ALSO UTILISED IN THIS STUDY.

THE DETAILS ARE SUMMARISED IN TABLE 3.1 AND 3.2

	TABLE 3.1 - DETAILS OF I	DAILY RAINFALL DATA	
STATION	NAME	PERIOD	TIMESTEP
066062	SYDNEY OBSERVATORY HILL	01/01/1981-31/08/1985	6 min

H

CON

TABLE 3.2	2 - SUMMAI		ENTIAL EVA ET)	APOTRANS	PIRATION
JAN	FEB	MAR	APR	MAY	JUN
180	135	128	85	58	43
JUL	AUG	SEP	OCT	NOV	DEC
43	58	88	127	152	163

3.3 CATCHMENT DEFINITION

THE POST DEVELOPED CATCHMENT CHARACTERISTICS ARE **IDENTIFIED IN TABLE 3.3.**

TABLE 3.3 - POST	DEVELOPMENT	SUB CATCHMEN	T DETAILS
SUB CATCHMENT ID	SUB CATCHMENT AREA (ha)	% IMPERVIOUS AREA	% PERVIOUS AREA
ROOF	0.244	100	0
IMPERVIOUS AREA TO OSD	0.080	100	0
DRIVEWAY DRAINING TO OSD	0.011	100	0

4 MUSIC MODEL

THE MUSIC MODEL IS BASED ON A 6 min RAINFALL-RUNOFF MODEL IN CONJUNCTION WITH REPRESENTATIVE BASEFLOW AND STORMFLOW EVENT MEAN CONCENTRATIONS (EMCs).

4.1 WATER QUALITY PARAMETERS

THE ADOPTED VALUES OF VARIOUS MUSIC RAINFALL AND RUNOFF PARAMETERS ARE SUMMARISED IN TABLE 4.1 AS PER THE DEFAULT VALUES WHEN ADOPTING THE NORTHERN BEACHES COUNCIL'S WSUD & MUSIC MODELING GUIDELINES

TABLE 4.1 - ADOPTED MUSIC RAINFALL/RUN	IOFF PARAMETERS
PARAMETER	VALUE
IMPERVIOUS AREA PROPER	<u>LIES</u>
RAINFALL THRESHOLD (mm/DAY)	0.3 (roof) else 1.5
PERVIOUS AREA PROPERTIES (SANDY	′ CLAY LOAM)
SOIL STORAGE CAPACITY (mm)	108
SOIL INITIAL STORAGE (% OF CAPACITY)	30
FIELD CAPACITY (mm)	73
INFILTRATION CAPACITY COEFFICIENT - a	250
INFILTRATION CAPACITY EXPONENT - b	1.3
GROUNDWATER PROPERTI	ES
INITIAL DEPTH (mm)	10
DAILY RECHARGE RATE (%)	60
DAILY BASEFLOW RATE (%)	45
DAILY DEEP SEEPAGE RATE (%)	0

∕DR∧€OR	HYDRACOR Consulting Engineers Pty Ltd Platinum Building, Suite 2.01, 4 Ilya Avenue ERINA NSW 2250, Australia	PROPOSED RESIDENTIAL	-	WATER		Y	
NSULTING ENGINEERS	T +61 2 4324 3499	No.116 - 120 FRENCHS FOREST ROAD	Drawn IK		Scale A1 AS NOTED	Q.A. Check -	Date -
	ENGINEERS CIVIL FLOOD STUDIES STORMWATER HYDRAULIC	No.11 GLADYS AVENUE	5	Project No. CC230	124	Dwg. No. SW14	Issue G
				00200		0111	

Architect

4.1 WATER QUALITY PARAMETERS CONT.

STORMWATER QUALITY IS CHARACTERISED USING EVENT MEAN CONCENTRATION (EMCs) UNDER STORM AND BASE FLOW CONDITIONS. THE VALUE OF WATER QUALITY PARAMETERS ADOPTED IN THIS STUDY IS SUMMARISED IN TABLE 4.2

TA	ABLE 4.2 -	ADOPTED N	MUSIC WA	ATER QUAL	ITY PARA	METERS	
		Log₀TSS	(mg/L)	Log₁0 TP	(mg/L)	Log₁₀TN	l (mg/L)
LAND-USE CA	TEGORY	STORM FLOW	BASE FLOW	STORM FLOW	BASE FLOW	STORM FLOW	BASE FLOW
	MEAN	2.15	1.20	-0.60	-0.85	0.30	0.11
RESIDENTIAL	STD DEV	0.32	0.17	0.25	0.19	0.19	0.12
SEALED	MEAN	2.43	1.20	-0.3	-0.85	0.34	0.11
ROADS	STD DEV	0.32	0.17	0.25	0.19	0.19	0.12
	MEAN	1.30	1.10	-0.89	-0.82	0.30	0.32
ROOFS	STD DEV	0.32	0.17	0.25	0.19	0.19	0.12

4.2 STORMWATER TREATMENT MEASURES

THE PROPOSED STORMWATER TREATMENT MEASURES INCLUDED IN THE POST DEVELOPED MODEL ARE AS FOLLOWS:

- 15,000 LITRE OSR TANK (FOR IRRIGATION ONLY)
- 6 x ATLAN FILTERS (FULL HEIGHT) (FORMERLY SPELFILTERS)
- 2 x ATLAN STORMSACKS (FORMERLY SPEL STORMSACKS)

THE SCHEMATIC LAYOUT FOR THE POST DEVELOPED MUSIC

MODEL IS DEPICTED IN FOLLOWING FIGURE 1

WATER QUALITY TREATMENT OPTIONS AND CONSTRAINTS

WE REFER TO GEOTECHNICAL INVESTIGATION REPORT PREPARED BY GREEN GEOTECHNICS PTY LTD, REFERENCE GG11138.001, DATED 8 AUGUST 2023 AND NOTE THAT THE SOIL PROFILE ON THE SITE CONSISTS GENERALLY OF FIRM TO STIFF AND STIFF TO VERY STIFF CLAYS OVERLAYING SHALE AND SANDSTONE BEDROCK. IN THIS REGARD, INFILTRATION IS EXTREMELY LIMITED ON THE SITE. THEREFORE INFILTRATION HAS NOT BEEN PROVIDED.

COPYRIGHT of this design and plan is the property of HYDRACOR Consulting Engineers Pty Ltd, ACN 127 012 104 ATF HYDRACOR Unit Trust trading as HYDRACOR ABN 81 392 991 647, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from HYDRACOR Consulting Engineers Pty Ltd.

						Client
G	RE-ISSUED FOR DEVELOPMENT APPROVAL	23.04.25	IK	BK	North	
F	RE-ISSUED FOR DEVELOPMENT APPROVAL	23.04.25	IK	BK		
E	ISSUED TO SUIT NEW ARCHITECTURALS	25.02.25	LW	BK		ARCHITECTS
D	RE-ISSUED IN RESPONSE TO COUNCIL RFI	04.02.25	IK	BK		
Issue	Description	Date	Drawn	Approved		
-1 0	1cm at full size					




FIGURE 1 - MUSIC MODEL SCHEMATIC

5 RESULTS & CONCLUSION

BASED ON THE FOREGOING THE PROPOSED STORMWATER QUALITY TREATMENT MEASURES MEET THE REQUIRED TARGETS OF TABLE 5 OF NORTHERN BEACHES WATER MANAGEMENT FOR DEVELOPMENT POLICY AND THE OBJECTIVES OUTLINED IN WARRINGAH DCP PART G SECTION G9.9 OBJECTIVE A AND B.

TABLE 5.1 - TREATMENT TRAIN EFFECTIVENESS

	Sources	Residual Load	% Reduction
Flow (ML/yr)	3.96	3.26	17.5
Total Suspended Solids (kg/yr)	285	33.2	88.3
Total Phosphorus (kg/yr)	0.784	0.189	75.8
Total Nitrogen (kg/yr)	8.78	2.86	67.4
Gross Pollutants (kg/yr)	101	0	100

HYDR∧€OR	HYDRACOR Consulting Engineers Pty Ltd Platinum Building, Suite 2.01, 4 Ilya Avenue ERINA NSW 2250, Australia	Project PROPOSED RESIDENTIAL DEVELOPMENT	_	MWATEF RT SHEE	R QUALIT T No. 2	Y	
	T +61 2 4324 3499	No.116 - 120 FRENCHS FOREST ROAD	Drawn IK	Date NOV 2024	Scale A1 AS NOTED	Q.A. Check -	Date -
	ENGINEERS CIVIL FLOOD STUDIES STORMWATER HYDRAULIC	No.11 GLADYS AVENUE FRENCHS FOREST	Designed BK	Project No.	124	Dwg. No. SW15	Issue G

Architect

GENERAL INSTRUCTIONS

- THIS SOIL AND WATER MANAGEMENT PLAN IS TO BE READ 1. IN CONJUNCTION WITH OTHER ENGINEERING PLANS RELATING TO THIS DEVELOPMENT
- CONTRACTORS WILL ENSURE THAT ALL SOIL AND WATER 2. MANAGEMENT WORKS ARE UNDERTAKEN AS INSTRUCTED IN THIS SPECIFICATION AND CONSTRUCTED FOLLOWING THE GUIDELINES OF "MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION". DEPT OF HOUSING, 1998 (BLUE BOOK).
- ALL SUBCONTRACTORS WILL BE INFORMED OF THEIR 3. RESPONSIBILITIES IN REDUCING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSLOPE AREAS.

LAND DISTURBANCE INSTRUCTIONS

- DISTURBANCE TO BE NO FURTHER THAN 5 (PREFERABLY 2) METRES FROM THE EDGE OF ANY ESSENTIAL ENGINEERING ACTIVITY AS SHOWN ON APPROVED PLANS. ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE ZONES THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH BARRIER FENCING (UPSLOPE) AND SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIALS.
- ACCESS AREAS ARE TO BE LIMITED TO A MAXIMUM WIDTH 5. OF 10 METRES THE SITE MANAGER WILL DETERMINE AND MARK THE LOCATION OF THESE ZONES ON-SITE. ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE BOUNDARIES THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH BARRIER FENCING (UPSLOPE) AND SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIALS.
- ENTRY TO LANDS NOT REQUIRED FOR CONSTRUCTION OR 6 ACCESS IS PROHIBITED EXCEPT FOR ESSENTIAL THINNING OF PLANT GROWTH.
- WORKS ARE TO PROCEED IN THE FOLLOWING SEQUENCE:
- INSTALL ALL BARRIER AND SEDIMENT FENCING A) WHERE SHOWN ON THE PLAN.
- CONSTRUCT THE STABILISED SITE ACCESS. B)
- CONSTRUCT DIVERSION DRAINS AS REQUIRED C)
- INSTALL MESH AND GRAVEL INLETS FOR ANY
- ADJACENT KERB INLETS. INSTALL GEOTEXTILE INLET FILTERS AROUND ANY F)
- ON-SITE DROP INLET PITS. CLEAR SITE AND STRIP AND STOCKPILE TOPSOIL IN F) LOCATIONS SHOWN ON THE PLAN.
- UNDERTAKE ALL ESSENTIAL CONSTRUCTION G) WORKS ENSURING THAT ROOF AND/OR PAVED AREA STORMWATER SYSTEMS ARE CONNECTED TO PERMANENT DRAINAGE AS SOON AS PRACTICABLE.
- H) GRADE LOT AREAS TO FINAL GRADES AND APPLY PERMANENT STABILISATION (LANDSCAPING) WITHIN 20 DAYS OF COMPLETION OF CONSTRUCTION WORKS.
- REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER THE PERMANENT LANDSCAPING HAS BEEN COMPLETED
- 5. ENSURE THAT SLOPE LENGTHS DO NOT EXCEED 80 METRES WHERE PRACTICABLE. SLOPE LENGTHS ARE DETERMINED BY SILTATION FENCING AND CATCH DRAIN SPACING.
- ON COMPLETION OF MAJOR WORKS LEAVE DISTURBED 6. LANDS WITH A SCARIFIED SURFACE TO ENCOURAGE WATER INFILTRATION AND ASSIST WITH KEYING TOPSOIL LATER.

SITE MAINTENANCE INSTRUCTIONS

- THE SITE SUPERINTENDENT WILL INSPECT THE SITE AT 16. EARTH BATTERS WILL BE CONSTRUCTED WITH AS LOW A LEAST WEEKLY AND AT THE CONCLUSION OF EVERY **GRADIENT AS PRACTICABLE BUT NO STEEPER, UNLESS** STORM EVENT TO: OTHERWISE NOTED. THAN: 2(H):1(V) WHERE SLOPE LENGTH LESS THAN 12 ENSURE THAT DRAINS OPERATE PROPERLY AND A) TO FFFECT ANY NECESSARY REPAIRS METRES REMOVE SPILLED SAND OR OTHER MATERIALS 2.5(H):1(V) WHERE SLOPE LENGTH BETWEEN 12 B) FROM HAZARD AREAS, INCLUDING LANDS CLOSER AND 16 METRES. THAN 5 METRES FROM AREAS OF LIKELY 3(H):1(V) WHERE SLOPE LENGTH BETWEEN 16 CONCENTRATED OR HIGH VELOCITY FLOWS AND 20 METRES. ESPECIALLY WATERWAYS AND PAVED AREAS. 4(H):1(V) WHERE SLOPE LENGTH GREATER THAN REMOVE TRAPPED SEDIMENT WHENEVER THE 20 METRES. C) 17. ALL WATERWAYS, DRAINS, SPILLWAYS AND THEIR DESIGN CAPACITY OF THAT STRUCTURE HAS BEEN EXCEEDED. OUTLETS WILL BE CONSTRUCTED TO BE STABLE IN AT D) ENSURE REHABILITATED LANDS HAVE LEAST THE 1:20 YEAR ARI. TIME OF CONCENTRATION EFFECTIVELY REDUCED THE EROSION HAZARD STORM EVENT. 18. WATERWAYS AND OTHER AREAS SUBJECT TO AND TO INITIATE UPGRADING OR REPAIR AS NECESSARY. CONCENTRATED FLOWS AFTER CONSTRUCTION ARE TO CONSTRUCT ADDITIONAL EROSION AND/OR HAVE A MAXIMUM GROUNDCOVER C-FACTOR OF 0.05 (70% E) SEDIMENT CONTROL WORKS AS MIGHT BECOME GROUND COVER) WITHIN 10 WORKING DAYS FROM NECESSARY TO ENSURE THE DESIRED COMPLETION OF FORMATION. FLOW VELOCITIES ARE TO PROTECTION IS GIVEN TO DOWNSLOPE LANDS AND BE LIMITED TO THOSE SHOWN IN TABLE 5-1 OF "MANAGING WATERWAYS. MAKE ONGOING CHANGES TO THE URBAN STORMWATER - SOILS AND CONSTRUCTION", DEPT PLAN WHERE IT PROVES INADEQUATE IN PRACTICE OF HOUSING 1998 (BLUE BOOK). FOOT AND VEHICULAR OR IS SUBJECTED TO CHANGES IN CONDITIONS ON TRAFFIC WILL BE PROHIBITED IN THESE AREAS. THE WORK-SITE OR ELSEWHERE IN THE 19. STOCKPILES AFTER CONSTRUCTION ARE TO HAVE A CATCHMENT. MAXIMUM GROUND-COVER C-FACTOR OF 0.1 (60% F) MAINTAIN EROSION AND SEDIMENT CONTROL GROUND-COVER) WITHIN 10 WORKING DAYS FROM STRUCTURES IN A FULLY FUNCTIONING CONDITION COMPLETION OF FORMATION UNTIL ALL EARTHWORK ACTIVITIES ARE 20. ALL LANDS, INCLUDING WATERWAYS AND STOCKPILES COMPLETED AND THE SITE IS REHABILITATED. DURING CONSTRUCTION ARE TO HAVE A MAXIMUM THE SITE SUPERINTENDENT WILL KEEP A LOGBOOK GROUND-COVER C-FACTOR OF 0.15 (50% GROUND COVER) MAKING ENTRIES AT LEAST WEEKLY, IMMEDIATELY WITHIN 20 WORKING DAYS FROM INACTIVITY EVEN BEFORE FORECAST RAIN AND AFTER RAINFALL. ENTRIES THOUGH WORKS MAY CONTINUE LATER. WILL INCLUDE: 21. FOR AREAS OF SHEET FLOW USE THE FOLLOWING THE VOLUME AND INTENSITY OF ANY RAINFALL GROUND COVER PLANT SPECIES FOR TEMPORARY A) EVENTS. COVER: JAPANESE MILLET 20 KG/HA AND OATS 20 KG/HA. THE CONDITION OF ANY SOIL AND WATER 22. PERMANENT REHABILITATION OF LANDS AFTER B) MANAGEMENT WORKS. CONSTRUCTION WILL ACHIEVE A GROUND-COVER THE CONDITION OF VEGETATION AND ANY NEED TO C-FACTOR OF LESS THAN 0.1 AND LESS THAN 0.05 WITHIN C) IRRIGATE. 60 DAYS. NEWLY PLANTED LANDS WILL BE WATERED THE NEED FOR DUST PREVENTION STRATEGIES **REGULARLY UNTIL AN EFFECTIVE COVER IS ESTABLISHED** D) E) ANY REMEDIAL WORKS TO BE UNDERTAKEN. AND PLANTS ARE GROWING VIGOROUSLY. FOLLOW-UP SEED AND FERTILISER WILL BE APPLIED AS NECESSARY THE LOGBOOK WILL BE KEPT ON-SITE AND MADE AVAILABLE TO ANY AUTHORISED PERSON UPON REQUEST 23. REVEGETATION SHOULD BE AIMED AT RE-ESTABLISHING IT WILL BE GIVEN TO THE PROJECT MANAGER AT THE NATURAL SPECIES. NATURAL SURFACE SOILS SHOULD BE CONCLUSION OF THE WORKS. REPLACED AND NON-PERSISTANT ANNUAL COVER CROPS SHOULD BE USED. WASTE CONTROL INSTRUCTIONS SEDIMENT FENCES WILL BE INSTALLED AS SHOWN ON THE 9

SEDIMENT CONTROL INSTRUCTIONS

- PLAN AND ELSEWHERE AT THE DISCRETION OF THE SITE SUPERINTENDENT TO CONTAIN SOIL AS NEAR AS POSSIBLE TO THEIR SOURCE.
- SEDIMENT FENCES WILL NOT HAVE CATCHMENT AREAS **EXCEEDING 900 SQUARE METRES AND HAVE A STORAGE** DEPTH OF AT LEAST 0.6 METRES.
- 11. SEDIMENT REMOVED FROM ANY TRAPPING DEVICES WILL BE RELOCATED WHERE FURTHER POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS CANNOT OCCUR.
- 12. STOCKPILES ARE NOT TO BE LOCATED WITHIN 5 METRES OF HAZARD AREAS INCLUDING AREAS OF HIGH VELOCITY FLOWS SUCH AS WATERWAYS, PAVED AREAS AND DRIVEWAYS.
- 13. WATER WILL BE PREVENTED FROM DIRECTLY ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR WATER HAS BEEN TREATED BY AN APPROVED DEVICE.
- 14. TEMPORARY SEDIMENT TRAPS WILL REMAIN IN PLACE UNTIL AFTER THE LANDS THEY ARE PROTECTING ARE COMPLETELY REHABILITATED.
- 15. ACCESS TO SITES SHOULD BE STABILISED TO REDUCE THE LIKELIHOOD OF VEHICLES TRACKING SOIL MATERIALS ONTO PUBLIC ROADS AND ENSURE ALL-WEATHER ENTRY/EXIT

	YRIGHT of this design and plan is the property of HYDRACOR Consulting Engineers Pty Ltd, ACN 127 012 104 ATF ights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permissior					91 647,
						Client
G	RE-ISSUED FOR DEVELOPMENT APPROVAL	23.04.25	IK	BK	North	
F	RE-ISSUED FOR DEVELOPMENT APPROVAL	23.04.25	IK	BK		
Е	ISSUED TO SUIT NEW ARCHITECTURALS	25.02.25	LW	BK		ARCHITECTS
D	RE-ISSUED IN RESPONSE TO COUNCIL RFI	04.02.25	IK	BK		
Issue	Description	Date	Drawn	Approved	1	
-1 _0	10cm				1	

EROSION AND SEDIMENT CONTROL NOTES

SOIL EROSION CONTROL	

- 24. ACCEPTABLE BINS WILL BE PROVIDED FOR ANY CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHING, LIGHTWEIGHT WASTE MATERIALS AND LITTER. CLEARANCE SERVICES WILL BE PROVIDED AT LEAST WEEKLY. DISPOSAL OF WASTE WILL BE IN A MANNER APPROVED BY THE SITE SUPERINTENDENT.
- 25. ALL POSSIBLE POLLUTANT MATERIALS ARE TO BE STORED WELL CLEAR OF ANY POORLY DRAINED AREAS, FLOOD PRONE AREAS, STREAMBANKS, CHANNELS AND STORMWATER DRAINAGE AREAS. STORE SUCH MATERIALS IN A DESIGNATED AREA UNDER COVER WHERE POSSIBLE AND WITHIN CONTAINMENT BUNDS.
- 26. ALL SITE STAFF AND SUB-CONTACTORS ARE TO BE INFORMED OF THEIR OBLIGATION TO USE WASTE CONTROL FACILITIES PROVIDED.
- 27. ANY DE-WATERING ACTIVITIES ARE TO BE CLOSELY MONITORED TO ENSURE THAT WATER IS NOT POLLUTED BY SEDIMENT, TOXIC MATERIALS OR PETROLEUM PRODUCTS.
- 28. PROVIDE DESIGNATED VEHICULAR WASHDOWN AND MAINTENANCE AREAS WHICH ARE TO HAVE CONTAINMENT BUNDS.

RAY	

Architect

HYDRA@OR CONSULTING ENGINEERS

HYDRACOR Consulting Engineers Pty Ltd Platinum Building, Suite 2.01, 4 Ilya Avenue ERINA NSW 2250, Australia T +61 2 4324 3499

ENGINEERS | CIVIL | FLOOD STUDIES | STORMWATER | HYDRAULIC

PROCEDURE FOR DE-WATERING

ENSURE PERMISSION FOR DE-WATERING IS RECEIVED FROM AUTHORITIES BEFORE PUMPING OUT.

2. AN ON-SITE TREATMENT PROCESS DISCHARGING TO THE STORMWATER SYSTEM WILL BE IMPLEMENTED. ALL SITE WATERS DURING CONSTRUCTION WILL BE CONTAINED ON SITE AND RELEASED ONLY WHEN pH IS BETWEEN 8.5 & 6.5, SUSPENDED SOLIDS ARE LESS THAN 50mg/L, TURBIDITY LESS THAN 100 NTU'S, OIL AND GREASE LESS THAN 10mg/L AND BIOCHEMICAL OXYGEN DEMAND (BOD5) LESS

THAN 30mg/L (FOR STORMS LESS INTENSE THAN 1 IN 5 YEAR EVENTS). 3. METHODS OF SAMPLING AND ANALYSIS OF WATER QUALITY WILL BE IN ACCORDANCE WITH THE APPLICABLE METHOD LISTED IN THE EPA PUBLISHED APPROVED METHODS FOR THE SAMPLING ANALYSIS OF WATER POLLUTANTS IN NEW SOUTH WALES.


4. WHERE LABORATORY ANALYSIS IS REQUIRED AS INDICATED BY IN-SITU TESTING, APPROPRIATE SAMPLE BOTTLES AND PRESERVATIVES WILL BE USED AND GUIDANCE FOR THE SAMPLING METHOD OBTAINED FROM APPLICABLE PARTS OF AS5667.1 AND AS5667.6. ANALYSIS WILL BE UNDERTAKEN WHERE PRACTICAL BY A NATA REGISTERED LABORATORY CERTIFIED TO PERFORM THE APPLICABLE ANALYSIS.


5. A FURTHER INSPECTION WILL BE CARRIED OUT DURING A STORM EVENT (DURING WORK HOURS WHERE POSSIBLE) TO ENSURE CONTROLS ARE COPING WITH THE EVENT. THIS APPLIES TO ANY RAIN EVENT AS WELL.


6. AS EXCAVATION TO TOP SOIL PROGRESSES, ANY WATER COLLECTED AT THE BOTTOM OF EXCAVATIONS WILL BE DIVERTED TO A TEMPORARY SEDIMENTATION BASIN OR SETTLEMENT TANK. IF THE WATER CONTAINS ONLY SEDIMENTS, IT WILL BE FILTERED AND PUMPED TO STORMWATER. BEFORE THIS CAN HAPPEN IT MUST CONTAIN LESS THAN 50mg/L TOTAL SUSPENDED SOLIDS


7. POLLUTED WATER MUST NOT ENTER THE STORMWATER SYSTEM. IN SOME CIRCUMSTANCES, A LIQUID WASTE COMPANY MAY BE REQUIRED TO COLLECT CONTAMINATED WATER FOR DISPOSAL AT A LICENSED TREATMENT FACILITY

SIDENTIAL		ON & SEI			
	Drawn	Date	Scale A1	Q.A. Check	Date
OREST ROAD	RH	NOV 2024	AS NOTED	-	-
	Designed	Project No.		Dwg. No.	Issue
	BK	CC230	124	SW16	G









1.5m STAR PICKETS AT

SELF-SUPPORTING


GEOTEXTILE


MAX 3m CENTRES


SOURCE: MANAGING URBAN STORMWATER

SOILS AND CONSTRUCTION

THIRD EDITION, AUGUST 1998







STOCKPILES

SD 4-1

AY	

Architect

HYDRAGOR CONSULTING ENGINEERS

HYDRACOR Consulting Engineers Pty Ltd Platinum Building, Suite 2.01, 4 Ilya Avenue ERINA NSW 2250, Australia T +61 2 4324 3499 Heroject PROPOSED RE DEVELOPMENT No.116 - 120 FRENCHS FO No.11 GLADYS AVENUE

FRENCHS FOREST

ENGINEERS | CIVIL | FLOOD STUDIES | STORMWATER | HYDRAULIC

SIDENTIAL		ON & SEI . SHEET	DIMENT	CONTROI	
	Drawn	Date	Scale A1	Q.A. Check	Date
DREST ROAD	RH	NOV 2024	AS NOTED	-	-
	Designed	Project No.		Dwg. No.	Issue
	BK	CC230	124	SW18	G

Appendix 16 – On-site Detention Checklist

This checklist is to be used to determine the on-site stormwater disposal requ must be completed and included with the submission of any development ap Please read this form carefully for its notes, guidelines, definition and relevan

For assistance and support, please contact Council's Development Engineer 1300 434 434.

Part 1 Location of the Property

House Humber 116-1	20 & 11	Legal Property Description	on
Street	CHS FOREST ROAD GLADYS AVENUE	Lot	LC
Suburb FREN	CHS FOREST	Section	
Postcode 2086		DP	25

Part 2 Site Details

Northern Beaches Stormwater Regions (refer to Map 2 of Northern Beaches Council's Water Management for Development policy)	2	Total Site Area
Pre-Development Impervious Area	1825m²	Post-Development Impervious Area

Is the site of the development located within an established Flood Prone La referred to Council's Local Environmental Plans?

If yes, On-site stormwater Detention system (OSD) is not required and pleas to part 5 of this checklist

If no, please proceed to part 3 of this checklist.

Part 3: Northern Beaches Stormwater Regions

(refer to Map 2 of Northern Beaches Council's Water Management for Deve

If the site of the development located within Region 1, please proceed to the

If the site of the development located within Region 2, please proceed to the

If the site of the development located within Region 3, please proceed to the

If the site of the development located within Region 4, please refer to Counc Management Specification.

Version 2 | 26 February 2021 | Water Management for Development Policy |

\sim	GHT of this design and plan is the property of HYDRACOR Consulting Engineers Pty Ltd, ACN 127 012 104 ATF H s reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission f			-		991 647,				
G F E	RE-ISSUED FOR DEVELOPMENT APPROVAL RE-ISSUED FOR DEVELOPMENT APPROVAL SSUED TO SUIT NEW ARCHITECTURALS	23.04.25 23.04.25 25.02.25	IK IK LW	BK BK BK	North	BREWSTER MURRAY	Architect	HYDR∧©OR	HYDRACOR Consulting Engineers Pty Ltd Platinum Building, Suite 2.01, 4 Ilya Avenue ERINA NSW 2250, Australia T +61 2 4324 3499	Project PROPOSED RES DEVELOPMENT
D Iss -1	 RE-ISSUED IN RESPONSE TO COUNCIL RFI Description	04.02.25 Date	IK Drawn	BK Approved	-			CONSULTING ENGINEERS	ENGINEERS CIVIL FLOOD STUDIES STORMWATER HYDRAULIC	No.116 - 120 FRENCHS FOR No.11 GLADYS AVENUE FRENCHS FOREST

	norther beacher council			
	developments and these works.		Part 4 Determinati	on of OSD Requirements
ng and Certi	ification team on		Part 4.1 Northern Be	eaches Stormwater Region 1
			Is the additional impe cumulative basis sinc	rvious area of the development more than 50
ription	24, 2, 1, 14		If yes, OSD is require Policy	ed and please refer to section 9.3.1 of Counc uired and please proceed to the part 5 of this
			Part 4.2 Northern Be	eaches Stormwater Region 2
2571	3 & 213608		Part 4.2.1 Descriptio	-
			Residential flat buildir resulting in the creation accordance with the s	ng, commercial, industrial, multiple occupand on of three lots or more, will require OSD in a section 9.3.2 of Council's Water Managemen building development, please proceed to pa
			Part 4.2.2 Exemption	n
	5740m²		Is the site area less th	nan 450m²?
pervious	3354m²			evelopment drain directly to the ocean witho inage control structure such as pipe, bridge, drainage system?
d as	Yes 🗆 No 🗆		Is it an alternation and	d addition development to the existing dwelli
e proceed				oove questions, OSD is not required. questions, proceed to part 4.2.3
			Part 4.2.3 Determina	ation of OSD Requirements
			Calculation	 a) Site area m² x 0.40 (40%) = b) Post- development impervious area = OSD will not be required when (a) is greater than the second second
opment poli	icy)			Is OSD required for this development (tic
part 4.1 of t	this checklist			If yes, provide a design in accordance with Management for Development Policy. If no, OSD is not required and please proc
part 4.2 of t	this checklist			
part 4.3 of t	this checklist			
il's Warriewo	ood Valley Water			
2021/15436	68)	Version 2 26 Febru	ary 2021 Vater Management for Developmen

	E Ster	northern beaches
	Core of	council
ents		
ion 1		
pment more than 50 m ² on a	Yes 🗆 No 🗆	
tion 9.3.1 of Council's Water Man	agement for Deve	lopment
to the part 5 of this checklist		
ian 0		
ion 2		
, multiple occupancy developmen vill require OSD in all case. Please Water Management for Developm ease proceed to part 4.2.2 of this	e provide a desigr nent Policy.	
	Yes 🗆 No 🗹	/
to the ocean without the need the as pipe, bridge, culvert, kerb	Yes 🗆 No 🗹	/
the existing dwellings?	Yes 🗆 No 🗹	/
ot required. t 4.2.3		
nts		
40%) =	. m² . m²	
red when (a) is greater than (b) s development (tick one only)	Yes 🗹 No 🗆]
in accordance with the section 9. opment Policy. ed and please proceed to part 5 c		Vater
ment for Development Policy 20	21/154368 Pag	ge 91 of 100
Project		Title
PROPOSED RESIDENTIAL	Drawing	


SIDENTIAL	ON-SITE DETENTION CHECKLIST					
	Drawn	Date	Scale A1	Q.A. Check	Date	
DREST ROAD	RH	NOV 2024	AS NOTED	-	-	
	Designed	Project No.		Dwg. No.	Issue	
	BK	CC230	124	SW19	G	

						Client
G	RE-ISSUED FOR DEVELOPMENT APPROVAL	23.04.25	IK	BK	North	
F	RE-ISSUED FOR DEVELOPMENT APPROVAL	23.04.25	IK	BK		
Е	ISSUED TO SUIT NEW ARCHITECTURALS	25.02.25	LW	BK		ARCHITECTS
D	RE-ISSUED IN RESPONSE TO COUNCIL RFI	04.02.25	IK	BK		
Issue	Description	Date	Drawn	Approved		
-1 0	1cm at full size			-		

© COPYRIGHT of this design and plan is the property of HYDRACOR Consulting Engineers Pty Ltd, ACN 127 012 104 ATF HYDRACOR Unit Trust trading as HYDRACOR ABN 81 392 991 647, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from HYDRACOR Consulting Engineers Pty Ltd.

VERTICAL SCALE 1:50/A1, 1:100/A3 HORIZONTAL SCALE 1:50/A1, 1:100/A3

	GRATED INLET	GAS
		0
FLOW RATE (L/s)		
PIPE DIAMETER SLOPE		
Datum El. 145		
HGL	151.716	
EXISTING SURFACE	152.700	
INVERT LEVEL	151.200	
CHAINAGE	0	



DRAINAGE LONG SECTION FROM PIT P1 TO PIT EX1

SCALE - 1:50/A1, 1:100/A3

0 0.5 1 2 5m 4



HYDRAGOR CONSULTING ENGINEERS

Project HYDRACOR Consulting Engineers Pty Ltd PROPOSED RES Platinum Building, Suite 2.01, 4 Ilya Avenue ERINA NSW 2250, Australia DEVELOPMENT T +61 2 4324 3499 No.116 - 120 FRENCHS FOR No.11 GLADYS AVENUE

FRENCHS FOREST

ENGINEERS | CIVIL | FLOOD STUDIES | STORMWATER | HYDRAULIC

SIDENTIAL	Drawing Title DRAINAGE LONG SECTION							
	Drawn	Date	Scale A1	Q.A. Check	Date			
OREST ROAD	RH	NOV 2024	AS NOTED	-	-			
	Designed	Project No.		Dwg. No.	Issue			
	ВК	CC230124		SW20	G			