

## Natural Environment Referral Response - Coastal

<b>Application Number:</b>	DA2024/1737
<b>Proposed Development:</b>	Alterations and additions to a dwelling house including a swimming pool
<b>Date:</b>	03/02/2025
<b>Responsible Officer</b>	Anne-Marie Young
<b>Land to be developed (Address):</b>	Lot 10 DP 228119 , 292 Hudson Parade CLAREVILLE NSW 2107

### Reasons for referral

This application seeks consent for land located within the Coastal Zone.

And as such, Council's Natural Environment Unit officers are required to consider the likely impacts on drainage regimes.

### Officer comments

The applicant seeks development consent to undertake the following:

- Construction of a swimming pool and minor alterations to landscaping

This application was assessed in consideration of:

- Supplied plans and reports;
- Coastal Management Act (2016)
- State Environmental Planning Policy (Resilience and Hazards) 2021 (section 2.10, 2.11 & 2.12);
- Relevant LEP and DCP clauses.

Comment: SUPPORTED WITH CONDITIONS

State Environmental Planning Policy (Resilience & Hazards) 2021

The subject land has been included on the 'Coastal Environmental Area' and 'Coastal Use Area' maps under the State Environmental Planning Policy (Resilience & Hazards) 2021 (SEPP R & H). Hence, Clauses 2.10, 2.11 and 2.12 of the CM (R & H) apply for this DA.

Comment:

On internal assessment, the DA satisfies requirements under clause 2.10, 2.11 & 2.12 of the SEPP R&H. As such, it is considered that the application does comply with the requirements of the State Environmental Planning Policy (Resilience & Hazards) 2021.

Pittwater LEP 2014 and Pittwater 21 DCP

No other coastal related issues identified.

As such, it is considered that the application does comply with the requirements of the coastal relevant

clauses of the Pittwater LEP 2014 and Pittwater 21 DCP

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

#### **Recommended Natural Environment Conditions:**

### **CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE**

#### **Erosion and Sediment Control Plan**

An Erosion and Sediment Control Plan (ESCP) shall be prepared by an appropriately qualified person and implemented onsite prior to commencement. The ESCP must meet the requirements outlined in the Landcom publication *Managing Urban Stormwater: Soils and Construction - Volume 1, 4th Edition* (2004). The ESCP must include the following as a minimum:

- Site Boundaries and contours
- Approximate location of trees and other vegetation, showing items for removal or retention (consistent with any other plans attached to the application)
- Location of site access, proposed roads and other impervious areas (e.g. parking areas and site facilities);
- Existing and proposed drainage patterns with stormwater discharge points
- Locations and methods of all erosion and sediment controls;
- North point and scale.

Details demonstrating compliance are to be submitted to the Certifier for approval prior to the issue of the Construction Certificate.

Reason: To protect the environment from the effects of sedimentation and erosion from development sites.

### **CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT**

#### **Installation and Maintenance of Sediment and Erosion Control**

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004). Techniques used for erosion and sediment control on site are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and the site is sufficiently stabilised with vegetation.

Reason: To protect the surrounding environment from the effects of sedimentation and erosion from

the site

## CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

### **Stockpiling materials**

During construction, all material associated with works is to be contained at source, covered and must be within the construction area. All material is to be removed off site and disposed of according to local regulations. The property is to be kept clean and any building debris removed as frequently as required to ensure no debris enters receiving waters.

Reason: To ensure pollution control measures are effective to protect the aquatic habitats within receiving waters throughout the construction period.