

Landscape Referral Response

Application Number:	DA2022/1968
Date:	05/12/2022
Responsible Officer:	Kye Miles
	Lot 23 DP 863357 , 26 Carnarvon Drive FRENCHS FOREST NSW 2086

Reasons for referral

This application seeks consent for the following:

- Construction / development works within 5 metres of a tree or
- New residential works with three or more dwellings. (RFB's, townhouses, seniors living, guesthouses, etc). or
- Mixed use developments containing three or more residential dwellings.
- New Dwellings or

Officer comments

The proposal is supported with regard to landscape issues.

The application is assessed by Landscape Referral against Warringah Local Environmental Plan 2011 and the following Warringah Development Control Plan 2011 controls (but not limited to):

- D1 Landscaped Open Space and Bushland Setting
- E1 Preservation of Trees or Bushland Vegetation

All trees and vegetation shown to be retained shall be protected as per the requirements outlined in the conditions of consent. One tree is proposed to be removed which is an exotic species and as such no concern is raised for its removal. A slight non-compliance with the landscape open space will be a result of the proposed works, and this matter shall be assessed and determined on merit consideration by the Assessing Planning Officer. Landscape Referral does not raise concerns with the slight landscape open space non-compliance.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

Recommended Landscape Conditions:

CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

Tree Removal Within the Property

This consent approves the removal of the following tree within the property:

i) the Magnolia species adjacent to the proposed pool on the eastern boundary, as shown for removal on drawing D.A.1-1 by Rolling Stones Landscapes dated 17/10/22,

ii) a qualified AQF level 5 Arborist shall identify these trees on site and tag or mark prior to removal.



Reason: To enable authorised development works.

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

Protection of Existing Street Trees

All existing street trees in the vicinity of the works shall be retained during all construction stages, and the street tree fronting the development site shall be protected by tree protection fencing in accordance with Section 4 of Australian Standard 4970-2009 Protection of Trees on Development Sites.

All street trees within the road verge are protected under Northern Beaches Council development control plans, except where Council's written consent for removal has been obtained. The felling, lopping, topping, ringbarking, or removal of any tree(s) is prohibited.

No excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of street trees.

Should any problems arise with regard to the existing or proposed trees on public land during construction, Council's Tree Services section is to be contacted immediately to resolve the matter to Council's satisfaction and at the cost of the applicant.

Reason: Street tree protection.

Tree and Vegetation Protection

a) Existing trees and vegetation shall be retained and protected, including:

i) all trees and vegetation within the site, excluding exempt trees and vegetation under the relevant planning instruments of legislation,

ii) all trees and vegetation located on adjoining properties,

iii) all road reserve trees and vegetation.

b) Tree protection shall be undertaken as follows:

i) tree protection shall be in accordance with Australian Standard 4970-2009 Protection of Trees on Development Sites, including the provision of temporary fencing to protect existing trees within 5 metres of development,

ii) existing ground levels shall be maintained within the tree protection zone of trees to be retained, unless authorised by an Arborist with minimum AQF Level 5 in arboriculture,

iii) removal of existing tree roots at or >25mm (\emptyset) diameter is not permitted without consultation with an Arborist with minimum AQF Level 5 in arboriculture,

iv) no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,

v) structures are to bridge tree roots at or >25mm (\emptyset) diameter unless directed by an Arborist with minimum AQF Level 5 in arboriculture on site,

vi) excavation for stormwater lines and all other utility services is not permitted within the tree protection zone, without consultation with an Arborist with minimum AQF Level 5 in arboriculture including advice on root protection measures,

vii) should either or all of v) or vi) occur during site establishment and construction works, an Arborist with minimum AQF Level 5 in arboriculture shall provide recommendations for tree protection measures. Details including photographic evidence of works undertaken shall be submitted by the Arborist to the Principal Certifier,

viii) any temporary access to, or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of Australian Standard 4970-2009 Protection of Trees on Development Sites,



ix) tree pruning from within the site to enable approved works shall not exceed 10% of any tree canopy, and shall be in accordance with Australian Standard 4373-2007 Pruning of Amenity Trees, and should additional pruning be required an application to Council's Tree Services shall be submitted for approval or otherwise.

The Principal Certifier must ensure that:

c) The activities listed in section 4.2 of Australian Standard 4970-2009 Protection of Trees on Development Sites, do not occur within the tree protection zone of any tree, and any temporary access to, or location of scaffolding within the tree protection zone of a protected tree, or any other tree to be retained on the site during the construction, is undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of that standard.

Reason: Tree and vegetation protection.