# PROPOSED CLUB REFURBISHEMENT 932 PITTWATER ROAD, DEE WHY NSW 2099 **CIVIL ENGINEERING PLANS**

# **GENERAL NOTES**

LOCAL AUTHORITIES

- THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL ARCHITECTURAL AND OTHER CONSULTANTS DRAWINGS AND SPECIFICATIONS AND WITH SUCH OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED.
- ALL DIMENSIONS RELEVANT TO SETTING OUT AND OFF-SITE WORK SHALL BE VERIFIED BY THE CONTRACTOR BEFORE CONSTRUCTION
- 3. DIMENSIONS SHALL NOT BE OBTAINED BY SCALING THE DRAWINGS.
- ALL DIMENSIONS ON DETAILS ARE IN MILLIMETRES UNLESS STATED OTHERWISE. ALL PLANS AND LEVELS ARE EXPRESSED IN METRES.
- 5. DURING CONSTRUCTION THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE STRUCTURAL STABILITY OF THE WORKS AND ENSURE NO PARTS BE OVER STRESSED UNDER CONSTRUCTION ACTIVITIES.
- WORKMANSHIP AND MATERIALS ARE TO BE IN ACCORDANCE WITH THE RELEVANT CURRENT S.A.A. CODES INCLUDING ALL AMENDMENTS, AND THE LOCAL STATUTORY AUTHORITIES, EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.
- THE APPROVAL OF A SUBSTITUTION SHALL BE SOUGHT FROM THE ENGINEER BUT IS NOT AN AUTHORISATION FOR A VARIATION, ANY VARIATIONS INVOLVED MUST BE TAKEN UP WITH THE ARCHITECT OR PROJECT MANAGER BEFORE THE WORK COMMENCES.
- ANY DISCREPANCIES OR OMISSIONS SHALL BE REFERRED TO THE ENGINEER FOR A DECISION BEFORE PROCEEDING WITH THE WORK.
- 9. THE BUILDER SHALL GIVE 48 HOURS NOTICE FOR ALL ENGINEERING INSPECTIONS.
- 10. BUILDING FROM THESE DRAWINGS IS NOT TO COMMENCE UNTIL APPROVED BY THE
- 11. THE WORD 'ENGINEER' USED IN THESE NOTES REFER TO AN EMPLOYEE OR NOMINATED REPRESENTATIVE OF ACOR CONSULTANTS PTY.LTD.

# EXISTING SERVICES AND FEATURES

- THE CONTRACTOR SHALL ALLOW FOR THE CAPPING OFF, EXCAVATION, REMOVAL AND DISPOSAL IF REQUIRED OF ALL EXISTING SERVICES IN AREAS AFFECTED BY WORKS WITHIN THE CONTRACT AREA, AS SHOWN ON THE DRAWINGS UNLESS DIRECTED OTHERWISE BY THE SUPERINTENDENT.
- 2. THE CONTRACTOR SHALL ENSURE THAT AT ALL TIMES SERVICES TO ALL BUILDINGS NOT AFFECTED BY THE WORKS ARE NOT DISRUPTED.
- PRIOR TO COMMENCEMENT OF ANY WORKS THE CONTRACTOR SHALL GAIN WRITTEN APPROVAL OF HIS PROGRAMME FOR THE RELOCATION/CONSTRUCTION OF TEMPORARY SERVICES.
- 4. EXISTING BUILDINGS, EXTERNAL STRUCTURES, AND TREES SHOWN ON THESE DRAWINGS ARE FEATURES EXISTING PRIOR TO ANY DEMOLITION WORKS.
- 5. CONTRACTOR SHALL CONSTRUCT TEMPORARY SERVICES TO MAINTAIN EXISTING SUPPLY TO BUILDINGS REMAINING IN OPERATION DURING WORKS TO THE SATISFACTION AND APPROVAL OF THE SUPERINTENDENT. ONCE DIVERSION IS IS COMPLETE AND COMMISSIONED THE CONTRACTOR SHALL REMOVE ALL SUCH TEMPORARY SERVICES AND MAKE GOOD TO THE SATISFACTION OF THE SUPERINTENDENT.
- 6. INTERRUPTION TO SUPPLY OF EXISTING SERVICES SHALL BE DONE SO AS NOT TO CAUSE ANY INCONVENIENCE TO THE PRINCIPAL. CONTRACTOR TO GAIN APPROVAL OF SUPERINTENDENT FOR TIME OF INTERRUPTION.

# STORMWATER NOTES

- 1. ALL DRAINAGE PIPES LARGER THAN Ø375 SHALL BE CLASS "2" APPROVED SPIGOT AND SOCKET FRC PIPES WITH RUBBER RING JOINTS. (U.N.O.) ALL DOWNPIPE DRAINAGE LINES SHALL BE SEWER GRADE uPVC WITH SOLVENT WELD JOINTS. (U.N.O.)
- 2. EQUIVALENT STRENGTH REINFORCED CONCRETE PIPES MAY BE USED.
- 3. ALL PIPE JUNCTIONS UP TO AND INCLUDING 450 DIA. AND TAPERS SHALL BE VIA PURPOSE MADE FITTINGS.
- 4. MINIMUM GRADE TO STORMWATER LINES TO BE 1%. (U.N.O.)
- 5. CONTRACTOR TO SUPPLY AND INSTALL ALL FITTINGS AND SPECIALS INCLUDING VARIOUS PIPE ADAPTORS TO ENSURE PROPER CONNECTION BETWEEN DISSIMILAR PIPEWORK.
- 6. ALL CONNECTIONS TO EXISTING DRAINAGE PITS SHALL BE MADE IN A TRADESMAN-LIKE MANNER AND THE INTERNAL WALL OF THE PIT AT THE POINT OF ENTRY SHALL BE CEMENT RENDERED TO ENSURE A SMOOTH FINISH.
- PRECAST PITS SHALL NOT BE USED UNLESS WRITTEN APPROVAL IS OBTAINED FROM THE SUPERINTENDENT.
- WHERE TRENCHES ARE IN ROCK, THE PIPE SHALL BE BEDDED ON A MIN. 50MM CONCRETE BED (OR 75MM THICK BED OF 12MM BLUE METAL) UNDER THE BARREL OF THE PIPE. THE PIPE COLLAR AT NO POINT SHALL BEAR ON THE ROCK. IN OTHER THAN ROCK, PIPES SHALL BE LAID ON A 75MM THICK SAND BED. IN ALL CASES BACKFILL THE TRENCH WITH SAND TO 200MM ABOVE THE PIPE. WHERE THE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH WITH SAND OR APPROVED GRANULAR BACKFILL COMPACTED IN 150MM LAYERS TO 98% STANDARD MAX, DRY DENSITY,
- 9. BEDDING SHALL BE (U.N.O.) TYPE H1, IN ACCORDANCE WITH CURRENT RELEVANT AUSTRALIAN STANDARDS.
- 10. PROVIDE 3.0M LENGTH OF 100 DIA. SUBSOIL DRAINAGE PIPE WRAPPED IN FABRIC SOCK, AT UPSTREAM END OF EACH PIT

COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

### This drawing has been assigned an electronic code that signifies the drawing has been checked and approved by: ISSUE FOR TENDER North 20.06.17 DW MB Е D ISSUE FOR COORDINATION 15.06.17 DW MB ISSUE FOR DEVELOPMENT APPLICATION 20.03.17 DW MB ISSUE FOR DEVELOPMENT APPLICATION 16.03.17 DW MB В Date Drawn Approved Issue Description

## SITEWORKS NOTES

- 1. ORIGIN OF LEVELS :- AUSTRALIAN HEIGHT DATUM (A.H.D.)
- CONTRACTOR MUST VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO COMMENCEMENT OF WORK.
- ALL WORK IS TO BE UNDERTAKEN IN ACCORDANCE WITH THE DETAILS SHOWN ON THE DRAWINGS, THE SPECIFICATIONS AND THE DIRECTIONS OF THE PRINCIPAL'S REPRESENTATIVE.
- EXISTING SERVICES HAVE BEEN PLOTTED FROM SUPPLIED DATA AND AS SUCH THEIR ACCURACY CANNOT BE GUARANTEED. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH THE LOCATION AND LEVEL OF ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF ANY WORK. ANY DISCREPANCIES SHALL BE REPORTED TO THE PRINCIPAL'S REPRESENTATIVE. CLEARANCES SHALL BE OBTAINED FROM THE RELEVANT SERVICE AUTHORITY.
- WHERE NEW WORKS ABUT EXISTING THE CONTRACTOR SHALL ENSURE THAT A SMOOTH EVEN PROFILE, FREE FROM ABRUPT CHANGES IS OBTAINED.
- 6. THE CONTRACTOR SHALL ARRANGE ALL SURVEY SETOUT TO BE CARRIED OUT BY A REGISTERED SURVEYOR.
- CARE IS TO BE TAKEN WHEN EXCAVATING NEAR EXISTING SERVICES. NO MECHANICAL EXCAVATIONS ARE TO BE UNDERTAKEN OVER COMMUNICATIONS OR ELECTRICAL SERVICES. HAND EXCAVATE IN THESE AREAS.
- ALL SERVICE TRENCHES UNDER VEHICULAR PAVEMENTS SHALL BE BACKFILLED WITH AN APPROVED NON-NATURAL GRANULAR MATERIAL AND COMPACTED TO 98% STANDARD MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS.1289.5.1.1.
- ALL TRENCH BACKFILL MATERIAL SHALL BE COMPACTED TO THE SAME DENSITY AS THE ADJACENT MATERIAL.
- 10. ON COMPLETION OF PIPE INSTALLATION ALL DISTURBED AREAS MUST BE RESTORED TO ORIGINAL, INCLUDING KERBS, FOOTPATHS, CONCRETE AREAS, GRAVEL AND GRASSED AREAS AND ROAD PAVEMENTS.
- 11. PROVIDE 12mm WIDE EXPANDING CORK JOINTS BETWEEN CONCRETE PAVEMENTS AND ALL BUILDINGS, WALLS, FOOTINGS, COLUMNS, KERBS, DISH DRAINS, GRATED DRAINS, BOLLARD FOOTINGS ETC
- 12. CONTRACTOR TO OBTAIN ALL AUTHORITY APPROVALS.
- 13. ALL BATTERS TO BE GRASSED LINED WITH MINIMUM 100 TOPSOIL AND APPROVED COUCH LAID AS TURF.
- 14. MAKE SMOOTH TRANSITION TO EXISTING SERVICES AND MAKE GOOD.
- 15. THE CONTRACTOR SHALL PROVIDE ALL TEMPORARY DIVERSION DRAINS AND MOUNDS TO ENSURE THAT AT ALL TIMES EXPOSED SURFACES ARE FREE DRAINING AND WHERE NECESSARY EXCAVATE SUMPS AND PROVIDE PUMPING EQUIPMENT TO DRAIN EXPOSED ARFAS
- 16. THESE PLANS SHALL BE READ IN CONJUNCTION WITH APPROVED ARCHITECTURAL, STRUCTURAL, HYDRAULIC AND MECHANICAL DRAWINGS AND SPECIFICATIONS.
- 17. TRENCHES THROUGH EXISTING ROAD AND CONCRETE PAVEMENTS SHALL BE SAWCUT TO FULL DEPTH OF CONCRETE AND A MIN 50mm IN BITUMINOUS PAVING.
- 18. ALL BRANCH GAS AND WATER SERVICES UNDER DRIVEWAYS AND BRICK PAVING SHALL BE LOCATED IN Ø80 uPVC SEWER GRADE CONDUITS EXTENDING A MIN OF 500mm PAST PAVING
- 19. ON COMPLETION OF WORKS ALL DISTURBED AREAS MUST BE RESTORED TO ORIGINAL INCLUDING, BUT NOT LIMITED TO, KERBS, FOOTPATHS, CONCRETE AREAS, GRASS AND LANDSCAPED AREAS.

# DEE WHY RSL CLUB

9321 PITTWATER ROAD DEE WHY NSW 2099

# **EROSION AND SEDIMENT CONTROL NOTES**

### GENERAL INSTRUCTIONS

- E1. THIS PLAN IS TO BE READ IN CONJUNCTION WITH THE ENGINEERING PLANS, AND ANY OTHER PLANS OR WRITTEN INSTRUCTIONS THAT MAY BE ISSUED AND RELATING TO DEVELOPMENT AT THE SUBJECT SITE.
- E2. THE SITE SUPERINTENDENT WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE LOCATED AS INSTRUCTED IN THIS SPECIFICATION.
- E3. ALL BUILDERS AND SUB-CONTRACTORS WILL BE INFORMED OF THEIR RESPONSIBILITIES IN MINIMISING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS.

### CONSTRUCTION SEQUENCE

- E4. THE SOIL EROSION POTENTIAL ON THIS SITE SHALL BE MINIMISED. HENCE WORKS SHALL BE UNDERTAKEN IN THE FOLLOWING SEQUENCE
- INSTALL SEDIMENT FENCES, TEMPORARY CONSTRUCTION EXIT AND SANDBAG KERB INLET а
- SEDIMENT TRAP UNDERTAKE SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE

### **EROSION CONTROL**

- E5. DURING WINDY CONDITIONS, LARGE, UNPROTECTED AREAS WILL BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL.
- E6. FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION ACTIVITIES.

### FENCING

- E7. STOCKPILES WILL NOT BE LOCATED WITHIN 2 METRES OF HAZARD AREAS, INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS. WHERE THEY ARE BETWEEN 2 AND 5 METRES FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSLOPE WATERS, E.G. THROUGH INSTALLATION OF SEDIMENT FENCING.
- E8. ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD OVER THE SURFACE) WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.
- E9. WATER WILL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE, I.E. THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AN APPROVED STRUCTURE.
- E10. TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.


### OTHER MATTERS

- E11. ACCEPTABLE RECEPTORS WILL BE PROVIDED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER.
- E12. RECEPTORS FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER ARE TO BE EMPTIED AS NECESSARY. DISPOSAL OF WASTE SHALL BE IN A MANNER APPROVED BY THE SITE SUPERINTENDENT.

### SITE INSPECTION & MAINTENANCE

E13. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSPECTED AFTER RAINFALL EVENTS TO ENSURE THAT THEY OPERATE EFFECTIVELY. REPAIR AND OR MAINTENANCE SHALL BE UNDERTAKEN AS REQUIRED.

ALTIS





architecture SUITE 123/26-32 PIRRAMA ROAD PYRMONT NSW 2009 PHONE : 02 9364 9000

CONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS


ACOR Consultants Pty Ltd Level 1, 24 Falcon Street PROPOSED CLUB REFURBISHMENT Crows Nest NSW 2065 DEE WHY RSL T +61 2 9438 5098

 $\bigcirc$ 932 PITWATER ROAD DEE WHY NSW 2099

NOT FOR CONSTRUCTION	

COVER SHEET, NOTES AND LEGENDS

Drawn	Date	Scale	A1	Q.A. Check		Date	1am
DW	13.04.16	N.T.S		NP	1	0.00.17	7 - 9:01
Designed	Project No.			Dwg. No.		lssue	201
MB	ŚY16	50161		C1.01		Е	Jul 10.




Drawing Title DETAILS SH	EET 1	-		
Drawn	Date	Scale	Δ1	


DW


Designed MB


Date	Scale	A1	Q.A. Check		Date
13.04.16	N.T.S		NP	1	0.03.1
Project No.			Dwg. No.		Issue
SY16	50161		C1.05		Е

TENDER ISSUE












TOTAL SITE AREA =	39 <u>00 m²</u>
DESIGN METHOD =	ILSAX
PRE-DEVELOPED IMPERVIOUS AREA =	<u>0</u> %
POST-DEVELOPED IMPERVIOUS AREA =	<u>90.</u> %
POST DEVELOPED FLOWS (I/s) = PRE DEVELOPED FLOWS (I/s) =	$Q_{5} = .84$ $Q_{20} = .84$ $Q_{100} = .171.$ $Q_{5} = .85$ $Q_{20} = 1.32$ $Q_{100} = .178$
PORTION OF SITE THROUGH OSD SYSTEM =	100.%
REQUIRED STORAGE VOLUME =	7 <u>1.</u> m³
ACTUAL STORAGE VOLUME =	79.5 <sub>.m³</sub>





ACOR Consultants Pty Ltd Level 1, 24 Falcon Street Crows Nest NSW 2065 T +61 2 9438 5098 Project PROPOSED CLUB REFURBISHMENT DEE WHY RSL 




# SURCHARGE PIT EDGE DETAIL

SCALE 1:10


Y160161\Drawings\CIV\Drawings\SY160161_C1.05.dwg
0161
9:01am

Drawing Title ENABLING V DETAIL SHE							P:\SY16\SY1
Drawn	Date	Scale	A1	Q.A. Check		Date	9:01am
DW	13.04.16	N.T.S		NP	1	0.03.17	7 - 9:0
Designed	Project No.			Dwg. No.		Issue	201
MB	SY16	60161		C1.07		A	lul 10,

TENDER ISSUE




Date	Scale	A1	Q.A. Check		Date
13.04.16	1:200		NP	10.	03.17
Project No.			Dwg. No.		lssue
SY16	60161		C2.01		G
	13.04.16 Project No.	13.04.16 1:200	13.04.16 1:200 Project No.	13.04.16         1:200         NP           Project No.         Dwg. No.	13.04.16         1:200         NP         10.           Project No.         Dwg. No.         Dwg. No.



	COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must
I	not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

D	ISSUE FOR REQUEST FOR TENDER	18.07.17	GP	MB	North
С	ISSUE FOR COORDINATION	07.07.17	KR	MB	$  \land  $
В	RE-ISSUE FOR DEVELOPMENT APPLICATION	20.03.17	DW	MB	
А	ISSUE FOR DA	14.03.17	DW	MB	
Issue	Description	Date	Drawn	Approved	
10	1cm at full size			20cm	

DEE WHY RSL CLUB 9321 PITTWATER ROAD DEE WHY NSW 2099



ACOR Consultants Pty Ltd Level 1, 24 Falcon Street Crows Nest NSW 2065 T +61 2 9438 5098




SUITE 123/26-32 PIRRAMA ROAD PYRMONT NSW 2009 PHONE : 02 9364 9000

ALTIS

architecture


		(	NOT FOI	R C(	ONSTRUCTIO	
LUB REFURBISHMENT	Drawing Title SOIL EROSI	ON AND SEDIN	IENT CONT	ROL	PLAN	
	Drawn DW	<sup>Date</sup> 13.04.16	Scale 1:500	A1	Q.A. Check	Date 0.03.17
	Designed MB	Project No. SY1	60161		Dwg. No. C3.01	lssue D

GENERAL INSTRUCTIONS	
E1. THIS PLAN IS TO BE READ IN CONJUNCTION WITH THE ENGINEERING PLANS, AND ANY OTHER PLANS OR WRITTEN INSTRUCTIONS THAT MAY BE ISSUED AND RELATING TO DEVELOPMENT AT THE SUBJECT SITE.	
E2. THE SITE SUPERINTENDENT WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE LOCATED AS INSTRUCTED IN THIS SPECIFICATION.	
E3. ALL BUILDERS AND SUB-CONTRACTORS WILL BE INFORMED OF THEIR RESPONSIBILITIES IN MINIMISING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS.	   GA
CONSTRUCTION SEQUENCE	AC
E4. THE SOIL EROSION POTENTIAL ON THIS SITE SHALL BE MINIMISED. HENCE WORKS SHALL BE UNDERTAKEN IN THE FOLLOWING SEQUENCE :	
<ul> <li>a. INSTALL SEDIMENT FENCES, TEMPORARY CONSTRUCTION EXIT AND SANDBAG KERB INLET SEDIMENT TRAP.</li> <li>b. UNDERTAKE SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.</li> </ul>	
EROSION CONTROL	
E5. DURING WINDY CONDITIONS, LARGE, UNPROTECTED AREAS WILL BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL.	
E6. FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION ACTIVITIES.	
FENCING	
E7. STOCKPILES WILL NOT BE LOCATED WITHIN 2 METRES OF HAZARD AREAS, INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS. WHERE THEY ARE BETWEEN 2 AND 5 METRES FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSLOPE WATERS, E.G. THROUGH INSTALLATION OF SEDIMENT FENCING.	
E8. ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD OVER THE SURFACE) WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.	
E9. WATER WILL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE, I.E. THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AN APPROVED STRUCTURE.	
E10. TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.	
OTHER MATTERS	
E11. ACCEPTABLE RECEPTORS WILL BE PROVIDED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER.	
E12. RECEPTORS FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER ARE TO BE EMPTIED AS NECESSARY. DISPOSAL OF WASTE SHALL BE IN A MANNER APPROVED BY THE SITE SUPERINTENDENT.	
SEDIMENTATION TANK	
E13. SEDIMENT TANK TO BE PROVIDED AND WATER TO BE TREATED IN LINE WITH BLUE BOOK RERQUIREMENTS	
SITE INSPECTION & MAINTENANCE	



COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

This drawing has been assigned an electronic code that signifies the drawing has been checked and approved by:						Client
D	ISSUE FOR REQUEST FOR TENDER	18.07.17	GP	MB	North	DEE WHY RSL
С	ISSUE FOR COORDINATION	07.07.17	KR	MB		
В	RE-ISSUE FOR DEVELOPMENT APPLICATION	20.03.17	DW	MB		
А	ISSUE FOR DA	14.03.17	DW	MB		9321 PITTWATER ROAD
Issue	Description	Date	Drawn	Approved		DEE WHY NSW 2099
-1 0	1cm at full size			20cm		



# IDBAG KERB INLET SEDIMENT TRAP.


### NOTE: ENSURE THAT ALL COUNCIL AND PUBLIC UTILITY ASSETS ARE MAINTAINED AND PROTECTED AT ALL TIMES IN THE VICINITY OF THE TEMPORARY CONSTRUCTION EXIT

GEOTEXTILE FABRIC DESIGNED TO PREVENT INTERMIXING OF SUBGRADE AND BASE MATERIALS AND TO MAINTAIN GOOD PROPERTIES OF THE SUB-BASE LAYERS. GEOTEXTILE MAY BE WOVEN OR NEEDLE PUNCHED PRODUCT WITH A MINIMUM CBR BURST STRENGTH (AS3706.4-90) OF 2500N.

## CONSTRUCTION NOTES


- STRIP TOPSOIL AND LEVEL SITE.
- COMPACT SUBGRADE. COVER AREA WITH NEEDLE-PUNCHED GEOTEXTILE. CONSTRUCT 200MM THICK PAD OVER GEOTEXTILE USING 4
- ROADBASE OR 30MM AGGREGATE. CONSTRUCT HUMP IMMEDIATELY WITHIN BOUNDARY TO DIVERT 5.
- WATER TO A SEDIMENT FENCE OR OTHER SEDIMENT TRAP WHERE THE SEDIMENT IS COLLECTED AND REMOVED.






# NDBAG SEDIMENT TRAP - AT KERB SAG PIT

BETWEEN BAGS ACT PILLWAY




SANDBAG SEDIMENT TRAP - AT OTHER THAN KERB SAG PIT

SANDBAG SEDIMENT TRAP DETAILS NTS



# SEDIMENT CONTROL FENCE



CONSTRUCTION NOTES

- OF THE SITE.
- 2. DRIVE 1.5m LONG STAR PICKETS INTO GROUND, 3 METRES APART. 3. DIG A 150mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM
- OF THE FABRIC TO BE ENTRENCHED. 4. BACKFILL TRENCH OVER BASE OF FABRIC.
- 5. FIX SELF-SUPPORTING GEOTEXTILE TO UPSLOPE SIDE OF POSTS WITH WIRE TIES OR AS RECOMMENDED BY GEOTEXTILE MANUFACTURER.
- 6. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150mm OVERLAP.

# SEDIMENT CONTROL FENCE

NTS

\_ CLUB


architecture SUITE 123/26-32 PIRRAMA ROAD PYRMONT NSW 2009 PHONE : 02 9364 9000

ALTIS



ACOR Consultants Pty Ltd Level 1, 24 Falcon Street Crows Nest NSW 2065 T +61 2 9438 5098 Crows Nest NSW 2065 T +61 2 9438 5098

 $\bigcirc$ 932 PITWATER ROAD DEE WHY NSW 2099



THE EXIT SHALL BE MAINTAINED IN A CONDITION WHICH PREVENTS TRACKING OR FLOWING OF SEDIMENT OFF THE CONSTRUCTION SITE. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL GRAVEL AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED OFF THE CONSTRUCTION SITE MUST BE REMOVED IMMEDIATELY.


# TEMPORARY STABILISED CONSTRUCTION EXIT

1. CONSTRUCT SEDIMENT FENCE AS CLOSE AS POSSIBLE TO PARALLEL TO THE CONTOURS

1	NOT FOR CONOTRUCTION	
	NOT FOR CONSTRUCTION	

### Drawing Title SOIL EROSION AND SEDIMENT CONTROL NOTES AND DETAILS PLAN

Drawn	Date	Scale	A1	Q.A. Check	Date	6:22pm
DW	13.04.16	N.T.S.		NP	10.00.17	7 - 6:2
Designed	Project No.		Dwg. No.		201	
MB	SY160161		C3.02		Jul 18,	



COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

	This drawin	g has been assigned an electronic code that signifies the drawing has been checked and approved by:				
	F	ISSUE FOR SECTION 96	13.03.18	DK	MB	North
	Е	ISSUE FOR SECTION 96	20.11.17	JH	MB	
	D	REISSUE FOR TENDER	10.08.17	GP	MB	
	С	REISSUE FOR TENDER	18.07.17	GP	MB	
Γ	lssue	Description	Date	Drawn	Approved	
-1	0	10m at full size			20cm	

DEE WHY RSL CLUB ALTIS architecture OR 9321 PITTWATER ROAD DEE WHY NSW 2099 SUITE 123/26-32 PIRRAMA ROAD PYRMONT NSW 2009 PHONE : 02 9364 9000 CONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

# NOTES

- 1. STORMWATER ENABLING WORKS PLAN TO BE READ IN CONJUNCTION WITH THE HYDRAULIC ENABLING WORKS PLANS.
- 2. CONTRACTOR TO CONFIRM LOCATION OF ALL EXISTING SERVICES PRIOR TO INSTALLATION OF PROPOSAL SERVICES

ACOR Consultants Pty Ltd Level 1, 24 Falcon Street Crows Nest NSW 2065 T +61 2 9438 5098 Project PROPOSED CLUB REFURBISHMENT DEE WHY RSL

932 PITWATER ROAD DEE WHY NSW 2099

# TENDER ISSUE

### Drawing Title STORMWATER ENABLING WORKS PLAN

Drawn	Date	Scale	A1	Q.A. Check	Date
DW	JUNE 2017	1:200		NP	نون 10.03.17
Designed	Project No.		Dwg. No.	Issue	
MB	SY16	Y160161		C4.01	F