

PRELIMINARY GEOTECHNICAL ASSESSMENT:

20 Molong Street, North Curl Curl

1.0	LANDSLIP RISK CLASS (Highlight indicates Landslip Risk Class of property)
<input type="checkbox"/>	A - Geotechnical Report not normally required
<input checked="" type="checkbox"/>	B - Geotechnical Engineer (Under Council Guidelines) to decide if Geotechnical Report is required
<input type="checkbox"/>	C - Geotechnical Report is required
<input type="checkbox"/>	D - Geotechnical Engineer (Under Council Guidelines) to decide if Geotechnical Report is required
<input type="checkbox"/>	E - Geotechnical Report required

2.0 Proposed Development

- 2.1** Construct a new awning over the existing balcony.
- 2.2** No excavations are required. No significant filling is shown on the plans.
- 2.3** Details of the proposed development are shown on 6 drawings prepared by Alex Bryden Architecture, drawings numbered DA 001, DA 100, DA 102, DA 200, DA 300, and DA 400 dated 25.1.24.

3.0 Site Location

- 3.1** The site was inspected on the 2nd February, 2023.
- 3.2** This residential property is on the high side of a private shared road and has an E aspect. It is located on the gently graded upper-middle reaches of a hillslope. Where sandstone is not exposed, it is expected to underlie the surface at relatively shallow depths. The natural surface of the block has been altered by an excavation for the garage level of the house. The proposed development will not alter the block further.

3.3 The site shows no indications of historical movement in the natural surface that could have occurred since the property was developed. We are aware of no history of instability on the property.

4.0 Site Description

The natural slope rises from Molong Street at gentle angles. At the road frontage, a brick paved driveway runs to a garage under the downhill side of the house. The two-storey house is supported on external rendered masonry walls. The external walls show no significant signs of movement. Access to the foundation space of the house was unavailable at the time of inspection. A pool and pool area extends off the NE side of the house. No significant movement in the shell of the pool was observed as indicated by the level of the water against the tiles. No significant signs of movement associated with slope instability were observed on the grounds. No cliffs or large rock faces were observed on the property or in the near vicinity. No geotechnical hazards that could impact on the subject property were observed on the surrounding neighbouring properties as viewed from the subject property and the street.

5.0 Recommendations

The proposed development and site conditions were considered and applied to the current council requirements. See the required inspection below that is to be carried out during construction and is a requirement for the final geotechnical certification. Apart from the inspection, it is not expected additional geotechnical input will be required provided good design and building practices are followed

6.0 Inspection

The client and builder are to familiarise themselves with the following required inspection as well as council geotechnical policy. We cannot provide geotechnical certification for the owners or the regulating authorities if the following inspection has not been carried out during the construction process.

- Any footings are to be inspected and approved by the geotechnical consultant while the excavation equipment and contractors are still onsite and before steel reinforcing is placed or concrete is poured.

White Geotechnical Group Pty Ltd.



Tyler Jay Johns
BEng (Civil)(Hons),
Geotechnical Engineer.

Reviewed By:



Nathan Gardner B.Sc. (Geol. & Geophys. & Env. Stud.)
AIG., RPGeo Geotechnical & Engineering.
No. 10307
Engineering Geologist & Environmental Scientist.



Information about your Preliminary Assessment

This Preliminary Assessment relies on visual observations of the surface features observed during the site inspection. Where reference is made to subsurface features (e.g., the depth to rock) these are interpretations based on the surface features present and previous experience in the area. No ground testing was conducted as part of this assessment and it is possible subsurface conditions will vary from those interpreted in the assessment.

In some cases, we will recommend no further geotechnical assessment is necessary despite the presence of existing fill or a rock face on the property that exceed the heights that would normally trigger a full geotechnical report, according to the Preliminary Assessment Flow Chart. Where this is the case, if it is an existing fill, it is either supported by a retaining wall that we consider stable, or is battered at a stable angle and situated in a suitable position on the slope. If it is a rock face that exceeds the flow chart limit height, the face has been deemed to be competent rock that is considered stable. These judgements are backed by the inspection of over 5000 properties on Geotechnical related matters.

The proposed excavation heights referred to in section 2.0 of this assessment are estimated by review of the plans we have been given for the job. Although we make every reasonable effort to provide accurate information excavation heights should be checked by the owner or person lodging the DA. If the excavation heights referred to in in section 2.0 of this assessment are incorrect, we are to be informed immediately and before this assessment is lodged with the DA.
