Certificate number: 0002389377-01 Certificate Date: 08 Feb 2018 ★ Star rating: 7.1

BERS Pro v4.3.0.0 (3.13) cannot be used to model 'roof windows'. Roof windows are 'openable or fixed windows in a roof and do not have a shaft, as distinct from skylights which incorporate a built-in shaft and are not ventilated. BERS Pro v4.3 can only model skylights. If a roof window is present on the floor plan

then this certificate is not valid.



Accreditation

number: VIC/BDAV/12/1441

Name: lan Fry

Organisation: Frys Energywise

Email: comply@frysenergywise.com.au

Phone: **02 9899 2825**

Declaration The Assessor has provided design

of interest: advice to the Applicant Software: BERS Pro v4.3.0.2b (3.13)

AAO: BDAV

Overview

Dwelling details

Street: Unit 6.1, 79 Cabbage Tree Road

Suburb: Bayview

Lot/DP

State: NSW Postcode: 2104
Type: New Dwelling NCC Class: 1A

NatHERS

climate zone: 56

number: 20/632081 Exposure: Suburban

Key construction and insulation materials

(see following pages for details)

Construction: Brick Veneer

Plasterboard

Waffle pod slab 175 mm

Insulation: R2.0 wall insulation

No ceiling insulation
No floor insulation

Glazing: BRD-001-01 A ESS Sliding Window

(52mm) SG 3CIr

Net floor area (m²)

Conditioned: 108.0 Unconditioned: 48.0 Garage: 42.0 TOTAL: 156.0


Annual thermal performance loads (MJ/m²)

Heating: 24.5 Cooling: 13.1 TOTAL: 37.6

Plan documents

Plan ref/date: Lot 20, 79 Cabbage Tree Road

Prepared by: IW



Ceiling penetrations

(see following pages for details)

Sealed: 0
Unsealed: 0

TOTAL:**

**NOTE: This total is the maximum number of ceiling penetrations allowed to a ceiling (under a roof) for this certificate. If this number is exceded in construction then this certificate IS NOT VALID and a new certificate is required. Loss of ceiling insulation for the penetrations listed has been taken into account with the rating.

Principle downlight type: Unknown

0

Window selection - default windows only

Note on allowable window values: Only a 5% tolerance to the nominated SHGC window values shown on page 2 can be used with this rating.

Note: Only a +/- 5% SHGC tolerance is allowed with this rating.

NB: This tolerance ONLY applies to SHGC, the U-value can always be lower but not higher than the values stated on page 2.

If any of windows selected are outside the 5% tolerance then this certificate is no longer valid and the dwelling will need to be rerated to confirm compliance.

Scan to access this certificate online and confirm this is valid.



BRD-001-01 A

BRD-033-01 A

Certificate number: **0002389377-01** Certificate Date: **08 Feb 2018**

n/a

n/a

★ Star rating:

Е

S

1800

3600



No Shading

No Shading

Building features

Kitchen/Living

Kitchen/Living

Window type	and performand	e value				
Window ID	Window type				U-value	SHGC
BRD-001-01 A	BRD-001-01 A	SS Sliding Wind	dow (52mm) SG	3Clr	6.4	0.76
BRD-033-01 A	BRD-033-01 A ESS Sliding Door (80mm) SG 4Clr				6.2	0.74
Window sche	dule					
Location	Window ID	Window no.	Height (mm)	Width (mm)	Orientation	Outdoor shade
Bedroom 1	BRD-001-01 A	n/a	2400	2400	S	No Shading
Bedroom 2	BRD-001-01 A	n/a	2400	2400	S	No Shading
Kitchen/Living	BRD-033-01 A	n/a	2400	2100	Е	No Shading

1350

2400

ID	Window type				U-value	SHGC
None Present						
Roof window	and skylight sch	edule				
Location	ID	Roof window/skylight	Area (m²)	Orientation	Outdoor shade	Indoor shade/diffuser

ID	Wall type		Insulation	Insulation		
EW-1	Brick Veneer		No insulation	No insulation		
EW-2	Cavity Brick		No insulation		No	
EW-3	Brick Veneer		Bulk Insulation R2		No	
External wall	schedule					
Location	ID	Width (mm)	Height (mm)	Orientation	Fixed Shade	Eaves (mm)
Garage 1	EW-1	6095	2830	N	No	100
Garage 1	EW-2	6095	2830	S	No	100
Bedroom 1	EW-3	1195	2830	S	No	100
Bedroom 1	EW-3	2600	2831	S	No	1300
Bedroom 1	EW-3	500	2830	S	No	100
Bedroom 1	EW-3	700	2830	W	No	100
Bedroom 2	EW-3	2900	2830	S	No	1300
Bedroom 2	EW-3	295	2831	S	No	100
Laundry	EW-3	2290	2830	N	No	100
Bath	EW-3	2190	2830	N	No	100
Kitchen/Living	EW-3	4795	2830	N	No	100
Kitchen/Living	EW-3	8700	2830	Е	No	100
Kitchen/Living	EW-3	6800	2830	S	No	2300
Kitchen/Living	EW-3	995	2830	W	No	2900
Kitchen/Living	EW-3	4990	2830	N	No	100

^{*} Nationwide House Energy Rating Scheme (NatHERS) is an initiative of the Australian, state and territory governments. For more details see www.nathers.gov.au

Certificate number: 0002389377-01 Certificate Date: 08 Feb 2018

★ Star rating:



Building features continued

Wall type	Area (m²)	Insulation	Wall wrap or foil
IW-1 - Cavity wall, direct fix plasterboard, single gap	20.0	Bulk Insulation, No Air Gap R2	No
IW-2 - Cavity brick, plasterboard	20.0	No Insulation	No
IW-3 - Cavity wall, direct fix plasterboard, single gap	102.0	No insulation	No

Floors					
Location	Construction	Area (m²)	Sub floor ventilation	Added insulation	Covering
Garage 1	Waffle pod slab 175 mm 100mm	42.4	None	Waffle Pod 175mm	Bare
Bedroom 1	Waffle pod slab 175 mm 100mm	15.0	None	Waffle Pod 175mm	Carpet 10mm
Ensuite 1	Waffle pod slab 175 mm 100mm	6.5	None	Waffle Pod 175mm	Ceramic Tiles 8mm
Bedroom 2	Waffle pod slab 175 mm 100mm	14.2	None	Waffle Pod 175mm	Carpet 10mm
Laundry	Waffle pod slab 175 mm 100mm	5.6	None	Waffle Pod 175mm	Ceramic Tiles 8mm
Bath	Waffle pod slab 175 mm 100mm	5.4	None	Waffle Pod 175mm	Ceramic Tiles 8mm
Kitchen/Living	Waffle pod slab 175 mm 100mm	48.9	None	Waffle Pod 175mm	Ceramic Tiles 8mm
Kitchen/Living	Waffle pod slab 175 mm 100mm	17.7	None	Waffle Pod 175mm	Ceramic Tiles 8mm

Location	Construction	Added insulation	Roof space above
Garage 1	Plasterboard	No insulation	No
Bedroom 1	Plasterboard	No insulation	No
Ensuite 1	Plasterboard	No insulation	No
Bedroom 2	Plasterboard	No insulation	No
Laundry	Plasterboard	No insulation	No
Bath	Plasterboard	No insulation	No
Kitchen/Living	Plasterboard	No insulation	No
Kitchen/Living	Plasterboard	No insulation	No

Ceiling penetrations					
Location	Number	Туре	Diameter (mm) Sealed/unsealed		
None Presen	nt				

Ceiling fans

Certificate number: **0002389377-01** Certificate Date:

08 Feb 2018 ★ S





Building features continued

Location	Number	Diameter (mm)
None Present		

Roof type	
Construction	Added Roof colour insulation
None Present	



Additional information	

Explanatory notes

About this report

Residential energy ratings address the quality of the building fabric i.e. walls, windows, floors and roof/ceilings. Ratings do not cover the energy or water efficiency of appliances including heating and cooling, hot water, dishwashers, ovens, fridges, TVs etc. or solar panel or water tank requirements. The efficiency or specification of these items is generally covered by other regulations, standards or guidelines.

General Information

A NatHERS House Energy Rating is a comprehensive, dynamic computer modelling evaluation of the floorplans, elevations and specifications to predict an energy load of a home. Not all of us use our homes in the same way, so ratings are generated using standard assumptions. This means homes can be compared across the country.

The actual energy consumption of your home may vary significantly from the predicted energy load figures in the report depending on issues such as the size of your household and your personal preferences, e.g. in terms of heating or cooling.

While the figures are an indicative guide to energy use, they can be used as a reliable guide for comparative purposes between different house designs and for demonstrating that the design meets the required regulatory compliance.

Homes that are energy efficient use less energy, are warmer in winter, cooler in summer and cost less to run. The higher the star rating the more energy efficient.

This NatHERS House Energy Rating report was carefully prepared by your assessor on the basis of comprehensive modelling using standard procedures to rate your home using the underlying engine developed by the Australian Commonwealth Scientific and Industrial Research Organisation (CSIRO).

All information relating to energy loads presented in this report is based on a range of standard assumptions in order to allow for comparisons with reports prepared for other homes and to demonstrate minimum regulatory compliance.

The standard assumptions include figures for occupancy, indoor air temperature and are based on a unique climate file for your region.

Accredited Assessors

To ensure you get a high-quality, professional NatHERS House Energy Rating report, you should always use an accredited assessor, accredited assessors are members of a professional body called an Assessor Accrediting Organisation (AAO).

AAOs have specific quality assurance processes in place and continuing professional development requirements to maintain a high and consistent standard of assessments across the country. Non-accredited assessors do not have this level of quality assurance or any on-going training requirements.

If you have any questions or concerns about this report, please direct them to your assessor in the first instance.

If your assessor is unable to address your questions or concerns, please contact their AAO listed under 'assessor details'. You can also find a range of information about accredited assessors on the AAO websites.

Disclaimer

The energy values quoted are for comparison purposes only; they are not a prediction of actual energy use. This rating only applies to the floor plan, construction details, orientation and climate as submitted and included in the attached drawing set that bears a stamp with the same number as this certificate. Changes to any of these details could affect the rating.

Contact

For more information on the Nationwide House Energy Rating Scheme (NatHERS), visit www.nathers.gov.au For more information on energy efficient design and insulation visit www.yourhome.gov.au

^{*} Nationwide House Energy Rating Scheme (NatHERS) is an initiative of the Australian, state and territory governments. For more details see www.nathers.gov.au