

Water Management Referral Response

Application Number:	DA2023/0152
Proposed Development:	Construction of a dwelling house on Lot 2
Date:	26/04/2023
To:	Grace Facer
Land to be developed (Address):	Lot C DP 367229 , 6 Orchard Street WARRIEWOOD NSW 2102

Reasons for referral

Council's Water Management Officers are required to consider the likely impacts.

Officer comments

Supported

This application was assessed in consideration of:

- Supplied plans and reports;
- State Environmental Planning Policy (Resilience and Hazards) 2021 (clauses 2.8 and 2.12);
- Northern Beaches Water Management for Development Policy (WM Policy); and
- Relevant LEP and DCP clauses.

NECC Water Management has no objections, subject to conditions.

Rainwater tank volume as per BASIX certificates or more than 3000 litres.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

Recommended Water Management Conditions:

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

Erosion and Sediment Control Plan

An Erosion and Sediment Control Plan (ESCP) shall be prepared by an appropriately qualified person and implemented onsite prior to commencement. The ESCP must meet the requirements outlined in the Landcom publication Managing Urban Stormwater: Soils and Construction - Volume 1, 4th Edition (2004). The ESCP must include the following as a minimum:

- Site Boundaries and contours
- Approximate location of trees and other vegetation, showing items for removal or retention (consistent with any other plans attached to the application)
- Location of site access, proposed roads and other impervious areas (e.g. parking areas and site facilities)
- Existing and proposed drainage patterns with stormwater discharge points
- Locations and methods of all erosion and sediment controls that must include sediment fences,

stabilised site access, materials and waste stockpiles locations, location of any stormwater pits on the site and how they are going to be protected.

- North point and scale.

Details demonstrating compliance are to be submitted to the Certifier for approval prior to the issue of the Construction Certificate.

Reason: Protection of the receiving environment.

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

Installation and Maintenance of Sediment and Erosion Controls

Council proactively regulates construction sites for sediment management.

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) and the Erosion and Sediment Control Plan prior to commencement of any other works on site.

Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and vegetation cover has been re-established across 70 percent of the site, and the remaining areas have been stabilised with ongoing measures such as jute mesh or matting.

Reason: Protection of the receiving environment.

ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

Maintenance of Stormwater Treatment Measures - Minor

Stormwater treatment measures must be maintained at all times in accordance with manufacturer's specifications and as necessary to achieve the required stormwater quality targets for the development.

Northern Beaches Council reserves the right to enter the property and carry out appropriate maintenance of the device at the cost of the property owner.

Reason: Protection of the receiving environment.