

Landscape Referral Response

Application Number:	DA2025/0490
Date:	09/05/2025
Proposed Development:	Alterations and additions to a dwelling house including a swimming pool
Responsible Officer:	
Land to be developed (Address):	Lot 241 DP 16362 , 325 Whale Beach Road PALM BEACH NSW 2108 Lot 242 DP 16362 , 325 Whale Beach Road PALM BEACH NSW 2108

Reasons for referral

This application seeks consent for the following:

- Construction / development works within 5 metres of a tree or
- New residential works with three or more dwellings. (RFB's, townhouses, seniors living, guesthouses, etc). or
- Mixed use developments containing three or more residential dwellings.
- New Dwellings or

Officer comments

The application is for alterations and additions as described in reports and as illustrated on plans. The existing landscape character supports an established setting with existing native trees, gardens and lawn, and is retained in the majority.

The proposed works result in impact to one existing Norfolk Island Pine identified as tree 1 in the submitted Arboricultural Impact Assessment (AIA) report and determines that this tree is unable to be retained should the application be approved and Landscape Referral raise no concerns with the AIA recommendation. Three other existing Norfolk Island Pines (trees 2, 3 and 4) within the property are retained, as are two existing Paperbarks (trees 11 and 12) within the property, and tree protection measures are included in the AIA report. The recommended removal of exempt palm species identified as trees 5 and 6 do not require Council consent for management or removal.

Subject to tree and vegetation protection conditions, Landscape Referral raise no concerns.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

Recommended Landscape Conditions:

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

DA2025/0490 Page 1 of 3



Tree and Vegetation Protection

- a) Existing trees and vegetation shall be retained and protected, including:
- i) all trees within the site not approved for removal,
- ii) all trees and vegetation located on adjoining properties,
- iii) all trees and vegetation within the road reserve.
- b) Tree protection shall be undertaken as follows:
- i) tree protection shall be in accordance with AS4970-2009 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment, and in particular sections 9, 10, 11 and 12,
- ii) existing ground levels shall be maintained within the tree protection zone of trees to be retained, unless authorised by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture,
- iii) removal of existing tree roots at or >25mm (\emptyset) diameter is not permitted without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture,
- iv) no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,
- v) structures are to bridge tree roots at or >25mm (\emptyset) diameter unless directed by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture on site,
- vi) excavation for stormwater lines and all other utility services is not permitted within the tree protection zone, without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture including advice on root protection measures,
- vii) should either or all of v) or vi) occur during site establishment and construction works, an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture shall provide recommendations for tree protection measures. Details including photographic evidence of works undertaken shall be submitted by the Arborist/Project Arborist to the Principal Certifier,
- viii) any temporary access to, or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of AS4970-2009 Protection of trees on development sites,
- ix) the activities listed in section 4.2 of AS4970-2009 Protection of trees on development sites, shall not occur within the tree protection zone of any tree on the lot or any tree on an adjoining site,
- x) tree pruning from within the site to enable approved works shall not exceed 10% of any tree canopy, and shall be in accordance with AS4373-2007 Pruning of amenity trees,
- xi) the tree protection measures specified in this clause must: i) be in place before work commences on the site, and ii) be maintained in good condition during the construction period, and iii) remain in place for the duration of the construction works.

The Principal Certifier must ensure that:

c) The arboricultural works listed in a) and b) are undertaken as complaint to AS4970-2009 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment and/or Project Arborist as applicable.

Reason: Tree and vegetation protection.

CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

Condition of Retained Vegetation

Prior to the issue of an Occupation Certificate, a report prepared by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture shall be submitted to the Principal Certifier, assessing the health and impact on all existing trees required to be retained on the approved Plans or as listed in the

DA2025/0490 Page 2 of 3



approved Arboricultural Impact Assessment, including the following information:

- a) compliance to any Arborist recommendations for tree protection generally and during excavation works,
- b) extent of damage sustained by vegetation as a result of the construction works,
- c) any subsequent remedial works required to ensure the long term retention of the vegetation.

Reason: Tree and vegetation protection.

DA2025/0490 Page 3 of 3