DEVELOPMENT APPLICATION - 10/2018

ARCHITECTURAL DRAWINGS

JUSTIN LONG DESIGN P: 02 9516 5010 E: JUSTIN@JLADESIGN.COM.AU

TITIE PAGE. GENERAL NOTES & SCHEDULE OF EXTERNAL FINISHES

EXISTING GROUND FLOOR PLAN EXISTING FIRST FLOOR PLAN EXISTING SECOND FLOOR PLAN PROPOSED GROUND FLOOR PLAN

PROPOSED FIRST FLOOR PLAN PROPOSED SECOND FLOOR PLAN

PROPOSED ROOF & CONCEPT STORMWATER DRAINAGE PLAN

PROPOSED WESTERN & EASTERN ELEVATIONS PROPOSED NORTHERN ELEVATION

PROPOSED SOUTHERN FLEVATION

PROPOSED LONGITUDINAL SECTION

PROPOSED LONGITUDINAL SECTION PROPOSED SITE & LANDSCAPE PLAN

PROPOSED GROUND FLOOR DEMOLITION & EXCAVATION PLAN PROPOSED FIRST FLOOR DEMOLITION & EXCAVATION PLAN

PROPOSED SECOND FLOOR DEMOLITION & EXCAVATION PLAN PROPOSED SITE ANALYSIS PLAN

PROPOSED EROSION, SEDIMENT CONTROL, WASTE MANAGEMENT & CONSTRUCTION / DEMOLITION PLAN

SHADOW DIAGRAM – WINTER SOLSTICE: 9AM SHADOW DIAGRAM – WINTER SOLSTICE: 12NOON SHADOW DIAGRAM - WINTER SOLSTICE: 3PM

COMPLIANCE NOTES

STANDARD OF WORK & REGULATIONS ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH:

- BUILDING CODE OF AUSTRALIA

AUSTRALIAN STANDARDS CONDITIONS OF COUNCIL

CONDITIONS OF SERVICE SUPPLY **AUTHORITIES**

RELEVANT ALISTRALIAN STANDARDS INCLUDING BUT NOT LIMITED TO THE STANDARDS LISTED BELOW.

DEMOLITION & RECYCLED MATERIAL DEMOLITION IN ACCORDANCE WITH METRO WASTE BOARD GUIDE.

SITE MANAGEMENT

NO BUILDING ACTIVITIES ON COUNCIL

ESTABLISH SEDIMENT CONTROLS AS REQUIRED BY ALL AUTHORITIES.

EARTHWORKS & EXCAVATION ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING:

- BCA PART 3.1.1 - AS 2870

STORMWATER DISPOSAL

ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING:

BCA PART 3.1.2 & BCA PART 352

- AS/NZ 3500.3.2

TERMITE PROTECTION ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING:

BCA PART 3.1.3 - AS 3660.1

FOOTINGS, SLAB DESIGN & RETAINING

ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE ENGINEERS DRAWINGS, SPECIFICATIONS AND THE FOLLOWING:

- BCA PART 3.2

- AS 2870

MASONRY CONSTRUCTION ALL WORK IS TO BE CARRIED OUT IN

ACCORDANCE WITH THE FOLLOWING: - BCA PART 3.3

AS 3700

STRUCTURAL STEEL FRAMING

ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE ENGINEERS DRAWINGS. SPECIFICATIONS AND THE FOLLOWING:

BCA PART 3.4.2 - AS 1250 & AS 3623

TIMBER FRAMING

ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING: BCA PART 3.4.3

AS 1684

ALL TIMBER IS TO BE FROM SUSTAINABLE SOURCES (PLANTATION RECYCLED TIMBERS) AS &:/OR FÓLLOWS:

ALL FRAMING SHOULD BE IN PLANTATION RADIATA PINE OR NZ DOUGLAS FUR

ALL STRUCTURAL TIMBER SHALL BE PLANTATION GROWN GLUE LAMINATED TIMBER

ALL FLOORING SHALL BE FROM RECYCLED TIMBER OR BAMBOO T+G FLOORING

ROOF CLADDING

ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING:

- BCA PART 3.5.1

GUTTERS & DOWNPIPES ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING:

 BCA PART 3.5.2 - AS 3500.3.2

WALL CLADDING

ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING: BCA PART 3.5.3

EXTERNAL WINDOWS & DOORS ALL WORK IS TO BE CARRIED OUT IN

ACCORDANCE WITH THE FOLLOWING: BCA PART 3.5.4 & BCA PART 3.6

INSTALLATION OF GLAZING

ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING: BCA PART 3.6

- AS 1288 OR AS 2047

VENTILATION OF EXHAUST FANS ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING: BCA PART 2.4 & BCA PART 3.8.5

AS 1668.2

CONSTRUCTION OF ROOF, WALLS & **FLOOR**

ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING: - BCA PART 3.5 & BCA PART 3.12

HOT WATER SUPPLY SYSTEM ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING: BCA PART 3125

- AS/NZ 3500.4 OR AS 3500.5

FIRE SEPARATION

ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING - BCA PART 3.7.1

SMOKE ALARMS

ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING: - BCA PART 3.7.2

- AS 3786

BUILDING FABRIC THERMAL INSULATION ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING:

BCA PART 2.3.1 AS/NZ 4859.1

BASIX COMPLIANCE

SPECIFICALLY THE INSULATION VALUES SHALL BE A MINIMUM TOTAL OF R3.0 FOR ALL ROOFS & CEILINGS & R1.5 FOR ALL WALLS

SOUND INSULATION
ALL WORK IS TO BE CARRIED OUT IN
ACCORDANCE WITH THE FOLLOWING: - BCA PART 3.8.6

WATERPROOFING OF WET AREAS ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING:

BCA PART 3.8.1 AS 3740

FACILITIES (HEALT & AMENITY) ALL WORK IS TO BE CARRIED OUT IN ACCORDANCE WITH THE FOLLOWING:

— BCA PART 3.8.3

HYDRAULICS

ALL TAPWARE & PLUMBING FIXTURES SHALL BE AAA RATED. HOT WATER SERVICE PIPES SHALL BE PROVIDED WITH INSULATION ACCORDANCE WITH:

BCA PART 3.12.1

AS 3500

GENERAL NOTES

REFER ALL QUERIES & DISCREPANCIES TO THE ARCHITECT. ALL MEASUREMENTS ARE IN MM UNLESS OTHERWISE NOTED.

- BUILDING WORK THAT INVOLVES RESIDENTIAL BUILDING WORK (WITHIN THE MEANING AND EXEMPTIONS PROVIDED IN THE HOME BUILDING ACT 1989) MUST NOT BE CARRIED OUT UNLESS THE PRINCIPAL CERTIFYING AUTHORITY FOR THE DEVELOPMENT TO WHICH THE WORK RELATES HAS GIVEN COUNCIL WRITTEN NOTICE OF THE FOLLOWING:
- IN THE CASE OF WORK FOR WHICH A PRINCIPAL CONTRACTOR IS REQUIRED TO BE APPOINTED THE NAME AND LICENCE NUMBER OF THE PRINCIPAL CONTRACTOR AND THE NAME OF THE INSURER BY WHICH THE WORK IS INSURED UNDER PART 6 OF THAT ACT
- IN THE CASE OF WORK TO BE DONE BY AN OWNER-BUILDER THE NAME OF THE OWNER-BUILDER AND IF THE OWNER-BUILDER IS REQUIRED TO HOLD AN OWNER-BUILDER PERMIT UNDER THAT ACT, THE NUMBER OF THE OWNER-BUILDER PERMIT.
- IF ARRANGEMENTS FOR DOING RESIDENTIAL BUILDING WORK ARE CHANGED WHILE THE WORK IS IN PROGRESS SO THAT THE INFORMATION SUBMITTED TO COUNCIL IS OUT OF DATE, FURTHER WORK MUST NOT BE CARRIED OUT UNLESS THE PRINCIPAL CERTIFYING AUTHORITY FOR THE DEVELOPMENT TO WHICH THE WORK RELATES (NOT BEING THE COUNCIL), HAS GIVEN THE COUNCIL WRITTEN NOTICE OF THE UPDATED INFORMATION.
- FOR THE PURPOSES OF SECTION 80A (11) OF THE ACT, IT IS A PRESCRIBED CONDITION OF DEVELOPMENT CONSENT THAT IF THE DEVELOPMENT INVOLVES AN EXCAVATION THAT EXTENDS BELOW THE LEVEL OF THE BASE OF THE FOOTINGS OF A BUILDING ON ADJOINING LAND, THE PERSON HAVING THE BENEFIT OF THE DEVELOPMENT CONSENT MUST, AT THE PERSON'S OWN EXPENSE:
- PROTECT AND SUPPORT THE ADJOINING PREMISES FROM POSSIBLE DAMAGE FROM THE EXCAVATION
- WHERE NECESSARY, UNDERPIN THE ADJOINING PREMISES TO PREVENT ANY SUCH DAMAGE

1167 BARRENJOEY ROAD, PALM BEACH, NSW

ALTERATIONS AND ADDITIONS TO AN EXISTING DWELLING FOR MICHAEL MILLS


Contractors Must verify all dimensions on site prior to starting any work or making any shop drawings. Figured dimensions are to be taken in preference to scale readings. This drawing is copyright and the property of Justin Long Design

BASIX NOTES


- THE APPLICANT MUST INSTALL A GAS INSTANTANEOUS GAS HOT WATER SYSTEM
- ALL NEW TIMBER FRAMED SUSPENDED FLOORS WITH OPEN SUBFLOORS MUST HAVE ADDITIONAL INSULATION WITH AN R-VALUE OF RO.8 (DOWN) (OR 1.50 INCLUDING CONSTRUCTION)
- ÀLL NÉW EXTERNAL TIMBER FRAMED, WEATHERBOARD CLAD WALLS MUST HAVE ADDITIONAL INSULATION WITH AN R-VALUE OF 1.30 (OR 1.70 INCLUDING CONSTRUCTION)
- ALL NEW FLAT CEILINGS MUST HAVE ADDITIONAL INSULATION WITH AN R-VALUE OF R3.00 (UP)
 ALL NEW ROOFS MUST HAVE FOIL/SARKING & A MEDIUM SOLAR ABSORPTANCE (SOLAR ABSORPTANCE 0.475 0.70)
- WINDOWS & DOORS GENERALLY TO HAVE A TIMBER FRAME WITH SINGLE CLEAR GLAZING (U-VALUE: 5.71, SHGC: 0.66)

SCHEDULE OF EXTERNAL FINISHES


AREA	FINISH	COMMENT	IMAGE
EXTERNAL CLADDING	SELECTED VERTICAL TIMBER CLADDING	GREYED KEBONY TIMBER	
METAL SHEET ROOFING	PRE-FINISHED KLIP-LOK METAL SHEET ROOFING FOR ROOFS WITH A PITCH >5' PRE-FINISHED COLORBOND CUSTOM-ORB METAL SHEET ROOFING FOR ROOFS WITH A PITCH <5'	PRE-FINISHED — COLOUR: 'WALLABY'	
GUTTERS & DOWNPIPES	PRE—FINISHED COLORBOND GUTTERS & DOWNPIPES	PRE-FINISHED - COLOUR: 'WALLABY'	
DOORS & WINDOWS	TIMBER FRAMED DOORS & WINDOWS, NATURAL FINISH	NATURAL FINISH	
TIMBER DECKING & STEPS	HARDWOOD DECKING & TIMBER STEPS WITH HARDWOOD DECKING TO ENCLOSED TREADS & RISERS	GREYED KEBONY TIMBER	





rawn	scale	date	issue	amend
TJ	N/A	19.09.18	DA	-
rawing				















1167 BARRENJOEY ROAD, PALM BEACH, NSW


ALTERATIONS AND ADDITIONS TO AN EXISTING DWELLING FOR MICHAEL MILLS


Contractors Must verify all dimensions on site prior to starting any work or making any shop drawings.


Figured dimensions are to be taken in preference to scale readings. This drawing is copyright and the property of Justin Long Design.











STRING 16 GAUGE WIRE TIGHTLY BETWEEN STAKES

LAP BIDIM OVER 50mm & STITCH WITH TIE WIRE

PROPOSED

GEOTEXTILE
FABRIC

S0-75MM
GRAVEL

RUNOFF FROM, PAD DIRECTED
TO SEDIMENT TRAP

ROADWAY

BERM

TEMPORARY CONSTRUCTION EXIT

ROPOSED N1

LOOPED AT 100MM CENTRES
REMOVE SILT AFTER EACH MAJOR STORM

D.P. 559450

D.P. 559450

D.P. 13374

D.P. 13374

D.P. 13374

D.P. 1340

SITE FENCING/SECURITY
THE SITE MUST BE APPROPRIATELY SECURED
AND FENCED TO THE SATISFACTION OF
COUNCIL DURING DEMOLITION, EXCAVATION
AND CONSTRUCTION WORK TO ENSURE THERE
ARE NO UNACCEPTABLE IMPACTS ON THE
AMENITY OF ADJOINING PROPERTIES OR
PITTWATER. PERMITS FOR HOARDINGS AND
OR SCAFFOLDING ON COUNCIL LAND MUST BE
OBTAINED AND CLEARLY DISPLAYED ON SITE.

SITE ACCESS
SITE ACCESS IS TO BE PROVIDED FROM
BOTH BARRENJOEY ROAD & PITTWATER.
ACCESS FROM BARRENJOEY ROAD IS
PRIMARILY FOR CONTRACTOR &
SUB-CONTRACTOR PARKING WHILST ACCESS
FROM PITTWATER IS PRIMARILY FOR THE THE
DELIVERY OF SUPPLIES & FOR THE REMOVAL
OF ANY SITE WASTE INCLUDING BUILDING
MATERIALS & EXCAVATED SPOIL.

CAR PARKING
EXISTING CAR PARKING PROVISIONS TO
BARRENJOEY ROAD ARE TO REMAIN & WILL
BE UNAFFECTED DURING THE CONSTRUCTION
PROCESS.

01 EROSION, SEDIMENT CONTROL, WASTE MANAGEMENT & CONSTRUCTION/DEMOLITON PLAN
1: 200

LEGEND

PROVISION AREA FOR STOCKPILING OF MATERIALS



AREA FOR STORING EXCAVATED MATERIAL



TRADE WASTE RECEPTABLE LOCATION



2.1M HIGH STEEL FRAMED CYCLONE CONSTRUCTION FENCE & SILT FENCE, REFER TO DETAIL



TEMPORARY CONSTRUCTION EXIT, REFER TO DETAIL

SEDIMENT & SOIL EROSION CONTROL NOTES

A SOIL AND WATER MANAGEMENT PLAN (ALSO KNOWN AS AN EROSION AND SEDIMENT CONTROL PLAN) SHALL BE PREPARED ACCORDING TO SSROC'S SOIL AND WATER MANAGEMENT BROCHURE AND THE NSW ENVIRONMENT PROTECTION AUTHORITY (EPA) MANAGING URBAN STORMWATER: SOILS AND CONSTRUCTION. THIS PLAN SHALL BE IMPLEMENTED PRIOR TO COMMENCEMENT OF ANY WORKS OR ACTIVITIES. ALL CONTROLS IN THE PLAN SHALL BE MAINTAINED AT ALL TIME. A COPY OF THE SOIL AND WATER MANAGEMENT PLAN MUST BE KEPT ON SITE AT ALL TIMES AND MADE AVAILABLE TO COUNCIL OFFICERS ON REQUEST.

RESPREAD TOPSOIL & REVEGETATE ALL BARE AREAS

RETAIN TEMPORARY STRAW BALE & SILT FENCE DRAINAGE STRUCTURES UNTIL STORMWATER DRAINAGE & LANDSCAPING IS IN PLACE

DOWNSTREAM EROSION TO BE CHECKED & MAINTAINED PERIODICALLY DURING CONSTRUCTION

BUILDER TO ENSURE CONSTRUCTION & STABILISATION OF ALL CULVERTS & SURFACE DRAINAGE WORKS AT EARLIEST PRACTICAL STAGE

REMOVAL OR DISTURBANCE OF VEGETATION AND TOP SOIL IS CONFINED TO WITHIN 3M OF THE APPROVED BUILDING AREA (NO TREES ARE TO BE REMOVED WITHOUT APPROVAL)

ALL UNCONTAMINATED RUN-OFF MUST BE DIVERTED AROUND CLEARED OR DISTURBED AREAS

THE INSTALLATION OF SILT FENCES OR OTHER DEVICES MUST PREVENT SEDIMENT AND OTHER DEBRIS ESCAPING FROM THE CLEARED OR DISTURBED AREAS INTO DRAINAGE SYSTEMS OR WATERWAYS

ALL EROSION AND SEDIMENT CONTROLS ARE FULLY MAINTAINED FOR THE DURATION OF THE DEMOLITION & DEVELOPMENT WORKS

CONTROLS MUST BE PUT INTO PLACE TO PREVENT TRACKING OF SEDIMENT BY VEHICLES ONTO ADJOINING ROADWAYS

ALL DISTURBED AREAS ARE RENDERED EROSION—RESISTANT BY TURFING, MULCHING, PAVING OR SIMILAR


ALL WATER PUMPED OR OTHERWISE REMOVED FROM EXCAVATIONS OR BASEMENT AREAS MUST BE FILTERED TO ACHIEVE SUSPENDED SOLIDS/NON FILTERABLE RESIDUE LEVELS COMPLYING WITH THE AUSTRALIAN WATER QUALITY GUIDELINES FOR FRESH AND MARINE WATERS

PUMPED OR OVERLAND FLOWS OF WATER ARE TO BE DISCHARGED SO AS NOT TO CAUSE, PERMIT OR ALLOW EROSION BEFORE THE COMMENCEMENT OF WORK (AND UNTIL ISSUE OF THE OCCUPATION CERTIFICATE)

ALL EXCAVATIONS MUST BE KEPT FREE FROM WATER ACCUMULATION

ANY EXCAVATION WORKS CARRIED OUT ON SITE SHOULD BE CLOSELY MONITORED TO ENSURE NO SIGNS OF POTENTIAL ACID SULPHATE SOIL (PASS) OR ACTUAL ACID SULPHATE SOIL (AASS) ARE OBSERVED. INDICATORS MAY INCLUDE GREY TO GREENISH BLUE CLAYS, UNUSUAL GOLD—YELLOW MOTTLING OR 'ROTTEN EGG' ODOURS. IF ANY OF THESE INDICATORS ARE OBSERVED, EXCAVATION OF THE SITE IS TO BE STOPPED IMMEDIATELY, COUNCIL IS TO BE NOTIFIED AND A SUITABLY QUALIFIED ENVIRONMENTAL SCIENTIST SHOULD BE CONTRACTED TO FURTHER ASSESS THE SITE.

IN THE EVENT OF A STORM ALL ESTABLISHED CONTROLS ARE TO BE ASSESSED & THE HYDRAULIC ENGINEER & ARCHITECT ARE TO BE NOTIFIED IMMEDIATELY OF ANY DOWNSTREAM SEDIMENTATION.



1167 BARRENJOEY ROAD, PALM BEACH, NSW ALTERATIONS AND ADDITIONS TO AN EXISTING DWELLING

26.00M M.H.W.M - DP.830669

257' 15' 40"

3A D.P.13374

FOR MICHAEL MILLS

Contractors Must verify all dimensions on site prior to starting any work or making any shop drawings.

Figured dimensions are to be taken in preference to scale readings. This drawing is copyright and the property of Justin Long Design.

PROPOSED







CONTROL PLAN

