

STORMWATER LAYOUT NOTES

-PITS UP TO 450 DEEP TO BE 350SQ U.N.O., PITS UP TO 600
DEEP TO BE 450 SQ U.N.O., PITS UP TO 900 DEEP TO BE 600
SQ U.N.O., PITS UP TO 1200 DEEP TO BE 900 x 600 U.N.O., PITS
EXCEEDING 1200 DEEP TO BE 900 SQ. U.N.O. PITS TO BE
PRECAST CONCRETE OR RENDERED BRICK WITH CONCRETE HEAVY DUTY GRATES. U.N.O. LIGHT DUTY PITS AND GRATES MAY BE USED ONLY IN LIGHT/FOOT TRAFFICABLE AREAS. U.N.O. ALL PITS TO BE BENCHED TO DISCHARGE PIPES U.N.O. GAL. STEP IRONS TO ALL PITS EXCEEDING 900 DEPTH.

-COVER AND SUMP GRATES SHALL COMPLY WITH AS2733 &

-DOWNPIPES TO BE 90 DIA IF CHARGED AND 100 x 50 BOX IF GRAVITY. U.N.O. DP'S SHALL BE INSTALLED IN ACCORDANCE WITH AS3500.3.2:4.11 & AS4198. MAX. ROOF AREA PER DOWNPIPE WITH A NOMINATED GUTTER SIZE TO BE DETERMINED USING

MANUFACTURERS SPECIFICATIONS WITH OVERFLOW PROVISIONS BY -PIPES TO HAVE 1% MIN.GRADE U.N.O. BY PIT INVERTS. PIPES TO BE V.C. CLASS 'X' OR U.P.V.C. CLASS STORMWATER PIPE TO

AS1254,1260,1273,1477,2179.2 AND WHERE EXPOSED TO DIRECT SUNLIGHT TO HAVE ADEQUATE PROTECTION TO U.V. RADIATION IN ACCORDANCE WITH AS2032. SEWER GRADE/GAL. PIPES AND KERB ADAPTORS TO BE USED WHERE COUNCIL POLICY OR CONSENT REQUIRE SUCH.

REQUIRE SUCH.
—GUTTER OUTLETS SHALL BE FITTED VERTICALLY TO THE SOLE OF
THE EAVE GUTTERS. RAINHEADS TO HAVE AN OVERFLOW DUCT OR WEIR 50mm BELOW THEIR CREST.

-PROVIDE OVERFLOW SPITTERS TO ALL COVERED BALCONIES/ TERRACES. NOT TO BE DIRECTED ON TO ROOF SURFACES -RISING MAINS (PRESSURE PIPE) TO BE IN ACCORDANCE WITH AS3500.1:2.

AS35UU.T:2.

-SUBSOIL DRAINS TO BE IN ACCORDANCE WITH AS2439.1 CLASS
100 TO BE USED ONLY IN SINGLE DWELLINGS.

-ALL PIPE JOINTS, VALVES TO BE IN ACCORDANCE WITH
AS3500.3.2:2.7 & AS3500.3.2

-EXPANSION JOINTS SHALL COMPLY WITH AS3500.3.2:TABLE 4.1

PVC JOINTS AND ACCESSORIES TO COMPLY WITH AS2179.2 & A8&U9BRENCHES TO BE IN ACCORDANCE WITH AS3500.3.2:7.2.8-14. EMBEDMENT MATERIAL AND TRENCH FILL TO ALL PIPES & SUBSOIL, DRAINS TO BE IN ACCORDANCE WITH AS3500.3.2:7, ALL WORKS TO BE IN ACCORDANCE WITH AS1254, 1741, 2032, 2733, 2865, 3996, 1260, 1477, 2179.1 & 2,2566, 6367, 8301, ARR97 & BCA

-IT IS THE BUILDER'S RESPONSIBILITY TO CONFIRM THAT LEVELS AND SURVEYS ARE IN ACCORDANCE WITH LEVELS ON SITE & ARE APPROVED BY COUNCIL & ARCHITECT BEFORE COMMENCING WORK. NO SEWER VENTS, GULLY PITS OR SIMILAR TO BE LOCATED BELOW THE MAXIMUM WATER SURFACE LEVEL IN DETENTION BASINS, ALL BASIN WALLS TO BE WATERTIGHT & STRUCTURALLY DESIGNED BY A STRUCTURAL ENGINEER.

-ALL FENCES WHICH MAY DIVERT FLOW FROM PROPOSED DIRECTION TO BE RAISED 100mm

-BUILDER TO ENSURE ALL DRAINAGE AREAS INCLUDING EXPOSED BALCONIES TO HAVE OVERFLOW MECHANISM IN PLACE IN THE EVENT OF BLOCKAGE WITH ADEQUATE OVERFLOW SECTION THROUGH

PLANTERS, PARAPETS ETC.
-ALL EXTERIOR FINISHED GROUND LEVELS TO BE SLOPING AWAY

FROM PERIMETER WALLS IN ALL CASES.

-ALL HEADROOM CLEARANCES TO BE COORDINATED BETWEEN
BUILDER & ARCHITECT. NOTIFY ENGINEER FOR APPROVAL IF ANY CHANGES OCCUR.

CALL GULLY POSITIONS ARE DIAGRAMMATIC ONLY— BUILDER SHOULD CONSULT ARCHITECTURALS FOR DIMENSIONS TO LOCATE STORMWATER

ELEMENTS U.N.O.

-FIRE RATING TO ARCHITECT'S SPECIFICATION. -ALL FINISHED FLOOR LEVELS ARE NOMINATED BY ARCHITECT. -ALL FINISHED FLOUR LEVELS ARE NOMINATED BY ARCHITECT.
-ALL SITE SAFETY MEASURES AND WORK METHOD STATEMENTS
PREPARED BY BUILDER/SUB-CONTRACTORS ARE TO BE
IMPLEMENTED DURING CONSTRUCTION. NO WORK IS TO COMMENCE
UNTIL ALL WORKERS CARRY OUT SITE INDUCTION, PREPARED AND
CARRIED OUT BY BUILDER. ANY HAZARD IDENTIFICATION TO BE CARRIED OUT BY BUILDER. ANY HAZARD IDENTIFICATION TO BE REPORTED IMMEDIATELY TO SITE SUPERVISOR TO CARRY OUT NECESSARY PROCEDURES TO ELIMINATE HAZARD, PRIOR TO PROCEEDING WITH WORK. STRUCTURAL AND GEOTECHNICAL ADVICE SHOULD BE SOUGHT IN ALL CASES.

-CONFINED SPACES SIGNAGE TO BE INSTALLED IN ACCESSIBLE UNDERGROUND TANKS TO WORK COVER SPECIFICATIONS. ALL PITS

EXCEEDING 600mm DEPTH TO HAVE 'J' BOLTS OR SIMILAR INSTALLED TO GRATES.

-MAINTENANCE DEVICES REQ'D BY AUTHORITIES ARE NOT TO BE ASSUMED SHOWN ON DRAWINGS. —EARTH MOUNDING SHOWN AS TEMPORARY MEASURE UNTIL

ANDSCAPING COMPLETED TO DIRECT FLOWS AS SHOWN.



THIS DRAWING IS DIAGRAMMATIC ONLY & NOT TO BE SCALED. IT IS NOT A PART 4A CERT. REFER TO ARCHITECTS DRAWINGS FOR DIMENSIONS. COPYRIGHT IN THIS DRAWING IS THE PROPERTY OF IBRAHIM STORMWATER CONSULTANTS AND THE DRAWING SHALL NOT BE REPRODUCED OR COPIED, WHOLE OR IN PART, IN ANY FORM WITHOUT THE PRIOR WRITTEN APPROVAL OF IBRAHIM STORMWATER CONSULTANTS

1	REVISIONS		
_)			
	В	Raint	
	Α	Raint	

В	Raintank	revised	per	revised	basix/owner	request
A	Raintank	revised	per	revised	basix/owner	request

ISSUE	PRINTS	ISSUED TO	DATE
1	EMAIL	BUILDER/CLIENT	26-7-21
2	EMAIL	BUILDER/CLIENT	3-9-21
3	EMAIL	BUILDER/CLIENT	16-9-21

SCALE(A3) 1:200,100 u.n.o. SCALE BAR - 1m INTERVALS DATE MAY . 2021

DRAWN M./. DESIGNED M./. APPROVED



IBRAHIM STORMWATER CONSULTANTS

P.O. BOX 400 CHERRYBROOK NSW 2126 TELEPHONE: (02) 9980 5515 FAX: (02) 9980 6114 www.stormwater.net.au email: mail@stormwater.net.au

PROPOSED RESIDENCE AT 29 CURRONG CIRCUIT TERREY HILLS FOR MR. & MRS. SYMES

THIS DRAWING


JOB NUMBER


SIORMWATER C10162-14901

CLARENDON HOMES

SHEET No. of REVISION B

a





SILT ARRESTOR PIT - P2

WHSA
ALL NEARBY SERVICES TO BE LOCATED PRIOR EXCAVATIONS.
ALL PIPES TO BE CUT FLUSH WITH PIT WALLS AND SPARGED.
PITS EXCEEDING 600mm IN DEPTH TO HAVE LOCK DOWN MECHANISM.
SAFETY GEAR TO BE WORN AT ALL TIMES. INCLUDING FOOTWEAR, CLOTHING
AND GLOVES AS PER SWMS.

RAINWATER TANK

TANK DETAILS SHOWN ARE A SUGGESTED CONFIGURATION ONLY. ANY MODIFICATIONS TO TANK VOLUME OR INLET AND OUTLET LEVELS MUST BE APPROVED BY ENGINEER PRIOR TO COMMENCEMENT OF CONSTRUCTION. TANK SHAPE, & DEVICES SHOWN ARE DIAGRAMMATIC ONLY. MINIMUM OF 450 CLEARANCE (UNLESS L.G.A. REQUIRES LARGER SETBACK) TO SIDE BOUNDARIES MUST BE MAINTAINED. CLIENT IS RESPONSIBLE TO ENSURE COMPLIANCE WITH THIS IN THE INSTALLED STATE. Charged stormwater lines from Roof Areas ONLY to rainwater tank.


All joints to be solvent welded. All exposed pipework to be painted to withstand external elements.

First flush water diverter at tank to comply with Sydney Water and council DCP's. An approved switch system similar to 'Rainbank' to be used via mains. Pumps to manuf, specs.

Rain Tank to be installed and maintainted to manufacturers specifications and to comply with all Sydney Water Guidelines.

Client to be responsible for maintenance system of charged pipelines. Debris accumulation significantly affects systems performance. Maintenance program essential. Structural details for tank base by manufacturer or others.

INSTALLATION OF RAINTANKS: PLUMBER/SITE SUPERVISOR TO ASSESS ACCESS SUITABILITY PRIOR OR POST SLAB CONSTRUCTION. INSTALLATION OF TANKS TO BE CARRIED OUT FOLLOWING SWMS OF TANK SUPPLIER AND PLUMBER. APPROPRIATE GLOVES TO BE WORN AT ALL TIMES WHILE HANDLING TANKS.




TANK MODULES WRAPPED IN GEO-TEXTILE FABRIC. BASE AND SIDES TO BE LINED FIRST WITH POLYPROPYLENE PLASTIC TO PROTECT GEO-FABRIC

MODULAR OSD TANK DETAILS

Suitable structural backfill compacted to 95% sandy modified proctor density. Utility markers-Use metallic tape at corners of install to mark the area for future utility detection. 100mm Sand bedding to base to achieve level base and compaction respectively.


DETENTION TANK TO ATLANTIS SPECIFICATIONS



PIT DCP1 -SECTION A


THIS DRAWING IS DIAGRAMMATIC ONLY & NOT TO BE SCALED. IT IS NOT A PART 4A CERT. REFER TO ARCHITECTS DRAWINGS FOR DIMENSIONS. COPYRIGHT IN THIS DRAWING IS THE PROPERTY OF IBRAHIM STORMWATER CONJULTANTS AND THE DRAWING SHALL NOT BE REPRODUCED OR COPIED, WHOLE OR IN PART, IN ANY FORM WITHOUT THE PRIOR NEWTON AND THE PROPERTY OF THE PROPERTY OF THE PRIOR NEWTON AND THE PROPERTY OF THE PRIOR NEWTON AND THE PRIOR NEW PRIOR NEW PART AND THE PRIOR NEWTON AND THE PRIOR NEWTON AND THE PRIOR NEW PART P

BUILDER/CLIENT TO ENSURE THAT ALL SAFETY MEASURES ARE TAKEN DURING CONSTRUCTION, INCLUDING BUT NOT LIMITED TO, SAFETY FENCING, SIGNAGE, OBTAINING STRUCTURAL AND GEOTECHNICAL ADVICE WHERE EXCAVATIONS ARE NEAR STRUCTURES OR SERVICES, SAFETY MEASURES RECOMMENDED BY PRODUCT SUPPLIERS ETC.



SLOPE JUNCTION CONNECTION

150ø dia. pipe using FLOCON CONCONNECT DEVICE AT 11-1 O'CLOCK POSITION. COUNCIL INSPECTION MUST BE BOOKED BEFORE WORKS COMMENCE. INSPECTIONS AT EXCAVATION, CORE DRILLING AND INSTALLATION MUST BE INSPECTED BY COUNCIL



10 dia. x 100 long dyna bolts or similar ORIFICE MACHINE CUT IN 3mm. STAINLESS STEEL PLATE

ORIFICE PLATE

REVISIONS

Raintank revised per revised basix/owner request

ISSUE	PRINTS	ISSUED TO	DATE
1	EMAIL	BUILDER/CLIENT	26-7-21
2	EMAIL	BUILDER/CLIENT	3-9-21
3	EMAIL	BUILDER/CLIENT	16-9-21

SCALE(A3)1:200,100 u.n.o. SCALE BAR - 1m INTERVALS DATE MAY . 2021 DRAWN M./. DESIGNED M./. APPROVED



P.O. BOX 400 CHERRYBROOK NSW 2126 TELEPHONE: (02) 9980 5515 FAX: (02) 9980 6114 www.stormwater.net.au email: mail@stormwater.net.a

PROPOSED RESIDENCE AT 29 CURRONG CIRCUIT TERREY HILLS FOR MR. & MRS. SYMES

THIS DRAWING STORMWATER **DETAILS SH.1**

NOT TO SCALE

JOB NUMBER C10162-14901

SHEET No CLARENDON HOMES 2 of 2

B

REVISION