

2 July 2020

ւիկկիիկվիրուկիկիել

Peter Princi Architects PO Box 615 FRENCHS FOREST NSW 1640

Dear Sir/Madam

Application Number:	DA2019/1248
Address:	Lot 12 DP 28236 , 143 McCarrs Creek Road, CHURCH POINT NSW 2105
	Lot 13 DP 28236 , 145 McCarrs Creek Road, CHURCH POINT NSW 2105
Proposed Development:	Construction of two dwelling houses

Please find attached the Notice of Determination for the above mentioned Application.

Please be advised that a copy of the Assessment Report associated with the application is available on Council's website at www.northernbeaches.nsw.gov.au

Please read your Notice of Determination carefully and the assessment report in the first instance.

If you have any further questions regarding this matter please contact the undersigned on 1300 434 434 or via email quoting the application number, address and description of works to council@northernbeaches.nsw.gov.au

Regards,

Tony Collier Principal Planner



NOTICE OF DETERMINATION

Application Number:	DA2019/1248
Determination Type:	Development Application

APPLICATION DETAILS

Applicant:	Peter Princi Architects
	Lot 12 DP 28236 , 143 McCarrs Creek Road CHURCH POINT NSW 2105 Lot 13 DP 28236 , 145 McCarrs Creek Road CHURCH POINT NSW 2105
Proposed Development:	Construction of two dwelling houses

DETERMINATION - APPROVED

Made on (Date)	02/07/2020
Consent to operate from (Date):	02/07/2020
Consent to lapse on (Date):	02/07/2025

Detail of Conditions

The conditions, which have been applied to the consent, aim to ensure that the Environmental Impacts of Development are minimised and the Health and Safety of the community is maintained in accordance with the relevant standards and the Building Code of Australia.

Note:

If the works are to be certified by a Private Certifying Authority, then it is the certifier's responsibility to ensure all outstanding fees and bonds have been paid to Council prior to the issue of the Construction Certificate or as otherwise specified by Consent conditions.



DEVELOPMENT CONSENT OPERATIONAL CONDITIONS

1. Approved Plans and Supporting Documentation

The development must be carried out in compliance (except as amended by any other condition of consent) with the following:

a) Approved Plans

Architectural Plans - Endorsed with Council's stamp		
Drawing No.	Dated	Prepared By
DA01(A) - Overall Site Plan	October 2019	Peter Princi Architects
DA02(A) - Site Plan (No. 143)	October 2019	Peter Princi Architects
DA03(A) - Site Plan (No. 145)	October 2019	Peter Princi Architects
DA04(A) - Floor Plan (No. 143)	October 2019	Peter Princi Architects
DA05(A) - Floor Plan (No. 145)	October 2019	Peter Princi Architects
DA06(A) - Roof Plan (No. 143)	October 2019	Peter Princi Architects
DA07(A) - Roof Plan (No. 145)	October 2019	Peter Princi Architects
DA08(A) - Elevations - North/South (No. 143)	October 2019	Peter Princi Architects
DA09(A) - Elevations - East/West (No. 143)	October 2019	Peter Princi Architects
DA10(A) - Section A-A (No. 143)	October 2019	Peter Princi Architects
DA11(A) - Elevations - East/West (No. 143)	October 2019	Peter Princi Architects
DA12(A) - Elevations - North/South (No. 145)	October 2019	Peter Princi Architects
DA13(A) - Section A-A (No. 145)	October 2019	Peter Princi Architects
DA14(A) - Garage (No. 143 & 145)	October 2019	Peter Princi Architects

Engineering Plans		
Drawing No.	Dated	Prepared By
1 of 4 - Driveway and Garages Plan View (Issue A)	June 2020	VDM Consulting Engineers
2 of 4 - Proposed Driveway Sections 1 (Issue A)	March 2020	VDM Consulting Engineers
3 of 4 - Driveway Sections 2 (Issue A)	March 2020	VDM Consulting Engineers
4 of 4 - Proposed Driveway Sections 2 (Issue A)	March 2020	VDM Consulting Engineers

Reports / Documentation – All recommendations and requirements contained within:

Report No. / Page No. / Section No.	Dated	Prepared By
Biodiversity Development Assessment Report	31 October 2019	GIS Environmental Consultants



Biodiversity Management Plan (No. 143)	3 March 2020	GIS Environmental Consultants
Biodiversity Management Plan (No. 145)	3 March 2020	GIS Environmental Consultants
Construction Management Plan	28 February 2020	Lloyd Constructions Pty Ltd
Arboricultural Impact Assessment Report (No. 143)	27 February 2020	Hugh the Arborist
Arboricultural Impact Assessment Report (No. 145)	28 February 2020	Hugh the Arborist
Bushfire Risk Assessment Report	15 October 2019	Planning for Bushfire Protection
Geotechnical Risk Management Report (No. 143)	30 August 2019	Hodgson Consulting Engineers
Geotechnical Risk Management Report (No. 145)	30 August 2019	Hodgson Consulting Engineers

b) Any plans and / or documentation submitted to satisfy the Conditions of this consent.

c) The development is to be undertaken generally in accordance with the following:

Waste Management Plan		
Drawing No/Title.	Dated	Prepared By
Waste Management Plan	Not dated	Peter Princi Architects

In the event of any inconsistency between conditions of this consent and the drawings/documents referred to above, the conditions of this consent will prevail.

Reason: To ensure the work is carried out in accordance with the determination of Council and approved plans.

2. Compliance with Other Department, Authority or Service Requirements

The development must be carried out in compliance with all recommendations and requirements, excluding general advice, within the following:

Other Department, Authority or Service	EDMS Reference	Dated
NSW Rural Fire Service	Referral response - NSW Rural Fire Service	4 January 2020
Transport for NSW (RMS)	Referral response - RMS (Concurrence)	29 June 2020

(NOTE: For a copy of the above referenced document/s, please see Application Tracking on Council's website <u>www.northernbeaches.nsw.gov.au</u>)

Reason: To ensure the work is carried out in accordance with the determination and the statutory requirements of other departments, authorities or bodies.

3. **Prescribed Conditions**



- (a) All building works must be carried out in accordance with the requirements of the Building Code of Australia (BCA).
- (b) BASIX affected development must comply with the schedule of BASIX commitments specified within the submitted BASIX Certificate (demonstrated compliance upon plans/specifications is required prior to the issue of the Construction Certificate);
- (c) A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:
 - (i) showing the name, address and telephone number of the Principal Certifying Authority for the work, and
 - (ii) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
 - (iii) stating that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.

- (d) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the following information:
 - (i) in the case of work for which a principal contractor is required to be appointed:
 - A. the name and licence number of the principal contractor, and
 - B. the name of the insurer by which the work is insured under Part 6 of that Act,
 - (ii) in the case of work to be done by an owner-builder:
 - A. the name of the owner-builder, and
 - B. if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under becomes out of date, further work must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.

- (e) Development that involves an excavation that extends below the level of the base of the footings of a building on adjoining land, the person having the benefit of the development consent must, at the person's own expense:
 - (i) protect and support the adjoining premises from possible damage from the excavation, and
 - (ii) where necessary, underpin the adjoining premises to prevent any such damage.
 - (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
 - (iv) the owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this clause, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.

In this clause, allotment of land includes a public road and any other public place.



Reason: Legislative requirement.

4. General Requirements

- (a) Unless authorised by Council: Building construction and delivery of material hours are restricted to:
 - 7.00 am to 5.00 pm inclusive Monday to Friday,
 - 8.00 am to 1.00 pm inclusive on Saturday,
 - No work on Sundays and Public Holidays.

Demolition and excavation works are restricted to:

• 8.00 am to 5.00 pm Monday to Friday only.

(Excavation work includes the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders and the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site).

- (b) At all times after the submission the Notice of Commencement to Council, a copy of the Development Consent and Construction Certificate is to remain onsite at all times until the issue of a final Occupation Certificate. The consent shall be available for perusal of any Authorised Officer.
- (c) Where demolition works have been completed and new construction works have not commenced within 4 weeks of the completion of the demolition works that area affected by the demolition works shall be fully stabilised and the site must be maintained in a safe and clean state until such time as new construction works commence.
- (d) Onsite toilet facilities (being either connected to the sewer or an accredited sewer management facility) for workers are to be provided for construction sites at a rate of 1 per 20 persons.
- (e) Prior to the release of the Construction Certificate, payment of the Long Service Levy is required. This payment can be made at Council or to the Long Services Payments Corporation. Payment is not required where the value of the works is less than \$25,000. The Long Service Levy is calculated on 0.35% of the building and construction work. The levy rate and level in which it applies is subject to legislative change. The applicable fee at the time of payment of the Long Service Levy will apply.
- (f) The applicant shall bear the cost of all works associated with the development that occurs on Council's property.
- (g) No building, demolition, excavation or material of any nature and no hoist, plant and machinery (crane, concrete pump or lift) shall be placed on Council's footpaths, roadways, parks or grass verges without Council Approval.
- (h) Demolition materials and builders' wastes are to be removed to approved waste/recycling centres.
- (i) No trees or native shrubs or understorey vegetation on public property (footpaths, roads, reserves, etc.) or on the land to be developed shall be removed or damaged during construction unless specifically approved in this consent including for the erection of any fences, hoardings or other temporary works.
- (j) Prior to the commencement of any development onsite for:



- i) Building/s that are to be erected
- ii) Building/s that are situated in the immediate vicinity of a public place and is dangerous to persons or property on or in the public place
- iii) Building/s that are to be demolished
- iv) For any work/s that is to be carried out
- v) For any work/s that is to be demolished

The person responsible for the development site is to erect or install on or around the development area such temporary structures or appliances (wholly within the development site) as are necessary to protect persons or property and to prevent unauthorised access to the site in order for the land or premises to be maintained in a safe or healthy condition. Upon completion of the development, such temporary structures or appliances are to be removed within 7 days.

- (k) Requirements for new swimming pools/spas or existing swimming pools/spas affected by building works.
 - (1) Child resistant fencing is to be provided to any swimming pool or lockable cover to any spa containing water and is to be consistent with the following;

Relevant legislative requirements and relevant Australian Standards (including but not limited) to:

- (i) Swimming Pools Act 1992
- (ii) Swimming Pools Amendment Act 2009
- (iii) Swimming Pools Regulation 2008
- (iv) Australian Standard AS1926 Swimming Pool Safety
- (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
- (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools.
- (2) A 'KEEP WATCH' pool safety and aquatic based emergency sign, issued by Royal Life Saving is to be displayed in a prominent position within the pool/spa area.
- (3) Filter backwash waters shall be conveyed to the Sydney Water sewerage system in sewered areas or managed on-site in unsewered areas in a manner that does not cause pollution, erosion or run off, is separate from the irrigation area for any wastewater system and is separate from any onsite stormwater management system.
- (4) Swimming pools and spas must be registered with the Division of Local Government.

Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community.

5. **RMS Condition - Operational**

- 1. In accordance with AS 2890.1- 2004 (Parking Facilities, Part 1: Off-street car parking), the driveway shall be a minimum of 5.5 metres in width for a minimum distance of 6 metres from the property boundary.
- 2. All vehicles are to enter and leave the site in a forward direction.
- 3. All vehicles are to be wholly contained on site before being required to stop.
- 4. All demolition and construction vehicles are to be contained wholly within the site and vehicles must enter the site before stopping. A work zone will not be permitted on



McCarrs Creek Road.

FEES / CHARGES / CONTRIBUTIONS

6. **Policy Controls**

Northern Beaches 7.12 Contributions Plan 2019

A monetary contribution of \$13,982.10 is payable to Northern Beaches Council for the provision of local infrastructure and services pursuant to section 7.12 of the Environmental Planning & Assessment Act 1979 and the Northern Beaches Section 7.12 Contributions Plan 2019. The monetary contribution is based on a development cost of \$1,398,210.00.

The monetary contribution is to be paid prior to the issue of the first Construction Certificate or Subdivision Certificate whichever occurs first, or prior to the issue of the Subdivision Certificate where no Construction Certificate is required. If the monetary contribution (total or in part) remains unpaid after the financial quarter that the development consent is issued, the amount unpaid (whether it be the full cash contribution or part thereof) will be adjusted on a quarterly basis in accordance with the applicable Consumer Price Index. If this situation applies, the cash contribution payable for this development will be the total unpaid monetary contribution as adjusted.

The proponent shall provide to the Certifying Authority written evidence (receipt/s) from Council that the total monetary contribution has been paid.

The Northern Beaches Section 7.12 Contributions Plan 2019 may be inspected at 725 Pittwater Rd, Dee Why and at Council's Customer Service Centres or alternatively, on Council's website at www.northernbeaches.nsw.gov.au

This fee must be paid prior to the issue of the Construction Certificate. Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To provide for contributions in accordance with the Contribution Plan to fund the provision of new or augmented local infrastructure and services.

7. Security Bond

A bond (determined from cost of works) of \$10,000 and an inspection fee in accordance with Council's Fees and Charges paid as security to ensure the rectification of any damage that may occur to the Council infrastructure contained within the road reserve adjoining the site as a result of construction or the transportation of materials and equipment to and from the development site.

An inspection fee in accordance with Council adopted fees and charges (at the time of payment) is payable for each kerb inspection as determined by Council (minimum (1) one inspection).

All bonds and fees shall be deposited with Council prior to Construction Certificate or demolition work commencing, details demonstrating payment are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

To process the inspection fee and bond payment a Bond Lodgement Form must be completed with the payments (a copy of the form is attached to this consent and alternatively a copy is located on Council's website at www.northernbeaches.nsw.gov.au).



Reason: To ensure adequate protection of Council's infrastructure.

8. Construction, Excavation and Associated Works Security Bond (Road works)

The applicant is to lodge a bond with Council of \$20000.00 as security against any damage or failure to complete the construction of road pavement, driveway and reconstruction works within public road as part of this consent.

Details confirming payment of the bond are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Protection of Council's Infrastructure.

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

9. Stormwater Disposal

The applicant is to demonstrate how stormwater from the new development within this consent is disposed of to an existing approved system or in accordance with Northern Beaches Council's Clause B 5.10 PITTWATER DCP21. Details by an appropriately qualified and practicing Civil Engineer demonstrating that the existing stormwater system is connected to Council's stormwater drainage system, or compliance with the Council's specification are to be submitted to the Certifying Authority for approval prior to the issue of the Construction Certificate.

Reason: To ensure appropriate provision for disposal and stormwater management arising from development.

10. Geotechnical Report Recommendations have been Incorporated into Designs and Structural Plans

The recommendations of the risk assessment required to manage the hazards as identified in the Geotechnical Report prepared by Hodgson Consulting Engineers dated 30th August, 2019 are to be incorporated into the construction plans. Prior to issue of the Construction Certificate, Form 2 of the Geotechnical Risk Management Policy for Pittwater (Appendix 5 of P21 DCP) is to be completed and submitted to the Accredited Certifier. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure geotechnical risk is mitigated appropriately.

11. Traffic Management and Control for works on public road

The Applicant is to submit an application for Traffic Management Plan to Council for approval prior to issue of the Construction Certificate. The Traffic Management Plan shall be prepared to RMS standards by an appropriately certified person.

Reason: To ensure appropriate measures have been considered for site access, storage and the operation of the site during all phases of the construction process.

12. Amendments to the approved plans

The following amendments are to be made to the approved plans:

Privacy Treatments

The northern edge of the elevated landing deck and elevated walkway to the dwelling at No. 143 McCarrs Creek Road is to include a fixed privacy screen which has a minimum height of 1.65m



above the finished floor level of the deck and walkway.

The screen may be lightweight and visually permeable but must be designed to direct viewing away from the private open space and rooms of the neighbouring dwelling at No. 141 McCarrs Creek Road.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the construction certificate.

Reason: To ensure development minimises unreasonable impacts upon surrounding land.

13. Boundary Identification Survey

A boundary identification survey, prepared by a Registered Surveyor, is to be prepared in respect of the subject site.

The plans submitted for the Construction Certificate are to accurately reflect the property boundaries as shown on the boundary identification survey, with setbacks between the property boundaries and the approved works consistent with those nominated on the Approved Plans of this consent.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of any Construction Certificate.

Reason: To ensure all approved works are constructed within the subject site and in a manner anticipated by the development consent.

14. Submission Roads Act Application for Civil Works in the Public Road

The Applicant is to submit an application for approval for Infrastructure works on Councils roadway. Engineering plans for the new development works within the road reserve and this development consent are to be submitted to Council for approval under the provisions of Sections 138 and 139 of the Roads Act 1993.

The application is to include four (4) copies of Civil Engineering plans for the design of shared driveway within the public road which are to be generally in accordance with the Council's specification for engineering works - AUS-SPEC #1. The plan shall be prepared by a qualified civil engineer. The design must include the following information:

- 1. Construction of a shared vehicular crossing and driveway 5.0 metres at the layback/dish drain crossing , transitioned to 3.0 metres driveway generally in accordance with plan prepared Mario F Benilez dated March 2020.
- 2. Construction of the concrete dish drain. The dish drain shall connect to the existing dish drain located north of the proposed access.
- 3. Construction of a retaining wall in accordance with the Geo-technical requirements. A report from the Geo-technical engineer is to be submitted in this regards.
- 4. Submission of a full Structural structural details of the driveway, retaining wall and associated works.
- 5. The proposed parking areas and driveway must comply with AS/NZS 2890.1:2004, in regards to driveway grades and safety barriers where required.
- 6. The proposed driveway where it intersects with the existing driveway to 141 McCarrs Creek Road must not be altered in order to maintain the existing access to No 141.
- 7. A suitable access agreement with the owner of 141 McCarrs Creek Road is required whilst the driveway is being constructed. Details to be provided with application.
- 8. The design plan shall show all public utility services affecting the proposed driveway.



Any relocation and/or adjustment, requires written approval from the public authority. All cost associated with the relocation or adjustments are to be borne by the property owner.

The fee associated with the assessment and approval of the application is to be in accordance with Council's Fee and Charges.

An approval is to be submitted to the Certifying Authority prior to the issue of the Construction Certificate

Reason: To ensure engineering works are constructed in accordance with relevant standards and Council's specification.

15. Structural Adequacy and Excavation Work

Excavation work is to ensure the stability of the soil material of adjoining properties, the protection of adjoining buildings, services, structures and / or public infrastructure from damage using underpinning, shoring, retaining walls and support where required. All retaining walls are to be structurally adequate for the intended purpose, designed and certified by a Structural Engineer, except where site conditions permit the following:

(a) maximum height of 900mm above or below ground level and at least 900mm from any property boundary, and

(b) Comply with AS3700, AS3600 and AS1170 and timber walls with AS1720 and AS1170.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Construction Certificate.

Reason: To provide public and private safety.

16. Soil and Water Management Program

A Soil and Water Management Plan prepared in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) and implemented on site until the works are completed.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To protect the environment from the effects of sedimentation and erosion from development sites. (DACHPC02)

17. Installation and Maintenance of Sediment and Erosion Control

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004).

Techniques used for erosion and sediment control on site are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and the site is sufficiently stabilised with vegetation.

Reason: To protect the surrounding environment from the effects of sedimentation and erosion from the site.



18. Tree Protection Plan

a) A Tree Protection Plan shall be submitted to the Certifying Authority for approval prior to the issue of a Construction Certificate, demonstrating tree protection measures to protect the following trees:

All trees not indicated for removal in the Arboricultural Impact Assessment Reports for 143 McCarrs Creek Road dated 13 October 2019 and 145 McCarrs Creek Road dated 17 October 2019 prepared by Hugh the Arborist.

b) The Tree Protection Plan shall be prepared by an Arborist with AQF minimum Level 5 qualifications in arboriculture/horticulture, showing the following:

i) layout of the development, including existing and proposed underground services,

ii) location of all trees identified for retention, including extent of canopy,

- iii) access routes throughout the site for construction activity,
- iv) location of tree protection fencing / barriers,
- v) root protection in the form of mulching within the tree protection zone,
- vi) trunk and branch protection within the tree protection zone,
- vii) location of stockpile areas and materials storage,
- viii) other general tree protection measures.

c) Tree protection fencing to the extent and alignment as determined by an AQF minimum Level 5 Arborist, shall comply to Australian Standard 4970-2009 Protection of Trees on Development Sites

Reason: to ensure compliance with the requirement to retain and protect trees required to be retained.

19. **Notification of determination to which the Biodiversity Offset Scheme applies** The applicant or Project Ecologist, on behalf of the applicant, must download and complete the "Biodiversity Offsets Scheme – Notification of Determination" form.

Council's Manager Bushland and Biodiversity and the Principal Certifying Authority must be copied into the notification email to confirm compliance.

Reason: To ensure the NSW Department of Planning, Industry and Environment are notified of determinations where the Biodiversity Offsets Scheme applies and Council are notified for compliance.

20. Water Quality Management

The applicant must install a filtration device: either a silt arrestor pit that captures organic matter and coarse sediments prior to discharge of stormwater from the land or an absorption trench that disperses stormwater on the land. Separate devices must be installed on each lot. All stormwater treatment measures must make provision for convenient and safe regular inspection, periodic cleaning, and maintenance.

Details demonstrating compliance are to be submitted to the Certifying Authority for approval prior to the issue of the Construction Certificate.



Reason: Protection of the receiving environment

21. Like for like credit retirement conditions - Ecosystem credit retirement conditions Prior to issue of the relevant Construction Certificate the class and number of ecosystem credits in Table 1 must be retired to offset the impacts of the development.

The requirement to retire credits outlined in Table 1 may be satisfied by payment to the Biodiversity Conservation Fund of an amount equivalent to the class and number of ecosystem credits, as calculated by the Biodiversity Offsets Payment Calculator.

Evidence of the retirement of credits or payment to the Biodiversity Conservation Fund in satisfaction of Table 1 requirements must be provided to the Manager Bushland and Biodiversity of Northern Beaches Council prior to release of construction certification.

Impacted Plant Community Type	TEC	Number of ecosystem credits	Cont HBT
1833-Lilly Pilly - Cabbage Tree Palm littoral rainforest on escarpment slopes and gullies of the Sydney basin	Littoral Rainforest in the New South Wales North Coast, Sydney Basin and South East Corner Bioregions	2	YES
1565-Turpentine - Rough-barked Apple - Forest Oak moist shrubby tall open forest of the Central Coast	Not a TEC	3	YES

Table 1 Ecosystem credits required to be retired – like for like

Reason: To offset the residual biodiversity impacts of the development in accordance with the NSW Biodiversity Offset Scheme.

22. Like for like credit retirement conditions - Species credit retirement conditions Prior to issue of the relevant Construction Certificate the class and number of species credits in Table 2 must be retired to offset the impacts of development.

The requirement to retire credits outlined in Table 2 may be satisfied by payment to the Biodiversity Conservation Fund of an amount equivalent to the class and number of ecosystem credits, as calculated by the Biodiversity Offsets Payment Calculator.

Evidence of the retirement of credits or payment to the Biodiversity Conservation Fund in



satisfaction of Table 2 requirements must be provided to the Manager Bushland and Biodiversity of Northern Beaches Council prior to release of construction certification.

Impacted species credit species	Number of species credits	IBRA sub-region
Cercartetus nanus/ Eastern Pygmy-possum	4	Any in NSW
Cryptostylis hunteriana/ Leafless Tongue Orchid	3	Any in NSW
Heleioporus australiacus/ Giant Burrowing Frog	4	Any in NSW
Petaurus norfolcensis/ Squirrel Glider	6	Any in NSW

Table 2 Species credits required to be retired – like for like

Reason: To offset the residual biodiversity impacts of the development in accordance with the NSW Biodiversity Offset Scheme.

23. Engagement of Project Ecologist

A Project Ecologist is to be employed for the duration of the approved works to ensure all biodiversity protection measures are carried out in accordance with these conditions of consent and the approved Biodiversity Development Assessment Report (GIS Environmental 31/10/19), relevant Biodiversity Management Plan (GIS Environmental 3/3/20), and Construction Environmental Management Plan (Lloyd Drilling Constructions Feb 2020).

The Project Ecologist must have one of the following memberships / accreditation:

- Practising member of the NSW Ecological Consultants Association (https://www.ecansw.org.au/find-a-consultant/) OR
- Biodiversity Assessment Method Accredited Assessor under the NSW Biodiversity Conservation Act 2016 (https://customer.lmbc.nsw.gov.au/assessment/AccreditedAssessor)

Evidence of engagement of the Project Ecologist is to be provided to the Principal Certifying Authority Prior to issue of Construction Certificate.

Reason: To protect native vegetation and wildlife in accordance with relevant Natural Environment LEP/DCP controls.

24. Compliance with Ecologist's Recommendations – Pre-construction

All pre-construction biodiversity-related measures specified in the approved Biodiversity Development Assessment Report (GIS Environmental 31/10/19), relevant Biodiversity Management Plan (GIS Environmental 3/3/20), and these conditions of consent are to be implemented at the appropriate stage of the development. Compliance with pre-construction measures are to be certified by the Project Ecologist prior to issue of the Construction Certificate.

Reason: To confirm compliance with wildlife and habitat protection/replacement measures in accordance with relevant Natural Environment LEP/DCP controls.



25. Implementation of Biodiversity Management Plan

All requirements in the relevant Biodiversity Management Plan (GIS Environmental 3/3/20) are to be implemented prior, during and post construction.

Details demonstrating pre-construction compliance are to be certified by the project ecologist and submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Biodiversity/Vegetation Conservation and Management.

26. Compliance with Standards

The development is required to be carried out in accordance with all relevant Australian Standards.

Details demonstrating compliance with the relevant Australian Standard are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure the development is constructed in accordance with appropriate standards.

27. Sydney Water "Tap In"

The approved plans must be submitted to the Sydney Water Tap in service, prior to works commencing, to determine whether the development will affect any Sydney Water assets and/or easements. The appropriately stamped plans must then be submitted to the Certifying Authority demonstrating the works are in compliance with Sydney Water requirements.

Please refer to the website www.sydneywater.com.au for:

- "Tap in" details see http://www.sydneywater.com.au/tapin
- Guidelines for Building Over/Adjacent to Sydney Water Assets.

Or telephone 13 000 TAP IN (1300 082 746).

Reason: To ensure compliance with the statutory requirements of Sydney Water.

28. **RMS Condition - Driveway Design and Construction**

The design and construction of the proposed driveway on the McCarrs Creek Road road reserve shall be in accordance with TfNSW requirements.

Details of these requirements should be obtained by email to DeveloperWorks.Sydney@rms.nsw.gov.au.

Detailed design plans of the proposed gutter crossing are to be submitted to TfNSW at development.sydney@rms.nsw.gov.au for approval prior to the issue of a Construction Certificate and commencement of any road works.

A plan checking fee and lodgement of a performance bond is required from the applicant prior to the release of the approved road design plans by TfNSW.

CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

29. **Tree protection**

(a)Existing trees which must be retained

i) All trees not indicated for removal in the Arboricultural Impact Assessment Reports for 143 McCarrs Creek Road dated 13 October 2019 and 145 McCarrs Creek Road dated



- 17 October 2019 prepared by Hugh the Arborist.
 - ii) Trees located on adjoining land
- (b) Tree protection

i) No tree roots greater than 25mm diameter are to be cut from protected trees unless authorised by the Project Arborist on site.

ii) All structures are to bridge tree roots greater than 50mm diameter unless directed otherwise by the Project Arborist on site.

iii) All tree protection to be in accordance with the approved Tree Protection Plan, the Arboricultural Impact Assessment Reports for 143 McCarrs Creek Road dated 13 October 2019 and 145 McCarrs Creek Road dated 17 October 2019 prepared by Hugh the Arborist.

and AS4970-2009 Protection of trees on development sites, with particular reference to Section 4 Tree Protection Measures.

iv) All tree pruning within the subject site is to be in accordance with WDCP2011 Clause

E1 Private Property Tree Management and AS 4373 Pruning of amenity trees

c) Tree protection measures are to be in place prior to commencement of works. The Project Arborist shall provide certification to the Certifying Authority that the tree protection measures are satisfactory prior to the commencement of works.

Reason: To ensure compliance with the requirement to retain and protect significant planting on the site.

30. Project Arborist

i) A Project Arborist with minimum qualification AQF Level 5 is to be appointed prior to commencement of works.

ii) The Project Arborist is to oversee all tree protection measures, removals and works adjacent to protected trees as outlined in the approved Tree Protection Plan and AS4970-2009 Protection of trees on development sites.

iii) The Project Arborist is to ensure compliance as relevant with any other environmental requirements conditioned under this consent.

iv) All tree protection measures specified must:

a) be in place before work commences on the site, and

b) be maintained in good condition during the construction period, and

c) remain in place for the duration of the construction works.

v) The Project Arborist shall provide certification to the Certifying Authority that all recommendations listed for the protection of the existing tree(s) have been carried out satisfactorily to ensure no impact to the health of the tree(s). Photographic documentation of the condition of all trees to be retained shall be recorded, including at commencement, during the works and at completion.

vi) The Certifying Authority must ensure that:

a) the activities listed in section 4.2 of Australian Standard 4970-2009 Protection of Trees on Development Sites, do not occur within the tree protection zone of any tree, and
b) any temporary access to, or location of scaffolding within the tree protection zone of a protected tree, or any other tree to be retained on the site during the construction, is undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of that standard.
vii) A separate permit or development consent may be required if the branches or roots of a protected tree on the site or on an adjoining site are required to be pruned or removed.

Reason: to ensure protection of vegetation proposed for retention on the site.



31. Installation and Maintenance of Sediment and Erosion Control

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004).

Techniques used for erosion and sediment control on site are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and the site is sufficiently stabilised with vegetation.

Reason: To protect the surrounding environment from the effects of sedimentation and erosion from the site.

32. Bushland Protection Fencing

Prior to the commencement of any onsite building works or commencement of vegetation clearance/modification, the boundary between the natural bushland zone or APZ and the construction area as shown on the Construction Environmental Management Plan (Lloyd Drilling Feb 2020) is to be surveyed and marked clearly on the ground.

A temporary 2.0 metre steel mesh fence is to be erected on the surveyed boundary between the natural bushland zone/APZ area and the construction area for the duration of construction work.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to commencement of works.

Reason: To ensure that the vegetation in the restricted development area is protected during and after construction.

33. **Compliance with Ecologist's Recommendations – During Construction**

All biodiversity-related measures are to be implemented during construction in accordance with the approved Biodiversity Development Assessment Report (GIS Environmental 31/10/19), relevant Biodiversity Management Plan (GIS Environmental 3/3/20), and these conditions of consent.

Compliance with these measures is to be certified by the Project Ecologist in writing to the Principal Certifying Authority prior to issue of the Occupation Certificate.

Reason: To confirm compliance with wildlife and habitat protection/replacement measures in accordance with relevant Natural Environment LEP/DCP controls.

34. Transplant Native Plant Species

As detailed within the approved Arborist Report, all native plants identified for transplantation are to be relocated within the subject site. The translocation is to be undertaken under the supervision of the Project Arborist.

Reason:To protect native vegetation and habitats in accordance with relevant Natural Environment LEP/DCP controls.

35. Ecologist to Induct Site Manager – Penguin and Bandicoot Habitat

Prior to commencement of construction works, the project ecologist is to meet with the site manager to:

a) advise of conditions to be implemented for protection of relevant threatened species



and endangered ecological communities;

- b) ensure that all workers are appropriately briefed on required protective measures; and
- c) inspect protective measures to confirm their adequacy and advise the proponent and site manager of the inspection results and their implications.

Reason: To prevent impacts to threatened species, endangered ecological communities and their habitats in accordance with the Biodiversity Conservation Act 2016.

36. **RMS Condition - Excavation of site and support structures**

The developer is to submit design drawings and documents relating to the excavation of the site and support structures to TfNSW for assessment, in accordance with Technical Direction GTD2012/001.

The developer is to submit all documentation at least six (6) weeks prior to commencement of construction and is to meet the full cost of the assessment by TfNSW. Documents should be submitted to Development.Sydney@rms.nsw.gov.au

If it is necessary to excavate below the level of the base of the footings of the adjoining roadways, the person acting on the consent shall ensure that the owner/s of the roadway is/are given at least seven (7) day notice of the intention to excavate below the base of the footings. The notice is to include complete details of the work.

37. RMS Condition - Stormwater Drainage System

Detailed design plans and hydraulic calculations of any changes to the stormwater drainage system are to be submitted to TfNSW for approval, prior to the commencement of any works.

Please send all documentation to development.sydney@rms.nsw.gov.au.

A plan checking fee will be payable and a performance bond may be required before TfNSW approval is issued.

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

38. Road Reserve

The applicant shall ensure the public footways and roadways adjacent to the site are maintained in a safe condition at all times during the course of the work.

Reason: Public Safety.

39. Installation and Maintenance of Sediment Control

Prior to any works commencing on site, including demolition, sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004). Techniques used for erosion and sediment control on site are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and the site is sufficiently stabilised with vegetation.

Reason: To protect the surrounding environment from the effects of sedimentation and erosion from the site.

40. Civil Works Supervision

The Applicant shall ensure all civil works approved in the Section 138 Road approval are



supervised by an appropriately qualified and practising Civil Engineer.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority and/or Roads Authority.

Reason: To ensure compliance of civil works with Council's specification for engineering works.

41. Protection of rock and sites of significance

a) All rock outcrops outside of the area of approved works are to be preserved and protected at all times during demolition excavation and construction works.

b) Should any Aboriginal sites be uncovered during the carrying out of works, those works are to cease and Council, the NSW Office of Environment and Heritage (OEH) and the Metropolitan Local Aboriginal Land Council are to be contacted.

Reason: Preservation of significant environmental features.

42. Fauna and Tree Hollow re-location

During any vegetation clearance for Asset Protection Zones and construction works the Project Ecologist is to be present to re-locate any displaced fauna that may be disturbed during this activity.

Tree hollows are to be salvaged from trees within the development area and placed within the retained vegetation / Conservation Areas within the Lots. This is to be done by a qualified and experienced Arborist, under the direction of the Project Ecologist.

Details prepared by the project ecologist in writing demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To ensure bushland management in accordance with Local Habitat Strategy 2007.

43. **CEMP to be Implemented**

Construction is to be undertaken in accordance with the Construction Environmental Management Plan (CEMP). All workers are to be made aware of the content of the CEMP.

Reason: To ensure conditions for the prevention of construction-related biodiversity impacts are complied with during the construction phase.

44. **Protection Fencing**

Protection fencing measures (including sedimentation fences) are to be installed in accordance with all approved plans including those specified in the Arborist Report and/or Ecological Sustainability Plan or Bushland Management Plan. Protection measures are to be maintained for the duration of the works. Protection fencing that is no longer required is to be removed once all works are completed.

Reason: Environmental Protection

45. Arborist Recommendations to be Implemented

As there are existing trees to be retained within 5 metres of proposed development works, all recommendations as outlined in the supplied arborist report by Hugh The Arborist, dated February 2020 are required to be complied with before and throughout the development period, particularly with regard to the following:



- a) Works, erection/demolition of structures, excavation or changes to soil levels within 5 metres of existing trees are not permitted unless part of the development as approved, and the storage of spoil, building materials, soil or the driving and parking of any vehicle or machinery within 5 metres of the trunk of a tree to be retained is not permitted;
- b) Where specified, tree guards are to be provided to all trees as indicated in the report, and are to be installed prior to the commencement of any work on the site. Tree guard materials and dimensions are specified in the arborist report;
- c) All works within 5 metres of existing trees including demolition, excavation, civil works, fencing and the like must be carried out by hand and under the supervision of an experienced and suitably qualified arborist. In the event that major structural or feeder roots are encountered, the arborist is to advise the builder to carry out appropriate action to ensure the retention of the tree.
- d) Signage is to be erected advising all contractors and visitors to the site that no works or storage is to take place within the calculated Tree Protection Zone (TPZ) of existing trees.

Any changes or alterations made to the tree management recommendations as outlined by the arborist report due to the discovery of new structural roots or underground services during development works must be reported to the Principal Certifying Authority prior to works recommencing.

Reason: To ensure the retention of the Urban Forest/Natural Environment and remain consistent with approved reports.

46. **RMS Condition - Road Occupancy Licence**

A Road Occupancy Licence (ROL) should be obtained from Transport Management Centre for any works that may impact on traffic flows on McCarrs Creek Road during construction activities. A ROL can be obtained through https://myrta.com/oplinc2/pages/security/oplincLogin.jsf

CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

47. Condition of retained vegetation

Prior to the issue of an Occupation Certificate, a report prepared by the Project Arborist shall be submitted to the Certifying Authority, assessing the health and impact of trees and vegetation required to be retained as a result of the proposed development, including the following information:

- a) Compliance to Arborist recommendations for tree protection and excavation works.
- b) Extent of damage sustained by vegetation as a result of the construction works.
- c) Any subsequent remedial works required to ensure the long term retention of the vegetation.

Reason: To ensure compliance with the requirement to retain and protect significant planting on development sites.

48. Stormwater Disposal

The stormwater drainage works shall be certified as compliant with all relevant Australian



Standards and Codes by a suitably qualified person. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater arising from the development.

49. **Retaining wall**

The retaining wall works shall be certified as compliant with all relevant Australian Standards and Codes by a Structural Engineer. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any final Occupation Certificate.

Reason: Public and Private Safety

50. Geotechnical Certification Prior to Occupation Certificate

The Applicant is to submit the completed Form 3 of the Geotechnical Risk Management Policy (Appendix 5 of P21 DCP) to the Principal Certifying Authority prior to issue of the Occupation Certificate.

Reason: To ensure geotechnical risk is mitigated appropriately.

51. Certification of Civil Works and Works as Executed Data on Council Land

The Applicant shall submit a suitably qualified Civil Engineer's certification that the completed road works have been constructed in accordance with this consent and the approved Section 138 Road Act approved plans. Works as Executed plan drawn in red over the approved plan certified by a registered surveyor in relation to boundaries shall be submitted to Council and the Principal Certifying Authority for approval prior to the issue of the Occupation Certificate.

Reason: To ensure compliance of works with Council's specification for engineering road works.

52. Weed Removal and Management

No weeds are to be imported on to the site.

All invasive and priority weeds on the site are to be removed and managed continuously, in accordance with the Biosecurity Act 2015.

Details demonstrating the removal and management of weeds are to be prepared by the project ecologist in writing and submitted to the Principal Certifying Authority prior to occupation certificate.

Reason: Weed management and biosecurity

53. Works as Executed Drawings - Stormwater Treatment Measures

Works as Executed Drawings for the stormwater treatment measures must be prepared in accordance with Council's Guideline for Preparing Works as Executed Data for Council Stormwater Assets.

The drawings shall be submitted to the Principal Certifying Authority prior to the release of the Occupation Certificate.



Reason: Protection of the receiving environment

54. **Compliance with Ecologist's Recommendations – Post Construction**

All biodiversity-related measures are to be implemented at the appropriate stage of development in accordance with the approved Biodiversity Development Assessment Report (GIS Environmental 31/10/19), relevant Biodiversity Management Plan (GIS Environmental 3/3/20) and these conditions of consent.

Satisfactory establishment/initiation of post-construction measures is to be certified by the Project Ecologist prior to issue of any Occupation Certificate.

Reason: To confirm compliance with wildlife and habitat protection/replacement measures in accordance with relevant Natural Environment LEP/DCP controls.

55. House / Building Number

House/building number is to be affixed to the building to be readily visible from the public domain.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: Proper identification of buildings.

ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

56. Undesirable Trees

Leighton Green Cypress Cupressocyparis leylandii or any of its cultivars, must not be planted on the site for the life of the development. In the event of any inconsistency between this condition and the development application documents, this condition will prevail to the extent of the inconsistency.

Reason: To reduce the potential for adverse amenity effects such as overshadowing, loss of views, and loss of plant diversity.

57. Environmental and priority weed control (PLEP)

Condition: All weeds are to be removed and controlled in accordance with the Biodiversity Conservation Act 2016.

Reason: Preservation of environmental amenity.

58. Control of Weeds

Prior to the completion of works, all priority weeds (as listed under the Biosecurity Act 2015) are to be removed/controlled within the subject site using an appropriately registered control method. Information on weeds of the Northern Beaches can be found at the NSW WeedWise website (http://weeds.dpi.nsw.gov.au/). All environmental weeds are to be removed and controlled. Refer to Council website

http://www.pittwater.nsw.gov.au/environment/noxious_weeds

Reason: Weed management.

59. Compliance with Ecologist's Recommendations – Ongoing

All ongoing biodiversity-related measures are to be implemented in accordance with the approved Biodiversity Development Assessment Report (GIS Environmental 31/10/19), relevant



Biodiversity Management Plan (GIS Environmental 3/3/20) and these conditions of consent.

Reason: To confirm compliance with wildlife and habitat protection/replacement measures in accordance with relevant Natural Environment LEP/DCP controls

60. Maintenance of Stormwater Treatment Measures

Stormwater treatment measures must be maintained at all times in accordance with manufacturer's specifications and as necessary to achieve the required stormwater quality targets for the development.

Northern Beaches Council reserves the right to enter the property and carry out appropriate maintenance of the device at the cost of the property owner.

Reason: Protection of the receiving environment

61. No Planting Environmental Weeds

No environmental weeds are to be planted on the site. Information on weeds of the Northern Beaches can be found at the NSW WeedWise website (http://weeds.dpi.nsw.gov.au/).

Reason: Weed management.

62. Works to cease if item found

If any Aboriginal Engravings or Relics are unearthed all work is to cease immediately and the Aboriginal Heritage Office (AHO) and Office of Environment and Heritage (OEH) are to be notified.

Reason: To protect Aboriginal Heritage.

63. Dead or Injured Wildlife

If construction activity associated with this development results in injury or death of a native mammal, bird, reptile or amphibian, a registered wildlife rescue and rehabilitation organisation must be contacted for advice.

Reason: To mitigate potential impacts to native wildlife resulting from construction activity.



Right to Review by the Council

You may request Council to review this determination of the application under Division 8.2 of the Environmental Planning & Assessment Act 1979. Any Division 8.2 Review of Determination application should be submitted to Council within 3 months of this determination, to enable the assessment and determination of the application within the 6 month timeframe.

NOTE: A fee will apply for any request to review the determination.

Right of Appeal

If you are dissatisfied with this decision Division 8.3 of the Environmental Planning & Assessment Act 1979 may give you the right to appeal to the Land and Environment Court within 6 months after the date on which you receive this notice.

Signed On behalf of the Consent Authority


Name Tony Collier, Principal Planner

Date 02/07/2020



GENERAL ADVICE Advisory Notes (General)

Where are you in the development process?



Note: The advice within this document is provided in good faith as a guide to assist applicants understand the broad process and will not detail every step or every requirement for demolition, building construction works or subdivision required or business operating requirements under New South Wales or Commonwealth Legislation. If you require clarification or have any questions, please contact your Certifier or Council's Planning and Development Enquiries Team.

The attached Notice of Determination includes conditions of consent which must be complied with.

(Note: A failure to gain approval prior to the works being carried out is a serious breach of the Environmental Planning & Assessment Act 1979 which attracts penalties and may also result in legal action.)



Building Certification

The Environmental Planning and Assessment Act 1979 provides that:

- Building work cannot occur unless a construction certificate has been issued;
- Occupation of building works cannot occur unless an occupation certificate has been issued
- Subdivision cannot be registered until a subdivision certificate has been issued
- Mandatory Inspection for building work must be completed

Please refer to process chart for more detail.

(Note: A failure to gain approval prior to the works being carried out is a serious breach of the Environmental Planning & Assessment Act 1979 which attracts penalties and may also result in legal action.)

Certification Services

Construction Certificates / Occupation Certificates / Subdivision Certificates / Strata Certificates, can be issued by Council or an accredited private certifier (Note Council must be the Principal Certifying Authority (PCA) for subdivisions).

Council is well placed to provide Certification Services. Council can issue Construction Certificates and act as your Principle Certifying Authority at competitive rates. Please visit our web site www.northernbeaches.nsw.gov.au or speak to our Customer Service Officers if you have any further questions about our Certification Services or if you wish to use Council as your certifier.

Charges Associated with the Development Consent

All bonds, fees, Development Contributions or the Long Service Levy detailed within the Notice of Determination are required to be paid prior to the issuing of any Construction Certificate.

Bonds are released after:

- 1. 'Final Occupation Certificate' has been received by Council; and
- 2. Final inspection by a Council Officer where:
 - the development is complete
 - o damage has not been caused to council assets during the works
 - o conditions of development consent have been met.

The bond will be released to the person or business who paid the bond to Council (The name that appears on the original receipt)

Acceptable Form of Security Bonds

Council will accept bank guarantee (in a form acceptable to Council) in lieu of cash and is required prior to the issue of a construction certificate.

Modifications to the consent

If you seek to make any changes to the development (which may include internal / external configuration of the building, variation to facades, site layout or any changes to the proposed operation or use), the modifications may require the submission and approval of an application to modify the development consent prior to the issuing of a Construction Certificate and prior to the works being



carried out. The proposed changes should be discussed with the PCA.

(Note: A failure to gain approval prior to the works being carried out is a serious breach of the Environmental Planning & Assessment Act 1979 which attracts penalties and may also result in legal action.)

Other Matters not detailed within the Notice of Determination

The Notice of Determination does not stipulate every requirement that must be completed to satisfy New South Wales and Commonwealth legislation.

You should check, as may be relevant, with other authorities including but not limited to:

- Workcover NSW for work safety and asbestos requirements
- Sydney Water Quick Check Agent for the provision of water and sewer services
- Energy & Gas suppliers for utility services
- Department of Fair Trading for advice about builders and licensing
- Building Professionals Board for advice about private certifiers
- NSW Roads and Maritime Services for works on state roads only
- Human Rights and Equal Opportunity Commission for access issues
- NSW Land and Property Information for Land Title matters
- Australia Post for the positioning and dimensions of mail boxes in new commercial and residential developments;

Dial Before You Dig

Underground assets may exist in the area that is subject to your application. In the interests of health and safety and in order to protect damage to third party assets please contact Dial before you dig at www.1100.com.au or telephone on 1100 before excavating or erecting structures (This is the law in NSW). If alterations are required to the configuration, size, form or design of the development upon contacting the Dial before You Dig service, an amendment to the development consent (or a new development application) may be necessary. Individuals owe asset owners a duty of care that must be observed when working in the vicinity of plant or assets. It is the individual's responsibility to anticipate and request the nominal location of plant or assets on the relevant property via contacting the Dial before you dig service in advance of any construction or planning activities.

Telecommunications Act 1997 (Commonwealth)

Telstra (and its authorised contractors) are the only companies that are permitted to conduct works on Telstra's network and assets. Any person interfering with a facility or installation owned by Telstra is committing an offence under the Criminal Code Act 1995 (Cth) and is liable for prosecution. Furthermore, damage to Telstra's infrastructure may result in interruption to the provision of essential services and significant costs. If you are aware of any works or proposed works which may affect or impact on Telstra's assets in any way, you are required to contact :Telstra's Network Integrity Team on Phone Number 1800810443.

(1) if the development is likely to disturb or impact upon telecommunications infrastructure, written confirmation from the service provider that they have agreed to the proposed works must be submitted



to the Principal Certifying Authority prior to the issue of a Construction Certificate or any works commencing, whichever occurs first; and

(2) The arrangements and costs associated with any adjustment to telecommunications infrastructure shall be borne in full by the applicant/developer.

Model

If you submitted a model with the application it must be collected from the Council offices within fourteen (14) days of the date of this determination. Models not collected will be disposed of by Council.

Trade waste agreement

A Trade Waste Agreement must be obtained from Sydney Water prior to the discharge of trade wastewater to the sewer system. Trade wastewater is defined as 'discharge water containing any substance produced through industrial or commercial activities or operation on the premises'.

Waste collection

Liquid and solid wastes generated on the site must be collected, transported and disposed of in accordance with the requirements of the Protection of the Environment Operations Act 1997. Records must be kept of all waste disposal from the site.

Material to be removed from the site must be source separated on site to maximise recycling, and the material disposed of to an appropriate disposal and recycling facility in accordance with the approved Waste Management Plan.

Aboriginal Heritage

If in undertaking excavation or works and any Aboriginal site or object is, or is thought to have been found, all works are to cease immediately and the applicant is to contact the Aboriginal Heritage Officer for Warringah Council, and the Cultural Heritage Division of the Department of Environment and Climate Change (DECC).

On-Site Sewage Management System

This approval does not authorise the installation or operation of a new or modification of an existing onsite wastewater management system. An On-Site Sewage Management System must not be installed or operated unless an 'Approval to Install an On Site Sewage Management System' is obtained from Warringah Council.

Cost of Works

The applicant shall bear the cost of all works associated with the development that occurs on Council's property.

Relocation of stormwater drainage

Council is not responsible for the cost of relocating Council's stormwater drainage pipes through the subject property.

Tree preservation

Where tree work has not been approved by this Development Consent the developer is notified that a general Tree Preservation Order applies to all trees in the Northern Beaches Local Government Area. This order prohibits the ringbarking, cutting down, topping, lopping, pruning, transplanting, injuring, or wilful destruction of such trees except without the prior written consent of Council.

Storage bins on footpath and roadway

Approval is required from Council prior to the placement of any storage bin on Council's footpath and/or roadway.



Protection of Public Places

(1) If the work involved in the erection or demolition of a building:

(a) is likely to cause pedestrian or vehicular traffic in a public place to be obstructed or rendered inconvenient; or

(b) building involves the enclosure of a public place,

a hoarding and site fencing must be erected between the work site and the public place.

(2) If necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.

(3) The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.

(4) Any such hoarding, fence or awning is to be removed when the work has been completed.(5) No access across public reserves or parks is permitted.

Note: Prior to the erection of any temporary fence or hoarding over property owned or managed by Council, written approval must be obtained.

Road Opening Permit

The developer/applicant is to obtain a "Road Opening Permit" from Council and pay all appropriate charges prior to commencement of any work on Council property. The developer/applicant shall be responsible for all public utilities and services in the area of the work, and as such shall notify all relevant Authorities, and bear all costs associated with any repairs and/or adjustments as those Authorities may deem necessary.

Special Permits

Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development are to occur entirely on the property. The applicant, owner or builder must apply for specific permits available from Council. A minimum of forty-eight (48) hours notice is required for all permits except work zones, which may require additional assessment time.

• Permit for on-street mobile plant

Restrictions apply to the hours of operation and the area of operation for on street mobile plant equipment (for example cranes, concrete pumps, cherry pickers). Separate permits are required for each occasion and each piece of equipment. It is the responsibility of the applicant, owner and builder to take whatever steps are necessary to ensure that the use of any equipment does not violate adjoining property owner's rights.

• Hoarding Permit

Permits are required to erect Class A, Class B and Class C hoardings. If an 'A' Class hoarding is to alienate a section of Council's property, that section will require a permit for the occupation of Council's property.

• Storage of building materials and building waste containers (skips) on Council's property

Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded by Council with no additional notice being given.



• Kerbside restrictions, work zones

Existing kerbside restrictions apply. An application must be made to Council for the alteration of existing kerbside restrictions or the provision of a construction zone. Other permits may include out of construction hours permits.

Licensing requirements for removal of bonded asbestos

Anyone who removes, repairs or disturbs bonded asbestos must hold a bonded or a friable asbestos licence, or a demolition licence in accordance with Workcover requirements and the Occupational Health and Safety Act 2000.

Pool Access

Access to pools are required to be restricted by a child resistant barrier in accordance with the regulations prescribed in all relevant Acts, Regulations and Australian Standards including:

- (i) Swimming Pools Act 1992;
- (ii) Swimming Pools Amendment Act 2012;
- (iii) Swimming Pools Regulation 2008
- (iv) Australian Standard AS1926 Swimming Pool Safety
- (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
- (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools

It is your responsibility as a land owner to ensure any fencing is maintained.

Dewatering

Where dewatering works are required on the development site during construction, the developer/applicant must apply for and obtain a bore license from the NSW Department of Water and Energy. The bore license must be obtained prior to commencement of dewatering works.

Requirement to Notify about New Contamination Evidence

Any new information revealed during works that has the potential to alter previous conclusions about site contamination or hazardous materials shall be immediately notified to Council and the Principal Certifying Authority.

Flood Evacuation Plan

If your site is on flood prone land you may wish to consider the preparation of a flood evacuation plan.

Generally a Flood Evacuation Plan would be prepared by suitably qualified Engineer (e.g. Hydraulic) with a number of years experience in flood management and who is eligible for Membership to the Australian Institute of Engineers.

Some matters that you may wish to consider (but not limited to) include:

- (i) a route of evacuation to higher ground and / or point of shelter
- (ii) depth of water for a Possible Maximum Flood event surrounding the building

(iii) details of 'last chance' evacuation water levels / times for evacuation prior to floodwaters surrounding the building

- (iv) provide details of flood warning systems and protocols
- (v) details of how this information will be distributed and people educated for users of the site.

You may seek to discuss this with the State Emergency Service of NSW.

Utility Service Requirements

DA2019/1248



Where development requires the installation of, or the relocation of utility services being (but not limited to) gas, water, electricity and telecommunications, the installation of, or the relocation of utility services shall be conducted in accordance with the requirements of the relevant service provider / authority (unless stipulated by any other condition of the consent or will result in damage to threatened or endangered species defined under the Threatened Species Conservation Act 1995).

Plant & Equipment Kept Within Site

All plant and equipment used in the erection of the building, including concrete pumps, wagons, lifts, mobile cranes, etc, shall be situated within the boundaries of the site and so placed that all concrete slurry, water, debris and the like shall be discharged onto the building site, and is to be contained within the site boundaries. This does not prevent any requirement to comply with the Protection of the Environment Operations Act.

Lighting

Illumination of the site is to be arranged in accordance with the requirements of Australian Standard 4282 - 1997 Control of the obtrusive effects of outdoor lighting so as not to impact upon the amenity of the occupants of adjoining and nearby residential premises.

Silt and Sediment Control

During any onsite demolition, excavation and construction works, the site should be maintained in accordance with "The Blue Book - Managing Urban Stormwater (MUS): Soils and Construction".

In managing the site provision shall be made throughout the period of works to prevent transmission of soil to the public road, drainage system, any riparian lands or off site in any manner. Upon completion of the development, any measures to prevent the transition of soil off site to remain in place until the site is stabilised.

A failure to prevent the transmission of silt and sediment and / or causing, water pollution, air pollution, noise pollution or land pollution may result in a breach of the Protection of the Environment Operations Act and orders, penalties and prosecutions may occur.

Maintenance of Sediment and Erosion Control Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain.

Reason: To avoid erosion and sedimentation impacts that will result in an adverse change in watercourse or riparian land condition

Installation and Maintenance of Sediment and Erosion Control

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: soils and construction (2004).

Techniques used for erosion and sediment control on site are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and the site is sufficiently stabilised with vegetation.

Reason: To protect the surrounding environment from the effects of sedimentation and erosion from the site

Dividing Fences Act 1991

The construction and maintenance of side boundary fences is to be agreed upon by all adjoining property owners of the fence. Works are to be in accordance with the Dividing Fences Act 1991.

OTHER MATTERS



Child Care Centres

A license to operate a child care centre must be obtained from the NSW Department of Community Services prior to the commencement of the use of the child care centre.

Disability Access

This decision does not ensure compliance with the Commonwealth Disability Discrimination Act 1992. Applicants are strongly advised to investigate their requirements under that Act

Food Premises

Food premises are required to comply with the requirements of the Food Act 2003, the Food Standards Code and Australian Standards.

The proprietor of a food business must notify the NSW Food Authority of the details of the business. Notification may be done either online at www.foodnotify.nsw.gov.au or by lodging a completed NSW Food Authority notification form to the NSW Food Authority or Council.

Wheel washing facility

All trucks leaving the site, having had access to unpaved or contaminated areas, shall depart via a wheel wash facility in order to prevent mud, dust or debris from being deposited on Council's roads. The wheel wash facility shall be constructed prior to any truck movements occurring. Water from the wheel wash facility must not cause pollution. Any direction of Council with regard to cleaning trucks or the clean up of road pavements adjoining the site shall be complied with immediately.

Monitoring State of Roadways

The applicant shall monitor the state of roadways leading to and from the site and shall take all necessary steps to clean up any adversely impacted road pavements as directed by Council.

Storage of Dangerous Goods

Prior to the storage of any "dangerous goods" on the premises, a copy of a license obtained from the Chemical Safety Branch of Work Cover Authority must be submitted to Council.

Storage of Flammable and Combustible Liquids

Flammable and combustible liquids must be stored in accordance with Australian Standard 1940 The Storage and Handling of Flammable and Combustible Liquids.

Noise and Vibration

The premises, including operation of vehicles, shall be conducted so as to avoid offensive noise or vibration and cause no interference to adjoining or nearby occupants. Special precautions must be taken to avoid nuisance in neighbouring residential areas, particularly from machinery, vehicles, warning sirens, public address systems and the like.

Hairdressing/Beauty Treatment/ Skin penetration Requirements

The premises must comply with the following requirements before the commencement of business: i) A hand wash basin with warm water delivered through a common spout must be provided in the treatment area. The hand wash basin must be provided with liquid soap and paper towel. ii) The wall behind the hand wash basin from the floor to a height of 450mm above the top of the washbasin and from the centre of the washbasin to a distance of 140mm beyond each side of the wash basin, must be finished with a material that is durable, smooth, impervious to moisture and capable of being easily cleaned (eg tiles).

iii) The premises must be provided with washing, drainage, ventilation and lighting that are adequate for the carrying out of hairdressing/beauty treatment/skin penetration procedures.

iv) The floor coverings must be smooth and impervious.



v) All furniture, shelves and fittings must be constructed of, or covered with a material that is smooth, impervious to moisture and capable of being easily cleaned.

vi) Adequate lockers must be provided for the storage of employees clothing and personal effects.

vii) The premises must be provided with facilities that are adequate for the purpose of storing of hairdressing/beauty treatment/skin penetration appliance and utensils.

viii) The premises must be provided with a sink sullied with hot and cold water for washing equipment.

Food Premises Construction Requirements

The food premises must comply with the following specific construction requirements:

Solid walls must be provided in all food handling areas (solid includes brick, cement and foam filled preformed panels);

ix) Walls in food preparation and wash up areas must be finished with a smooth and impervious surface to a height of at least 2 metres.

x) Hand wash basins must be provided with warm water delivered through a common spout with taps that are hands free operation;

xi) Coving with a radius of 25mm must be provided between all floor and wall joints in food handling areas;

xii) The open space between the top of the coolroom and the ceiling must be fully enclosed and kept insect and pest proof;

xiii) The coolroom must be able to be opened from the inside with out a key and fitted with an alarm that can only be operated from within the coolroom;

xiv) The doors to the toilet air lock and toilet compartment must be tight fitting and self closing;

xv) The rear external door must be self closing or be provided with a fly screen that is self closing;

xvi) Where cooking or extensive heating processes or such other processes as may be specified are carried out in food preparation areas, an approved mechanical ventilation system shall be installed and operated in accordance with AS 1668 part 1 & 2.

Legionella Control

Cooling towers, warm water systems, water cooling systems must be registered with the Council. Details of registration are to be provided to the Council prior to operation.

Pool/Spa Safety

Owners of properties with swimming pools and spa's must meet safety compliance and registration requirements. Provisions also apply when renting/selling properties. Details are available from the Division of Local Government.

Grease Trap

Contact Sydney Water to determine what trade waste provisions you are required to provide to your food premises. Should a grease trap be required by Sydney Water, it must be located in an area that is easily accessible for the removal of waste water and must not be installed in any kitchen, food preparation or food stage area. The design and location of the grease trap should also not impede on any commercial right of way or pedestrian access.

Bandicoot/Penguin

Long-nosed Bandicoots & Little Penguins – Best Practices for Residents Residents are encouraged to follow a number of *Best Practices* to assist with the protection and management of the endangered populations of Long-nosed Bandicoots and Little Penguins:

- Long-nosed Bandicoots, Little Penguins and other native animals should never be fed as it may cause them nutritional problems, hardship if supplementary feeding is stopped, and it may increase predation.
- Feral cats or foxes should never be fed or food left out where they can access it, such as rubbish bins without lids or pet food bowls, as these animals present a significant threat to Long-nosed Bandicoots, Little Penguins and other wildlife.
- The use of insecticides, fertilisers, poisons and/or baits should be avoided on the property.



Garden insects will be kept in low numbers if Long-nosed Bandicoots are present.

- When the North Head Long-nosed Bandicoot Recovery Plan is released it should be implemented where relevant.
- Dead Long-nosed Bandicoots or Little Penguins should be reported by phoning Manly Council on 9976 1500 or Department of Environment and Conservation on 9960 6266.
- Please drive carefully as vehicle related injuries and deaths of Long-nosed Bandicoots and Little Penguins have occurred in the area. Care should also be taken at night in the drive way when moving cars as bandicoots will seek shelter beneath vehicles.
- Cat/s and or dog/s that currently live on the property should be kept indoors at night to avoid disturbance/death of native animals. Ideally, when the current cat/s and/or dog/s that live on the property no longer reside on the property it is recommended that they not be replaced by new dogs or cats.
- Report all sightings of feral rabbits, feral or stray cats and/or foxes to N B Council.