

## Landscape Referral Response

<b>Application Number:</b>	DA2022/0964
<b>Date:</b>	29/06/2022
<b>Responsible Officer:</b>	Claire Ryan
<b>Land to be developed (Address):</b>	Lot 45 DP 15318 , 42 Bix Road DEE WHY NSW 2099

### Reasons for referral

This application seeks consent for the following:

- Construction / development works within 5 metres of a tree or
- New residential works with three or more dwellings. (RFB's, townhouses, seniors living, guesthouses, etc). or
- Mixed use developments containing three or more residential dwellings.
- New Dwellings or

### Officer comments

The application seeks consent for alterations and additions to a dwelling house including a carport and a swimming pool.

The application is assessed by Landscape Referral against Warringah Local Environmental Plan 2011 and the following Warringah Development Control Plan 2011 controls (but not limited to):

I D1 Landscaped Open Space and Bushland Setting  
I E1 Preservation of Trees or Bushland Vegetation and  
I E6 Retaining Unique Environmental Features

The Arborist's Report prepared by Complete Arborcare dated 29/05/2022 is noted.

The Report assesses 3 trees in relation to the proposed works. One tree is a street tree and the two others are on the subject site.

The Report indicates that one tree, Tree 2 should be removed due to health and structural issues. The other two trees are recommended for retention, subject to Arboricultural supervision.

No other significant landscape features are indicated to be affected by the works.

No objections are raised with regard to landscape issues subject to conditions.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

### Recommended Landscape Conditions:

## CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

### Project Arborist

a) A Project Arborist, with minimum AQF Level 5 in arboriculture, shall be engaged to provide tree protection measures in accordance with the Arboricultural Impact Assessment prepared by Complete Arborcare dated 29/05/2022 and Australian Standard 4970-2009 Protection of Trees on Development Sites. The Project Arborist is to specify and oversee all tree protection measures such as tree protection fencing, trunk and branch protection and ground protection.

b) The Project Arborist is to supervise all demolition, excavation and construction works near all trees to be retained including construction methods near the existing trees to protect tree roots, trunks, branches and canopy. Where required, manual excavation is to occur ensuring no tree root at or >25mm (Ø) is damaged by works unless approved by the Project Arborist.

c) Existing ground levels shall be maintained within the tree protection zone of trees to be retained unless authorised by the Project Arborist.

d) All tree protection measures specified must:

- i) be in place before work commences on the site, and
- ii) be maintained in good condition during the construction period, and
- iii) remain in place for the duration of the construction works.

e) The Project Arborist shall provide certification to the Certifying Authority that all recommendations listed for the protection of the existing tree(s) have been carried out satisfactorily to ensure no impact to the health of the tree(s). Photographic documentation of the condition of all trees to be retained shall be recorded including at commencement, during the works and at completion.

- Note:
- i) A separate permit or development consent may be required if the branches or roots of a protected tree on the site or on an adjoining site are required to be pruned or removed.
  - ii) Any potential impact to trees as assessed by the Project Arborist will require redesign of any approved component to ensure existing trees upon the subject site and adjoining properties are preserved and shall be the subject of a modification application where applicable.

Reason: Tree protection.

### Tree Removal Within the Property

This consent approves the removal of the following tree(s) within the property:

- i) Tree 2 as identified in the Arboricultural Impact Assessment prepared by Complete Arborcare dated 29/05/2022

Note: Exempt Species as listed in the Development Control Plan or the Arboricultural Impact Assessment do not require Council consent for removal.

Reason: To enable authorised building works.

## CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

### **Protection of Existing Street Trees**

a) All existing street trees in the vicinity of the works shall be retained during all construction stages and the street trees fronting the development site shall be protected by tree protection fencing in accordance with Australian Standard 4687-2007 Temporary Fencing and Hoardings and in accordance with Section 4 of Australian Standard 4970-2009 Protection of Trees on Development Sites.

b) As a minimum, the tree protection fencing for street tree(s) fronting the development site shall consist of standard 2.4m panel length to four sides unless otherwise directed by an Arborist with minimum AQF Level 5 in arboriculture.

c) All fencing shall be located to allow for unrestricted and safe pedestrian access upon the road verge.

d) Should any problems arise with regard to the existing or proposed trees on public land during construction, Council's Tree Services section is to be contacted immediately to resolve the matter to Council's satisfaction and at the cost of the applicant.

Reason: Tree protection.

### **Tree and Vegetation Protection**

- a) Existing trees and vegetation shall be retained and protected including:
- i) all trees and vegetation within the site not approved for removal, excluding exempt trees and vegetation under the relevant planning instruments of legislation,
  - ii) all trees and vegetation located on adjoining properties,
  - iii) all road reserve trees and vegetation.
- b) Tree protection shall be undertaken as follows:
- i) tree protection shall be in accordance with the Arboricultural Impact Assessment prepared by Complete Arborcare dated 29/05/2022 and Australian Standard 4970-2009 Protection of Trees on Development Sites including the provision of temporary fencing to protect existing trees within 5 metres of development,
  - ii) existing ground levels shall be maintained within the tree protection zone of trees to be retained unless authorised by the Project Arborist,
  - iii) removal of existing tree roots at or >25mm (Ø) diameter is not permitted without consultation with the Project Arborist,
  - iv) no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,
  - v) structures are to bridge tree roots at or >25mm (Ø) diameter unless directed by the Project Arborist on site,
  - vi) excavation for stormwater lines and all other utility services is not permitted within the tree protection zone without consultation with the Project Arborist including advice on root protection measures,
  - vii) should either or all of v), vi) and vii) occur during site establishment and construction works, the Project Arborist shall provide recommendations for tree protection measures. Details including photographic evidence of works undertaken shall be submitted by the Arborist to the Certifying Authority,
  - viii) any temporary access to or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of Australian Standard 4970-2009 Protection of Trees on Development Sites,

- ix) the activities listed in section 4.2 of Australian Standard 4970-2009 Protection of Trees on Development Sites shall not occur within the tree protection zone of any tree on the lot or any tree on an adjoining site,
- x) tree pruning from within the site to enable approved works shall not exceed 10% of any tree canopy and shall be in accordance with Australian Standard 4373-2007 Pruning of Amenity Trees,
- xi) the tree protection measures specified in this clause must:
  - i) be in place before work commences on the site, and
  - ii) be maintained in good condition during the construction period, and
  - iii) remain in place for the duration of the construction works.

The Certifying Authority must ensure that:

- c) The activities listed in section 4.2 of Australian Standard 4970-2009 Protection of Trees on Development Sites do not occur within the tree protection zone of any tree and any temporary access to or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained on the site during the construction is undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of that standard.

Note: All street trees within the road verge and trees within private property are protected under Northern Beaches Council development control plans except where Council's written consent for removal has been obtained. The felling, lopping, topping, ringbarking or removal of any tree (s) is prohibited.

Reason: Tree and vegetation protection.

## **CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE**

### **Required Tree Planting**

a) Trees shall be planted in accordance with the following:

- i) 1 tree capable of attaining a minimum height of 5m at maturity; located within the grounds of the property; minimum pot size 200mm

b) Native tree planting species may be selected from Council's list:

[www.northernbeaches.nsw.gov.au/environment/native-plants/native-plant-species-guide](http://www.northernbeaches.nsw.gov.au/environment/native-plants/native-plant-species-guide).

c) Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any Occupation Certificate.

Reason: To maintain environmental amenity.