

Natural Environment Referral Response - Coastal

Application Number:	DA2019/0666
Responsible Officer	Renee Ezzy
Land to be developed (Address):	Lot 701 DP 1143488 , 13 Amiens Road CLONTARF NSW 2093

Reasons for referral

This application seeks consent for land located within the Coastal Zone.

And as such, Council's Natural Environment Unit officers are required to consider the likely impacts on drainage regimes.

Officer comments

The application has been assessed in consideration of the Coastal Management Act 2016, State Environmental Planning Policy (Coastal Management) 2018, Sydney Harbour Catchment Regional Environment Plan, 2005 and Sydney Harbour Foreshores and Waterways Area Development Control Plan, 2005. It has also been assessed against requirements of the Manly LEP and DCP.

The proposed development meets Clauses 12 and 15 of the Coastal Management SEPP (13 and 14 do not apply) and meets the requirements of the Sydney Harbour REP and DCP, and relevant clauses of the Manly LEP and DCP.

The impacts on the coastal environment have been assessed as acceptable subject to conditions.

Referral Body Recommendation

Recommended for approval, subject to conditions

Refusal comments

Recommended Natural Environment Conditions:

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

Swimming Pools

The backwash of Swimming Pool water must be discharged to Sydney Water's sewer in accordance with Australian/New Zealand Standard AS/NZS 3500. Detailed plans and specification must be submitted prior to the issue of the Construction Certificate. The drawings must show the location of Sydney Water's sewer, the yard gully or any new connection to the sewer system including a detailed cross section of the connection complying with Australian/New Zealand Standard AS/NZS 3500.

Reason: To ensure compliance with legislation and Australian Standards and to protect public health, amenity and to ensure the protection and preservation of receiving waters.

CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

Installation and Maintenance of Sediment and Erosion Control

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004). Techniques used for erosion and sediment control on site are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and the site is sufficiently stabilised with vegetation.

Reason: To protect the surrounding environment from the effects of sedimentation and erosion from the site

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

Pollution Control

All stockpiles, materials, waste and slurry associated with works (including excavated material) is to be contained at source within the construction area and enclosed in waterproof covering and/or sediment and erosion control while not in use. All waste/debris is to be removed off site and disposed of as frequently as required in accordance to local regulations.

Reason: To protect the surrounding environment, and ensure that pollutants and building associated waste do not leave the construction site.

Pollution Control

Any excess materials such as cleaning paintbrushes, lacquers, and any water from cleaning tools must not enter the stormwater network and/or receiving waterways.

Reason: To ensure that building associated chemicals and pollutants don't enter the surrounding environment.