


SEDIMENT & EROSION CONTROL PLAN

~ 1:200 All excavation works to be carried out in a safe building manner in accordance with the Geotechnical Consultants spec, NCC, BCA and industry standards etc. Sediment and erosion control measures to be installed before any excavation works and monitored / improved continually to prevent sediment leaving the site, including immediate cleaning of spillage etc from vehicles leaving the property. All material stock piles to be protected from rainfall and runoff at all times.

ISS	SUE:		Barrenjoey Consulting Engineers Ptyltd	PROJECT:	DR
Preli		Issued for comment Issued for DA submission	Stormwater Structural Civil POBox 672	PROPOSED	
		 	Avalon NSW 2107 M: 0418 620 330 E: lucasbce@bigpond.com ABN: 13124694917	RESIDENTIAL DEVELOPMENT 7 & 8 CORONATION STREET MONA VALE	
			ACN: 124694917		



SEDIMENT FENCE CONSTRUCTION NOTES:

- 1. CONSTRUCT SEDIMENT FENCES AS CLOSE AS POSSIBLE TO BEING PARALLEL TO THE CONTOURS OF THE SITE, BUT WITH SMALL RETURNS AS SHOWN IN THE DRAWING TO LIMIT THE CATCHMENT AREA OF ANY ONE SECTION. THE CATCHMENT AREA SHOULD BE
- BOTTOM OF THE FABRIC TO BE ENTRENCHED.
- 3. DRIVE 1.5m LONG STAR PICKETS INTO GROUND @ 2.5m INTERVALS (MAX.) AT THE DOWNSLOPE EDGE OF THE TRENCH. ENSURE ANY STAR PICKETS ARE FITTED WITH
- 4. FIX SELF-SUPPORTING GEOTEXTILE TO THE UPSLOPE SIDE OF THE POSTS ENSURING IT GOES TO THE BASE OF THE TRENCH. FIX THE GEOTEXTILE WITH WIRE TIES OR AS RECOMMENDED BY THE MANUFACTURER. ONLY USE GEOTEXTILE SPECIFICALLY PRODUCED FOR SEDIMENT FENCING. THE USE OF SHADE CLOTH FOR THIS PURPOSE IS NOT
- JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150mm OVERLAP. BACKFILL THE TRENCH OVER THE BASE OF THE FABRIC AND COMPACT IT THOROUGHLY