

## Water Management Referral Response

<b>Application Number:</b>	DA2020/0273
<b>Date:</b>	30/03/2020
<b>To:</b>	Kye Miles
<b>Land to be developed (Address):</b>	Lot 8 DP 1206507 , 43 Warriewood Road WARRIEWOOD NSW 2102

### Reasons for referral

Council's Water Management Officers are required to consider the likely impacts.

### Officer comments

This application has been assessed for compliance with the Water Management Report for the subdivision of 29-31 Warriewood Road, prepared by Civil Cert and dated 1/1/2018.

The application is recommended for approval. Site coverage is less than the maximum allowed under the WMR.

A sediment and erosion control plan has not been provided. The sediment and erosion control plan must prevent sediment entering the stormwater network and impacting the bio-retention basin on the site, which is the responsibility of the property owners to clean.

Sediment and erosion controls must be installed prior to disturbing any soil on site and maintained until all work is complete and groundcover re-established.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

### Recommended Water Management Conditions:

## CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

### Erosion and Sediment Control Plan

An Erosion and Sediment Control Plan (ESCP) shall be prepared by an appropriately qualified person and implemented onsite prior to commencement. The ESCP must meet the requirements outlined in the Landcom publication Managing Urban Stormwater: Soils and Construction - Volume 1, 4th Edition (2004). The ESCP must include the following as a minimum:

- Site Boundaries and contours
- Approximate location of trees and other vegetation, showing items for removal or retention (consistent with any other plans attached to the application)
- Location of site access, proposed roads and other impervious areas (e.g. parking areas and site facilities)
- Existing and proposed drainage patterns with stormwater discharge points

- Locations and methods of all erosion and sediment controls that must include sediment fences, stabilised site access, materials and waste stockpiles locations, location of any stormwater pits on the site and how they are going to be protected.
- North point and scale.

Details demonstrating compliance are to be submitted to the Certifying Authority for approval prior to the issue of the Construction Certificate.

Reason: Protection of the receiving environment

## **CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK**

### **Installation and Maintenance of Sediment and Erosion Control**

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) and the Erosion and Sediment Control Plan prior to commencement of any other works on site.

Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and vegetation cover has been re-established across 70 percent of the site, and the remaining areas have been stabilised with ongoing measures such as jute mesh or matting.

Reason: Protection of the receiving environment