

ALTERATIONS & ADDITIONS TO PITTWATER RSL

82 Mona Vale Rd, Mona Vale NSW 2103

Job No. N0240888

STORMWATER SERVICES

- PROPOSED STORMWATER/RAINWATER
- EXISTING STORMWATER/RAINWATER
- SUB-SOIL DRAINAGE LINE
- CAST IN SLAB PIPE

STORMWATER LEGEND

- PROPOSED SEALED JUNCTION PIT
- PROPOSED GRATED SURFACE INLET PIT. PIT DIMENSIONS ARE GOVERNED BY DEPTH REFER TO DETAIL.
- EXISTING PIT
- PIT TO BE REMOVED
- PROPOSED KERB INLET PIT
- PROPOSED GRATED DRAIN
- PROPOSED RAINWATER TANK
- DOWNPIPE, RISER OR VERTICAL DROP
- RWO - RAINWATER OUTLET FOR BALCONIES, ROOF, CARPARK ETC
- GS1 - DOWNPIPE WITH RAIN HEAD OVERFLOW
- GS2 - DOWNPIPE WITH SUMP SIDE OVERFLOW
- GS3 - DOWNPIPE WITH SUMP HIGH CAPACITY OVERFLOW
- SWALE DRAIN
- OVERLAND FLOW PATH
- ROOF FALL DIRECTION
- P 35.05
- GL 35.05
- IL 34.75
- FFL 23.56
- + 35.11
- 36.00
- EXISTING SURFACE LEVEL
- EXISTING SURVEY CONTOUR

GENERAL PIPEWORK LEGEND

- FLOW DIRECTION
- PIPE FROM ABOVE
- PIPE TO BELOW
- FALL DIRECTION
- PIPE TYPE, SIZE AND GRADE
- CONNECTION
- CONTINUATION
- END CAP
- KEYNOTE TAG

PROJECT INFORMATION TABLE

THE TABLES BELOW ARE TO BE READ IN CONJUNCTION WITH THE ADJACENT NOTES

SURVEY INFORMATION

THE SURVEY INFORMATION ON THESE DRAWINGS HAS BEEN PROVIDED BY

COMPANY	DATED
LTS SURVEYORS	03/07/2024

SAFETY IN DESIGN

THERE ARE INHERENT RISKS WITH CONSTRUCTING, MAINTAINING, OPERATING, DEMOLISHING, DISMANTLING AND DISPOSING THIS DESIGN THAT ARE TYPICAL OF SIMILAR DESIGNS. AS FAR AS IS REASONABLY PRACTICABLE RISKS HAVE BEEN ELIMINATED OR MINIMISED THROUGH THE DESIGN PROCESS. HAZARD CONTROLS MUST STILL BE IMPLEMENTED BY THE CONTRACTOR, OWNER OR OPERATOR TO ENSURE THE SAFETY OF WORKERS.

- JN DO NOT CONSIDER THAT THERE ARE ANY UNIQUE RISKS ASSOCIATED WITH THE DESIGN OF THIS PROJECT.

SAFETY IN DESIGN

THERE ARE INHERENT RISKS WITH CONSTRUCTING, MAINTAINING, OPERATING, DEMOLISHING, DISMANTLING AND DISPOSING THIS DESIGN THAT ARE TYPICAL OF SIMILAR DESIGNS. AS FAR AS IS REASONABLY PRACTICABLE RISKS HAVE BEEN ELIMINATED OR MINIMISED THROUGH THE DESIGN PROCESS. HAZARD CONTROLS MUST STILL BE IMPLEMENTED BY THE CONTRACTOR, OWNER OR OPERATOR TO ENSURE THE SAFETY OF WORKERS.

- JN DO NOT CONSIDER THAT THERE ARE ANY UNIQUE RISKS ASSOCIATED WITH THE DESIGN OF THIS PROJECT.

DRAWING STATUS

PRELIMINARY
PRELIMINARY DRAWINGS ARE NOT TO BE USED FOR TENDER OR CONSTRUCTION PURPOSES.

TENDER

TENDER DRAWINGS ARE NOT TO BE USED FOR CONSTRUCTION PURPOSES AND ARE INTENDED FOR AN EXTENT OF WORKS. ALL OTHER CONSULTANT DRAWINGS AND CONTRACT DOCUMENTS SHOULD BE READ IN CONJUNCTION WITH THESE DOCUMENTS TO DETERMINE THE FULL EXTENT OF WORKS.

CONSTRUCTION CERTIFICATE

CONSTRUCTION CERTIFICATE DRAWINGS ARE NOT TO BE USED FOR CONSTRUCTION UNLESS APPROVED & STAMPED BY THE PCA.

CONSTRUCTION

CONSTRUCTION DRAWINGS CAN BE USED FOR CONSTRUCTION PURPOSES AND/OR FOR THE CREATION OF FABRICATION DRAWINGS.

GENERAL

- ALL EXISTING LEVELS TO BE CONFIRMED ON SITE PRIOR TO COMMENCEMENT OF WORKS
- ALL WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE NOMINATED OR APPLICABLE COUNCIL SPECIFICATION, WHERE A SPECIFICATION HAS NOT BEEN NOMINATED THEN THE CURRENT NSW DEPARTMENT OF HOUSING CONSTRUCTION SPECIFICATION IS TO BE USED. THE NOMINATED SPECIFICATION SHALL TAKE PRECEDENCE TO THESE NOTES.
- THESE DRAWINGS ARE DIAGRAMMATIC AND SHOW THE GENERAL ARRANGEMENT. ALL DIMENSIONS SHOWN SHALL BE VERIFIED BY THE CONTRACTOR ON SITE. ENGINEERS DRAWINGS SHALL NOT BE SCALED FOR DIMENSIONS.
- ALL DRAWINGS SHOULD BE READ IN CONJUNCTION WITH THE RELEVANT ARCHITECTURAL DRAWINGS & DRAWINGS FROM OTHER CONSULTANTS.
- THE CONTRACTOR SHOULD REPORT ANY DISCREPANCIES ON THE DRAWINGS TO THE ENGINEER RESPONSIBLE FOR THE DESIGN.
- THE CONTRACTOR SHOULD LOCATE AND LEVEL ALL EXISTING SERVICES PRIOR TO COMMENCING CONSTRUCTION AND PROTECT AND MAKE ARRANGEMENTS WITH THE RELEVANT AUTHORITY TO RELOCATE AND/OR ADJUST IF NECESSARY. INFORMATION GIVEN ON THE DRAWINGS IN RESPECT TO SERVICES IS FOR GUIDANCE ONLY AND IS NOT GUARANTEED COMPLETE NOR CORRECT.
- CONTRACTOR IS NOT TO ENTER UPON NOR DO ANY WORK WITHIN ADJACENT LANDS WITHOUT THE PERMISSION OF THE OWNER.
- SURPLUS EXCAVATED MATERIAL SHALL BE PLACED WHERE DIRECTED OR REMOVED FROM SITE.
- ALL NEW WORKS SHALL MAKE A SMOOTH JUNCTION WITH EXISTING.
- ALL DRAINAGE LINES THROUGH ADJACENT LOTS SHALL BE CONTAINED WITHIN EASEMENTS CONFORMING TO COUNCIL'S STANDARDS.
- THE CONTRACTOR SHALL CLEAR THE SITE BY REMOVING ALL RUBBISH, FENCES AND DEBRIS ETC. TO THE EXTENT SPECIFIED PRIOR TO COMMENCEMENT OF WORK. THE CONTRACTOR SHALL PROVIDE A TRAFFIC MANAGEMENT PLAN PREPARED BY AN ACCREDITED PERSON IN ACCORDANCE WITH RMS REQUIREMENTS. FOR ANY WORK ON OR ADJACENT TO PUBLIC ROADS, PLAN TO BE SUBMITTED TO COUNCIL & RMS.

SURVEY

- JONES NICHOLSON IS NOT RESPONSIBLE FOR THE ACCURACY OF ANY 3RD PARTY INFORMATION PROVIDED ON THIS DRAWING.
- ALL LEVELS ARE TO A.H.D.
- ALL CHAINAGES AND LEVELS ARE IN METRES, AND DIMENSIONS IN MILLIMETRES.
- SET OUT COORDINATES ARE BASED ON SURVEY DRAWINGS PROVIDED FOR THE PURPOSE OF CARRYING OUT THE ENGINEERING DESIGN.
- CONTRACTOR SHALL VERIFY ALL SET OUT COORDINATES SHOWN ON THE PLANS BY A REGISTERED SURVEYOR
- CONTRACTORS SHALL ARRANGE FOR THE WORKS TO BE SET OUT BY A REGISTERED SURVEYOR.
- ANY DISCREPANCIES SHOULD BE CLARIFIED IN WRITING WITH THE ENGINEER PRIOR TO COMMENCEMENT OF THE WORK FOR CONFIRMATION OF THE SURVEY.

STORMWATER DRAINAGE

- STORMWATER DRAINAGE SHALL BE GENERALLY IN ACCORDANCE WITH CURRENT AUSTRALIAN STANDARDS AND COUNCIL'S SPECIFICATION.
- PIPES OF 225mm DIA. AND UNDER SHALL BE UPVC.
- PIPES OF 300mm DIA. AND LARGER SHALL BE FRC OR CONCRETE CLASS 2 RUBBER RING JOINTED UNO.
- ALL FRC OR RCP STORMWATER PIPES WITHIN ROAD RESERVE AREAS TO BE CLASS 3 U.N.O.
- MINIMUM COVER TO PIPES 300mm DIA. AND OVER GENERALLY SHALL BE 600mm IN CARPARK & ROADWAY AREAS UNO.
- PIPES SHALL GENERALLY BE LAID AT THE GRADES INDICATED ON THE DRAWINGS.
- PIPES UP TO 150mm DIA SHALL BE LAID AT 1.0% MIN. GRADE U.N.O.
- PIPES 225mm DIA AND OVER SHALL BE LAID AT 0.5% MIN. GRADE U.N.O.
- BACKFILL TRENCHES WITH APPROVED FILL COMPACTED IN 200mm LAYERS TO 98% OF STANDARD DENSITY.
- ANY PIPES OVER 16% GRADE SHALL HAVE CONCRETE BULKHEADS AT ALL JOINTS.
- PITS SHALL BE AS DETAILED WITH METAL GRATES AT LEVELS INDICATED. ALL PITS DEEPER THAN 1200mm TO HAVE CLIMB IRONS.
- BUILD INTO UPSTREAM FACE OF ALL PITS A 3.0m SUBSOIL LINE FALLING TO PITS TO MATCH PIT INVERTS.
- ALL COURTYARD & LANDSCAPED PITS TO BE 450 SQUARE LOAD CLASS A UNLESS NOTED OTHERWISE.
- ALL DRIVEWAY & OSD PITS TO BE 600 SQUARE LOAD CLASS D UNLESS NOTED OTHERWISE.
- INSTALL TEMPORARY SEDIMENT BARRIERS TO INLET PITS, TO COUNCIL'S STANDARDS UNTIL SURROUNDING AREAS ARE PAVED OR GRASSED.
- PITS & DOWNPIPE LOCATIONS AND LEVELS MAY BE VARIED TO SUIT SITE CONDITIONS AFTER CONSULTING THE ENGINEER.
- DOWNPIPES SHOWN ARE INDICATIVE ONLY. ALL ROOF GUTTERING AND DOWNPIPES TO THE CURRENT AUSTRALIAN STANDARDS.
- ALL PLANTER BOXES AND BALCONIES TO BE CONNECTED TO THE PROPOSED STORMWATER DRAINAGE LINE.
- HAND-EXCAVATE STORMWATER PIPES IN VICINITY OF TREE ROOTS.
- FOOTPATH CROSSING LEVELS SHOWN ARE TO BE ADJUSTED TO FINAL COUNCIL'S ISSUED LEVELS.
- GEOTEXTILE FABRIC TO BE PLACED UNDER RIP RAP SCOUR PROTECTION.
- ALL BASES OF PITS TO BE BENCHED TO HALF PIPE DEPTH AND PROVIDE GALVANISED ANGLE SURROUNDINGS TO GRATE.
- SUBSOIL LINE PIPES AND FITTINGS SHALL BE PERFORATED PLASTIC TO CURRENT AUSTRALIAN STANDARDS. LAY PIPES ON FLOOR OF TRENCH GRADED AT 1% MIN. AND OVERLAY WITH FILTER MATERIAL. EXTENDING TO WITHIN 200mm OF SURFACE. PROVIDE FILTER FABRIC OF PERMEABLE POLYPROPYLENE BETWEEN FILTER MATERIAL AND TOPSOIL.
- SHOULD THE CONTRACTOR ELECT TO INSTALL PRECAST STORMWATER PITS AND THEY ARE PERMITTED BY COUNCIL AND THE CLIENT, THE PRECAST PITS ARE TO BE CONSTRUCTED IN ACCORDANCE WITH RMS STANDARDS INCLUDING:
 - SEAL THE SEGMENTS TOGETHER USING A SITE-APPROVED NON-SHRINK GROUT OR MASTIC-TYPE PRODUCT. APPLY THE SEALANT IN ACCORDANCE WITH THE PRODUCT MANUFACTURER'S REQUIREMENTS.
 - ENSURE THAT NO GAPS REMAIN AND THAT A SMOOTH FACE EXISTS BETWEEN MULTIPLE UNITS.
 - LEAVE THE SEGMENTS UNDISTURBED UNTIL THE PERIOD OF CURING IS COMPLETED IN ACCORDANCE WITH THE GROUT OR SEALANT PRODUCT MANUFACTURER'S REQUIREMENTS.

STORMWATER DRAINAGE INSTALLATION

- SUPPLY & INSTALLATION OF DRAINAGE WORKS TO BE IN ACCORDANCE WITH THESE DRAWINGS, THE COUNCIL SPECIFICATION AND THE CURRENT APPLICABLE AUSTRALIAN STANDARDS.
- BEDDING OF THE PIPELINES IS TO BE TYPE 'HS2' IN ACCORDANCE WITH THE STANDARDS AND AS FOLLOWS:
 - COMPACTED GRANULAR MATERIAL IS TO COMPLY WITH THE FOLLOWING GRADINGS:

SIEVE SIZE (mm)	19	2.36	0.60	0.30	0.15	0.075
% MASS PASSING	100	50-100	20-90	10-40	0-25	0-10

- AND THE MATERIAL PASSING THE 0.075 SIEVE HAVING LOW PLASTICITY AS DESCRIBED IN APPENDIX D OF AS1726.
 - BEDDING DEPTH UNDER THE PIPE TO BE 100mm.
 - BEDDING MATERIAL TO BE EXTENDED FROM THE TOP OF THE BEDDING ZONE UP TO 0.3 TIMES PIPE OUTSIDE DIAMETER. THIS REPRESENTS THE 'HAUNCH ZONE'.
 - THE BEDDING & HAUNCH ZONE MATERIAL IS TO BE COMPACTED TO A MINIMUM RELATIVE COMPACTION OF 98% WITHIN ROAD RESERVES AND TRAFFICABLE AREAS AND 95% ELSEWHERE FOR COHESIVE MATERIAL OR A MINIMUM DENSITY INDEX OF 70% IN ACCORDANCE WITH THE STANDARDS FOR COHESIONLESS MATERIAL.
 - COMPACTION TESTING SHALL BE CARRIED OUT BY AN APPROVED ORGANISATION WITH A NATA CERTIFIED LABORATORY FOR ALL DRAINAGE LINES LAID WHOLLY OR IN PART UNDER THE KERB & GLITTER OR PAVEMENT.
- BACKFILL SHALL BE PLACED & COMPACTED IN ACCORDANCE WITH THE SPECIFICATION. A GRANULAR GRAVEL AGGREGATE MATERIAL (<10mm) BACKFILL IS RECOMMENDED FOR THE BEDDING, HAUNCH SUPPORT AND SIDE ZONE DUE TO ITS SELF COMPACTING ABILITY.
 - A MINIMUM OF 150mm CLEARANCE IS TO BE PROVIDED BETWEEN THE OUTSIDE OF THE PIPE BARREL AND THE TRENCH WALL FOR PIPES < 600 DIA. 200mm CLEARANCE FOR PIPES 600 TO 1200 DIA AND D/6 CLEARANCE FOR PIPES > 1200 DIA.

ISSUED FOR DA



This document is issued by
Jones Nicholson Pty Ltd (ABN 51 003 316 032)

DESIGN	LM
DATE	30/10/2024
SIZE	A1
SCALE	NTS
PROJECT MGR	LM

CIVIL SKETCH


NOTES & LEGEND

ALTERATIONS & ADDITIONS
TO PITTWATER RSL


82 Mona Vale Rd, Mona Vale NSW
2103

LINKED PM


N0240888
CSK000 1




BOX GUTTER SUMP DETAIL



TYPICAL SUBSOIL OUTLET DETAIL




SUBSOIL PIPE CONNECTION




- NOTES:
- MINIMUM GRADE OF SUBSOIL DRAINAGE PIPES IS TO BE 1.0%. JOINTS IN FILTER FABRIC TO BE LAPPED A MINIMUM 300mm.


SUBSOIL PIPE FLUSHING POINT



TYPICAL DOWNPIPE TO PIT DETAIL (OPTION)




TYPICAL SUBSOIL RETAINING WALL DETAIL



MINIMUM INTERNAL DIMENSIONS FOR STORMWATER PITS			
DEPTH OF INVERT OF OUTLET	< 600	DEPTH OF INVERT OF OUTLET	
		WIDTH	LENGTH
> 600	< 600	450	450
> 900	< 600	600	600
> 1200	< 600	600	900
> 1200	< 600	900	900

- NOTE:
- CLIMB IRONS SHALL BE PROVIDED UNDER LID AT 300 CTS TO COUNCIL STANDARDS WHERE PIT DEPTH IS DEEPER THAN 1000.
 - PROVIDE 90Dia x 3000 LONG SUBSOIL DRAINAGE STUB PIPE SURROUNDED WITH 100mm THICKNESS OF NOMINAL 20mm COARSE FILTER MATERIAL WRAPPED IN GEOTEXTILE FILTER FABRIC, (BIDUM A24 OR APPROVED SIMILAR), TO BE PARALLEL TO UPSTREAM SIDE OF EACH INLET PIPE.
 - ALTERNATIVE PIT CONSTRUCTION MAY BE USED SUBJECT TO THE ENGINEERS APPROVAL.
 - CONCRETE STRENGTH F_c = 32 MPa


TYPICAL CONCRETE INLET PIT - CONCRETE SURFACE




MINIMUM INTERNAL DIMENSIONS FOR STORMWATER PITS			
DEPTH OF INVERT OF OUTLET	< 600	DEPTH OF INVERT OF OUTLET	
		WIDTH	LENGTH
> 600	< 600	450	450
> 900	< 600	600	600
> 1200	< 600	600	900
> 1200	< 600	900	900

- NOTE:
- CLIMB IRONS SHALL BE PROVIDED UNDER LID AT 300 CTS TO COUNCIL STANDARDS WHERE PIT DEPTH IS DEEPER THAN 1000.
 - PROVIDE 90Dia x 3000 LONG SUBSOIL DRAINAGE STUB PIPE SURROUNDED WITH 100mm THICKNESS OF NOMINAL 20mm COARSE FILTER MATERIAL WRAPPED IN GEOTEXTILE FILTER FABRIC, (BIDUM A24 OR APPROVED SIMILAR), TO BE PARALLEL TO UPSTREAM SIDE OF EACH INLET PIPE.
 - ALTERNATIVE PIT CONSTRUCTION MAY BE USED SUBJECT TO THE ENGINEERS APPROVAL.
 - CONCRETE STRENGTH F_c = 32 MPa


TYPICAL CONCRETE INLET PIT - NATURAL SURFACE



TYPICAL SUBSOIL PIPE/PIT BENCHING



STEP IRON DETAIL



TYPICAL SCHEMATIC PIPE TRENCH DETAIL

ISSUED FOR DA



This document is issued by Jones Nicholson Pty Ltd (ABN 51 003 316 032)

DESIGN LM
DATE 30/10/2024
SIZE A1
SCALE 1:200
PROJECT MGR LM

CIVIL SKETCH

TYPICAL DETAILS
SHEET 1

ALTERATIONS & ADDITIONS
TO PITTWATER RSL


82 Mona Vale Rd, Mona Vale NSW
2103

LINKED PM


N0240888
CSK051 1

MONA VALE ROAD

- NOTES:
1. NEW ROOF OVER PREVIOUSLY PAVED AREA AND DISCHARGING TO EXISTING DRAINAGE LINES UNDER
 2. NO INCREASE IN IMPERVIOUS AREA THEREFORE NO INCREASE IN SITE STORMWATER FLOWS I.E. NO ON-SITE DETENTION (OSD) PROPOSED
 3. PROPOSED UNDERCROFT WORKS TO GENERALLY MAINTAIN EXISTING GRADES AND LEVELS TOWARDS EXISTING STORMWATER OUTLETS



ISSUED FOR DA




This document is issued by
Jones Nicholson Pty Ltd (ABN 51 003 316 032)

DESIGN	LM
DATE	30/10/2024
SIZE	A1
SCALE	1:200
PROJECT MGR	LM


CIVIL SKETCH
STORMWATER SITE
PLAN

ALTERATIONS & ADDITIONS
TO PITTPATER RSL
82 Mona Vale Rd, Mona Vale NSW
2103
LINKED PM

N0240888
CSK100 1



ISSUED FOR DA



This document is issued by
Jones Nicholson Pty Ltd (ABN 51 003 316 032)

DESIGN	LM
DATE	30/10/2024
SIZE	A1
SCALE	1:200
PROJECT MGR	LM

CIVIL SKETCH

STORMWATER ROOF
PLAN

ALTERATIONS & ADDITIONS
TO PITTWATER RSL

82 Mona Vale Rd, Mona Vale NSW
2103

LINKED PM


N0240888
CSK101 1

ALTERATIONS & ADDITIONS TO PITTWATER RSL

82 Mona Vale Rd, Mona Vale NSW 2103

Job No. N0240888

ENVIRONMENTAL SITE MANAGEMENT LEGEND



SAFETY IN DESIGN

THERE ARE INHERENT RISKS WITH CONSTRUCTING, MAINTAINING, OPERATING, DEMOLISHING, DISMANTLING AND DISPOSING THIS DESIGN THAT ARE TYPICAL OF SIMILAR DESIGNS. AS FAR AS IS REASONABLY PRACTICABLE RISKS HAVE BEEN ELIMINATED OR MINIMISED THROUGH THE DESIGN PROCESS. HAZARD CONTROLS MUST STILL BE IMPLEMENTED BY THE CONTRACTOR, OWNER OR OPERATOR TO ENSURE THE SAFETY OF WORKERS.

- JN DO NOT CONSIDER THAT THERE ARE ANY UNIQUE RISKS ASSOCIATED WITH THE DESIGN OF THIS PROJECT.

ENVIRONMENTAL SITE MANAGEMENT

- EROSION & SEDIMENT CONTROLS TO BE INSTALLED IN ACCORDANCE WITH COUNCIL'S SPECIFICATION & THE NSW DEPARTMENT OF HOUSING 'BLUE BOOK' - SOILS AND CONSTRUCTION - MANAGING URBAN STORMWATER, 2004. REFER TO THE BLUE BOOK FOR STANDARD DRAWINGS 'SD'.
- SEDIMENT & EROSION CONTROLS MUST BE IN PLACE PRIOR TO THE COMMENCEMENT OF ANY EARTHWORKS OR DEMOLITION ACTIVITY. THE LOCATION OF SUCH DEVICES IS INDICATIVE ONLY AND FINAL POSITION SHOULD BE DETERMINED ON SITE.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT ALL MEASURES ARE TAKEN DURING THE COURSE OF CONSTRUCTION TO PREVENT SEDIMENT EROSION AND POLLUTION OF THE DOWNSTREAM SYSTEM. SUPERVISING ENGINEER SHOULD BE CONTACTED IF IN DOUBT. ALL SEDIMENT CONTROL STRUCTURES TO BE INSPECTED AFTER EACH RAINFALL EVENT FOR STRUCTURAL DAMAGE AND ALL TRAPPED SEDIMENT TO BE REMOVED TO A NOMINATED SOIL STOCKPILE SITE.
- RETAIN ALL EXISTING GRASS COVER WHEREVER POSSIBLE. TOPSOIL FROM ALL AREAS THAT WILL BE DISTURBED TO BE STRIPPED AND STOCKPILED AT THE NOMINATED SITE. A SEDIMENT FENCE TO BE PLACED DOWNHILL OF STOCKPILE.
- AREAS OF SITE REGRADING ARE TO BE COMPLETED PROGRESSIVELY DURING THE WORKS AND STABILISED AS EARLY AS POSSIBLE. THE SUPERVISING ENGINEER MAY DIRECT THE CONTRACTOR TO HAVE AREAS OF DISTURBANCE COMPLETED AND STABILISED DURING THE COURSE OF THE WORKS.
- ALL DISTURBED AREAS ARE TO BE SEEDED & FERTILISED WITHIN 14 DAYS OF EXPOSURE.
- ALL EXISTING TREES TO BE RETAINED UNLESS SHOWN OTHERWISE ON APPROVED DRAWINGS. TREES RETAINED ARE TO BE PROTECTED WITH A HIGH VISIBILITY FENCE, PLUS FLAGGING TO INDIVIDUAL TREES AS NECESSARY.
- INSTALL TEMPORARY SEDIMENT BARRIERS TO ALL INLET PITS LIKELY TO COLLECT SILT LADEN WATER. UNTIL SURROUNDING AREAS ARE PAVED OR REGRASSED, GRAVEL OR GEOTEXTILE INLET FILTERS TO SD6-11 & SD4-12.
- ALL SILT FENCES & BARRIERS ARE TO BE MAINTAINED IN GOOD ORDER & REGULARLY DESILTED DURING THE CONSTRUCTION PERIOD. SILT FENCES TO SD4-8 OR SD4-9.
- STOCKPILES OF LOOSE MATERIALS SUCH AS SAND, SOIL, GRAVEL MUST BE COVERED WITH GEOTEXTILE SILT FENCE MATERIAL. PLASTIC SHEETING OR MEMBRANE MUST NOT BE USED. SAFETY BARRICADING SHOULD BE USED TO ISOLATE STOCKPILES OF SOLID MATERIALS SUCH AS STEEL REINFORCING, FORMWORK AND SCAFFOLDING.
- WASTE MATERIALS ARE TO BE STOCKPILED OR LOADED INTO SKIP-BINS LOCATED ON SITE AS SHOWN ON PLAN.
- NO MORE THAN 150m OF TRENCHING TO BE OPEN AT ANY ONE TIME. IMMEDIATELY AFTER TRENCH BACKFILLING, PROVIDE SANDBAGS OR SAUSAGE FILTERS ACROSS EACH TRENCH AT MAXIMUM 20m SPACINGS. FILTERS TO REMAIN IN PLACE UNTIL REVEGETATION HAS OCCURRED.
- ALL VEHICLES LEAVING THE SITE MUST PASS OVER THE STABILISED SITE ACCESS BALLAST AREA (SIMILAR TO SD4-14) TO SHAKE OFF SITE CLAY AND SOIL. IF NECESSARY WHEELS AND AXLES ARE TO BE HOSED DOWN. BALLAST IS TO BE MAINTAINED & REPLACED AS NECESSARY DURING THE CONSTRUCTION PERIOD.
- THE HEAD CONTRACTOR IS TO INFORM ALL SITE STAFF AND SUB-CONTRACTORS OF THEIR OBLIGATIONS UNDER THE EROSION AND SEDIMENT CONTROL PLAN.
- ANY SEDIMENT DEPOSITED ON THE PUBLIC WAY, INCLUDING FOOTPATH RESERVE AND ROAD SURFACE, IS TO BE REMOVED IMMEDIATELY.
- PROVIDE BARRIERS AROUND ALL CONSTRUCTION WORKS WITHIN THE FOOTPATH AREA TO PROVIDE SAFE ACCESS FOR PEDESTRIANS.
- CONCRETE PUMPS AND CRANES ARE TO OPERATE FROM WITHIN THE BALLAST ENTRY DRIVEWAY AREA, AND ARE NOT TO OPERATE FROM THE PUBLIC ROADWAY UNLESS SPECIFIC COUNCIL PERMISSION IS OBTAINED.
- TRUCKS REMOVING EXCAVATED / DEMOLISHED MATERIAL SHOULD TRAVEL ON STABILISED CONSTRUCTION PATHS. MATERIAL TO BE TAKEN TO THE TRUCK TO REDUCE TRUCK MOVEMENT ON SITE. TRUCKS TO BE LIMITED TO SINGLE UNIT HEAVY RIGID VEHICLES. (NO SEMITRAILERS)
- ANY EXCAVATION WORK ADJACENT TO ADJOINING PROPERTIES OR THE PUBLIC ROADWAY IS NOT TO BE COMMENCED UNTIL THE STRUCTURAL ENGINEER IS CONSULTED AND SPECIFIC INSTRUCTIONS RECEIVED FROM THE ENGINEER.
- TOILET FACILITIES MUST BE EITHER A FLUSHING TYPE OR APPROVED PORTABLE CHEMICAL CLOSET. CHEMICAL CLOSETS ARE TO BE MAINTAINED & SERVICED ON A REGULAR BASIS SO THAT OFFENSIVE ODOUR IS NOT EMITTED.
- DURING TRENCH EXCAVATION ALL SPOIL SHALL BE MOUNDED ON THE UPHILL SIDE OF TRENCHES AND PLACEMENT IS TO COMPLY WITH THE SUPERINTENDENTS REQUIREMENT.
- DIVERSION BANKS SHOULD BE CONSTRUCTED BY MOUNDING STRIPPED TOPSOIL (MIN HEIGHT 600mm) WHERE DIRECTED. MATERIAL TO BE RESPREAD ON FOOTWAYS AFTER FINAL TRIMMING.
- UNDISTURBED BUFFER ZONE AREAS ARE CLOSED TO ALL TRAFFIC MOVEMENTS UNLESS OTHERWISE NOTED BY THE SUPERINTENDENT AND ACCESS TO THE SEWER OR C.D.L. TRENCHING WILL BE AS SHOWN, OR HEAVY PENALTIES MAY BE IMPOSED.
- TRAFFIC MANAGEMENT MEASURES ARE REQUIRED TO BE IMPLEMENTED AND MAINTAINED DURING CONSTRUCTION. IN ACCORDANCE WITH 'R.T.A. TRAFFIC CONTROL AT WORK SITES - CURRENT EDITION' AND AS 1742 'MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES'.
- PEDESTRIAN CONTROL MEASURES ARE REQUIRED TO BE IMPLEMENTED AND MAINTAINED DURING CONSTRUCTION. IN ACCORDANCE WITH AS 1742 'MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES'.

ISSUED FOR DA



This document is issued by
Jones Nicholson Pty Ltd (ABN 51 003 316 032)

DESIGN	LM
DATE	30/10/2024
SIZE	A1
SCALE	NTS
PROJECT MGR	LM

CIVIL SKETCH

EROSION & SEDIMENT
CONTROL NOTES


ALTERATIONS & ADDITIONS
TO PITTWATER RSL

82 Mona Vale Rd, Mona Vale NSW
2103

LINKED PM

N0240888
CSK900 1

ISSUED FOR DA



This document is issued by
Jones Nicholson Pty Ltd (ABN 51 003 316 032)

DESIGN	LM
DATE	30/10/2024
SIZE	A1
SCALE	1:200
PROJECT MGR	LM

CIVIL SKETCH


EROSION & SEDIMENT CONTROL PLAN

ALTERATIONS & ADDITIONS TO PITTWATER RSL

82 Mona Vale Rd, Mona Vale NSW
2103

LINKED PM


N0240888
CSK901 1



STOCKPILES

- GENERAL CONSTRUCTION NOTES:**
1. LOCATE STOCKPILE AT LEAST 5m FROM VEGETATION, CONCENTRATED WATER FLOWS, ROADS AND HAZARD AREAS.
 2. CONSTRUCT ON THE CONTOUR AS A LOW FLAT ELONGATED MOUND.
 3. WHERE THERE IS A SUFFICIENT AREA TOPSOIL STOCKPILES SHALL BE LESS THAN 2m IN HEIGHT. (TO ALLOW AIR VENTILATION FOR FUTURE REUSE)
 4. REHABILITATE IN ACCORDANCE WITH THE SWMP/ESCP.
 5. CONSTRUCT EARTH BANK ON THE UPSLOPE SIDE TO DIVERT RUN OFF AROUND THE STOCKPILE AND A SEDIMENT FENCE 1m to 2m DOWNSLOPE OF STOCKPILE.


STOCKPILES



1. FABRICATE A SLEEVE MADE FROM GEOTEXTILE OR WIRE MESH LONGER THAN THE LENGTH ON THE INLET PIT.
2. FILL THE SLEEVE WITH 25mm TO 50mm GRAVEL.
3. FORM AN ELLIPTICAL CROSS SECTION ABOUT 150mm HIGH x 400mm WIDE.
4. MAINTAIN A CLEAR DISTANCE AWAY FROM THE PIT WITH SPACER BLOCKS.

SAUSAGE BARRIER DETAIL


SCALE 1 : 20



- GENERAL CONSTRUCTION NOTES:**
1. CONSTRUCT SEDIMENT FENCE AS CLOSE AS POSSIBLE TO PARALLEL TO THE CONTOURS OF THE SITE.
 2. FIX SELF-SUPPORTING GEOTEXTILE TO UPSLOPE SIDE OF POSTS WITH WIRE TIES OR AS RECOMMENDED BY GEOTEXTILE MANUFACTURER.
 3. JOIN SECTIONS OF FABRIC AT A SUPPORT WITH A 150mm OVERLAP.
 4. REFER TO DETAIL SD 6-9 "BLUE BOOK"


SEDIMENT FENCE - ALTERNATIVE

SCALE 1 : 20




SEDIMENT SILT FENCE DETAIL

SCALE 1 : 20



TEMPORARY CONSTRUCTION EXIT DETAIL - SHAKER

SCALE 1 : 20




GEOTEXTILE FABRIC DESIGNED TO PREVENT INTERMIXING OF SUB-GRADE AND BASE MATERIALS AND TO MAINTAIN GOOD PROPERTIES OF THE SUB-BASE LAYERS. GEOTEXTILE MAY BE A WOVEN OR NEEDLE PUNCHED PRODUCT WITH A MINIMUM CBR BURST STRENGTH (AS3706.4-90) OF 2500N.

TEMPORARY CONSTRUCTION NOTES

1. STRIP TOPSOIL AND LEVEL SITE.
2. COMPACT SUBGRADE.
3. COVER THE AREA WITH NEEDLE PUNCHED GEOTEXTILE.
4. CONSTRUCT 200mm THICK PAD OVER GEOTEXTILE USING ROAD-BASE OR 30mm AGGREGATE. MINIMUM LENGTH 15m OR TO BUILDING ALIGNMENT, MINIMUM 3m WIDTH.
5. CONSTRUCT HUMPS IMMEDIATELY WITHIN BOUNDARY TO DIVERT WATER TO A SEDIMENT FENCE OR OTHER SEDIMENT DEVICE.

TEMPORARY CONSTRUCTION EXIT DETAIL

SCALE 1 : 20



GEOTEXTILE FILTER FABRIC DROP INLET SEDIMENT TRAP DETAIL

SCALE 1 : 20

ISSUED FOR DA



This document is issued by
Jones Nicholson Pty Ltd (ABN 51 003 316 032)

DESIGN LM
DATE 30/10/2024
SIZE A1
SCALE 1:200
PROJECT MGR LM

CIVIL SKETCH

EROSION & SEDIMENT
CONTROL DETAILS
SHEET 1

ALTERATIONS & ADDITIONS
TO PITTWATER RSL

82 Mona Vale Rd, Mona Vale NSW
2103

LINKED PM

N0240888
CSK951 1