

Geotechnical Assessment

Project: Alterations & Additions 106 Rose Avenue, Wheeler Heights NSW

Prepared for:

Phoebe Buchanan, c/Rapid Plans

Ref: AG 24574 20 January 2025





WHAT TO DO WITH THIS REPORT

While your geotechnical assessment report may be a statutory requirement from council in support of your development application, it also contains information important to the structural design and construction methodology of your project. Therefore, it is critical that all relevant parties are provided with a copy of this report.

We suggest you give a copy of your geotechnical assessment report to:

Your Architect/Building Designer Your Structural/Stormwater/Civil Engineer

Your Certifier Your Project Manager

Your Excavation Contractor Your Builder

We would also suggest that if any of your project team have questions regarding the contents of this report, that we be contacted for clarification.

NEXT CRITICAL STAGES

Keep in mind that you will need AscentGeo again at different stages of your project. This may include:

Review or endorsement of structural plans/architectural plans for a Construction Certificate Foundation/Footing inspection during construction

Excavation hold point inspection, usually at hold points not exceeding 1.5m drops Final inspection and certification for an Occupation Certificate upon completion of works

GENERAL ADVICE

If after reading this report you have any questions, are unsure what to do next or when you need to get in touch, please reach out to us.

Given AscentGeo can't be on site the whole time, we recommend that you or/and your builder take a lot of progress photos, especially during excavation. Many of the potential problems that may pop up can be resolved if we have clear photos of the work that's been done.

A lot can change on site during a construction project: some of these changes are normal and innocuous, while others can be symptoms of larger or more serious issues. For this reason, it's important to contact us to discuss any changes you notice on site that you aren't sure about. This could include but not be limited to changes to ground or surface water, movement of structures, and settlement of paths or landscaping elements.

We're here to help.

The AscentGeo Team



Geotechnical Assessment

For Alterations & Additions at

106 Rose Avenue, Wheeler Heights NSW

Document Status			Approved for Issue				
Version	Author		Reviewer	Date			
1	Riley Turnbull BScMngt Geo		Ben Morgan BScGeol MAIG RPGeo	21.01.2025			
	Document Distribution						
Version	Copies	Format	То	Date			
1	1 PDF		Phoebe Buchanan	21.01.2025			
1	1 PDF		Rapid Plans	21.01.2025			

Limitations

This report has been prepared for Phoebe Buchanan, c/- Rapid Plans, in accordance with AscentGeo's fee proposal dated 17 December 2024.

The report is provided for the exclusive use of the property owner and their nominated agents for the specific development and purpose as described in the report. This report must not be used for purposes other than those outlined in the report or applied to any other projects.

The information contained within this report is considered accurate at the time of issue with regard to the current conditions on site as identified by AscentGeo and the documentation provided by others.

The report should be read in its entirety and should not be separated from its attachments or supporting notes. It should not have sections removed or included in other documents without the express approval of AscentGeo.



Contents

1	Overv	iew		2	
	1.1	Background	d	3	
	1.2	Proposed Development			
	1.3	Relevant In	nstruments	3	
2	Site D	escription		4	
	2.1	Summary			
	2.2	Site Description			
	2.3	Geology an	nd Geological Interpretation	5	
	2.3	Fieldwork		5	
3	Geote	chnical Asses	ssment	6	
	3.1	Geological	Model	6	
	3.2	Site Classification			
	3.3	Groundwater			
	3.4	Surface Water			
	3.5	Slope Instability			
	3.6	Geotechnical Hazards and Risk Analysis			
	3.7	Conclusion	and Recommendations	9	
4	Refere	ences		14	
5	Appen	dices			
	Appen	dix A:	Site plan/ground test locations and geological cross section		
	Appen	dix B:	Site photos		
	Appen	dix C:	Engineering logs		
	Appen	dix D:	General notes		
			CSIRO Publishing, 2012. 'Foundation Maintenance and Footing Performance: A Homeowners Guide', Sheet BTF-18.		
			Australian GeoGuide LR8, 2007. 'Examples of Good/Bad Hillside Construction Practice'.		
			Australian Geomechanics, 2007. 'Practice Note Guidelines for Landslid Management', Appendix C: Qualitative Terminology.	е	



1 Overview

1.1 Background

This report presents the findings of a geotechnical assessment carried out at 106 Rose Avenue, Wheeler Heights (the 'Site'), by AscentGeo. This geotechnical assessment has been prepared to meet Northern Beaches Council lodgement requirements for a Development Application (DA), as well as informing detailed structural design and construction methodology.

1.2 Proposed Development

The proposed development will take place on Lot 10 in DP206961, being 106 Rose Avenue, Wheeler Heights.

Details of the proposed development are outlined in a series of architectural drawings prepared by Rapid Plans, drawing numbers DA1002-DA1014, DA2001-DA2003, DA3000-DA3002, DA4000-DA4001, DA5000-DA5005, dated 21 January 2025.

The works comprise the following:

- Partial demolition of existing dwelling, excavation and footings preparation
- Construction of new ground floor additions to the existing dwelling
- Construction of new first floor addition to the existing dwelling
- Construction of new in ground swimming pool and associated works
- Various soft and hard landscaping.

1.3 Relevant Instruments

This geotechnical assessment has been prepared in accordance with the following relevant guidelines and standards:

- Northern Beaches Council Warringah Local Environment Plan (WLEP) 2011 and Warringah Development Control Plan (WDCP) 2011
- Australian Geomechanics Society's 'Landslide Risk Management Guidelines' (AGS 2007)
- Australian Standard 1726–2017 Geotechnical Site Investigations
- Australian Standard 2870–2011 Residential Slabs and Footings
- Australian Standard 1289.6.3.2–1997 Methods of Testing Soils for Engineering Purposes
- Australian Standard 3798–2007 Guidelines on Earthworks for Commercial and Residential Developments.



2 Site Description

2.1 Summary

A summary of site conditions identified at the time of our assessment is provided in Table 1.

Table 1. Summary of site conditions

Parameter	Description
Site visit	Riley Turnbull, Engineering Geologist – 14/01/2024
Site address	106 Rose Avenue, Wheeler Heights – Lot 10 in DP206961
Site area m² (approx.)	562.4 m ² (by calc.)
Existing development	Single storey rendered dwelling with attached timber decking, detached rendered single car garage, concrete driveway and paved areas.
Slope Aspect	North-west
Average gradient	<5 degrees
Vegetation	Lawn areas, shrubs and large well-established trees.
Retaining structures	Masonry block landscaping wall appears in good condition considering its age.
Neighbouring environment	Residentially developed to the north, east and west. Rose Avenue to the south.



Figure 1. Site location – 106 Rose Avenue, Wheeler Heights (© SIX Maps NSW Gov)



2.2 Site Description

The subject site is situated in a residential area, has a rectangular shape and is bounded by residential dwellings to the north, east and west. Rose Avenue runs along the southern (front) boundary of the site. The site is on a minimally sloping ground with a gradient of <5 degrees, with north easterly aspect (generally falling to the northeastern corner of site). A site plan is included in Appendix A.

The existing building at the site is a single storey dwelling with a grassed front yard and larger grassed backyard area. Neighbouring buildings are mostly single and double storey dwellings.

The four photos presented in Appendix B show the general conditions of the site on the day of the site visit conducted by AscentGeo.

2.3 Geology and Geological Interpretation

The Sydney 1:100,000 Geological Sheet 9130 (NSW Dept. Mineral Resources, 1983) indicates that the site is underlain by Middle Triassic Hawkesbury Sandstones (Rh). The Hawkesbury rocks are typically comprised of medium to course-grained quartz sandstones, minor shale and laminite lenses.

The soil profile consists of shallow uncontrolled fill and silty topsoil (O & A Horizons), silty sand (B Horizon) and weathered bedrock (C Horizon). Based on our observations and the results of testing on site, we would expect weathered sandstone bedrock to be found within 1.4 to 1.5 metres below current surface levels across the area of the proposed works and potentially deeper where filling has been carried out.

Note: The local geology is comprised predominantly of sandstone. The sandstone bedrock is often found in benched terraces, subsequently ground conditions on site may alter significantly across short distances. This variability should be anticipated and accounted for in the design and construction of any new foundations.

2.3 Fieldwork

A site visit and investigation was undertaken on 14 January 2025, which included a geotechnically focused visual assessment of the property and its surrounds; geotechnical mapping; photographic documenting; and a limited subsurface investigation including hand auger borehole and dynamic cone penetrometer (DCP) testing.

Hand Auger Borehole Testing

Two hand auger boreholes (BH01 & BH02) tests were drilled at the approximate locations shown on the site plan to visually identify the subsurface material. Engineering logs of the hand auger boreholes are presented in Appendix C.

Dynamic Cone Penetrometer (DCP) Testing

Five (5) DCP (DCP1-DCP5) tests were carried out to assess the in situ relative density of the shallow soils and the depth to weathered rock. These tests were carried out in accordance with the Australian Standard for ground testing: AS 1289.6.3.2–1997 'Methods of testing soils for engineering purposes.' Test locations were constrained by existing structures, hard surfaces and the presence of utilities.



The location of these tests is shown on the site plan provided in Appendix B and a summary of the test results is presented below in Table 2, with the full details presented in the engineering logs in Appendix C.

Table 2. Summary DCP test results

Test	Summary
DCP 1	Refusal @ 1.4m Bouncing on bedrock. Brown sand on moist tip.
DCP 2	Refusal @ 1.5m Bouncing on bedrock. Brown sand on moist tip.
DCP 3	Refusal @ 0.7m Bouncing on possible buried surface in FILL. Dark brown sand on moist tip.
DCP 4	Refusal @ 0.6m Bouncing on possible buried surface in FILL. Dark brown sand on moist tip.
DCP 5	Refusal @ 1.4m Bouncing on bedrock. Brown sand on moist tip.

Note: The equipment chosen to undertake ground investigations provides the most cost-effective method for understanding the subsurface conditions given site access constraints. Our interpretation of the subsurface conditions is limited to the results of testing undertaken and the known geology in the area. While care is taken to identify the subsurface conditions on site, variation between the interpreted model presented herein and the actual conditions on site may occur. Should actual ground conditions vary from those anticipated, we recommend that the geotechnical consultant at AscentGeo is informed as soon as possible to advise if modifications to our recommendations are required.

3 Geotechnical Assessment

3.1 Geological Model

Based on the results of our site assessment, ground testing, geological mapping and our experience in the area, the subsurface conditions encountered on site may be summarised as follows in Table 3.

Table 3. Interpreted geological model

Unit	Material	Comments		
1	Topsoil / Fill Sandy disturbed topsoil and uncontrolled, poorly compacted fill material.			
2	Sandy Clay	Low plasticity Sandy Clay. Soft to hard in consistency, increasing stiffness with depth.		
3	Sandstone	Medium strength or greater sandstone bedrock (Class III+*) expected to be found below the weathered crust (Class V*).		

^{*} Pells, PJN, Mostyn, G & Walker, F, 1998 (Dec). 'Foundations on sandstone and shale in the Sydney region'. *Australian Geomechanics Journal*, vol. 33, no. 3, pp. 17–29.



3.2 Site Classification

Due to the presence of large-well established trees, the site is classified as "P" in accordance with AS 2870-2011. A classification of "A" may be adopted for footings taken to confirmed competent bedrock.

Table 4. Site classification table for residential slabs and footings (AS2870-2011)

Site Classification	Soil description	Expected range of movement
А	Most sand and rock sites with little or no ground movement from moisture changes.	
S	Slight reactive clay sites, which may experience only slight ground movement from moisture changes.	0–20mm
М	Moderately reactive clay or silt sites, which may experience moderate ground movement from moisture changes.	20–40mm
H1	Highly reactive clay sites, which may experience high ground movement from moisture changes.	40–60mm
H2	Highly reactive clay sites, which may experience very high ground movement from moisture changes.	60–75mm
E	Extremely reactive sites, which may experience extreme ground movement from moisture changes.	>75mm
Р	May consist of any of the above soil types, but in combination with site conditions produce undesirable foundations. P sites may also include fill, soft soils, mine subsidence, collapsing soils, prior or potential landslip, soils subject to erosion, reactive sites subject to abnormal moisture conditions, or sites which cannot be classified otherwise.	

3.3 Groundwater

No groundwater was encountered during testing at the time of our inspection. Whilst dedicated groundwater monitoring was not within the scope of this assessment, due to the site elevation and position of the site relative to the slope and the underlying geology, no significant standing water table is expected to influence the Site. The groundwater regime is not expected to be significantly affected by the proposed works, and it is considered unnecessary to undertake preconstruction or construction stage groundwater monitoring.

Groundwater seepage during and after periods of inclement weather should be anticipated through permeable soil layers, close to the interface with weathered rock and from joints and discontinuities deeper in the weathered rock. Appropriate ground support measures should be utilised in soils overlying rock to manage any localised groundwater inflows and prevent ground loss due to saturated/fluidised sands.



There is a potential for natural intermittent perched groundwater to develop above shallow bedrock and/or above any other low permeability impervious horizons, such as clays in overlying soils or siltstone/shale bands in rock.

3.4 Surface Water

Overland or surface flows entering the site from the adjoining areas were not identified at the time of our inspection; however, normal overland runoff could enter the site from adjacent areas during heavy or extended rainfall. Appropriate surface water diversions should be implemented to prevent overland runoff entering the site from adjacent areas during heavy or extended rainfall.

3.5 Slope Instability

A landslide hazard assessment of the existing slope has been undertaken in general accordance with Australian Geomechanics Society's 'Practice Note Guidelines for Landslide Risk Management', published in March 2007.

- No evidence of significant soil creep, tension cracks or landslip instability were identified across the site or on adjacent properties as viewed from the subject site at the time of our inspection.
- The property is classified as **Area D** with reference to Northern Beaches Council WLEP Warringah Landslip Risk Map (**Image 2**).




Image 2. Warringah Landslip Risk Map: 106 Rose Avenue, Wheeler Heights (© NBC Maps)



3.6 Geotechnical Hazards and Risk Analysis

No significant geotechnical hazards were identified above, beside or below the subject site, including but not limited to the immediately adjoining residential properties, and the road reserve.

The scope of the proposed excavations on site, and the local geology make this site susceptible to instability during the proposed construction works. Careful control of all site works will be required during the installation of any required retention systems, excavations, and the construction of the proposed structures to maintain the stability of the block, and adjacent land.

Based on observation made during our site assessment, the following geological/geotechnical hazards have been identified in relation to the proposed works:

• **Hazard One:** Failure of the proposed excavations.

Table 5. Risk analysis summary

HAZARDS	HAZARD ONE		
ТҮРЕ	Failure of the proposed excavations		
LIKELIHOOD	'Possible' (10 ⁻³)		
CONSEQUENCES TO PROPERTY	'Insignificant' (1.0%)		
RISK TO PROPERTY	'Very Low' (2 x 10 ⁻³)		
RISK TO LIFE	7.0 x 10 ⁻⁴ /annum		
COMMENTS	This level of risk to life and property is 'ACCEPTABLE'.		

3.7 Conclusion and Recommendations

The proposed development is considered to be suitable for the site. The existing conditions and proposed development are considered to constitute an 'ACCEPTABLE' risk to life and a 'LOW' risk to property provided that the recommendations outlined in Table 6 are adhered to during design and construction.



Table 6. Geotechnical recommendations

Recommendation	Description
Soil Excavation	Soil excavation will be required to establish pad levels and new footings across the site. It is anticipated that these excavations will encounter shallow uncontrolled fill and sandy topsoil, sandy clay and weathered bedrock. The excavation of soil, clay and extremely weathered rock should be possible with the use of bucket excavators and rippers, or for piered footings, traditional auger attachments.
	Temporary batter slopes may be considered where setbacks from existing structures and property boundaries permits. For shallow excavations (<1.0m), provided the residual soil is battered back to a minimum of 35 degrees, they should remain stable without support for a short period until permanent support is in place. Unsupported batter slopes in sandy soil will be prone to erosion in inclement weather.
Rock Excavation	All excavation recommendations as outlined below should be read in conjunction with Safe Work Australia's <i>Code of Practice: Excavation Work</i> , published in October 2018.
	It is essential that any excavation through rock that cannot be readily achieved with a bucket excavator or ripper should be carried out initially using a rock saw to minimise the vibration impact and disturbance on the adjoining properties, existing structures and any previously installed supporting systems. Any rock breaking must be carried out only after the rock has been sawed, and in short bursts (2–5 seconds), to prevent the vibration amplifying. The break in the rock from the saw must be between the rock to be broken and the closest adjoining structure.
	All excavated material is to be removed from the site in accordance with current Office of Environment and Heritage (OEH) regulations.
Vibrations	The Australian Standard AS2670.1–2001 'Evaluation of human exposure to whole-body vibration General requirements. Part 1: General requirements', suggests a daytime limit of 5mm/s component PPV for human comfort is acceptable. In general, vibration criteria for human disturbance are more stringent than vibration criteria for effects on building contents and building structural damage. Hence, compliance with the more stringent limits dictated for human exposure, would ensure that compliance is also achieved for the other two categories. Furthermore, it is noted that this approach satisfies the requirements of Appendix J of AS2187.2–2006 'Explosives – storage and use', which also limits PPV to 5mm/s for residential settings.
	As such, we would suggest that the recommendations for method and/or equipment presented in the table below be adopted to maintain an allowable vibration limit of 5mm/s PPV.



Recommendation	Description				
		Maximum Peak Particle Velocity 5mm/sec			
	Distance from adjoining structure (m)	Equipment	Operating Limit (% of Maximum Capacity)		
	1.5 – 2.5	Hand operated jackhammer only	100		
	2.5 – 5.0	300kg rock hammer	50		
	5.0 – 10.0	300kg rock hammer or 600kg rock hammer	100 (300kg) or 50 (600kg)		
	rock saws if vibrations limi		ers or to rotary grinders or actures of the plant should on output.)		
		tions can be mitigated best, utilising line sawing alor	y pulsing the use of rocking boundaries.		
	It is essential that at all times excavation equipment must be operated by experienced personnel, according to the manufacturer's instructions and in a manner consistent with minimising vibration effects.				
Excavation Support	Provided the appropriate batter angles, mentioned above, are achieved, and any exposed soil batter is covered to prevent excessive infiltration or evaporation of moisture, no significant excavation support is anticipated.				
Footings		ew footings are taken to a bedrock (Unit 3) using pie	and founded directly upon rs as required.		
	The allowable bearing pressure for footings taken to competent weathered bedrock of at least low strength is 800kPa . Higher allowable bearing capacities may be achievable subject to inspection and certification of excavated footings by AscentGeo.				
	Pier footings should be of sufficient diameter to enable effective base cleaning to be carried out during construction.				
	To mitigate the risk of differential settlement, it is essential that all footings are founded on competent bedrock of similar consistency. This may require excavation through sandstone floaters or the relocation of planned footings.				
	inspected and approved This inspection should be	before steel reinforcemer e scheduled while excava	Il footing excavations be nt and concrete is placed. tion plant and operators t has been fixed or the		



Recommendation	Description
Fills	Any fill that may be required is to comprise local sand, clay, and weathered rock. Existing organic topsoil is to be cleared in preparation for the introduction of fill.
	Any new fill material is to be placed in layers not more than 250mm thick and compacted to not less than 95% of Standard Optimum Dry Density at plus or minus 2% of Standard Optimum Moisture Content. If supporting pavements or slabs, any new fill must be compacted to not less than 98% of Standard Optimum Dry Density at plus or minus 2% of Standard Optimum Moisture Content for the uppermost 300mm.
	All new fill placement is to be carried out in accordance with AS 3798–2007 'Guidelines on earthworks for commercial and residential developments.'
	Fill should not be placed on the site outside of the lateral extent of new engineered retaining walls. The retaining walls should be in place prior to the placement of new fill, with suitable permanent and effective drainage of backfill.
Sediment and Erosion Control	Appropriate design and construction methods shall be required during site works to minimise erosion and provide sediment control. In particular, siltation fencing, and barriers will be required and are to be designed by others.
Stormwater Disposal	The effective management of ground and surface water on site is an important factor in maintaining the long-term performance of built structures, and the stability of the block more generally.
	It is essential that gutters, downpipes, drains, pipes, and connections are appropriately sized, functioning effectively, and discharging appropriately via non-erosive discharge.
	All stormwater collected from hard surfaces is to be collected and piped directly to the council stormwater network through any storage tanks or onsite detention that may be required by the regulating authorities, and in accordance with all relevant Australian Standards and the detailed stormwater management plan by others.
	Where discharge to council curb and gutter stormwater system, or easement, is not available, on-site stormwater management via non-erosive discharge such and dispersion, or absorption systems may be achievable subject to further testing to establish soil infiltration rates (if necessary), and the detailed stormwater management plan by others.
	Saturation of soils is one of the key triggers for many landslide events and a significant factor in destabilisation of structures over time. As such, the review and design of stormwater systems must consider climate change and the increased potential for periods of concentrated heavy rainfall.



Recommendation	Description			
Inspections	It is essential that the foundation materials of all footing excavations be visually assessed and approved by AscentGeo before steel reinforcement and concrete is placed.			
	Failure to engage AscentGeo for the required hold point / excavation / or foundation material inspections will negate our ability to provide final geotechnical sign off or certification.			
Conditions Relating to Design	To comply with Northern Beaches Council conditions and/or Private Certifier requirements it may be necessary at the following stages for AscentGeo to:			
and Construction Monitoring	Review the geotechnical content of all structural designs prior to the issue of Construction Certificate			
	 Complete the abovementioned excavation hold point and/or foundation material inspections during construction to ensure compliance to design with respect to stability and geotechnical design parameters 			
	 By Occupation Certificate stage (project completion), AscentGeo must have inspected and certified excavation/foundation materials. A final site inspection will be required at this stage before the issue of the Occupation Certificate. 			

Should you have any queries regarding this report, please do not hesitate to contact the author of this report, undersigned.

For and on behalf of AscentGeo,

Riley Turnbull BScMngt Geo

Engineering Geologist

Ben Morgan BScGeol MAIG RPGeo

Managing Director | Engineering Geologist



4 References

Australian Geomechanics Society Landslide Taskforce, Landslide Practice Note Working Group 2007 (Mar). 'Practice Note Guidelines for Landslide Risk Management 2007'. *Australian Geomechanics Journal*, vol. 42, no. 1, pp. 63–114.

Herbert C., 1983, Sydney 1:100 000 Geological Sheet 9130, 1st edition. Geological Survey of New South Wales, Sydney.

NSW Department of Finance, Services and Innovation, Spatial Information Viewer, maps.six.nsw.gov.au.

Northern Beaches Council, Online mapping, Warringah Landslip Risk Map (WLEP 2011).

NSW Department of Finance, Services and Innovation, Spatial Information Viewer, maps.six.nsw.gov.au.

Pells, PJN, Mostyn, G & Walker, F, 1998 (Dec). 'Foundations on sandstone and shale in the Sydney region'. *Australian Geomechanics Journal*, vol. 33, no. 3, pp. 17–29.

Safe Work Australia, 2018 (Oct), Code of Practice: Excavation Work, Safe Work Australia.

Standards Australia 1997, *Methods of Testing Soils for Engineering Purposes*, AS1289.6.3.2:1997, Standards Australia, NSW.

Standards Australia 2001, Evaluation of human exposure to whole-body vibration. Part 1: General requirements, AS2670.1:2001, Standards Australia, NSW.

Standards Australia 2002, Earth-retaining structures, AS4678:2002, Standards Australia, NSW.

Standards Australia 2007, *Guidelines for Earthworks for Commercial and Residential Developments*. AS3798:2007, Standards Australia, NSW.

Standards Australia 2011, Residential Slabs and Footings, AS2870:2011, Standards Australia, NSW.

Standards Australia 2017, Geotechnical Site Investigations, AS1726:2017, Standards Australia, NSW.



Appendix A

Information Sheets

General Notes About This Report



INTRODUCTION

These notes have been prepared by Ascent Geotechnical Consulting Pty Ltd (Ascent) to help our Clients interpret and understand the limitations of this report. Not all sections below are necessarily relevant to all reports.

SCOPE OF SERVICES

This report has been prepared in accordance with the scope of services set out in Ascent's proposal under Ascent's Terms and Conditions, or as otherwise agreed with the Client. The scope of work may have been limited by a range of factors including time, budget, access and/or site constraints.

RELIANCE ON INFORMATION PROVIDED

In preparing the report, Ascent has necessarily relied upon information provided by the Client and/or their Agents. Such data may include surveys, analyses, designs, maps and design plans. Ascent has not verified the accuracy or completeness of the data except as stated in this report.

GEOTECHNICAL AND ENVIRONMENTAL REPORTING

Geotechnical and environmental reporting relies on the interpretation of factual information, based on judgment and opinion, and is far less exact than other engineering or design disciplines.

Geotechnical and environmental reports are prepared for a specific purpose, development, and site, as described in the report, and may not contain sufficient information for other purposes, developments, or sites (including adjacent sites), other than that described in the report.

SUBSURFACE CONDITIONS

Subsurface conditions can change with time and can vary between test locations. For example, the actual interface between the materials may be far more gradual or abrupt than indicated.

Therefore, actual conditions in areas not sampled may differ from those predicted, since no subsurface investigation, no matter how comprehensive, can reveal all subsurface details and anomalies.

Construction operations at or adjacent to the site and natural events such as floods, earthquakes or groundwater fluctuations can also affect subsurface conditions, and thus the continuing adequacy of a geotechnical report. Ascent should be kept informed of any such events, and should be retained to identify variances, conduct additional tests if required, and recommend solutions to problems encountered on site.

GROUNDWATER

Groundwater levels indicated on borehole and test pit logs are recorded at specific times. Depending on ground permeability, measured levels may or may not reflect actual levels if measured over a longer time period. Also, groundwater levels and seepage inflows may fluctuate with seasonal and environmental variations and construction activities.

INTERPRETATION OF DATA

Data obtained from nominated discrete locations, subsequent laboratory testing and empirical or external sources are interpreted by trained professionals in order to provide an opinion about overall site conditions, their likely impact with respect to the report purpose and recommended actions in accordance with any relevant industry standards, guidelines or procedures.

SOIL AND ROCK DESCRIPTIONS

Soil and rock descriptions are based on AS 1726 – 1993, using visual and tactile assessment, except at discrete locations where field and / or laboratory tests have been carried out. Refer to the accompanying soil and rock terms sheet for further information.

COPYRIGHT AND REPRODUCTION

The contents of this document are and remain the intellectual property of Ascent. This document should only be used for the purpose for which it was commissioned and should not be used for other projects, or by a third party without written permission from Ascent

This report shall not be reproduced either totally or in part without the permission of Ascent. Where information from this report is to be included in contract documents or engineering specification for the project, the entire report should be included in order to minimise the likelihood of misinterpretation.

FURTHER ADVICE

Ascent would be pleased to further discuss how any of the above issues could affect a specific project. We would also be pleased to provide further advice or assistance including:

Assessment of suitability of designs and construction techniques;

Contract documentation and specification; Construction advice (foundation assessments, excavation support).

Abbreviations, Notes & Symbols

SUBSURFACE INVESTIGATION

ΙE		

METHOD			
Borehole Logs		Excavation Logs	
AS#	Auger screwing (#-bit)	ВН	Backhoe/excavator bucket
AD#	Auger drilling (#-bit)	NE	Natural exposure
В	Blank bit	HE	Hand excavation
V	V-bit	Χ	Existing excavation
T	TC-bit		
HA	Hand auger	Cored Bo	orehole Logs
R	Roller/tricone	NMLC	NMLC core drilling
W	Washbore	NQ/HQ	Wireline core drilling
AH	Air hammer		
AT	Air track		
LB	Light bore push tube		
MC	Macro core push tube		
DT	Dual core push tube		

SUPPORT

Borehole Logs		Excava	ation Logs
С	Casing	S	Shoring
M	Mud	В	Benched

SAMPLING

U#

В	Bulk sample
D	Disturbed sample

Thin-walled tube sample (#mmdiameter)

ES

EW Environmental water sample

FIELD TESTING

PP	Pocket penetrometer (kPa)
DCP	Dynamic cone penetrometer
PSP	Perth sand penetrometer
SPT	Standard penetration test
PBT	Plate bearing test

Vane shear strength peak/residual (kPa) and vane size (mm)

N* SPT (blows per 300mm) SPT with solid cone Refusal

*denotes sample taken

BOUNDARIES

 Known
 Probable
 Possible

SOIL

MOISTURE CONDITION

D	Dry
M	Moist
W	Wet
Wp	Plastic Limit
WI	Liquid Limit
MC	Moisture Content

CONSISTENCY **DENSITY INDEX** VLVery Loose Very Soft s Soft Loose F Firm MD Medium Dense St Stiff D Dense VSt Very Stiff VD Very Dense

Hard Friable

USCS SYMBOLS

GW	Well graded gravels and gravel-sand mixtures, little or no fines
GP	Poorly graded gravels and gravel-sand mixtures, little or no

GM Silty gravels, gravel-sand-silt mixtures GC Clayey gravels, gravel-sand-clay mixtures

SW	Well graded sands and gravelly sands, little orno fines
SP	Poorly graded sands and gravelly sands, little or no fines

SM Silty sand, sand-silt mixtures SC Clayey sand, sand-clay mixtures

ML Inorganic silts of low plasticity, very fine sands, rock flour, silty

or clayey fine sands

CL Inorganic clays of low to medium plasticity, gravelly clays,

OL

organic clays of now of meeting plasticity, gravely, sandy clays, silty clays
Organic silts and organic silty clays of low plasticity
Inorganic clays of high plasticity
Organic clays of medium to high plasticity
Deat much and other highly organic soils МН CH ОН

Peat muck and other highly organicsoils

ROCK

WEATHERING		STRENGTH	
RS	Residual Soil	EL	Extremely Low
XW	Extremely Weathered	VL	Very Low
HW	Highly Weathered	L	Low
MW	Moderately Weathered	M	Medium
DW*	Distinctly Weathered	Н	High
SW	Slightly Weathered	VH	Very High
FR	Fresh	EH	Extremely High

*covers both HW & MW

ROCK QUALITY DESIGNATION (%)

= sum of intact core pieces > 100mm x 100 total length of section being evaluated

CORE RECOVERY (%)

= core recovered x 100 core IIft

NATURAL FRACTURES

_	٠.	_	_
	v	n	Е

VN

JT	Joint
BP	Bedding plane
SM	Seam
FZ	Fractured zone
S7	Shear zone

Vein

Infill or Coating

Cn	Clean
St	Stained
Vn	Veneer
Co	Coating
CI	Clay
Ca	Calcite
Fe	Iron oxide
Mi	Micaceous
Qz	Quartz

Shape

pl	Planar
cu	Curved
un	Undulose
st	Stepped
ir	Irregular

Roughness

pol	Polished
slk	Slickensided
smo	Smooth
rou	Rough


Soil & Rock Terms

SOIL				STRENGTH			
MOISTURE CON				Term	Is50 (MPa)	Term	Is50 (MPa)
Term	Description			Extremely Low	< 0.03	High	1 – 3
Dry			emented soils are ed granular soils run	Very Low Low Medium	0.03 - 0.1 0.1 - 0.3 0.3 - 1	Very High Extremely High	3 – 10 > 10
Moist		arkened in colour. On the colour of the colo		WEATHERING			
Wet			ning on hands when	Term Residual Soil	Description Soil developed	on extremely weathe	red rock: the mass
	s, moisture content		ped in relation to an, > greater than, <			ubstance fabric are n	
less than, << muc	ch less than].			Extremely Weathered		red to such an extent t either disintegrates	
CONSISTENCY Term	c (kPa)	Term	c (kPa)		remoulded, in w visible	ater. Fabric of origin	al rock is still
Very Soft Soft	u < 12 12 - 25	Very Stiff Hard	u 100 200 > 200	Highly Weathered	Rock strength u	sually highly change	d by weathering;
Firm	25 - 50	Friable	-	Moderately	Rock strength i	sually moderately ch	anged by
Stiff	50 - 100			Weathered	weathering; roc	k may be moderately	discoloured
DENSITY INDEX Term	I _D (%)	Term	I _D (%)	Distinctly Weathered	See 'Highly We	athered' or 'Moderate	ely Weathered'
Very Loose Loose	< 15 15 – 35	Dense Very Dense	65 – 8 > 85	Slightly Weathered		discoloured but show gth from fresh rock	s little or no
Medium Dense	35 – 65			Fresh	Rock shows no	signs of decompositi	on or staining
PARTICLE SIZE	Cultulistics	Sine (mam)		NATURAL FRAC	TURES		
Name Boulders	Subdivision	Size (mm) > 200		Туре	Description		
Cobbles		63 - 200		Joint		or crack across which	
Gravel	coarse medium	20 - 63 6 - 20		Bedding plane		ength. May be open layers of mineral gra	
	fine	2.36 - 6		0	or composition	itdil (i-fill)t-	
Sand	coarse medium	0.6 -2.36 0.2 - 06		Seam	insitu rock (XW	osited soil (infill), extro), or disoriented usua a bost rock (crushed)	lly angular
Cilt 9 Olev	fine	0.075 0.2		Choor zono	_	e host rock (crushed)	
Silt & Clay MINOR COMPO	NENTS	< 0.075		Shear zone	material interse	nly parallel planar bou cted by closely space nd /or microscopic fra	ed (generally <
Term	Proportion by	fine grained			planes		
rem	Mass coarse grained	ille grained		Vein	Intrusion of any mass. Usually i	shape dissimilar to t gneous	he adjoining rock
Trace	≤ 5%	≤ 15%					
Some	5 - 2%	15 - 30%		Shape	Description		
SOIL ZONING				Planar	Consistent orier		
Layers	Continuous expos	sures		Curved	Gradual change	e in orientation	
Lenses	·	yers of lenticular sh	аре	Undulose Stepped	Wavy surface	ell defined steps	
Pockets	ets Irregular inclusions of different material			Irregular		anges in orientation	
SOIL CEMENTING Weakly Easily broken up by hand			Infill or Coating	Description			
Moderately	Moderately Effort is required to break up the soil by hand			Clean	No visible coating or discolouring		
COIL STRUCTUR				Stained	No visible coating but surfaces are discoloured		
SOIL STRUCTURE Massive Coherent, with any partings both vertically and horizontally spaced at greater than 100mm			Veneer	A visible coating of soil or mineral, too thin to measure; may be patchy			
Weak	Peds indistinct ar	nd barely observable . 30% consist of per	e on pit face. When	Coating	Visible coating ≤ 1mm thick. Ticker soil material described as seam		
Strong		stinct in undisturbe	d soil. When	Roughness	Description		
J		consists of peds sm		Polished Slickensided	Shiny smooth s Grooved or strice	urface ated surface, usually	polished
ROCK				Smooth		h. Few or no surface	•
<u> </u>	ROCK TYPE DEFIN	JITIONS		Rough		ace irregularities (ame fine to coarse sand	
Rock Type		than 50% of rock c	onsists of)		,		•
Conglomerate	gravel sized (>	> 2mm) fragments	•			generally in accorda	nce with AS1726-
Sandstone Siltstone		06 to 2mm) grains 06mm) particles, roo	ck is not laminated	1993 Geotechnic	al Site Investigatio	ns	

Definition (more than 50% of rock consists of....)
... gravel sized (> 2mm) fragments
... sand sized (0.06 to 2mm) grains
... silt sized (<0.06mm) particles, rock is not laminated
... clay, rock is not laminated
... silt or clay sized particles, rock is laminated

Siltstone Claystone Shale

Graphic Symbols Index



Foundation Maintenance and Footing Performance: A Homeowner's Guide



BTF 18 replaces Information Sheet 10/91

Buildings can and often do move. This movement can be up, down, lateral or rotational. The fundamental cause of movement in buildings can usually be related to one or more problems in the foundation soil. It is important for the homeowner to identify the soil type in order to ascertain the measures that should be put in place in order to ensure that problems in the foundation soil can be prevented, thus protecting against building movement.

This Building Technology File is designed to identify causes of soil-related building movement, and to suggest methods of prevention of resultant cracking in buildings.

Soil Types

The types of soils usually present under the topsoil in land zoned for residential buildings can be split into two approximate groups — granular and clay. Quite often, foundation soil is a mixture of both types. The general problems associated with soils having granular content are usually caused by erosion. Clay soils are subject to saturation and swell/shrink problems.

Classifications for a given area can generally be obtained by application to the local authority, but these are sometimes unreliable and if there is doubt, a geotechnical report should be commissioned. As most buildings suffering movement problems are founded on clay soils, there is an emphasis on classification of soils according to the amount of swell and shrinkage they experience with variations of water content. The table below is Table 2.1 from AS 2870, the Residential Slab and Footing Code.

Causes of Movement

Settlement due to construction

There are two types of settlement that occur as a result of construction:

- Immediate settlement occurs when a building is first placed on its foundation soil, as a result of compaction of the soil under the weight of the structure. The cohesive quality of clay soil mitigates against this, but granular (particularly sandy) soil is susceptible.
- Consolidation settlement is a feature of clay soil and may take
 place because of the expulsion of moisture from the soil or because
 of the soil's lack of resistance to local compressive or shear stresses.
 This will usually take place during the first few months after
 construction, but has been known to take many years in
 exceptional cases.

These problems are the province of the builder and should be taken into consideration as part of the preparation of the site for construction. Building Technology File 19 (BTF 19) deals with these problems.

Erosion

All soils are prone to erosion, but sandy soil is particularly susceptible to being washed away. Even clay with a sand component of say 10% or more can suffer from erosion.

Saturation

This is particularly a problem in day soils. Saturation creates a boglike suspension of the soil that causes it to lose virtually all of its bearing capacity. To a lesser degree, sand is affected by saturation because saturated sand may undergo a reduction in volume particularly imported sand fill for bedding and blinding layers. However, this usually occurs as immediate settlement and should normally be the province of the builder.

Seasonal swelling and shrinkage of soil

All clays react to the presence of water by slowly absorbing it, making the soil increase in volume (see table below). The degree of increase varies considerably between different clays, as does the degree of decrease during the subsequent drying out caused by fair weather periods. Because of the low absorption and expulsion rate, this phenomenon will not usually be noticeable unless there are prolonged rainy or dry periods, usually of weeks or months, depending on the land and soil characteristics.

The swelling of soil creates an upward force on the footings of the building, and shrinkage creates subsidence that takes away the support needed by the footing to retain equilibrium.

Shear failure

This phenomenon occurs when the foundation soil does not have sufficient strength to support the weight of the footing. There are two major post-construction causes:

- Significant load increase.
- Reduction of lateral support of the soil under the footing due to erosion or excavation.
- In clay soil, shear failure can be caused by saturation of the soil adjacent to or under the footing.

	GENERAL DEFINITIONS OF SITE CLASSES
Class	Foundation
A	Most sand and rock sites with little or no ground movement from moisture changes
S	Slightly reactive clay sites with only slight ground movement from moisture changes
М	Moderately reactive clay or silt sites, which can experience moderate ground movement from moisture changes
Н	Highly reactive day sites, which can experience high ground movement from moisture changes
Е	Extremely reactive sites, which can experience extreme ground movement from moisture changes
A to P	Filled sites
P	Sites which include soft soils, such as soft clay or silt or loose sands; landslip; mine subsidence; collapsing soils; soils subject to crosion; reactive sites subject to abnormal moisture conditions or sites which cannot be classified otherwise

Tree root growth

Trees and shrubs that are allowed to grow in the vicinity of footings can cause foundation soil movement in two ways

- Roots that grow under footings may increase in cross-sectional size, exerting upward pressure on footings.
- Roots in the vicinity of footings will absorb much of the moisture in the foundation soil, causing shrinkage or subsidence.

Unevenness of Movement

The types of ground movement described above usually occur unevenly throughout the building's foundation soil. Settlement due to construction tends to be uneven because of:

- · Differing compaction of foundation soil prior to construction.
- · Differing moisture content of foundation soil prior to construction.

Movement due to non-construction causes is usually more uneven still. Erosion can undermine a footing that traverses the flow or can create the conditions for shear failure by eroding soil adjacent to a footing that runs in the same direction as the flow.

Saturation of clay foundation soil may occur where subfloor walls create a dam that makes water pond. It can also occur wherever there is a source of water near footings in clay soil. This leads to a severe reduction in the strength of the soil which may create local shear

Seasonal swelling and shrinkage of clay soil affects the perimeter of the building first, then gradually spreads to the interior. The swelling process will usually begin at the uphill extreme of the building, or on the weather side where the land is flat. Swelling gradually reaches the interior soil as absorption continues. Shrinkage usually begins where the sunk heat is greatest.

Effects of Uneven Soil Movement on Structures

Erosion and saturation

Erosion removes the support from under footings, tending to create subsidence of the part of the structure under which it occurs. Brickwork walls will resist the stress created by this removal of support by bridging the gap or cantilevering until the bricks or the mortar bedding fail. Older masonry has little resistance. Evidence of failure varies according to circumstances and symptoms may include:

- Step cracking in the mortar beds in the body of the wall or above/below openings such as doors or windows.
- Vertical cracking in the bricks (usually but not necessarily in line with the vertical beds or perpends).

Isolated piers affected by erosion or saturation of foundations will eventually lose contact with the bearers they support and may tilt or fall over. The floors that have lost this support will become bouncy, sometimes rattling ornaments etc.

Seasonal swelling/shrinkage in clay

Swelling foundation soil due to rainy periods first lifts the most exposed extremities of the footing system, then the remainder of the perimeter footings while gradually permeating inside the building footprint to lift internal footings. This swelling first tends to create a dish effect, because the external footings are pushed higher than the internal ones.

The first noticeable symptom may be that the floor appears slightly dished. This is often accompanied by some doors binding on the floor or the door head, together with some cracking of comice mitres. In buildings with timber flooring supported by bearers and joists, the floor can be bouncy. Externally there may be visible dishing of the hip or ridge lines.

As the moisture absorption process completes its journey to the innermost areas of the building, the internal footings will rise. If the spread of moisture is roughly even, it may be that the symptoms will temporarily disappear, but it is more likely that swelling will be uneven, creating a difference rather than a disappearance in symptoms. In buildings with timber flooring supported by bearers and joists, the isolated piers will rise more easily than the strip footings or piers under walls, creating noticeable doming of flooring.



As the weather pattern changes and the soil begins to dry out, the external footings will be first affected, beginning with the locations where the sun's effect is strongest. This has the effect of lowering the external footings. The doming is accentuated and cracking reduces or disappears where it occurred because of dishing, but other cracks open up. The roof lines may become convex.

Doming and dishing are also affected by weather in other ways. In areas where warm, wet summers and cooler dry winters prevail, water migration tends to be toward the interior and doming will be accentuated, whereas where summers are dry and winters are cold and wet, migration tends to be toward the exterior and the underlying propensity is toward dishing.

Movement caused by tree roots

In general, growing roots will exert an upward pressure on footings, whereas soil subject to drying because of tree or shrub roots will tend to remove support from under footings by inducing shrinkage.

Complications caused by the structure itself Most forces that the soil causes to be exerted on structures are vertical — i.e. either up or down. However, because these forces are seldom spread evenly around the footings, and because the building resists uneven movement because of its rigidity, forces are exerted from one part of the building to another. The net result of all these forces is usually rotational. This resultant force often complicates the diagnosis because the visible symptoms do not simply reflect the original cause. A common symptom is binding of doors on the

Effects on full masonry structures

vertical member of the frame

Brickwork will resist cracking where it can. It will attempt to span areas that loss support because of subsided foundations or raised points. It is therefore usual to see cracking at weak points, such as openings for windows or doors.

In the event of construction settlement, cracking will usually remain unchanged after the process of settlement has ceased.

With local shear or erosion, cracking will usually continue to develop until the original cause has been remedied, or until the subsidence has completely neutralised the affected portion of footing and the structure has stabilised on other footings that remain effective.

In the case of swell/shrink effects, the brickwork will in some cases return to its original position after completion of a cycle, however it is more likely that the rotational effect will not be exactly reversed, and it is also usual that brickwork will settle in its new position and will resist the forces trying to return it to its original position. This means that in a case where swelling takes place after construction and cracking occurs, the cracking is likely to at least partly remain after the shrink segment of the cycle is complete. Thus, each time the cycle is repeated, the likelihood is that the cracking will become wider until the sections of brickwork become virtually independent.

With repeated cycles, once the cracking is established, if there is no other complication, it is normal for the incidence of cracking to stabilise, as the building has the articulation it needs to cope with the problem. This is by no means always the case, however, and monitoring of cracks in walls and floors should always be treated exclusive.

Upheaval caused by growth of tree roots under footings is not a simple vertical shear stress. There is a tendency for the root to also exert lateral forces that attempt to separate sections of brickwork after initial cracking has occurred. The normal structural arrangement is that the inner leaf of brickwork in the external walls and at least some of the internal walls (depending on the roof type) comprise the load-bearing structure on which any upper floors, ceilings and the roof are supported. In these cases, it is internally visible cracking that should be the main focus of attention, however there are a few examples of dwellings whose external leaf of masonry plays some supporting role, so this should be checked if there is any doubt. In any case, externally visible cracking is important as a guide to stresses on the structure generally, and it should also be remembered that the external walls must be capable of supporting themselves.

Effects on framed structures

Timber or steel framed buildings are less likely to exhibit cracking due to swell/shrink than masonry buildings because of their flexibility. Also, the doming/dishing effects tend to be lower because of the lighter weight of walls. The main risks to framed buildings are encountered because of the isolated pier footings used under walls. Where crosion or saturation cause a footing to fall away, this can double the span which a wall must bridge. This additional stress can create cracking in wall linings, particularly where there is a weak point in the structure caused by a door or window opening. It is, however, unlikely that framed structures will be so stressed as to suffer serious damage without first exhibiting some or all of the above symptoms for a considerable period. The same warning period should apply in the case of upheaval. It should be noted, however, that where framed buildings are supported by strip footings there is only one leaf of brickwork and therefore the externally visible walls are the supporting structure for the building. In this case, the subfloor masonry walls can be expected to behave as full brickwork walls.

Effects on brick veneer structures

Because the load-bearing structure of a brick veneer building is the frame that makes up the interior leaf of the external walls plus perhaps the internal walls, depending on the type of roof, the building can be expected to behave as a framed structure, except that the external masonry will behave in a similar way to the external leaf of a full masonry structure.

Water Service and Drainage

Where a water service pipe, a sewer or stormwater drainage pipe is in the vicinity of a building, a water leak can cause erosion, swelling or saturation of susceptible soil. Even a minuscule leak can be enough to saturate a clay foundation. A leaking tap near a building can have the same effect. In addition, trenches containing pipes can become watercourses even though backfilled, particularly where broken nubble is used as fill. Water that runs along these trenches can be responsible for scrious crosion, interstrata scepage into subfloor areas and saturation.

Pipe leakage and trench water flows also encourage tree and shrub roots to the source of water, complicating and exacerbating the problem.

Poor roof plumbing can result in large volumes of rainwater being concentrated in a small area of soil:

 Incorrect falls in roof guttering may result in overflows, as may gutters blocked with leaves etc.

- · Corroded guttering or downpipes can spill water to ground.
- Downpipes not positively connected to a proper stormwater collection system will direct a concentration of water to soil that is directly adjacent to footings, sometimes causing large-scale problems such as erosion, saturation and migration of water under the building.

Seriousness of Cracking

In general, most cracking found in masonry walls is a cosmetic nuisance only and can be kept in repair or even ignored. The table below is a reproduction of Table C1 of AS 2870.

AS 2870 also publishes figures relating to cracking in concrete floors, however because wall cracking will usually reach the critical point significantly earlier than cracking in slabs, this table is not reproduced here.

Prevention/Cure

Plumbing

Where building movement is caused by water service, roof plumbing, sewer or stormwater failure, the remedy is to repair the problem. It is prudent, however, to consider also rerouting pipes away from the building where possible, and relocating taps to positions where any leakage will not direct water to the building vicinity. Even where gully traps are present, there is sometimes sufficient spill to create erosion or saturation, particularly in modern installations using smaller diameter PVC fixtures. Indeed, some gully traps are not situated directly under the taps that are installed to charge them, with the result that water from the tap may enter the backfilled trench that houses the sewer piping. If the trench has been poorly backfilled, the water will either pond or flow along the bottom of the trench. As these trenches usually run alongside the footings and can be at a similar depth, it is not hard to see how any water that is thus directed into a trench can easily affect the foundation's ability to support footings or even gain entry to the subfloor area.

Ground drainage

In all soils there is the capacity for water to travel on the surface and below it. Surface water flows can be established by inspection during and after heavy or prolonged rain. If necessary, a grated drain system connected to the stormwater collection system is usually an easy solution.


It is, however, sometimes necessary when attempting to prevent water migration that testing be carried out to establish watertable height and subsoil water flows. This subject is referred to in BTF 19 and may properly be regarded as an area for an expert consultant.

Protection of the building perimeter

It is essential to remember that the soil that affects footings extends well beyond the actual building line. Watering of garden plants, shrubs and trees causes some of the most senious water problems.

For this reason, particularly where problems exist or are likely to occur, it is recommended that an apron of paving be installed around as much of the building perimeter as necessary. This paving

Description of typical damage and required repair	Approximate crack width limit (see Note 3)	Damage
Hairline cracks	<0.1 mm	0
Fine cracks which do not need repair	<1 mm	1
Cracks noticeable but easily filled. Doors and windows stick slightly	⊲ mm	2
Cracks can be repaired and possibly a small amount of wall will need to be replaced. Doors and windows stick. Service pipes can fracture. Weathertightness often impaired	5-15 mm (or a number of cracks 3 mm or more in one group)	3
Extensive repair work involving breaking-out and replacing sections of walls, especially over doors and windows. Window and door frames distort. Walls lean or bulge noticeably, some loss of bearing in beams. Service pipes disrupted	15-25 mm but also depend on number of cracks	4



should extend outwards a minimum of 900 mm (more in highly reactive soil) and should have a minimum fall away from the building of 1:60. The finished paving should be no less than 100 mm below brick vent bases.

It is prudent to relocate drainage pipes away from this paving, if possible, to avoid complications from future leakage. If this is not practical, earthenware pipes should be replaced by PVC and backfilling should be of the same soil type as the surrounding soil and compacted to the same density.

Except in areas where freezing of water is an issue, it is wise to remove taps in the building area and relocate them well away from the building – preferably not uphill from it (see BTF 19).

It may be desirable to install a grated drain at the outside edge of the paving on the uphill side of the building. If subsoil drainage is needed this can be installed under the surface drain.

Condensation

In buildings with a subfloor void such as where bearers and joists support flooring, insufficient wentilation creates ideal conditions for condensation, particularly where there is little clearance between the floor and the ground. Condensation adds to the moisture already present in the subfloor and significantly slows the process of drying out. Installation of an adequate subfloor ventilation system, either natural or mechanical, is desirable.

Warning: Although this Building Technology File deals with cracking in buildings, it should be said that subfloor moisture can result in the development of other problems, notably:

- Water that is transmitted into masonry, metal or timber building elements causes damage and/or decay to those elements.
- High subfloor humidity and moisture content create an ideal environment for various pests, including termites and spiders.
- Where high moisture levels are transmitted to the flooring and walls, an increase in the dust mite count can ensue within the living areas. Dust mites, as well as dampness in general, can be a health hazard to inhabitants, particularly those who are abnormally susceptible to respiratory ailments.

The garden

The ideal vegetation layout is to have lawn or plants that require only light watering immediately adjacent to the drainage or paving edge, then more demanding plants, shrubs and trees spread out in that order.

Overwatering due to misuse of automatic watering systems is a common cause of saturation and water migration under footings. If it is necessary to use these systems, it is important to remove garden beds to a completely safe distance from buildings.

Existing trees

Where a tree is causing a problem of soil drying or there is the existence or threat of upheaval of footings, if the offending roots are subsidiary and their removal will not significantly damage the tree, they should be severed and a concrete or metal barrier placed vertically in the soil to prevent future root growth in the direction of the building. If it is not possible to remove the relevant roots without damage to the tree, an application to remove the tree should be made to the local authority. A prudent plan is to transplant likely offenders before they become a problem.

Information on trees, plants and shrubs State departments overseeing agriculture can give information

State departments overseeing agriculture can give information regarding root patterns, volume of water needed and safe distance from buildings of most species. Botanic gardens are also sources of information. For information on plant roots and drains, see Building Technology File 17.

Excavation

Excavation around footings must be properly engineered. Soil supporting footings can only be safely excavated at an angle that allows the soil under the footing to remain stable. This angle is called the angle of repose (or friction) and varies significantly between soil types and conditions. Removal of soil within the angle of repose will cause subsidence.

Remediation

Where erosion has occurred that has washed away soil adjacent to footings, soil of the same classification should be introduced and compacted to the same density. Where footings have been undermined, augmentation or other specialist work may be required. Remediation of footings and foundations is generally the realm of a specialist consultant.

Where isolated footings rise and fall because of swell/shrink effect, the homeowner may be tempted to alleviate floor bounce by filling the gap that has appeared between the bearer and the pier with blocking. The danger here is that when the next swell segment of the cycle occurs, the extra blocking will push the floor up into an accentuated dome and may also cause local shear failure in the soil. If it is necessary to use blocking, it should be by a pair of fine wedges and monitoring should be carried out fortnightly.

This BTF was prepared by John Lewer FAIB, MIAMA, Partner, Construction Diagnosis.

The information in this and other issues in the series was derived from various sources and was believed to be correct when published.

The information is advisory. It is provided in good faith and not claimed to be an exhaustive treatment of the relevant subject.

Further professional advice needs to be obtained before taking any action based on the information provided.


Distributed by

CSIRO PUBLISHING PO Box 1139, Collingwood 3066, Australia


Freecall 1800 645 051 Tel (03) 9662 7666 Fax (03) 9662 7555 www.publish.csiro.au Email: publishing.sales@csiro.au

© CSIRO 2003. Unauthorised copying of this Building Technology file is prohibited

EXAMPLES OF GOOD HILLSIDE PRACTICE



EXAMPLES OF POOR HILLSIDE PRACTICE



PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007 APPENDIX C: LANDSLIDE RISK ASSESSMENT

QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY

QUALITATIVE MEASURES OF LIKELIHOOD

Approximate A1	Approximate Annual Probability	Implied Indicative Landslide	ve Landslide			
Indicative Value	Notional Boundary	Recurrence Interval	Interval	Description	Descriptor	Level
10.1	5×10-2	10 years		The event is expected to occur over the design life.	ALMOST CERTAIN	A
10-2	OA10	100 years	20 years	The event will probably occur under adverse conditions over the design life.	LIKELY	В
10-3	0X10	1000 years	2000 years	The event could occur under adverse conditions over the design life.	POSSIBLE	C
10-4	5x10"	10,000 years	Succession of the	The event might occur under very adverse circumstances over the design life.	UNLIKELY	D
10-5	5x10°	100,000 years	200,000 years	The event is conceivable but only under exceptional circumstances over the design life.	RARE	Ε
10-6	OVYC	1,000,000 years	Zou, uou years	The event is inconceivable or fanciful over the design life.	BARELY CREDIBLE	F

The table should be used from left to right; use Approximate Annual Probability or Description to assign Descriptor, not vice versa. \equiv Note:

QUALITATIVE MEASURES OF CONSEQUENCES TO PROPERTY

Approximate	Approximate Cost of Damage			
Indicative Value	Notional Boundary	Description	Descriptor	Level
200%	70001	Structure(s) completely destroyed and/or large scale damage requiring major engineering works for stabilisation. Could cause at least one adjacent property major consequence damage.	CATASTROPHIC	1
%09	%001	Extensive damage to most of structure, and/or extending beyond site boundaries requiring significant stabilisation works. Could cause at least one adjacent property medium consequence damage.	MAJOR	2
20%	40%	Moderate damage to some of structure, and/or significant part of site requiring large stabilisation works, Could cause at least one adjacent property minor consequence damage.	MEDIUM	3
5%	10%	Limited damage to part of structure, and/or part of site requiring some reinstatement stabilisation works.	MINOR	4
0.5%		Little damage. (Note for high probability event (Almost Certain), this category may be subdivided at a notional boundary of 0.1%. See Risk Matrix.)	INSIGNIFICANT	5

The Approximate Cost of Damage is expressed as a percentage of market value, being the cost of the improved value of the unaffected property which includes the land plus the 5 Notes:

The Approximate Cost is to be an estimate of the direct cost of the damage, such as the cost of reinstatement of the damaged portion of the property (land plus structures), stabilisation works required to render the site to tolerable risk level for the landslide which has occurred and professional design fees, and consequential costs such as legal fees, temporary accommodation. It does not include additional stabilisation works to address other landslides which may affect the property. 3

(4) The table should be used from left to right, use Approximate Cost of Damage or Description to assign Descriptor, not vice versa

APPENDIX C: - QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY (CONTINUED) PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

QUALITATIVE RISK ANALYSIS MATRIX – LEVEL OF RISK TO PROPERTY

LIKELIHOOD	OOD	CONSEQUE	NCES TO PROP	CONSEQUENCES TO PROPERTY (With Indicative Approximate Cost of Damage)	ve Approximate Cos	t of Damage)
	Indicative Value of Approximate Annual Probability	1: CATASTROPHIC 200%	2: MAJOR 60%	3: MEDIUM 20%	4: MINOR 5%	5: INSIGNIFICANT 0.5%
A - ALMOST CERTAIN	10.1	VIII	ÍΙΛ.	IIA	н	MorL(5)
B - LIKELY	10-2	VII	VII	Н	M	T
C - POSSIBLE	10-3	ΗΛ	Н	M	M	NF.
D - UNLIKELY	104	Н	M	ı	Ţ	TA
E - RARE	10-5	M	Г	Г	AL	VL
F - BARELY CREDIBLE	10-6	Г	N.	ΛΓ	AL	AL

ତ୍ର Notes:

For Cell A5, may be subdivided such that a consequence of less than 0.1% is Low Risk.

When considering a risk assessment it must be clearly stated whether it is for existing conditions or with risk control measures which may not be implemented at the current

RISK LEVEL IMPLICATIONS


Unacceptable without treatment. Extensive detailed investigation and research, planning and implementation of treatment options essential to reduce risk to Low; may be too expensive and not practical. Work likely to cost more than value of the property. HIGH RISK MODERATE RISK MODERATE RISK LOW RISK Usually acceptable to regulators. Where treatment has been required to reduce the risk to this level, ongoing maintenance is required. VERY LOW RISK Acceptable. Manage by normal slope maintenance procedures.	- -	Risk Level	Example Implications (7)
	TEA.	VERY HIGH RISK	Unacceptable without treatment. Extensive detailed investigation and research, planning and implementation of treatment options essential to reduce risk to Low; may be too expensive and not practical. Work likely to cost more than value of the property.
	Н	HIGH RISK	Unacceptable without treatment. Detailed investigation, planning and implementation of treatment options required to reduce risk to Low. Work would cost a substantial sum in relation to the value of the property.
	M	MODERATE RISK	May be tolerated in certain circumstances (subject to regulator's approval) but requires investigation, planning and implementation of treatment options to reduce the risk to Low. Treatment options to reduce to Low risk should be implemented as soon as practicable.
	Т	LOW RISK	Usually acceptable to regulators. Where treatment has been required to reduce the risk to this level, ongoing maintenance is required.
	N.	VERY LOW RISK	Acceptable. Manage by normal slope maintenance procedures.

The implications for a particular situation are to be determined by all parties to the risk assessment and may depend on the nature of the property at risk; these are only given as a general guide. Note: (7)




Appendix A

Site plans



INTERPRETED SUBSURFACE SECTION ONLY. ACTUAL GROUND CONDITIONS MAY VARY.



<u>LEGEND</u>

SILTY TOPSOIL / UNCONTROLLED FILL

SANDY CLAY

SANDSTONE BEDROCK

INFERRED GEOLOGICAL SECTION

SCALE NTS

					L
					/
Α	15.01.25	PRELIMINARY ISSUE	VT	ВМ	
REV	DATE	REVISION DESCRIPTION	REV BY	CHCKD	



ABN: 71 621 428 402 www.ascentgeo.com.au

(02) 9913 3179 admin@ascentgeo.com.au

1457 Pittwater Road North Narrabeen NSW 2101

PHOEBE BUCHANAN INFERRED GEOLOG

COPYRIGHT:
THE INFORMATION CONTAINED IN THIS DOCUMENT IS THE PROPERTY OF ASCENT GEOTECHNICAL CONSULTING, COPYING OF THIS MATERIAL IN WHOLE OR IN PART WITHOUT THE WRITTEN PERMISSION OF ASCENT GEOTECHNICAL CONSULTING CONSTITUTES AN INFRINGEMENT OF COPYRIGHT

TICAL CECTION	DATE: 15/01/2025
SICAL SECTION	SCALE: AS SHOWN @ A3
ENUE 'S NSW	DRAWING TITLE: SECTION
	AG 24574- S2



Appendix B

Site photos





Photo 1: Site frontage, looking north.



Photo 2: Western boundary of site, showing front yard conditions, looking south-east.



Photo 3: Northern boundary of site, looking south.



Photo 4: Subsurface soil profile of BH01.



Appendix C

Bore Logs | DCP Test Results

ASCENT**GEO**®

Ascent Geo

1457 Pittwater Road, North Narrabeen 2101

Phone: (02) 9913 3179

Geotechnical Log - Borehole

BH1

Easting Location : 106 Rose Avenue Wheeler Heights Job Number : AG 24574 : 0.00 Northing : 0.00 Logged By : RT Client : Phoebe Buchanan : 14/01/2025 Total Depth : 1.1 m Date Project : Alterations and Additions Material Description Classification Code **Drilling Method** Ξ Soil Origin Moisture Depth (FILL TOPSOIL: Gravelly SAND SW: poorly compacted, dark brown, fine to coarse grained, fine to coarse sized gravel, Ē sw РС М - 0.25 Natural Sandy CLAY CL: soft to firm, low plasticity, light brown mottled grey, fine to coarse grained sand, trace fine sized gravel, inorganic, moist. - 0.50 CL S-F Natural Sandy CLAY CL: stiff to very stiff, low plasticity, grey mottled light brown, fine to coarse grained sand, trace fine - 0.75 St-VSt CL BH1 refusal at 1.1m (Auger unable to penetrate through hard sandy CLAY) SOIL CONSISTENCY METHOD PENETRATION FIELD TESTS SAMPLES EX Excavator bucket VE Very Easy(No Resistance) SPT - Standard Penetration Test - Bulk disturbed sample vs - Very soft Ripper - Soft - Disturbed sample Е Easy - Hand/Pocket Penetrometer HA Hand auger - Firm Firm ES - Environmental sample DCP - Dynamic Cone Penetrometer Push tube - Stiff U - Thin wall tube "undisturbed" н Hard SON Sonic drilling PSP - Perth Sand Penetrometer VSt - Very stiff VH Very Hard(Refusal) AH Air hammer MOISTURE - Hard MC - Moisture Content PS Percussion sampler ${\bf D}$ - Dry PBT - Plate Bearing Test RELATIVE DENSITY AS Short spiral auger М - Moist Solid flight auger:V-Bit IMP - Borehole Impression Test AD/V VL - Very loose - Wet Solid flight auger:TC-Bit AD/T - Loose - Photo Ionisation Detector __ Water inflow PL - plastic limit Hollow flight auger MD - Medium dense Water outflow - Vane Shear; P=Peak, R=residual LL - liquid limit WB Washbore drilling - Dense (unconnected kPa) W - Moisture content Rock roller VD - Very dense Refer to explanatory notes for details of abbreviations and basis of descriptions Ascent Geo



Ascent Geo

1457 Pittwater Road, North Narrabeen 2101

Phone: (02) 9913 3179

Geotechnical Log - Borehole

BH2

Easting : 106 Rose Avenue Wheeler Heights Job Number : AG 24574 : 0.00 Location Northing : 0.00 Logged By : RT Client : Phoebe Buchanan Total Depth : 0.6 m Date : 16/01/2025 Project : Alterations and Additions Material Description Classification Code **Drilling Method** Œ Soil Origin Moisture Water Depth (FILL TOPSOIL: Gravelly SAND SW: poorly compacted, dark brown, fine to coarse grained, fine to coarse sized gravel, Ē SW PC M FILL: Gravelly to silty SAND SM: poorly compacted, dark brown, fine to coarse grained, fine to coarse sized gravel, - 0.25 trace low plasticity clay, moist. SM - 0.50 BH2 refusal at 0.6m (Auger teeth grinding on possible buried surface in fill material, dull thud.) SOIL CONSISTENCY METHOD PENETRATION FIELD TESTS SAMPLES EX VE Very Easy(No Resistance) SPT - Standard Penetration Test - Bulk disturbed sample vs - Very soft Excavator bucket Ripper - Soft - Disturbed sample E Easy - Hand/Pocket Penetrometer Hand auger - Firm Firm ES - Environmental sample DCP - Dynamic Cone Penetrometer Push tube - Stiff н Hard U - Thin wall tube "undisturbed" SON Sonic drilling PSP - Perth Sand Penetrometer VSt - Very stiff VH Very Hard(Refusal) ΑH Air hammer MOISTURE - Hard MC - Moisture Content PS Percussion sampler ${\bf D}$ - Dry PBT - Plate Bearing Test RELATIVE DENSITY AS Short spiral auger M - Moist Solid flight auger:V-Bit IMP AD/V Water Level on Date - Borehole Impression Test VL - Very loose Solid flight auger:TC-Bit AD/T - Loose - Photo Ionisation Detector __ Water inflow PL - plastic limit Hollow flight auger → Water outflow MD - Medium dense - Vane Shear; P=Peak, R=residual LL - liquid limit WB Washbore drilling - Dense (unconnected kPa) W - Moisture content Rock roller VD - Very dense Refer to explanatory notes for details of abbreviations and basis of descriptions Ascent Geo

ASCENT**GEO**®

Ascent Geo

1457 Pittwater Road, North Narrabeen 2101

Phone: (02) 9913 3179

Geotechnical Log - Borehole

BH1

Easting Location : 106 Rose Avenue Wheeler Heights Job Number : AG 24574 : 0.00 Northing : 0.00 Logged By : RT Client : Phoebe Buchanan : 14/01/2025 Total Depth : 1.1 m Date Project : Alterations and Additions Material Description Classification Code **Drilling Method** Ξ Soil Origin Moisture Depth (FILL TOPSOIL: Gravelly SAND SW: poorly compacted, dark brown, fine to coarse grained, fine to coarse sized gravel, Ē sw PC М - 0.25 Natural Sandy CLAY CL: soft to firm, low plasticity, light brown mottled grey, fine to coarse grained sand, trace fine sized gravel, inorganic, moist. - 0.50 CL S-F Natural Sandy CLAY CL: stiff to very stiff, low plasticity, grey mottled light brown, fine to coarse grained sand, trace fine - 0.75 St-VSt CL BH1 refusal at 1.1m (Auger unable to penetrate through hard sandy CLAY) SOIL CONSISTENCY METHOD PENETRATION FIELD TESTS SAMPLES EX Excavator bucket VE Very Easy(No Resistance) SPT - Standard Penetration Test - Bulk disturbed sample vs - Very soft Ripper - Soft - Disturbed sample Е Easy - Hand/Pocket Penetrometer HA Hand auger - Firm Firm ES - Environmental sample DCP - Dynamic Cone Penetrometer Push tube - Stiff U - Thin wall tube "undisturbed" н Hard SON Sonic drilling PSP - Perth Sand Penetrometer VSt - Very stiff VH Very Hard(Refusal) AH Air hammer MOISTURE - Hard MC - Moisture Content PS Percussion sampler ${\bf D}$ - Dry PBT - Plate Bearing Test RELATIVE DENSITY AS Short spiral auger М - Moist Solid flight auger:V-Bit IMP - Borehole Impression Test AD/V VL - Very loose - Wet Solid flight auger:TC-Bit AD/T - Loose - Photo Ionisation Detector __ Water inflow PL - plastic limit Hollow flight auger MD - Medium dense Water outflow - Vane Shear; P=Peak, R=residual LL - liquid limit WB Washbore drilling - Dense (unconnected kPa) W - Moisture content Rock roller VD - Very dense Refer to explanatory notes for details of abbreviations and basis of descriptions Ascent Geo



Ascent Geo

1457 Pittwater Road, North Narrabeen 2101

Phone: (02) 9913 3179

Geotechnical Log - Borehole

BH2

Easting : 106 Rose Avenue Wheeler Heights Job Number : AG 24574 : 0.00 Location Northing : 0.00 Logged By : RT Client : Phoebe Buchanan Total Depth : 0.6 m Date : 16/01/2025 Project : Alterations and Additions Material Description Classification Code **Drilling Method** Œ Soil Origin Moisture Water Depth (FILL TOPSOIL: Gravelly SAND SW: poorly compacted, dark brown, fine to coarse grained, fine to coarse sized gravel, Ē SW PC M FILL: Gravelly to silty SAND SM: poorly compacted, dark brown, fine to coarse grained, fine to coarse sized gravel, - 0.25 trace low plasticity clay, moist. SM - 0.50 BH2 refusal at 0.6m (Auger teeth grinding on possible buried surface in fill material, dull thud.) SOIL CONSISTENCY METHOD PENETRATION FIELD TESTS SAMPLES EX VE Very Easy(No Resistance) SPT - Standard Penetration Test - Bulk disturbed sample vs - Very soft Excavator bucket Ripper - Soft - Disturbed sample E Easy - Hand/Pocket Penetrometer Hand auger - Firm Firm ES - Environmental sample DCP - Dynamic Cone Penetrometer Push tube - Stiff н Hard U - Thin wall tube "undisturbed" SON Sonic drilling PSP - Perth Sand Penetrometer VSt - Very stiff VH Very Hard(Refusal) ΑH Air hammer MOISTURE - Hard MC - Moisture Content PS Percussion sampler ${\bf D}$ - Dry PBT - Plate Bearing Test RELATIVE DENSITY AS Short spiral auger M - Moist Solid flight auger:V-Bit IMP AD/V Water Level on Date - Borehole Impression Test VL - Very loose Solid flight auger:TC-Bit AD/T - Loose - Photo Ionisation Detector __ Water inflow PL - plastic limit Hollow flight auger → Water outflow MD - Medium dense - Vane Shear; P=Peak, R=residual LL - liquid limit WB Washbore drilling - Dense (unconnected kPa) W - Moisture content Rock roller VD - Very dense Refer to explanatory notes for details of abbreviations and basis of descriptions Ascent Geo



Appendix D

Information Sheets

General Notes About This Report



INTRODUCTION

These notes have been prepared by Ascent Geotechnical Consulting Pty Ltd (Ascent) to help our Clients interpret and understand the limitations of this report. Not all sections below are necessarily relevant to all reports.

SCOPE OF SERVICES

This report has been prepared in accordance with the scope of services set out in Ascent's proposal under Ascent's Terms and Conditions, or as otherwise agreed with the Client. The scope of work may have been limited by a range of factors including time, budget, access and/or site constraints.

RELIANCE ON INFORMATION PROVIDED

In preparing the report, Ascent has necessarily relied upon information provided by the Client and/or their Agents. Such data may include surveys, analyses, designs, maps and design plans. Ascent has not verified the accuracy or completeness of the data except as stated in this report.

GEOTECHNICAL AND ENVIRONMENTAL REPORTING

Geotechnical and environmental reporting relies on the interpretation of factual information, based on judgment and opinion, and is far less exact than other engineering or design disciplines.

Geotechnical and environmental reports are prepared for a specific purpose, development, and site, as described in the report, and may not contain sufficient information for other purposes, developments, or sites (including adjacent sites), other than that described in the report.

SUBSURFACE CONDITIONS

Subsurface conditions can change with time and can vary between test locations. For example, the actual interface between the materials may be far more gradual or abrupt than indicated.

Therefore, actual conditions in areas not sampled may differ from those predicted, since no subsurface investigation, no matter how comprehensive, can reveal all subsurface details and anomalies.

Construction operations at or adjacent to the site and natural events such as floods, earthquakes or groundwater fluctuations can also affect subsurface conditions, and thus the continuing adequacy of a geotechnical report. Ascent should be kept informed of any such events, and should be retained to identify variances, conduct additional tests if required, and recommend solutions to problems encountered on site.

GROUNDWATER

Groundwater levels indicated on borehole and test pit logs are recorded at specific times. Depending on ground permeability, measured levels may or may not reflect actual levels if measured over a longer time period. Also, groundwater levels and seepage inflows may fluctuate with seasonal and environmental variations and construction activities.

INTERPRETATION OF DATA

Data obtained from nominated discrete locations, subsequent laboratory testing and empirical or external sources are interpreted by trained professionals in order to provide an opinion about overall site conditions, their likely impact with respect to the report purpose and recommended actions in accordance with any relevant industry standards, guidelines or procedures.

SOIL AND ROCK DESCRIPTIONS

Soil and rock descriptions are based on AS 1726 – 1993, using visual and tactile assessment, except at discrete locations where field and / or laboratory tests have been carried out. Refer to the accompanying soil and rock terms sheet for further information.

COPYRIGHT AND REPRODUCTION

The contents of this document are and remain the intellectual property of Ascent. This document should only be used for the purpose for which it was commissioned and should not be used for other projects, or by a third party without written permission from Ascent

This report shall not be reproduced either totally or in part without the permission of Ascent. Where information from this report is to be included in contract documents or engineering specification for the project, the entire report should be included in order to minimise the likelihood of misinterpretation.

FURTHER ADVICE

Ascent would be pleased to further discuss how any of the above issues could affect a specific project. We would also be pleased to provide further advice or assistance including:

Assessment of suitability of designs and construction techniques;

Contract documentation and specification; Construction advice (foundation assessments, excavation support).

Abbreviations, Notes & Symbols

SUBSURFACE INVESTIGATION

ΙE		

	WILLINGS			
Borehole Logs		Excavation Logs		
	AS#	Auger screwing (#-bit)	ВН	Backhoe/excavator bucket
	AD#	Auger drilling (#-bit)	NE	Natural exposure
	В	Blank bit	HE	Hand excavation
	V	V-bit	Χ	Existing excavation
	T	TC-bit		
	HA	Hand auger	Cored Borehole Logs	
	R	Roller/tricone	NMLC	NMLC core drilling
	W	Washbore	NQ/HQ	Wireline core drilling
	AH	Air hammer		
	AT	Air track		
	LB	Light bore push tube		
	MC	Macro core push tube		
	DT	Dual core push tube		

SUPPORT

Borehole Logs		Excavation Logs	
С	Casing	S	Shoring
M	Mud	В	Benched

SAMPLING

U#

•	
В	Bulk sample
D	Disturbed sample

Thin-walled tube sample (#mmdiameter)

ES

sample

EW Environmental water sample

FIELD TESTING

PP	Pocket penetrometer (kPa)
DCP	Dynamic cone penetrometer
PSP	Perth sand penetrometer
SPT	Standard penetration test
PBT	Plate bearing test

Vane shear strength peak/residual (kPa) and vane size (mm)

N* SPT (blows per 300mm) SPT with solid cone Refusal

*denotes sample taken

BOUNDARIES

 Known
 Probable
 Possible

SOIL

MOISTURE CONDITION

D	Dry
M	Moist
W	Wet
Wp	Plastic Limit
WI	Liquid Limit
MC	Moisture Content

CONSISTENCY **DENSITY INDEX** VL Very Loose Very Soft S Soft Loose F Firm MD Medium Dense St Stiff D Dense

VSt Very Stiff Hard Friable

USCS SYMBOLS

GW	Well graded gravels and gravel-sand mixtures, little or no fines
GP	Poorly graded gravels and gravel-sand mixtures, little or no

VD

Very Dense

GM Silty gravels, gravel-sand-silt mixtures GC Clayey gravels, gravel-sand-clay mixtures

SW	Well graded sands and gravelly sands, little orno fines
SP	Poorly graded sands and gravelly sands, little or no fines

SM Silty sand, sand-silt mixtures SC Clayey sand, sand-clay mixtures

ML Inorganic silts of low plasticity, very fine sands, rock flour, silty

or clayey fine sands

CL Inorganic clays of low to medium plasticity, gravelly clays,

OL

organic clays of low of mediam plasticity, gravely sandy clays, silty clays
Organic silts and organic silty clays of low plasticity
Inorganic clays of high plasticity
Organic clays of medium to high plasticity
Dest muck and other highly organics pile МН CH

ОН

Peat muck and other highly organicsoils

ROCK

WEATHERING		STRENGTH	
RS	Residual Soil	EL	Extremely Low
XW	Extremely Weathered	VL	Very Low
HW	Highly Weathered	L	Low
MW	Moderately Weathered	M	Medium
DW*	Distinctly Weathered	Н	High
SW	Slightly Weathered	VH	Very High
FR	Fresh	EH	Extremely High

*covers both HW & MW

ROCK QUALITY DESIGNATION (%)

= <u>sum of intact core pieces > 100mm</u> x 100 total length of section being evaluated

CORE RECOVERY (%)

= core recovered x 100

core IIft

NATURAL FRACTURES

Type

JT Joint

BP Bedding plane SM Seam FΖ Fractured zone S7 Shear zone

Infill or Coating

Cn	Clean
St	Stained
Vn	Veneer
Co	Coating
CI	Clay
Ca	Calcite
Fe	Iron oxide
Mi	Micaceous
Qz	Quartz

Shape

pl	Planar
cu	Curved
un	Undulose
st	Stepped
ir	Irregular

Roughness

pol	Polished
slk	Slickensided
smo	Smooth
rou	Rough


Soil & Rock Terms

SOIL				STRENGTH			
MOISTURE CON				Term	Is50 (MPa)	Term	Is50 (MPa)
Term	Description			Extremely Low	< 0.03	High	1 – 3
Dry			emented soils are ed granular soils run	Very Low Low Medium	0.03 - 0.1 0.1 - 0.3 0.3 - 1	Very High Extremely High	3 – 10 > 10
Moist		arkened in colour. On the colour of the colo		WEATHERING			
Wet			ning on hands when	Term Residual Soil	Description Soil developed	on extremely weathe	red rock: the mass
	s, moisture content		ped in relation to an, > greater than, <			ubstance fabric are n	
less than, << muc	ch less than].			Extremely Weathered		red to such an extent t either disintegrates	
CONSISTENCY Term	c (kPa)	Term	c (kPa)		remoulded, in w visible	ater. Fabric of origin	al rock is still
Very Soft Soft	u < 12 12 - 25	Very Stiff Hard	u 100 200 > 200	Highly Weathered	Rock strength u	sually highly change	d by weathering;
Firm	25 - 50	Friable	-	Moderately	Rock strength i	isually moderately ch	anged by
Stiff	50 - 100			Weathered	weathering; roc	k may be moderately	discoloured
DENSITY INDEX Term	I _D (%)	Term	I _D (%)	Distinctly Weathered	See 'Highly We	athered' or 'Moderate	ely Weathered'
Very Loose Loose	< 15 15 – 35	Dense Very Dense	65 – 8 > 85	Slightly Weathered		discoloured but show gth from fresh rock	s little or no
Medium Dense	35 – 65			Fresh	Rock shows no	signs of decompositi	on or staining
PARTICLE SIZE	Cultulistics	Sine (mam)		NATURAL FRAC	TURES		
Name Boulders	Subdivision	Size (mm) > 200		Туре	Description		
Cobbles		63 - 200		Joint		or crack across which	
Gravel	coarse medium	20 - 63 6 - 20		Bedding plane		ength. May be open layers of mineral gra	
	fine	2.36 - 6		0	or composition	itdil (i-fill)t-	
Sand	coarse medium	0.6 -2.36 0.2 - 06		Seam	insitu rock (XW	osited soil (infill), extro), or disoriented usua o bost rock (crushed)	lly angular
Cilt 9 Olev	fine	0.075 0.2		Choor zono	_	e host rock (crushed)	
Silt & Clay MINOR COMPO	NENTS	< 0.075		Shear zone	material interse	nly parallel planar bou cted by closely space nd /or microscopic fra	ed (generally <
Term	Proportion by	fine grained			planes		
rem	Mass coarse grained	ille grained		Vein	Intrusion of any mass. Usually i	shape dissimilar to t gneous	he adjoining rock
Trace	≤ 5%	≤ 15%					
Some	5 - 2%	15 - 30%		Shape	Description		
SOIL ZONING				Planar	Consistent orier		
Layers	Continuous expos	sures		Curved	Gradual change	e in orientation	
Lenses	·	yers of lenticular sh	аре	Undulose Stepped	Wavy surface	ell defined steps	
Pockets	Irregular inclusion	ns of different mater	rial	Irregular		anges in orientation	
SOIL CEMENTIN Weakly	G Easily broken up	by hand		Infill or Coating	Description		
Moderately	Effort is required	to break up the soil	by hand	Clean	No visible coati	ng or discolouring	
SOIL STRUCTUR	DE			Stained		ng but surfaces are d	iscoloured
Massive	Coherent, with ar	ny partings both ver ed at greater than 1		Veneer	A visible coating may be patchy	g of soil or mineral, to	o thin to measure;
Weak	Peds indistinct ar	nd barely observable . 30% consist of per	e on pit face. When	Coating	described as se	≤ 1mm thick. Ticker s eam	oil material
Strong		stinct in undisturbe	d soil. When	Roughness	Description		
J		consists of peds sm		Polished Slickensided	Shiny smooth s Grooved or strice	urface ated surface, usually	polished
ROCK				Smooth		h. Few or no surface	•
<u> </u>	ROCK TYPE DEFIN	JITIONS		Rough		ace irregularities (ame fine to coarse sand	
Rock Type		than 50% of rock c	onsists of)		,		•
Conglomerate	gravel sized (>	> 2mm) fragments	•			generally in accorda	nce with AS1726-
Sandstone Siltstone		06 to 2mm) grains 06mm) particles, roo	ck is not laminated	1993 Geotechnic	al Site Investigatio	ns	

Definition (more than 50% of rock consists of....)
... gravel sized (> 2mm) fragments
... sand sized (0.06 to 2mm) grains
... silt sized (<0.06mm) particles, rock is not laminated
... clay, rock is not laminated
... silt or clay sized particles, rock is laminated

Siltstone Claystone Shale

Graphic Symbols Index



Foundation Maintenance and Footing Performance: A Homeowner's Guide



BTF 18 replaces Information Sheet 10/91

Buildings can and often do move. This movement can be up, down, lateral or rotational. The fundamental cause of movement in buildings can usually be related to one or more problems in the foundation soil. It is important for the homeowner to identify the soil type in order to ascertain the measures that should be put in place in order to ensure that problems in the foundation soil can be prevented, thus protecting against building movement.

This Building Technology File is designed to identify causes of soil-related building movement, and to suggest methods of prevention of resultant cracking in buildings.

Soil Types

The types of soils usually present under the topsoil in land zoned for residential buildings can be split into two approximate groups — granular and clay. Quite often, foundation soil is a mixture of both types. The general problems associated with soils having granular content are usually caused by erosion. Clay soils are subject to saturation and swell/shrink problems.

Classifications for a given area can generally be obtained by application to the local authority, but these are sometimes unreliable and if there is doubt, a geotechnical report should be commissioned. As most buildings suffering movement problems are founded on clay soils, there is an emphasis on classification of soils according to the amount of swell and shrinkage they experience with variations of water content. The table below is Table 2.1 from AS 2870, the Residential Slab and Footing Code.

Causes of Movement

Settlement due to construction

There are two types of settlement that occur as a result of construction:

- Immediate settlement occurs when a building is first placed on its foundation soil, as a result of compaction of the soil under the weight of the structure. The cohesive quality of clay soil mitigates against this, but granular (particularly sandy) soil is susceptible.
- Consolidation settlement is a feature of clay soil and may take
 place because of the expulsion of moisture from the soil or because
 of the soil's lack of resistance to local compressive or shear stresses.
 This will usually take place during the first few months after
 construction, but has been known to take many years in
 exceptional cases.

These problems are the province of the builder and should be taken into consideration as part of the preparation of the site for construction. Building Technology File 19 (BTF 19) deals with these problems.

Erosion

All soils are prone to erosion, but sandy soil is particularly susceptible to being washed away. Even clay with a sand component of say 10% or more can suffer from erosion.

Saturation

This is particularly a problem in day soils. Saturation creates a boglike suspension of the soil that causes it to lose virtually all of its bearing capacity. To a lesser degree, sand is affected by saturation because saturated sand may undergo a reduction in volume particularly imported sand fill for bedding and blinding layers. However, this usually occurs as immediate settlement and should normally be the province of the builder.

Seasonal swelling and shrinkage of soil

All clays react to the presence of water by slowly absorbing it, making the soil increase in volume (see table below). The degree of increase varies considerably between different clays, as does the degree of decrease during the subsequent drying out caused by fair weather periods. Because of the low absorption and expulsion rate, this phenomenon will not usually be noticeable unless there are prolonged rainy or dry periods, usually of weeks or months, depending on the land and soil characteristics.

The swelling of soil creates an upward force on the footings of the building, and shrinkage creates subsidence that takes away the support needed by the footing to retain equilibrium.

Shear failure

This phenomenon occurs when the foundation soil does not have sufficient strength to support the weight of the footing. There are two major post-construction causes:

- Significant load increase.
- Reduction of lateral support of the soil under the footing due to erosion or excavation.
- In day soil, shear failure can be caused by saturation of the soil adjacent to or under the footing.

	GENERAL DEFINITIONS OF SITE CLASSES
Class	Foundation
A	Most sand and rock sites with little or no ground movement from moisture changes
S	Slightly reactive clay sites with only slight ground movement from moisture changes
М	Moderately reactive clay or silt sites, which can experience moderate ground movement from moisture changes
Н	Highly reactive day sites, which can experience high ground movement from moisture changes
E	Extremely reactive sites, which can experience extreme ground movement from moisture changes
A to P	Filled sites
P	Sites which include soft soils, such as soft clay or silt or loose sands; landslip; mine subsidence; collapsing soils; soils subject to crosion; reactive sites subject to abnormal moisture conditions or sites which cannot be classified otherwise

Tree root growth

Trees and shrubs that are allowed to grow in the vicinity of footings can cause foundation soil movement in two ways

- Roots that grow under footings may increase in cross-sectional size, exerting upward pressure on footings.
- Roots in the vicinity of footings will absorb much of the moisture in the foundation soil, causing shrinkage or subsidence.

Unevenness of Movement

The types of ground movement described above usually occur unevenly throughout the building's foundation soil. Settlement due to construction tends to be uneven because of:

- · Differing compaction of foundation soil prior to construction.
- · Differing moisture content of foundation soil prior to construction.

Movement due to non-construction causes is usually more uneven still. Erosion can undermine a footing that traverses the flow or can create the conditions for shear failure by eroding soil adjacent to a footing that runs in the same direction as the flow.

Saturation of clay foundation soil may occur where subfloor walls create a dam that makes water pond. It can also occur wherever there is a source of water near footings in clay soil. This leads to a severe reduction in the strength of the soil which may create local shear

Seasonal swelling and shrinkage of clay soil affects the perimeter of the building first, then gradually spreads to the interior. The swelling process will usually begin at the uphill extreme of the building, or on the weather side where the land is flat. Swelling gradually reaches the interior soil as absorption continues. Shrinkage usually begins where the sunk heat is greatest.

Effects of Uneven Soil Movement on Structures

Erosion and saturation

Erosion removes the support from under footings, tending to create subsidence of the part of the structure under which it occurs. Brickwork walls will resist the stress created by this removal of support by bridging the gap or cantilevering until the bricks or the mortar bedding fail. Older masonry has little resistance. Evidence of failure varies according to circumstances and symptoms may include:

- Step cracking in the mortar beds in the body of the wall or above/below openings such as doors or windows.
- Vertical cracking in the bricks (usually but not necessarily in line with the vertical beds or perpends).

Isolated piers affected by erosion or saturation of foundations will eventually lose contact with the bearers they support and may tilt or fall over. The floors that have lost this support will become bouncy, sometimes rattling ornaments etc.

Seasonal swelling/shrinkage in clay

Swelling foundation soil due to rainy periods first lifts the most exposed extremities of the footing system, then the remainder of the perimeter footings while gradually permeating inside the building footprint to lift internal footings. This swelling first tends to create a dish effect, because the external footings are pushed higher than the internal ones.

The first noticeable symptom may be that the floor appears slightly dished. This is often accompanied by some doors binding on the floor or the door head, together with some cracking of comice mitres. In buildings with timber flooring supported by bearers and joists, the floor can be bouncy. Externally there may be visible dishing of the hip or ridge lines.

As the moisture absorption process completes its journey to the innermost areas of the building, the internal footings will rise. If the spread of moisture is roughly even, it may be that the symptoms will temporarily disappear, but it is more likely that swelling will be uneven, creating a difference rather than a disappearance in symptoms. In buildings with timber flooring supported by bearers and joists, the isolated piers will rise more easily than the strip footings or piers under walls, creating noticeable doming of flooring.



As the weather pattern changes and the soil begins to dry out, the external footings will be first affected, beginning with the locations where the sun's effect is strongest. This has the effect of lowering the external footings. The doming is accentuated and cracking reduces or disappears where it occurred because of dishing, but other cracks open up. The roof lines may become convex.

Doming and dishing are also affected by weather in other ways. In areas where warm, wet summers and cooler dry winters prevail, water migration tends to be toward the interior and doming will be accentuated, whereas where summers are dry and winters are cold and wet, migration tends to be toward the exterior and the underlying propensity is toward dishing.

Movement caused by tree roots

In general, growing roots will exert an upward pressure on footings, whereas soil subject to drying because of tree or shrub roots will tend to remove support from under footings by inducing shrinkage.

Complications caused by the structure itself
Most forces that the soil causes to be exerted on structures are
vertical — i.e. either up or down. However, because these forces are
seldom spread evenly around the footings, and because the building
resists uneven movement because of its rigidity, forces are exerted
from one part of the building to another. The net result of all these
forces is usually rotational. This resultant force often complicates the
diagnosis because the visible symptoms do not simply reflect the
original cause. A common symptom is binding of doors on the

Effects on full masonry structures

vertical member of the frame

Brickwork will resist cracking where it can. It will attempt to span areas that lose support because of subsided foundations or raised points. It is therefore usual to see cracking at weak points, such as openings for windows or doors.

In the event of construction settlement, cracking will usually remain unchanged after the process of settlement has ceased.

With local shear or erosion, cracking will usually continue to develop until the original cause has been remedied, or until the subsidence has completely neutralised the affected portion of footing and the structure has stabilised on other footings that remain effective.

In the case of swell/shrink effects, the brickwork will in some cases return to its original position after completion of a cycle, however it is more likely that the rotational effect will not be exactly reversed, and it is also usual that brickwork will settle in its new position and will resist the forces trying to return it to its original position. This means that in a case where swelling takes place after construction and cracking occurs, the cracking is likely to at least partly remain after the shrink segment of the cycle is complete. Thus, each time the cycle is repeated, the likelihood is that the cracking will become wider until the sections of brickwork become virtually independent.

With repeated cycles, once the cracking is established, if there is no other complication, it is normal for the incidence of cracking to stabilise, as the building has the articulation it needs to cope with the problem. This is by no means always the case, however, and monitoring of cracks in walls and floors should always be treated exclusive.

Upheaval caused by growth of tree roots under footings is not a simple vertical shear stress. There is a tendency for the root to also exert lateral forces that attempt to separate sections of brickwork after initial cracking has occurred. The normal structural arrangement is that the inner leaf of brickwork in the external walls and at least some of the internal walls (depending on the roof type) comprise the load-bearing structure on which any upper floors, ceilings and the roof are supported. In these cases, it is internally visible cracking that should be the main focus of attention, however there are a few examples of dwellings whose external leaf of masonry plays some supporting role, so this should be checked if there is any doubt. In any case, externally visible cracking is important as a guide to stresses on the structure generally, and it should also be remembered that the external walls must be capable of supporting themselves.

Effects on framed structures

Timber or steel framed buildings are less likely to exhibit cracking due to swell/shrink than masonry buildings because of their flexibility. Also, the doming/dishing effects tend to be lower because of the lighter weight of walls. The main risks to framed buildings are encountered because of the isolated pier footings used under walls. Where erosion or saturation cause a footing to fall away, this can double the span which a wall must bridge. This additional stress can create cracking in wall linings, particularly where there is a weak point in the structure caused by a door or window opening. It is, however, unlikely that framed structures will be so stressed as to suffer serious damage without first exhibiting some or all of the above symptoms for a considerable period. The same warning period should apply in the case of upheaval. It should be noted, however, that where framed buildings are supported by strip footings there is only one leaf of brickwork and therefore the externally visible walls are the supporting structure for the building. In this case, the subfloor masonry walls can be expected to behave as full brickwork walls.

Effects on brick veneer structures

Because the load-bearing structure of a brick veneer building is the frame that makes up the interior leaf of the external walls plus perhaps the internal walls, depending on the type of roof, the building can be expected to behave as a framed structure, except that the external masonry will behave in a similar way to the external leaf of a full masonry structure.

Water Service and Drainage

Where a water service pipe, a sewer or stormwater drainage pipe is in the vicinity of a building, a water leak can cause erosion, swelling or saturation of susceptible soil. Even a minuscule leak can be enough to saturate a clay foundation. A leaking tap near a building can have the same effect. In addition, trenches containing pipes can become watercourses even though backfilled, particularly where broken nubble is used as fill. Water that runs along these trenches can be responsible for scrious crosion, interstrata scepage into subfloor areas and saturation.

Pipe leakage and trench water flows also encourage tree and shrub roots to the source of water, complicating and exacerbating the problem.

Poor roof plumbing can result in large volumes of rainwater being concentrated in a small area of soil:

 Incorrect falls in roof guttering may result in overflows, as may gutters blocked with leaves etc.

- · Corroded guttering or downpipes can spill water to ground.
- Downpipes not positively connected to a proper stormwater collection system will direct a concentration of water to soil that is directly adjacent to footings, sometimes causing large-scale problems such as erosion, saturation and migration of water under the building.

Seriousness of Cracking

In general, most cracking found in masonry walls is a cosmetic nuisance only and can be kept in repair or even ignored. The table below is a reproduction of Table C1 of AS 2870.

AS 2870 also publishes figures relating to cracking in concrete floors, however because wall cracking will usually reach the critical point significantly earlier than cracking in slabs, this table is not reproduced here.

Prevention/Cure

Plumbing

Where building movement is caused by water service, roof plumbing, sewer or stormwater failure, the remedy is to repair the problem. It is prudent, however, to consider also rerouting pipes away from the building where possible, and relocating taps to positions where any leakage will not direct water to the building vicinity. Even where gully traps are present, there is sometimes sufficient spill to create erosion or saturation, particularly in modern installations using smaller diameter PVC fixtures. Indeed, some gully traps are not situated directly under the taps that are installed to charge them, with the result that water from the tap may enter the backfilled trench that houses the sewer piping. If the trench has been poorly backfilled, the water will either pond or flow along the bottom of the trench. As these trenches usually run alongside the footings and can be at a similar depth, it is not hard to see how any water that is thus directed into a trench can easily affect the foundation's ability to support footings or even gain entry to the subfloor area.

Ground drainage

In all soils there is the capacity for water to travel on the surface and below it. Surface water flows can be established by inspection during and after heavy or prolonged rain. If necessary, a grated drain system connected to the stormwater collection system is usually an easy solution.


It is, however, sometimes necessary when attempting to prevent water migration that testing be carried out to establish watertable height and subsoil water flows. This subject is referred to in BTF 19 and may properly be regarded as an area for an expert consultant.

Protection of the building perimeter

It is essential to remember that the soil that affects footings extends well beyond the actual building line. Watering of garden plants, shrubs and trees causes some of the most senious water problems.

For this reason, particularly where problems exist or are likely to occur, it is recommended that an apron of paving be installed around as much of the building perimeter as necessary. This paving

Description of typical damage and required repair	Approximate crack width limit (see Note 3)	Damage
Hairline cracks	<0.1 mm	0
Fine cracks which do not need repair	<1 mm	1
Cracks noticeable but easily filled. Doors and windows stick slightly	⊲ mm	2
Cracks can be repaired and possibly a small amount of wall will need to be replaced. Doors and windows stick. Service pipes can fracture. Weathertightness often impaired	5-15 mm (or a number of cracks 3 mm or more in one group)	3
Extensive repair work involving breaking-out and replacing sections of walls, especially over doors and windows. Window and door frames distort. Walls lean or bulge noticeably, some loss of bearing in beams. Service pipes disrupted	15-25 mm but also depend on number of cracks	4



should extend outwards a minimum of 900 mm (more in highly reactive soil) and should have a minimum fall away from the building of 1:60. The finished paving should be no less than 100 mm below brick vent bases.

It is prudent to relocate drainage pipes away from this paving, if possible, to avoid complications from future leakage. If this is not practical, earthenware pipes should be replaced by PVC and backfilling should be of the same soil type as the surrounding soil and compacted to the same density.

Except in areas where freezing of water is an issue, it is wise to remove taps in the building area and relocate them well away from the building – preferably not uphill from it (see BTF 19).

It may be desirable to install a grated drain at the outside edge of the paving on the uphill side of the building. If subsoil drainage is needed this can be installed under the surface drain.

Condensation

In buildings with a subfloor void such as where bearers and joists support flooring, insufficient wentilation creates ideal conditions for condensation, particularly where there is little clearance between the floor and the ground. Condensation adds to the moisture already present in the subfloor and significantly slows the process of drying out. Installation of an adequate subfloor ventilation system, either natural or mechanical, is desirable.

Warning: Although this Building Technology File deals with cracking in buildings, it should be said that subfloor moisture can result in the development of other problems, notably:

- Water that is transmitted into masonry, metal or timber building elements causes damage and/or decay to those elements.
- High subfloor humidity and moisture content create an ideal environment for various pests, including termites and spiders.
- Where high moisture levels are transmitted to the flooring and walls, an increase in the dust mite count can ensue within the living areas. Dust mites, as well as dampness in general, can be a health hazard to inhabitants, particularly those who are abnormally susceptible to respiratory ailments.

The garden

The ideal vegetation layout is to have lawn or plants that require only light watering immediately adjacent to the drainage or paving edge, then more demanding plants, shrubs and trees spread out in that order.

Overwatering due to misuse of automatic watering systems is a common cause of saturation and water migration under footings. If it is necessary to use these systems, it is important to remove garden beds to a completely safe distance from buildings.

Existing trees

Where a tree is causing a problem of soil drying or there is the existence or threat of upheaval of footings, if the offending roots are subsidiary and their removal will not significantly damage the tree, they should be severed and a concrete or metal barrier placed vertically in the soil to prevent future root growth in the direction of the building. If it is not possible to remove the relevant roots without damage to the tree, an application to remove the tree should be made to the local authority. A prudent plan is to transplant likely offenders before they become a problem.

Information on trees, plants and shrubs State departments overseeing agriculture or

State departments overseeing agriculture can give information regarding root patterns, volume of water needed and safe distance from buildings of most species. Botanic gardens are also sources of information. For information on plant roots and drains, see Building Technology File 17.

Excavation

Excavation around footings must be properly engineered. Soil supporting footings can only be safely excavated at an angle that allows the soil under the footing to remain stable. This angle is called the angle of repose (or friction) and varies significantly between soil types and conditions. Removal of soil within the angle of repose will cause subsidence.

Remediation

Where erosion has occurred that has washed away soil adjacent to footings, soil of the same classification should be introduced and compacted to the same density. Where footings have been undermined, augmentation or other specialist work may be required. Remediation of footings and foundations is generally the realm of a specialist consultant.

Where isolated footings rise and fall because of swell/shrink effect, the homeowner may be tempted to alleviate floor bounce by filling the gap that has appeared between the bearer and the pier with blocking. The danger here is that when the next swell segment of the cycle occurs, the extra blocking will push the floor up into an accentuated dome and may also cause local shear failure in the soil. If it is necessary to use blocking, it should be by a pair of fine wedges and monitoring should be carried out fortnightly.

This BTF was prepared by John Lewer FAIB, MIAMA, Partner, Construction Diagnosis.

The information in this and other issues in the series was derived from various sources and was believed to be correct when published.

The information is advisory. It is provided in good faith and not claimed to be an exhaustive treatment of the relevant subject.

Further professional advice needs to be obtained before taking any action based on the information provided.


Distributed by

CSIRO PUBLISHING PO Box 1139, Collingwood 3066, Australia


Freecall 1800 645 051 Tel (03) 9662 7666 Fax (03) 9662 7555 www.publish.csiro.au Email: publishing.seles@csiro.au

© CSIRO 2003. Unauthorised copying of this Building Technology file is prohibited

EXAMPLES OF GOOD HILLSIDE PRACTICE



EXAMPLES OF POOR HILLSIDE PRACTICE



PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007 APPENDIX C: LANDSLIDE RISK ASSESSMENT

QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY

QUALITATIVE MEASURES OF LIKELIHOOD

pproximate At	Approximate Annual Probability	Implied Indicative Landslide	ve Landslide			
Indicative Value	Notional Boundary	Recurrence Interval	Interval	Description	Descriptor	Level
10.1	5×10-2	10 years		The event is expected to occur over the design life.	ALMOST CERTAIN	Y
10-2	OA10	100 years	20 years	The event will probably occur under adverse conditions over the design life.	LIKELY	В
10-3	0X10	1000 years	2000 years	The event could occur under adverse conditions over the design life.	POSSIBLE	C
10-4	5x10"	10,000 years	20 000 transc	The event might occur under very adverse circumstances over the design life.	UNLIKELY	D
10.5	5x10°	100,000 years	co,ooo years	The event is conceivable but only under exceptional circumstances over the design life.	RARE	E
10-6	OTYC	1,000,000 years	200,000 years	The event is inconceivable or fanciful over the design life.	BARELY CREDIBLE	H

The table should be used from left to right; use Approximate Annual Probability or Description to assign Descriptor, not vice versa. \equiv Note:

QUALITATIVE MEASURES OF CONSEQUENCES TO PROPERTY

Approximate	Approximate Cost of Damage		-	
Indicative Value	Notional Boundary	Description	Descriptor	Level
200%	7000	Structure(s) completely destroyed and/or large scale damage requiring major engineering works for stabilisation. Could cause at least one adjacent property major consequence damage.	CATASTROPHIC	-
%09	2007	Extensive damage to most of structure, and/or extending beyond site boundaries requiring significant stabilisation works. Could cause at least one adjacent property medium consequence damage.	MAJOR	2
20%	40%	Moderate damage to some of structure, and/or significant part of site requiring large stabilisation works. Could cause at least one adjacent property minor consequence damage.	MEDIUM	3
5%	10%	Limited damage to part of structure, and/or part of site requiring some reinstatement stabilisation works.	MINOR	4
0.5%		Little damage. (Note for high probability event (Almost Certain), this category may be subdivided at a notional boundary of 0.1%. See Risk Matrix.)	INSIGNIFICANT	5

The Approximate Cost of Damage is expressed as a percentage of market value, being the cost of the improved value of the unaffected property which includes the land plus the 5 Notes:

The Approximate Cost is to be an estimate of the direct cost of the damage, such as the cost of reinstatement of the damaged portion of the property (land plus structures), stabilisation works required to render the site to tolerable risk level for the landslide which has occurred and professional design fees, and consequential costs such as legal fees, temporary accommodation. It does not include additional stabilisation works to address other landslides which may affect the property. 3

(4) The table should be used from left to right; use Approximate Cost of Damage or Description to assign Descriptor, not vice versa

APPENDIX C: - QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY (CONTINUED) PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

QUALITATIVE RISK ANALYSIS MATRIX – LEVEL OF RISK TO PROPERTY

LIKELIHOOD	HOOD	CONSEQUE	NCES TO PROP	CONSEQUENCES TO PROPERTY (With Indicative Approximate Cost of Damage)	ve Approximate Cos	t of Damage)
	Indicative Value of Approximate Annual Probability	1: CATASTROPHIC 200%	2: MAJOR 60%	3: MEDIUM 20%	4: MINOR 5%	5: INSIGNIFICANT 0.5%
A - ALMOST CERTAIN	10.1	VII	VII	MI	Н	MorL(5)
B - LIKELY	10-2	VII	VΗ	Н	M	T
C - POSSIBLE	10-3	VH	Н	M	M	N.F.
D - UNLIKELY	104	Н	M	ı	Ţ	N.
E - RARE	10-5	M	L	Г	AL.	VL
F - BARELY CREDIBLE	10-6	Ţ	ΛΓ	AL	N.	AL

ଡିଡ Notes:

For Cell A5, may be subdivided such that a consequence of less than 0.1% is Low Risk.

When considering a risk assessment it must be clearly stated whether it is for existing conditions or with risk control measures which may not be implemented at the current

RISK LEVEL IMPLICATIONS

Unacceptable without treatment. Extensive detailed investigation and research, planning and implementation of treatment options essential to reduce risk to Low; may be too expensive and not practical. Work likely to cost more than value of the property. HIGH RISK		Risk Level	Example Implications (7)
	EA	VERY HIGH RISK	Unacceptable without treatment. Extensive detailed investigation and research, planning and implementation of treatment options essential to reduce risk to Low; may be too expensive and not practical. Work likely to cost more than value of the property.
	Н	HIGH RISK	Unacceptable without treatment. Detailed investigation, planning and implementation of treatment options required to reduce risk to Low. Work would cost a substantial sum in relation to the value of the property.
	M	MODERATE RISK	May be tolerated in certain circumstances (subject to regulator's approval) but requires investigation, planning and implementation of treatment options to reduce the risk to Low. Treatment options to reduce to Low risk should be implemented as soon as practicable.
	Т	LOW RISK	Usually acceptable to regulators. Where treatment has been required to reduce the risk to this level, ongoing maintenance is required.
	N.	VERY LOW RISK	Acceptable. Manage by normal slope maintenance procedures.

The implications for a particular situation are to be determined by all parties to the risk assessment and may depend on the nature of the property at risk; these are only given as a general guide. Note: (7)