



**REPORT**

**TO**

**ANGLICAN RETIREMENT VILLAGES**

**ON**

**GEOTECHNICAL SLOPE STABILITY RISK ASSESSMENT**  
(In Accordance with Pittwater Council Risk Management Policy)

**FOR**

**PROPOSED STAGES 4 TO 6 OF**  
**WARRIEWOOD BROOK RETIREMENT VILLAGE**

**AT**

**6 TO 14 MACPHERSON STREET, WARRIEWOOD, NSW**

**5 July 2013**  
**Ref: 21140SB3rpt**



**JK Geotechnics**  
GEOTECHNICAL & ENVIRONMENTAL ENGINEERS

PO Box 976, North Ryde BC NSW 1670  
Tel: 02 9888 5000 Fax: 02 9888 5001  
[www.kgeotechnics.com.au](http://www.kgeotechnics.com.au)

Jeffery & Katauskas Pty Ltd, trading as  
JK Geotechnics ABN 17 003 550 801

Date: 5 July 2013  
Report No: 21140SB3rpt  
Revision No: 0

Report prepared by:



Daniel Bliss  
Senior Associate Geotechnical Engineer

Report reviewed by:



Paul Stubbs  
Principal Geotechnical Engineer

For and on behalf of  
JK GEOTECHNICS  
PO Box 976  
NORTH RYDE BC NSW 1670

© Document Copyright of JK Geotechnics.

This Report (which includes all attachments and annexures) has been prepared by JK Geotechnics (JK) for its Client, and is intended for the use only by that Client.

This Report has been prepared pursuant to a contract between JK and its Client and is therefore subject to:

- a) JK's proposal in respect of the work covered by the Report;
- b) the limitations defined in the Client's brief to JK;
- c) the terms of contract between JK and the Client, including terms limiting the liability of JK.

If the Client, or any person, provides a copy of this Report to any third party, such third party must not rely on this Report, except with the express written consent of JK which, if given, will be deemed to be upon the same terms, conditions, restrictions and limitations as apply by virtue of (a), (b), and (c) above.

Any third party who seeks to rely on this Report without the express written consent of JK does so entirely at their own risk and to the fullest extent permitted by law, JK accepts no liability whatsoever, in respect of any loss or damage suffered by any such third party.



## **TABLE OF CONTENTS**

<b>1</b>	<b>INTRODUCTION</b>	<b>4</b>
<b>2</b>	<b>ASSESSMENT METHODOLOGY</b>	<b>4</b>
<b>3</b>	<b>SUMMARY OF OBSERVATIONS</b>	<b>5</b>
<b>4</b>	<b>SUBSURFACE CONDITIONS</b>	<b>6</b>
<b>5</b>	<b>PROPOSED DEVELOPMENT</b>	<b>7</b>
<b>6</b>	<b>GEOTECHNICAL ASSESSMENT</b>	<b>8</b>
6.1	Potential Landslide Hazards	8
6.2	Risk Analysis	8
6.1	Risk Assessment	9
<b>7</b>	<b>COMMENTS AND RECOMMENDATIONS</b>	<b>10</b>
7.1	Conditions Recommended to Establish the Design Parameters	10
7.2	Conditions Recommended to Allow the Detailed Design to be Undertaken for the Construction Certificate	11
7.3	Conditions Recommended During the Construction Period	11
7.2	Conditions Recommended for Ongoing Management of the Site/Structure(s)	12
<b>8</b>	<b>GENERAL COMMENTS</b>	<b>13</b>

**TABLE A: SUMMARY OF RISK ASSESSMENT TO PROPERTY**

**TABLE B: SUMMARY OF RISK ASSESSMENT TO LIFE**

**FIGURE 1: GEOTECHNICAL SKETCH PLAN**

**FIGURE 2: GEOTECHNICAL MAPPING SYMBOLS**

**APPENDIX A: LANDSLIDE RISK MANAGEMENT TERMINOLOGY**

**APPENDIX B: SOME GUIDELINES FOR HILLSIDE CONSTRUCTION**



## **1 INTRODUCTION**

This report presents the results of our geotechnical slope stability risk assessment of the site of Stages 4 to 6 of the Warriewood Brook Retirement Village located at 6 to 14 MacPherson Street, Warriewood, NSW. The assessment was commissioned by Morgan Moore & Associates, on behalf of Anglican Retirement Villages, and was carried out in accordance with our proposal dated 14 May 2013, Ref: P36143SB1. The site was inspected by our Senior Associate, Mr Daniel Bliss, on 19 June 2013, in order to assess the existing stability of the site and the effect on stability of the proposed development.

Details of the proposed development are presented in Section 5 below. In summary, however, it is proposed to extend the existing Warriewood Brook Village by the construction of a series of single storey villas within the south-eastern portion of the site.

This report has been prepared in accordance with the requirements of the Geotechnical Risk Management Policy for Pittwater (2009) as discussed in Section 6 below. It is understood that the report will be submitted to Council as part of the DA documentation. Our report is preceded by the completed Council Forms 1 and 1a.

## **2 ASSESSMENT METHODOLOGY**

This stability assessment is based upon a detailed inspection of the topographic, surface drainage and geological conditions of the site and its immediate environs. The attached Appendix A defines the terminology adopted for the risk assessment together with a flowchart illustrating the Risk Management Process based on the guidelines given in AGS 2007c (Reference 1).

A summary of our observations is presented in Section 3 below. Our specific recommendations regarding the proposed development are discussed in Section 7 following our geotechnical assessment.

The attached Figure 1 presents a geotechnical sketch plan showing the principal geotechnical features present at the site. Figure 1 is based on the survey plan prepared by Lockley Land Title Solutions (Ref: 35118DT, dated 21/8/2012). Additional features on Figure 1 have been measured by hand held inclinometer and tape measure techniques and hence are only approximate.



Should any of the features be critical to the proposed development, we recommend they be located more accurately using instrument survey techniques.

### **3 SUMMARY OF OBSERVATIONS**

We recommend that the summary of observations which follows be read in conjunction with the attached Figure 1.

The site comprises the south-eastern portion of 6 to 14 MacPherson Street, to the south-east of the main entry road to the existing Warriewood Brook Retirement Village. The site occupies about half the area of 6 to 14 MacPherson Street.

The site is located on the side of a hill that slopes down towards the north and north-west at slopes of about 2° to 4°. Surface levels within the site range from about RL9.5m towards the southern corner to about RL2.7m on the north-eastern side.

The site is vacant, but is predominantly covered with stockpiles about 1m to 1.5m high. The stockpiles are covered with grass, as are the areas in between the stockpiles. Very occasional trees are located within the site and also along the boundaries, particularly the south-eastern boundary. Towards the north-eastern side of the site are several ponds in amongst the stockpiles, as shown on Figure 1. At the time of the inspection the ponds contained water and reeds were growing throughout the ponds.

To the north-west of the site are the existing earlier stages of Warriewood Brook Retirement Village, with an entry road and village green immediately adjacent to the subject site and then two to four storey brick and rendered buildings. These buildings appeared to be in good external condition. To the south-west of the site is MacPherson Street, with three storey rendered unit buildings on the far side of Macpherson Street.

Along the south-eastern boundary is a row of thick trees limiting inspection within the adjoining property. However, for the majority it appeared that the ground surface across this boundary was similar to the subject site, with the adjoining property mostly occupied by garden areas. At the MacPherson Street frontage is a one storey house, in good condition, located about 8m to 10m from the common boundary. Opposite the house the ground surface slopes down from the common boundary at about 20° to the top of a brick retaining wall of about 1m high. The retaining wall is located about 5m from the common boundary.



To the north-east of the site is a heavily vegetated area associated with the Narrabeen Creek. Surface levels appear to slope gently towards the creek with the creek itself obscured by the vegetation cover. On the far side of the creek the ground surface rises gently within the properties that front Warriewood Road.

#### **4 SUBSURFACE CONDITIONS**

The completion of a subsurface investigation was outside the scope of this report, but several preliminary geotechnical investigations have been completed within the Warriewood Brook site as a whole as follows:

- Geotechnical investigation report by GHD-LongMac dated 21 June 2005, Ref: 21/13577/16. This geotechnical investigation involved a broad spacing of boreholes, test pits and Electrical Friction Cone Penetrometer (EFCP) testing.
- Geotechnical investigation report by Jeffery and Katauskas Pty Ltd (now JK Geotechnics) dated 22 May 2007, Ref: 21140VBrpt. The aim of that geotechnical investigation was to drill boreholes, again on a broad coverage, to assess the depth of the rock and the depth of groundwater; testing of the soils above the rock was not undertaken.
- Geotechnical investigation report by Jeffery and Katauskas Pty Ltd (now JK Geotechnics) dated 3 August 2007, Ref: 21140SBrpt. This geotechnical investigation was carried out for the proposed reconstruction of the MacPherson Street pavement and involved the drilling of shallow boreholes along MacPherson Street.

From these previous geotechnical investigations the subsurface conditions within the site will be somewhat variable, with residual soils covering sandstone bedrock at relatively shallow depths within the southern corner of the site, with the depth to the sandstone increasing towards the north. Based on our previous boreholes the depth of the sandstone may range from depths of less than 1m in the southern corner of the subject site to depths of about 13m in the northern corner. These estimated depths are from the natural surface levels and do not take into account the depth of the stockpiles currently on the site. The soils above the sandstone are expected to comprise residual silty clays and sandy clays within (about) the southern half of the site and alluvial soils within the northern portion, comprising silty clay, sandy clay, silty sand and silty clayey sand. Groundwater levels were previously measured at depths ranging from about 0.5m to 2m.



We have also inspected several test pits excavated within the existing stockpiles (see Site Report 1 dated 18 June 2013) and the material within the stockpiles comprises a clayey silt topsoil-like material. This material would not be suitable for use as engineered fill, but could be used as form fill below fully suspended structures.

## **5 PROPOSED DEVELOPMENT**

As shown in the supplied architectural drawings by Environa Studio (Project: 731, Drawing Nos 001 to 003 and 101, Issue SK, dated 2/7/13) the Stage 4 to 6 development will comprise the construction of 61 single storey villas occupying the majority of the site. The villas will be serviced by an internal loop road and access roads branching off the loop road. At the north-eastern end of the site a bowling green about 40m by 15m in size and a community BBQ area will be constructed.

Although the design levels of the buildings have not been determined, we understand that it is planned to use the fill contained within the existing stockpiles to fill the lower end of the site. Therefore, earthworks will be required to remove the stockpiles so that the Macpherson Street frontage is at about the level of the existing roadway and fill the lower end by about 2m to 3m. we have assumed that the fill will be formed at appropriate permanent batters or retaining by retaining walls of less than 3m high.



## **6 GEOTECHNICAL ASSESSMENT**

Overall the site slopes down towards the north-west and is underlain by residual soils within the south-eastern portion and alluvial soils within the north-western portion. Our inspection revealed no signs of major hillside instability.

### **6.1 Potential Landslide Hazards**

We consider that the potential landslide hazards associated with the site following construction of the proposed retirement village to be the following. This assumes that the existing fill stockpiles are removed or regarded to appropriate slopes or retained by engineer designed retaining walls.

- A Instability of the hillside slope below the site and proposed buildings.
- B Instability of any proposed retaining walls.
- C. Instability of permanent batter slopes formed by the proposed earthworks.

### **6.2 Risk Analysis**

The attached Table A summarises our qualitative assessment of each potential landslide hazard and of the consequences to property should the landslide hazard occur. Based on this, the qualitative risks to property have been determined. The terminology adopted for this qualitative assessment is in accordance with Table A1 given in Appendix A. Table A indicates that the assessed risk to property is Very Low, which would be considered acceptable in accordance with the criteria given in Reference 1 and the Pittwater Council Risk Management Policy.

We have also used the indicative probabilities associated with the assessed likelihood of instability to calculate the risk to life. Due to the unknowns in assessing the number of persons using the site sand their duration of use, we have limited our assessment to the risk to life for the person most at risk. We have assumed that the person most at risk will be present on site at all times. The temporal and vulnerability factors that have been adopted are given in the attached Table B together with the resulting risk calculation. Our assessed risk to life for the person most at risk is about  $10^{-7}$ . This would be considered to be acceptable in relation to the criteria given in Reference 1 and the Pittwater Council Risk Management Policy.





## 6.1 Risk Assessment

The Pittwater Risk Management Policy requires suitable measures 'to remove risk'. It is recognised that, due to the many complex factors that can affect a site, the subjective nature of a risk analysis, and the imprecise nature of the science of geotechnical engineering, the risk of instability for a site and/or development cannot be completely removed. It is, however, essential that risk be reduced to at least that which could be reasonably anticipated by the community in everyday life and that landowners are made aware of reasonable and practical measures available to reduce risk as far as possible. Hence, where the policy requires that 'reasonable and practical measures have been identified to remove risk', it means that there has been an active process of reducing risk, but it does not require the geotechnical engineer to warrant that risk has been completely removed, only reduced, as removing risk is not currently scientifically achievable.

Similarly, the Pittwater Risk Management Policy requires that the design project life be taken as 100 years unless otherwise justified by the applicant. This requirement provides the context within which the geotechnical risk assessment should be made. The required 100 years baseline broadly reflects the expectations of the community for the anticipated life of a residential structure and hence the timeframe to be considered when undertaking the geotechnical risk assessment and making recommendations as to the appropriateness of a development, and its design and remedial measures that should be taken to control risk. It is recognised that in a 100 year period external factors that cannot reasonably be foreseen may affect the geotechnical risks associated with a site. Hence, the Policy does not seek the geotechnical engineer to warrant the development for a 100 year period, rather to provide a professional opinion that foreseeable geotechnical risks to which the development may be subjected in that timeframe have been reasonably considered.

In preparing our recommendations given below we have adopted the above interpretations of the Risk Management Policy requirements. We have also assumed that no activities on surrounding land which may affect the risk on the subject site would be carried out. We have further assumed that all Council's buried services are, and will be regularly maintained to remain, in good condition.

**We consider that our risk analysis has shown that the site and existing and proposed development can achieve the 'Acceptable Risk Management' criteria in the Pittwater Risk Management Policy provided that the recommendations given in Section 7 below are adopted. These recommendations form an integral part of the Landslide Risk Management Process.**



## **7 COMMENTS AND RECOMMENDATIONS**

We consider that the proposed development may proceed provided the following specific design, construction and maintenance recommendations are adopted to maintain and reduce the present risk of instability of the site and to control future risks. These recommendations address geotechnical issues only and other conditions may be required to address other aspects.

### **7.1 Conditions Recommended to Establish the Design Parameters**

- 7.1.1 A geotechnical investigation of the site must be carried out to determine the parameters for design of the proposed buildings and pavements. The previous geotechnical investigations do not have sufficient information on the near surface soils to enable foundation properties to be assessed; since the proposed buildings are single storey the soils should be sufficient to support the structures. The design and construction of the proposed development must follow the recommendations given in the geotechnical investigation report.
- 7.1.2 The material within the stockpiles on site is a clayey silt topsoil like material and is not considered suitable for reuse as engineered fill. Therefore, if this material is used it is not suitable for use as engineered fill and any structures built over such fill will need to be designed as fully suspended structures supported on piles founded within the natural soils or weathered rock.
- 7.1.3 If material suitable for use as engineered fill is used on site and is placed and compacted under Level 1 inspection and testing in accordance with AS37980-2007 then the structures can potentially be supported on footings founded within the fill. This must be confirmed by the geotechnical engineer with regard to uniformity of the foundations and the potential for differential settlements and following review of the fill placement records. Careful stripping and inspection of the base of the existing ponds will be required so that a suitable base for the placement of the fill is achieved. Excavation of sediment or wet subgrade soils will be required in these areas.
- 7.1.4 Subject to the results of the geotechnical investigation, preliminary design of any proposed retaining walls may be carried out using the following parameters:
- For cantilever walls, where some deflections are tolerable, adopt a triangular lateral earth pressure distribution and an 'active' earth pressure coefficient,  $K_a$ , of 0.33, for the retained height, assuming a horizontal backfill surface.



- Where deflections are to be reduced, an ‘at rest’ earth pressure coefficient,  $K_0$ , of 0.6 should be used, assuming a horizontal backfill surface.
  - A bulk unit weight of  $20\text{kN/m}^3$  should be adopted for the soil profile.
  - Any surcharge affecting the walls (e.g. traffic loading, live loading, compaction stresses, etc) should be allowed in the design.
  - The retaining walls should be provided with complete and permanent drainage of the ground behind the walls. The subsoil drains should incorporate a non-woven geotextile fabric (eg. Bidim A34), to act as a filter against subsoil erosion.
- 7.1.5 The surface water discharging from the new roof and paved areas must be diverted to outlets for controlled discharge to the existing stormwater system which appears to drain to Narrabeen Creek.
- 7.1.6 The guidelines for Hillside Construction given in Appendix B should also be adopted.

## **7.2 Conditions Recommended to Allow the Detailed Design to be Undertaken for the Construction Certificate**

- 7.2.1 All structural design drawings must be reviewed by the geotechnical engineer who should endorse that the recommendations contained in this report have been adopted in principle. The structural design must be carried out following completion of the geotechnical investigation of the site as recommended above.
- 7.2.2 All hydraulic design drawings must be reviewed by the geotechnical engineer who should endorse that the recommendations contained in this report have been adopted in principle.
- 7.2.3 All landscape design drawings must be reviewed by the geotechnical engineer who should endorse that the recommendations contained in this report have been adopted in principle.

## **7.3 Conditions Recommended During the Construction Period**

- 7.3.1 The geotechnical engineer must approve material for use as engineered fill prior to placement.
- 7.3.2 Where fill is to support footing or slab loads it must be placed and compacted under Level 1 inspection and testing as defined in AS3798-2007.



- 7.3.3 Proposed material to be used for backfilling behind retaining walls must be approved by the geotechnical engineer prior to placement.
- 7.3.4 The geotechnical engineer must inspect all subsurface drains prior to backfilling.
- 7.3.5 The geotechnical engineer must inspect footing excavations or pile drilling prior to placing reinforcement or pouring the concrete. The extent of the geotechnical inspections will depend on the structural design adopted.
- 7.3.6 An 'as-built' drawing of all buried services at the site must be prepared (including all pipe diameters, pipe depths, pipe types, inlet pits, inspection pits, etc).
- 7.3.7 The geotechnical engineer must confirm that the proposed development has been completed in accordance with the geotechnical reports.

We note that all above Conditions have to be complied with to allow the geotechnical engineer to complete Pittwater Council's Form 3 at the end of construction. Where this has not been done, it may not be possible to complete Form 3, which is required for the Occupation Certificate to be signed.

## **7.2 Conditions Recommended for Ongoing Management of the Site/Structure(s)**

The following recommendations have been included so that the current and future owners of the subject property are aware of their responsibilities:

- 7.4.1 All existing and proposed surface (including roof) and subsurface drains must be subject to ongoing and regular maintenance by the property owners.
- 7.4.2 No cut or fill in excess of 0.5m (eg. for landscaping, buried pipes, retaining walls, etc), is to be carried out on site without prior consent from Pittwater Council.
- 7.4.3 Where the structural engineer has indicated a design life of less than 100 years then the structure and/or structural elements must be inspected by a structural engineer at the end of their design life; including a written report confirming scope of work completed and identifying the required remedial measures to extend the design life over the remaining 100 year period.



## **8 GENERAL COMMENTS**

It is possible that the subsurface soil, rock or groundwater conditions encountered during construction may be found to be different (or may be interpreted to be different) from those inferred from our surface observations in preparing this report. Also, we have not had the opportunity to observe surface run-off patterns during heavy rainfall and cannot comment directly on this aspect. If conditions appear to be at variance or cause concern for any reason, then we recommend that you immediately contact this office.

This report has been prepared for the particular project described and no responsibility is accepted for the use of any part of this report in any other context or for any other purpose. Copyright in this report is the property of JK Geotechnics. We have used a degree of care, skill and diligence normally exercised by consulting engineers in similar circumstances and locality. No other warranty expressed or implied is made or intended. Subject to payment of all fees due for the investigation, the client alone shall have a licence to use this report. The report shall not be reproduced except in full.



Reference 1: Australian Geomechanics Society (2007c) *'Practice Note Guidelines for Landslide Risk Management'*, Australian Geomechanics, Vol 42, No 1, March 2007, pp63-114.

---



**TABLE A**  
**SUMMARY OF RISK ASSESSMENT TO PROPERTY**

	<b>A</b>	<b>B</b>	<b>C</b>
<b>POTENTIAL LANDSLIDE HAZARD</b>	Instability of the hillside slope below the site and proposed buildings	Instability of any proposed retaining walls	Instability of permanent batter slopes formed by the proposed earthworks
Assessed Likelihood	Barely Credible to Rare	Rare	Rare
Assessed Consequences	Minor	Minor	Minor
Risk	Very Low	Very Low	Very Low
Comments	Provided design and construction are carried out to good engineering standards. Placement of fill to be controlled or structures designed to be fully suspended supported on piers founded within natural soils or rock.	Assumes walls are of relatively small height and are engineer designed and constructed to the engineering drawings.	Assumes batters formed at suitable permanent batters as recommended by the geotechnical investigation.



24  
SEC C  
DP 5464



### GEOTECHNICAL SKETCH PLAN

**JK Geotechnics**  
 GEOTECHNICAL & ENVIRONMENTAL ENGINEERS  
 Report No. 21140SB3 Figure No. 1



COPYRIGHT



**TABLE B**  
**SUMMARY OF RISK ASESMENT TO LIFE**

	<b>A</b>	<b>B</b>	<b>C</b>
<b>POTENTIAL LANDSLIDE HAZARD</b>	Instability of the hillside slope below the site and proposed buildings	Instability of any proposed retaining walls	Instability of permanent batter slopes formed by the proposed earthworks
Assessed Likelihood	Barely Credible to Rare	Rare	Rare
Indicative Annual Probability	$5 \times 10^{-6}$	$10^{-5}$	$10^{-5}$
Persons at Risk	Person on site at all times	Person on site at all times	Person on site at all times
Duration of Use of Area Affected (Temporal Probability)	1	1	1
Probability of Not Evacuating Area Affected	0.1 (warning likely in the form of cracking)	0.1 (warning likely in the form of cracking)	0.1 (warning likely due to deformation of batter)
Spatial Probability	0.1	0.1	0.1
Vulnerability to Life if Failure Occurs Whilst Person Present	0.2	0.2	0.1
Risk for Person Most at Risk	$1 \times 10^{-8}$	$2 \times 10^{-7}$	$1 \times 10^{-8}$
Combined Risk for Person Most at Risk	$2.2 \times 10^{-7}$		




## TOPOGRAPHY

Symbol	Ground Profile	
		convex
		concave
		convex
		concave
		convex and concave too close together to allow the use of separate symbols
		ridge crest
		Cliff or escarpment or sharp break 40° or more (estimated height in metres)
		Slope direction and angle (Degrees)
		Cut or fill slope, arrows pointing down slope
		Hummocky or irregular ground


## OTHER FEATURES

	Boulder
	Seepage/spring
	Swallow hole for runoff
	Natural water course
	Open drain, unlined
	Open drain, lined
	Fence line
	Property boundary
	Dry Stone Wall
	Major joint in rock face (opening in millimetres)
	Tension crack (opening in millimetres)
	Masonry or concrete wall
	Ponding water
	Boggy or swampy area

## EXAMPLE OF USE OF TOPOGRAPHIC SYMBOLS:



## GEOTECHNICAL PLAN



(After Gardiner, V & Dackombe, R.V. (1983), Geomorphological Field Manual; George Allen & Unwin).

## GEOTECHNICAL MAPPING SYMBOLS

**JK Geotechnics**  
GEOTECHNICAL & ENVIRONMENTAL ENGINEERS

Report No. 21140SB3

Figure No. 2





# **APPENDIX A**

---

**LANDSLIDE RISK  
MANAGEMENT  
TERMINOLOGY**



## **APPENDIX A**

### **LANDSLIDE RISK MANAGEMENT**

#### **Definition of Terms and Landslide Risk**

<b>Risk Terminology</b>	<b>Description</b>
<b>Acceptable Risk</b>	A risk for which, for the purposes of life or work, we are prepared to accept as it is with no regard to its management. Society does not generally consider expenditure in further reducing such risks justifiable.
<b>Annual Exceedance Probability (AEP)</b>	The estimated probability that an event of specified magnitude will be exceeded in any year.
<b>Consequence</b>	The outcomes or potential outcomes arising from the occurrence of a landslide expressed qualitatively or quantitatively, in terms of loss, disadvantage or gain, damage, injury or loss of life.
<b>Elements at Risk</b>	The population, buildings and engineering works, economic activities, public services utilities, infrastructure and environmental features in the area potentially affected by landslides.
<b>Frequency</b>	A measure of likelihood expressed as the number of occurrences of an event in a given time. See also 'Likelihood' and 'Probability'.
<b>Hazard</b>	A condition with the potential for causing an undesirable consequence (the landslide). The description of landslide hazard should include the location, volume (or area), classification and velocity of the potential landslides and any resultant detached material, and the likelihood of their occurrence within a given period of time.
<b>Individual Risk to Life</b>	The risk of fatality or injury to any identifiable (named) individual who lives within the zone impacted by the landslide; or who follows a particular pattern of life that might subject him or her to the consequences of the landslide.
<b>Landslide Activity</b>	The stage of development of a landslide; pre failure when the slope is strained throughout but is essentially intact; failure characterised by the formation of a continuous surface of rupture; post failure which includes movement from just after failure to when it essentially stops; and reactivation when the slope slides along one or several pre-existing surfaces of rupture. Reactivation may be occasional (eg. seasonal) or continuous (in which case the slide is 'active').
<b>Landslide Intensity</b>	A set of spatially distributed parameters related to the destructive power of a landslide. The parameters may be described quantitatively or qualitatively and may include maximum movement velocity, total displacement, differential displacement, depth of the moving mass, peak discharge per unit width, or kinetic energy per unit area.
<b>Landslide Risk</b>	The AGS Australian GeoGuide LR7 (AGS, 2007e) should be referred to for an explanation of Landslide Risk.
<b>Landslide Susceptibility</b>	The classification, and volume (or area) of landslides which exist or potentially may occur in an area or may travel or retrogress onto it. Susceptibility may also include a description of the velocity and intensity of the existing or potential landsliding.
<b>Likelihood</b>	Used as a qualitative description of probability or frequency.
<b>Probability</b>	<p>A measure of the degree of certainty. This measure has a value between zero (impossibility) and 1.0 (certainty). It is an estimate of the likelihood of the magnitude of the uncertain quantity, or the likelihood of the occurrence of the uncertain future event.</p> <p>These are two main interpretations:</p> <p>(i) Statistical – frequency or fraction – The outcome of a repetitive experiment of some kind like flipping coins. It includes also the idea of population variability. Such a number is called an 'objective' or relative frequentist probability because it exists in the real world and is in principle measurable by doing the experiment.</p>



Risk Terminology	Description
<b>Probability</b> <i>(continued)</i>	(ii) Subjective probability (degree of belief) – Quantified measure of belief, judgment, or confidence in the likelihood of an outcome, obtained by considering all available information honestly, fairly, and with a minimum of bias. Subjective probability is affected by the state of understanding of a process, judgment regarding an evaluation, or the quality and quantity of information. It may change over time as the state of knowledge changes.
<b>Qualitative Risk Analysis</b>	An analysis which uses word form, descriptive or numeric rating scales to describe the magnitude of potential consequences and the likelihood that those consequences will occur.
<b>Quantitative Risk Analysis</b>	An analysis based on numerical values of the probability, vulnerability and consequences and resulting in a numerical value of the risk.
<b>Risk</b>	A measure of the probability and severity of an adverse effect to health, property or the environment. Risk is often estimated by the product of probability x consequences. However, a more general interpretation of risk involves a comparison of the probability and consequences in a non-product form.
<b>Risk Analysis</b>	The use of available information to estimate the risk to individual, population, property, or the environment, from hazards. Risk analyses generally contain the following steps: scope definition, hazard identification and risk estimation.
<b>Risk Assessment</b>	The process of risk analysis and risk evaluation.
<b>Risk Control or Risk Treatment</b>	The process of decision-making for managing risk and the implementation or enforcement of risk mitigation measures and the re-evaluation of its effectiveness from time to time, using the results of risk assessment as one input.
<b>Risk Estimation</b>	The process used to produce a measure of the level of health, property or environmental risks being analysed. Risk estimation contains the following steps: frequency analysis, consequence analysis and their integration.
<b>Risk Evaluation</b>	The stage at which values and judgments enter the decision process, explicitly or implicitly, by including consideration of the importance of the estimated risks and the associated social, environmental and economic consequences, in order to identify a range of alternatives for managing the risks.
<b>Risk Management</b>	The complete process of risk assessment and risk control (or risk treatment).
<b>Societal Risk</b>	The risk of multiple fatalities or injuries in society as a whole: one where society would have to carry the burden of a landslide causing a number of deaths, injuries, financial, environmental and other losses.
<b>Susceptibility</b>	See 'Landslide Susceptibility'.
<b>Temporal Spatial Probability</b>	The probability that the element at risk is in the area affected by the landsliding, at the time of the landslide.
<b>Tolerable Risk</b>	A risk within a range that society can live with so as to secure certain net benefits. It is a range of risk regarded as non-negligible and needing to be kept under review and reduced further if possible.
<b>Vulnerability</b>	The degree of loss to a given element or set of elements within the area affected by the landslide hazard. It is expressed on a scale of 0 (no loss) to 1 (total loss). For property, the loss will be the value of the damage relative to the value of the property; for persons, it will be the probability that a particular life (the element at risk) will be lost, given the person(s) is affected by the landslide.

**NOTE:** Reference should be made to Figure A1 which shows the inter-relationship of many of these terms and the relevant portion of Landslide Risk Management.

Reference should also be made to the paper referenced below for Landslide Terminology and more detailed discussion of the above terminology.

**This appendix is an extract from PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT as presented in Australian Geomechanics, Vol 42, No 1, March 2007, which discusses the matter more fully.**




FIGURE A1: Flowchart for Landslide Risk Management.

This figure is an extract from GUIDELINE FOR LANDSLIDE SUSCEPTIBILITY, HAZARD AND RISK ZONING FOR LAND USE PLANNING, as presented in Australian Geomechanics Vol 42, No 1, March 2007, which discusses the matter more fully.



**TABLE A1: LANDSLIDE RISK ASSESSMENT  
QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY**

**QUALITATIVE MEASURES OF LIKELIHOOD**

Approximate Annual Probability		Implied Indicative Landslide Recurrence Interval		Description	Descriptor	Level
Indicative Value	Notional Boundary					
10 <sup>-1</sup>	5x10 <sup>-2</sup>	10 years	20 years	The event is expected to occur over the design life.	ALMOST CERTAIN	A
10 <sup>-2</sup>		100 years		The event will probably occur under adverse conditions over the design life.	LIKELY	B
10 <sup>-3</sup>	5x10 <sup>-3</sup>	1000 years	200 years	The event could occur under adverse conditions over the design life.	POSSIBLE	C
10 <sup>-4</sup>	5x10 <sup>-4</sup>	10,000 years	2000 years	The event might occur under very adverse circumstances over the design life.	UNLIKELY	D
10 <sup>-5</sup>	5x10 <sup>-5</sup>	100,000 years	20,000 years	The event is conceivable but only under exceptional circumstances over the design life.	RARE	E
10 <sup>-6</sup>	5x10 <sup>-6</sup>	1,000,000 years	200,000 years	The event is inconceivable or fanciful over the design life.	BARELY CREDIBLE	F

**Note:** (1) The table should be used from left to right; use Approximate Annual Probability or Description to assign Descriptor, not *vice versa*.

**QUALITATIVE MEASURES OF CONSEQUENCES TO PROPERTY**

Approximate Cost of Damage		Description	Descriptor	Level
Indicative Value	Notional Boundary			
200%	100%	Structure(s) completely destroyed and/or large scale damage requiring major engineering works for stabilisation. Could cause at least one adjacent property major consequence damage.	CATASTROPHIC	1
60%		Extensive damage to most of structure, and/or extending beyond site boundaries requiring significant stabilisation works. Could cause at least one adjacent property medium consequence damage.	MAJOR	2
20%	40%	Moderate damage to some of structure, and/or significant part of site requiring large stabilisation works. Could cause at least one adjacent property minor consequence damage.	MEDIUM	3
5%	10%	Limited damage to part of structure, and/or part of site requiring some reinstatement stabilisation works.	MINOR	4
0.5%	1%	Little damage. (Note for high probability event (Almost Certain), this category may be subdivided at a notional boundary of 0.1%. See Risk Matrix.)	INSIGNIFICANT	5

- Notes:** (2) The Approximate Cost of Damage is expressed as a percentage of market value, being the cost of the improved value of the unaffected property which includes the land plus the unaffected structures.
- (3) The Approximate Cost is to be an estimate of the direct cost of the damage, such as the cost of reinstatement of the damaged portion of the property (land plus structures), stabilisation works required to render the site to tolerable risk level for the landslide which has occurred and professional design fees, and consequential costs such as legal fees, temporary accommodation. It does not include additional stabilisation works to address other landslides which may affect the property.
- (4) The table should be used from left to right; use Approximate Cost of Damage or Description to assign Descriptor, not *vice versa*.

Extract from PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT as presented in Australian Geomechanics, Vol 42, No 1, March 2007, which discusses the matter more fully.



**TABLE A1: LANDSLIDE RISK ASSESSMENT  
QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY (continued)**

**QUALITATIVE RISK ANALYSIS MATRIX – LEVEL OF RISK TO PROPERTY**

LIKELIHOOD		CONSEQUENCES TO PROPERTY (With Indicative Approximate Cost of Damage)				
	Indicative Value of Approximate Annual Probability	1: CATASTROPHIC 200%	2: MAJOR 60%	3: MEDIUM 20%	4: MINOR 5%	5: INSIGNIFICANT 0.5%
<b>A - ALMOST CERTAIN</b>	10 <sup>-1</sup>	VH	VH	VH	H	M or L (5)
<b>B - LIKELY</b>	10 <sup>-2</sup>	VH	VH	H	M	L
<b>C - POSSIBLE</b>	10 <sup>-3</sup>	VH	H	M	M	VL
<b>D - UNLIKELY</b>	10 <sup>-4</sup>	H	M	L	L	VL
<b>E - RARE</b>	10 <sup>-5</sup>	M	L	L	VL	VL
<b>F - BARELY CREDIBLE</b>	10 <sup>-6</sup>	L	VL	VL	VL	VL

- Notes:** (5) Cell A5 may be subdivided such that a consequence of less than 0.1% is Low Risk.  
(6) When considering a risk assessment it must be clearly stated whether it is for existing conditions or with risk control measures which may not be implemented at the current time.

**RISK LEVEL IMPLICATIONS**

Risk Level		Example Implications (7)
VH	VERY HIGH RISK	Unacceptable without treatment. Extensive detailed investigation and research, planning and implementation of treatment options essential to reduce risk to Low; may be too expensive and not practical. Work likely to cost more than value of the property.
H	HIGH RISK	Unacceptable without treatment. Detailed investigation, planning and implementation of treatment options required to reduce risk to Low. Work would cost a substantial sum in relation to the value of the property.
M	MODERATE RISK	May be tolerated in certain circumstances (subject to regulator's approval) but requires investigation, planning and implementation of treatment options to reduce the risk to Low. Treatment options to reduce to Low risk should be implemented as soon as practicable.
L	LOW RISK	Usually acceptable to regulators. Where treatment has been required to reduce the risk to this level, ongoing maintenance is required.
VL	VERY LOW RISK	Acceptable. Manage by normal slope maintenance procedures.

**Note:** (7) The implications for a particular situation are to be determined by all parties to the risk assessment and may depend on the nature of the property at risk; these are only given as a general guide.

Extract from PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT as presented in Australian Geomechanics, Vol 42, No 1, March 2007, which discusses the matter more fully.



## AUSTRALIAN GEOGUIDE LR2 (LANDSLIDES)

### What is a Landslide?

Any movement of a mass of rock, debris, or earth, down a slope, constitutes a "landslide". Landslides take many forms, some of which are illustrated. More information can be obtained from Geoscience Australia, or by visiting its Australian landslide Database at [www.ga.gov.au/urban/factsheets/landslide.jsp](http://www.ga.gov.au/urban/factsheets/landslide.jsp). Aspects of the impact of landslides on buildings are dealt with in the book "Guideline Document Landslide Hazards" published by the Australian Building Codes Board and referenced in the Building Code of Australia. This document can be purchased over the internet at the Australian Building Codes Board's website [www.abcb.gov.au](http://www.abcb.gov.au).

Landslides vary in size. They can be small and localised or very large, sometimes extending for kilometres and involving millions of tonnes of soil or rock. It is important to realise that even a 1 cubic metre boulder of soil, or rock, weighs at least 2 tonnes. If it falls, or slides, it is large enough to kill a person, crush a car, or cause serious structural damage to a house. The material in a landslide may travel downhill well beyond the point where the failure first occurred, leaving destruction in its wake. It may also leave an unstable slope in the ground behind it, which has the potential to fall again, causing the landslide to extend (regress) uphill, or expand sideways. For all these reasons, both "potential" and "actual" landslides must be taken very seriously. The present a real threat to life and property and require proper management.

Identification of landslide risk is a complex task and must be undertaken by a geotechnical practitioner (GeoGuide LR1) with specialist experience in slope stability assessment and slope stabilisation.

### What Causes a Landslide?

Landslides occur as a result of local geological and groundwater conditions, but can be exacerbated by inappropriate development (GeoGuide LR8), exceptional weather, earthquakes and other factors. Some slopes and cliffs never seem to change, but are actually on the verge of failing. Others, often moderate slopes (Table 1), move continuously, but so slowly that it is not apparent to a casual observer. In both cases, small changes in conditions can trigger a landslide with series consequences. Wetting up of the ground (which may involve a rise in groundwater table) is the single most important cause of landslides (GeoGuide LR5). This is why they often occur during, or soon after, heavy rain. Inappropriate development often results in small scale landslides which are very expensive in human terms because of the proximity of housing and people.

### Does a Landslide Affect You?

Any slope, cliff, cutting, or fill embankment may be a hazard which has the potential to impact on people, property, roads and services. Some tell-tale signs that might indicate that a landslide is occurring are listed below:

- Open cracks, or steps, along contours
- Groundwater seepage, or springs
- Bulging in the lower part of the slope
- Hummocky ground
- trees leaning down slope, or with exposed roots
- debris/fallen rocks at the foot of a cliff
- tilted power poles, or fences
- cracked or distorted structures

These indications of instability may be seen on almost any slope and are not necessarily confined to the steeper ones (Table 1). Advice should be sought from a geotechnical practitioner if any of them are observed. Landslides do not respect property boundaries. As mentioned above they can "run-out" from above, "regress" from below, or expand sideways, so a landslide hazard affecting your property may actually exist on someone else's land.

Local councils are usually aware of slope instability problems within their jurisdiction and often have specific development and maintenance requirements. **Your local council is the first place to make enquiries if you are responsible for any sort of development or own or occupy property on or near sloping land or a cliff.**

TABLE 1 – Slope Descriptions

Appearance	Slope Angle	Maximum Gradient	Slope Characteristics
Gentle	0° - 10°	1 on 6	Easy walking.
Moderate	10° - 18°	1 on 3	Walkable. Can drive and manoeuvre a car on driveway.
Steep	18° - 27°	1 on 2	Walkable with effort. Possible to drive straight up or down roughened concrete driveway, but cannot practically manoeuvre a car.
Very Steep	27° - 45°	1 on 1	Can only climb slope by clutching at vegetation, rocks, etc.
Extreme	45° - 64°	1 on 0.5	Need rope access to climb slope.
Cliff	64° - 84°	1 on 0.1	Appears vertical. Can abseil down.
Vertical or Overhang	84° - 90±°	Infinite	Appears to overhang. Abseiler likely to lose contact with the face.





Some typical landslides which could affect residential housing are illustrated below:

**Rotational or circular slip failures (Figure 1)** - can occur on moderate to very steep soil and weathered rock slopes (Table 1). The sliding surface of the moving mass tends to be deep seated. Tension cracks may open at the top of the slope and bulging may occur at the toe. The ground may move in discrete "steps" separated by long periods without movement. More rapid movement may occur after heavy rain.




Figure 1

**Translational slip failures (Figure 2)** - tend to occur on moderate to very steep slopes (Table 1) where soil, or weak rock, overlies stronger strata. The sliding mass is often relatively shallow. It can move, or deform slowly (creep) over long periods of time. Extensive linear cracks and hummocks sometimes form along the contours. The sliding mass may accelerate after heavy rain.




Figure 2

**Wedge failures (Figure 3)** - normally only occur on extreme slopes, or cliffs (Table 1), where discontinuities in the rock are inclined steeply downwards out of the face.

**Rock falls (Figure 3)** - tend to occur from cliffs and overhangs (Table 1).

Cliffs may remain, apparently unchanged, for hundreds of years. Collections of boulders at the foot of a cliff may indicate that rock falls are ongoing. Wedge failures and rock falls do not "creep". Familiarity with a particular local situation can instil a false sense of security since failure, when it occurs, is usually sudden and catastrophic.




Figure 3

**Debris flows and mud slides (Figure 4)** - may occur in the foothills of ranges, where erosion has formed valleys which slope down to the plains below. The valley bottoms are often lined with loose eroded material (debris) which can "flow" if it becomes saturated during and after heavy rain. Debris flows are likely to occur with little warning; they travel a long way and often involve large volumes of soil. The consequences can be devastating.




Figure 4

More information relevant to your particular situation may be found in other Australian GeoGuides:

- GeoGuide LR1 - Introduction
- GeoGuide LR3 - Soil Slopes
- GeoGuide LR4 - Rock Slopes
- GeoGuide LR5 - Water & Drainage
- GeoGuide LR6 - Retaining Walls
- GeoGuide LR7 - Landslide Risk
- GeoGuide LR8 - Hillside Construction
- GeoGuide LR9 - Effluent & Surface Water Disposal
- GeoGuide LR10 - Coastal Landslides
- GeoGuide LR11 - Record Keeping

The Australian GeoGuides (LR series) are a set of publications intended for property owners; local councils; planning authorities; developers; insurers; lawyers and, in fact, anyone who lives with, or has an interest in, a natural or engineered slope, a cutting, or an excavation. They are intended to help you understand why slopes and retaining structures can be a hazard and what can be done with appropriate professional advice and local council approval (if required) to remove, reduce, or minimise the risk they represent. The GeoGuides have been prepared by the [Australian Geomechanics Society](#), a specialist technical society within Engineers Australia, the national peak body for all engineering disciplines in Australia, whose members are professional geotechnical engineers and engineering geologists with a particular interest in ground engineering. The GeoGuides have been funded under the Australian governments' National Disaster Mitigation Program.



## AUSTRALIAN GEOGUIDE LR7 (LANDSLIDE RISK)

### Concept of Risk

Risk is a familiar term, but what does it really mean? It can be defined as "a measure of the probability and severity of an adverse effect to health, property, or the environment." This definition may seem a bit complicated. In relation to landslides, geotechnical practitioners (see GeoGuide LR1) are required to assess risk in terms of the likelihood that a particular landslide will occur and the possible consequences. This is called landslide risk assessment. The consequences of a landslide are many and varied, but our concerns normally focus on loss of, or damage to, property and loss of life.

### Landslide Risk Assessment

Some local councils in Australia are aware of the potential for landslides within their jurisdiction and have responded by designating specific "landslide hazard zones". Development in these areas is normally covered by special regulations. If you are contemplating building, or buying an existing house, particularly in a hilly area, or near cliffs, then go first for information to your local council. If you have any concern that you could be dealing with a landslide hazard that your local council is not aware of you should seek advice from a geotechnical practitioner.

**Landslide risk assessment must be undertaken by a geotechnical practitioner.** It may involve visual inspection, geological mapping, geotechnical

investigation and monitoring to identify:

- potential landslides (there may be more than one that could impact on your site);
- the likelihood that they will occur;
- the damage that could result;
- the cost of disruption and repairs; and
- the extent to which lives could be lost.

Risk assessment is a predictive exercise, but since the ground and the processes involved are complex, prediction inevitably lacks precision. If you commission a landslide risk assessment for a particular site you should expect to receive a report prepared in accordance with current professional guidelines and in a form that is acceptable to your local council, or planning authority.

### Risk to Property

Table 1 indicates the terms used to describe risk to property. Each risk level depends on an assessment of how likely a landslide is to occur and its consequences in dollar terms. Likelihood is the chance of it happening in any one year, as indicated in Table 2. Consequences are related to the cost of the repairs and perhaps temporary loss of use. These two factors are combined by the geotechnical practitioner to determine the Qualitative Risk.

**TABLE 1 – RISK TO PROPERTY**

Qualitative Risk		Significance - Geotechnical engineering requirements
Very high	VH	<b>Unacceptable</b> without treatment. Extensive detailed investigation and research, planning and implementation of treatment options essential to reduce risk to Low. May be too expensive and not practical. Work likely to cost more than the value of the property.
High	H	<b>Unacceptable</b> without treatment. Detailed investigation, planning and implementation of treatment options required to reduce risk to acceptable level. Work would cost a substantial sum in relation to the value of the property.
Moderate	M	<b>May be tolerated</b> in certain circumstances (subject to regulator's approval) but requires investigation, planning and implementation of treatment options to reduce the risk to Low. Treatment options to reduce to Low risk should be implemented as soon as possible.
Low	L	<b>Usually acceptable</b> to regulators. Where treatment has been needed to reduce the risk to this level, ongoing maintenance is required.
Very Low	VL	<b>Acceptable.</b> Manage by normal slope maintenance procedures.

**TABLE 2 – LIKELIHOOD**

Likelihood	Annual Probability
Almost Certain	1:10
Likely	1:100
Possible	1:1,000
Unlikely	1:10,000
Rare	1:100,000
Barely credible	1:1,000,000

The terms "unacceptable", "tolerable" etc. in Table 1 indicate how most people react to an assessed risk level. However, some people will always be more prepared, or better able, to tolerate a higher risk level than others. Some local councils and planning authorities stipulate a maximum tolerable risk level. This may be lower than you feel is reasonable for your block but it is, nonetheless, a pre-requisite for development. Reasons for this include the fact that a landslide on your block may pose a risk to neighbours and passers-by and that, should you sell, subsequent owners of the block may be more risk averse than you.



### Risk to Life

Most of us have some difficulty grappling with the concept of risk and deciding whether, or not, we are prepared to accept it. However, without doing any sort of analysis, or commissioning a report from an "expert", we all take risks every day. One of them is the risk of being killed in an accident. This is worth thinking about, because it tells us a lot about ourselves and can help to put an assessed risk into a meaningful context. By identifying activities that we either are, or are not, prepared to engage in, we can get some indication of the maximum level of risk that we are prepared to take. This knowledge can help us to decide whether we really are able to accept a particular risk, or to tolerate a particular likelihood of loss, or damage, to our property (Table 2).

In Table 3, data from NSW for the years 1998 to 2002, and other sources, is presented. A risk of 1 in 100,000 means that, in any one year, 1 person is killed for every 100,000 people undertaking that particular activity. The NSW data assumes that the whole population undertakes the activity. That is, we are all at risk of being killed in a fire, or of choking on our food, but it is reasonable to assume that only people who go deep sea fishing run a risk of being killed while doing it.

It can be seen that the risks of dying as a result of falling, using a motor vehicle, or engaging in water-related activities (including bathing) are all greater than 1:100,000 and yet few people actively avoid situations where these risks are present. Some people are averse to flying and yet it represents a lower risk than choking to death on food. The data also indicate that, even when the risk of dying as a consequence of a particular event is very small, it could still happen to any one of us today. If this were not so, there would be no risk at all and clearly that is not the case.

In NSW, the planning authorities consider that 1:1,000,000 is the maximum tolerable risk for domestic housing built near an obvious hazard, such as a chemical factory. Although not specifically considered in the NSW guidelines there is little difference between the hazard presented by a neighbouring factory and a landslide: both have the capacity to destroy life and property and both are always present.

**TABLE 3 – RISK TO LIFE**

Risk (deaths per participant per year)	Activity/Event Leading to Death (NSW data unless noted)
1:1,000	Deep sea fishing (UK)
1:1,000 to 1:10,000	Motor cycling, horse riding , ultra-light flying (Canada)
1:23,000	Motor vehicle use
1:30,000	Fall
1:70,000	Drowning
1:180,000	Fire/burn
1:660,000	Choking on food
1:1,000,000	Scheduled airlines (Canada)
1:2,300,000	Train travel
1:32,000,000	Lightning strike

**More information relevant to your particular situation may be found in other AUSTRALIAN GEOGUIDES:**

- GeoGuide LR1 - Introduction
- GeoGuide LR2 - Landslides
- GeoGuide LR3 - Landslides in Soil
- GeoGuide LR4 - Landslides in Rock
- GeoGuide LR5 - Water & Drainage
- GeoGuide LR6 - Retaining Walls
- GeoGuide LR8 - Hillside Construction
- GeoGuide LR9 - Effluent & Surface Water Disposal
- GeoGuide LR10 - Coastal Landslides
- GeoGuide LR11 - Record Keeping

The Australian GeoGuides (LR series) are a set of publications intended for property owners; local councils; planning authorities; developers; insurers; lawyers and, in fact, anyone who lives with, or has an interest in, a natural or engineered slope, a cutting, or an excavation. They are intended to help you understand why slopes and retaining structures can be a hazard and what can be done with appropriate professional advice and local council approval (if required) to remove, reduce, or minimise the risk they represent. The GeoGuides have been prepared by the Australian Geomechanics Society, a specialist technical society within Engineers Australia, the national peak body for all engineering disciplines in Australia, whose members are professional geotechnical engineers and engineering geologists with a particular interest in ground engineering. The GeoGuides have been funded under the Australian governments' National Disaster Mitigation Program.



# **APPENDIX B**

---

## **SOME GUIDELINES FOR HILLSIDE CONSTRUCTION**



## APPENDIX B – SOME GUIDELINES FOR HILLSIDE CONSTRUCTION


	GOOD ENGINEERING PRACTICE	POOR ENGINEERING PRACTICE
<b>ADVICE</b>		
<b>GEOTECHNICAL ASSESSMENT</b>	Obtain advice from a qualified, experienced geotechnical consultant at early stage of planning and before site works.	Prepare detailed plan and start site works before geotechnical advice.
<b>PLANNING</b>		
<b>SITE PLANNING</b>	Having obtained geotechnical advice, plan the development with the risk arising from the identified hazards and consequences in mind.	Plan development without regard for the Risk.
<b>DESIGN AND CONSTRUCTION</b>		
<b>HOUSE DESIGN</b>	Use flexible structures which incorporate properly designed brickwork, timber or steel frames, timber or panel cladding. Consider use of split levels. Use decks for recreational areas where appropriate.	Floor plans which require extensive cutting and filling. Movement intolerant structures.
<b>SITE CLEARING</b>	Retain natural vegetation wherever practicable.	Indiscriminately clear the site.
<b>ACCESS &amp; DRIVEWAYS</b>	Satisfy requirements below for cuts, fills, retaining walls and drainage. Council specifications for grades may need to be modified. Driveways and parking areas may need to be fully supported on piers.	Excavate and fill for site access before geotechnical advice.
<b>EARTHWORKS</b>	<b>CUTS</b>	Indiscriminant bulk earthworks.
	<b>FILLS</b>	Large scale cuts and benching. Unsupported cuts. Ignore drainage requirements.
<b>ROCK OUTCROPS &amp; BOULDERS</b>	Remove or stabilise boulders which may have unacceptable risk. Support rock faces where necessary.	Loose or poorly compacted fill, which if it fails, may flow a considerable distance (including onto properties below). Block natural drainage lines. Fill over existing vegetation and topsoil. Include stumps, trees, vegetation, topsoil, boulders, building rubble etc. in fill. Disturb or undercut detached blocks or boulders.
<b>RETAINING WALLS</b>	Engineer design to resist applied soil and water forces. Found on bedrock where practicable. Provide subsurface drainage within wall backfill and surface drainage on slope above. Construct wall as soon as possible after cut/fill operation.	Construct a structurally inadequate wall such as sandstone flagging, brick or unreinforced blockwork. Lack of subsurface drains and weepholes.
<b>FOOTINGS</b>	Found within bedrock where practicable. Use rows of piers or strip footings oriented up and down slope. Design for lateral creep pressures if necessary. Backfill footing excavations to exclude ingress of surface water.	Found on topsoil, loose fill, detached boulders or undercut cliffs.
<b>SWIMMING POOLS</b>	Engineer designed. Support on piers to rock where practicable. Provide with under-drainage and gravity drain outlet where practicable. Design for high soil pressures which may develop on uphill side whilst there may be little or no lateral support on downhill side.	
<b>DRAINAGE</b>	<b>SURFACE</b>	Discharge at top of fills and cuts. Allow water to pond bench areas.
	<b>SUBSURFACE</b>	Discharge of roof run-off into absorption trenches.
	<b>SEPTIC &amp; SULLAGE</b>	Discharge sullage directly onto and into slopes. Use of absorption trenches without consideration of landslide risk.
<b>EROSION CONTROL &amp; LANDSCAPING</b>	Control erosion as this may lead to instability. Revegetate cleared area.	Failure to observe earthworks and drainage recommendations when landscaping.
<b>DRAWINGS AND SITE VISITS DURING CONSTRUCTION</b>		
<b>DRAWINGS</b>	Building Application drawings should be viewed by a geotechnical consultant.	
<b>SITE VISITS</b>	Site visits by consultant may be appropriate during construction.	
<b>INSPECTION AND MAINTENANCE BY OWNER</b>		
<b>OWNER'S RESPONSIBILITY</b>	Clean drainage systems; repair broken joints in drains and leaks in supply pipes. Where structural distress is evident seek advice. If seepage observed, determine cause or seek advice on consequences.	

This table is an extract from PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT as presented in *Australian Geomechanics*, Vol 42, No 1, March 2007 which discusses the matter more fully.

## HILLSIDE CONSTRUCTION PRACTICE

Sensible development practices are required when building on hillsides, particularly if the hillside has more than a low risk of instability (GeoGuide LR7). Only building techniques intended to maintain, or reduce, the overall level of landslide risk should be considered. Examples of good hillside construction practice are illustrated below.

### EXAMPLES FOR **GOOD** HILLSIDE CONSTRUCTION PRACTICE



#### WHY ARE THESE PRACTICES GOOD?

**Roadways and parking areas** - are paved and incorporate kerbs which prevent water discharging straight into the hillside (GeoGuide LR5).

**Cuttings** - are supported by retaining walls (GeoGuide LR6).

**Retaining walls** - are engineer designed to withstand the lateral earth pressures and surcharges expected, and include drains to prevent water pressures developing in the backfill. Where the ground slopes steeply down towards the high side of a retaining wall, the disturbing force (see GeoGuide LR6) can be two or more times that due to level ground. Retaining walls must be designed taking these forces into account.

**Sewage** - whether treated or not is either taken away in pipes or contained in properly founded tanks so it cannot soak into the ground.

**Surface water** - from roofs and other hard surfaces is piped away to a suitable discharge point rather than being allowed to infiltrate into the ground. Preferably, the discharge point will be in a natural creek where ground water exits, rather than enters, the ground. Shallow, lined, drains on the surface can fulfill the same purpose (GeoGuide LR5).

**Surface loads** - are minimised. No fill embankments have been built. The house is a lightweight structure. Foundation loads have been taken down below the level at which a landslide is likely to occur and, preferably, to rock. This sort of construction is probably not applicable to soil slopes (GeoGuide LR3). If you are uncertain whether your site has rock near the surface, or is essentially a soil slope, you should engage a geotechnical practitioner to find out.

**Flexible structures** - have been used because they can tolerate a certain amount of movement with minimal signs of distress and maintain their functionality.


**Vegetation clearance** - on soil slopes has been kept to a reasonable minimum. Trees, and to a lesser extent smaller vegetation, take large quantities of water out of the ground every day. This lowers the ground water table, which in turn helps to maintain the stability of the slope. Large scale clearing can result in a rise in water table with a consequent increase in the likelihood of a landslide (GeoGuide LR5). An exception may have to be made to this rule on steep rock slopes where trees have little effect on the water table, but their roots pose a landslide hazard by dislodging boulders.

Possible effects of ignoring good construction practices are illustrated on page 2. Unfortunately, these poor construction practices are not as unusual as you might think and are often chosen because, on the face of it, they will save the developer, or owner, money. You should not lose sight of the fact that the cost and anguish associated with any one of the disasters illustrated, is likely to more than wipe out any apparent savings at the outset.

**ADOPT GOOD PRACTICE ON HILLSIDE SITES**  
Extract from Geoguide LR8 – Hillside Construction Practice



## EXAMPLES FOR **POOR** HILLSIDE CONSTRUCTION PRACTICE



### WHY ARE THESE PRACTICES POOR?

**Roadways and parking areas** - are unsurfaced and lack proper table drains (gutters) causing surface water to pond and soaks into the ground.

**Cut and fill** - has been used to balance earthworks quantities and level the site leaving unstable cut faces and added large surface loads to the ground. Failure to compact the fill properly has led to settlement, which will probably continue for several years after completion. The house and pool have been built on the fill and have settled with it and cracked. Leakage from the cracked pool and the applied surface loads from the fill have combined to cause landslides.

**Retaining walls** - have been avoided, to minimise cost, and hand placed rock walls used instead. Without applying engineering design principles, the walls have failed to provide the required support to the ground and have failed, creating a very dangerous situation.

**A heavy, rigid, house** - has been built on shallow, conventional, footings. Not only has the brickwork cracked because of the resulting ground movements, but it has also become involved in a man-made landslide.

**Soak-away drainage** - has been used for sewage and surface water run-off from roofs and pavements. This water soaks into the ground and raises the water table (GeoGuide LR5). Subsoil drains that run along the contours should be avoided for the same reason. If felt necessary, subsoil drains should run steeply downhill in a chevron, or herringbone, pattern. This may conflict with the requirements for effluent and surface water disposal (GeoGuide LR9) and if so, you will need to seek professional advice.

**Rock debris** - from landslides higher up on the slope seems likely to pass through the site. Such locations are often referred to by geotechnical practitioners as "debris flow paths". Rock is normally even denser than ordinary fill, so even quite modest boulders are likely to weigh many tonnes and do a lot of damage once they start to roll. Boulders have been known to travel hundreds of metres downhill leaving behind a trail of destruction.

**Vegetation** - has been completely cleared, leading to a possible rise in the water table and increased landslide risk (GeoGuide LR5).

### DON'T CUT CORNERS ON HILLSIDE SITES - OBTAIN ADVICE FROM A GEOTECHNICAL PRACTITIONER

More information relevant to your particular situation may be found in other Australian GeoGuides:

- |                                     |  |
|-------------------------------------|--|
| • GeoGuide LR1 - Introduction       | • GeoGuide LR6 - Retaining Walls                   |
| • GeoGuide LR2 - Landslides         | • GeoGuide LR7 - Landslide Risk                    |
| • GeoGuide LR3 - Landslides in Soil | • GeoGuide LR9 - Effluent & Surface Water Disposal |
| • GeoGuide LR4 - Landslides in Rock | • GeoGuide LR10 - Coastal Landslides               |
| • GeoGuide LR5 - Water & Drainage   | • GeoGuide LR11 - Record Keeping                   |

The Australian GeoGuides (LR series) are a set of publications intended for property owners; local councils; planning authorities; developers; insurers; lawyers and, in fact, anyone who lives with, or has an interest in, a natural or engineered slope, a cutting, or an excavation. They are intended to help you understand why slopes and retaining structures can be a hazard and what can be done with appropriate professional advice and local council approval (if required) to remove, reduce, or minimise the risk they represent. The GeoGuides have been prepared by the [Australian Geomechanics Society](#), a specialist technical society within Engineers Australia, the national peak body for all engineering disciplines in Australia, whose members are professional geotechnical engineers and engineering geologists with a particular interest in ground engineering. The GeoGuides have been funded under the Australian governments' National Disaster Mitigation Program.

Extract from Geoguide LR8 – Hillside Construction Practice.

**GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER  
FORM NO. 1 – To be submitted with Development Application**

Development Application for <u>Anglican Retirement Villages</u>	Name of Applicant
Address of site <u>Stages 4 to 6, 6 to 14 MacPherson Street, Warriewood, NSW</u>	

**Declaration made by geotechnical engineer or engineering geologist or coastal engineer (where applicable) as part of a geotechnical report**

I Daniel Bliss on behalf of JK Geotechnics  
(Insert Name) (Trading or Company Name)

on this the 5 July 2013 certify that I am a geotechnical engineer or engineering geologist or coastal engineer as defined by the Geotechnical Risk Management Policy for Pittwater - 2009 and I am authorised by the above organisation/company to issue this document and to certify that the organisation/company has a current professional indemnity policy of at least \$2million.  
we/I have:

**Please mark appropriate box**

- Prepared the detailed Geotechnical Report referenced below in accordance with the Australia Geomechanics Society's Landslide Risk Management Guidelines (AGS 2007) and the Geotechnical Risk Management Policy for Pittwater - 2009
- I *Am/*am willing to technically verify that the detailed Geotechnical Report referenced below has been prepared in accordance with the Australian Geomechanics Society's Landslide Risk Management Guidelines (AGS 2007) and the Geotechnical Risk Management Policy for Pittwater - 2009
- Have examined the site and the proposed development in detail and have carried out a risk assessment in accordance with Section 6.0 of the Geotechnical Risk Management Policy for Pittwater - 2009. *We/I* confirm that the results of the risk assessment for the proposed development are in compliance with the Geotechnical Risk Management Policy for Pittwater - 2009 and further detailed geotechnical reporting is not required for the subject site.
- Have examined the site and the proposed development/alteration in detail and *are/am* of the opinion that the Development Application only involves Minor Development/Alterations that do not require a Detailed Geotechnical Risk Assessment and hence *my/our* report is in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009 requirements for Minor Development/Alterations.
- Provided the coastal process and coastal forces analysis for inclusion in the Geotechnical Report

**Geotechnical Report Details:**

Report Title: Geotechnical Slope Stability Risk Assessment for Proposed Stages 4 to 6 of Warriewood Brook Retirement Village at 6 to 14 MacPherson Street, Warriewood, NSW	
Report Date: 5 July 2013	Report Ref No: 21140SB3rpt
Author: <u>Daniel Bliss</u>	
Author's Company/Organisation: <u>JK Geotechnics</u>	

**Documentation which relate to or are relied upon in report preparation:**

See text of report

I ~~am~~ *We are* aware that the above Geotechnical Report, prepared for the abovementioned site is to be submitted in support of a Development Application for this site and will be relied on by Pittwater Council as the basis for ensuring *confirming* that the Geotechnical Risk Management aspects of the proposed development have been adequately addressed to achieve an "Acceptable Risk Management" level for the life of the structure, taken as at least 100 years unless otherwise stated and justified in the Report and that reasonable and practical measures have been identified to remove foreseeable risk, as *discussed in the Report*.

Signature 

Name	Daniel Bliss
Chartered Professional Status	MIEAust; CPEng
Membership No.	969495
Company:	JK Geotechnics



**GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER  
FORM NO. 1(a) - Checklist of Requirements For Geotechnical Risk Management Report for  
Development Application**

Development Application for <u>Anglican Retirement Villages</u>	Name of Applicant
Address of site <u>Stages 4 to 6, 6 to 14 MacPherson Street, Warriewood, NSW</u>	

The following checklist covers the minimum requirements to be addressed in a Geotechnical Risk Management Geotechnical Report. This checklist is to accompany the Geotechnical Report and its certification (Form No. 1).


**Geotechnical Report Details:**

Report Title: Geotechnical Slope Stability Risk Assessment for Proposed Stages 4 to 6 of Warriewood Brook Retirement Village at 6 to 14 MacPherson Street, Warriewood, NSW	
Report Date: 5 July 2013	Report Ref No: 21140SB3rpt
Author: Daniel Bliss	
Author's Company/Organisation: JK Geotechnics	

**Please mark appropriate box**

- Comprehensive site mapping conducted 19 June 2013  
(date)
- Mapping details presented on contoured site plan with geomorphic mapping to a minimum scale of 1:200 (as appropriate)
- Subsurface investigation required
  - No Justification ..... to be carried out to allow development at future time .....
  - Yes Date conducted .....
- Geotechnical model developed and reported as an inferred subsurface type-section
- Relevant Geotechnical hazards identified
  - Above the site
  - On the site
  - Below the site
  - Beside the site
- Geotechnical hazards described and reported
- Risk assessment conducted in accordance with the Geotechnical Risk Management Policy for Pittwater – 2009
  - Consequence analysis
  - Frequency analysis
- Risk calculation
- Risk assessment for property conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009
- Risk assessment for loss of life conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009
- Assessed risks have been compared to "Acceptable Risk Management" criteria as defined in the Geotechnical Risk Management Policy for Pittwater - 2009
- Opinion has been provided that the design can achieve the "Acceptable Risk Management" criteria provided that the specified conditions are achieved *recommendations presented in the Report are adopted.*
- Design Life Adopted:
  - 100 years
  - Other .....  
specify
- Geotechnical Conditions to be applied to all four phases as described in the Geotechnical Risk Management Policy for Pittwater - 2009 have been specified
- Additional action to remove risk where reasonable and practical have been identified and included in the report.
- Risk assessment within Bushfire Asset Protection Zone.

I am We are aware that Pittwater Council will rely on the Geotechnical Report, to which this checklist applies, as the basis for ensuring confirming that the geotechnical risk management aspects of the proposal have been adequately addressed to achieve an "Acceptable Risk Management" level for the life of the structure, taken as at least 100 years unless otherwise stated, and justified in the Report and that reasonable and practical measures have been identified to remove foreseeable risk as discussed in the Report.

Signature .....  .....

Name Daniel Bliss

Chartered Professional Status MIEAust CPEng

Membership No. 969495

Company JK Geotechnics