

# Talia Integrated Housing Lots 5-13

Civil Engineering Works Development Application





Prepared for Sekisui House 19 December 2024



# **Document Information**

Prepared by Enspire Solutions Pty Ltd Level 4, 153 Walker Street North Sydney NSW 2060 ABN 71 624 801 690 © Enspire 2024. Copyright in the whole and every part of this document belongs to Enspire and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or in or on any media to any person other than by agreement with Enspire.

This document is produced by Enspire solely for the benefit and use by the client in accordance with the terms of the engagement. Enspire does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by any third party on the content of this document.

Document Title	Talia Integrated Housing Lots 5-13		
Document Subject Civil Engineering Works Development Application			
Prepared For	Sekisui House		
Project Name	53A & 53B Warriewood Road, Warriewood		
Project Number	220122		
File Name	REPT001-220122-01-Enspire-R01-241219-TaliaIntegratedHousing01Report.docx		

# **Transmittal**

Revision	Date	Prepared by	Checked by	Approved by
40/40/0004	T. Bleasdale	M.Condos	M.Condos	
1	19/12/2024	Issued for Development Appli	cation	



# **Contents**

1	Introduction	1
2	Related Reports and Documents	2
3	The Development	3
	3.1 Proposed Development Works	3
	3.2 Existing Site Conditions	3
4	Erosion and Sediment Control	4
	4.1 Sediment Basin	4
	4.2 Sediment and Erosion Control Measures	4
5	Bulk Earthworks	6
	5.1 Cut and Fill Operations	6
6	Stormwater Management Strategy	7
	6.1 Objectives and Controls	7
	6.2 Proposed Stormwater Management Strategy	7
	6.3 Flooding	7
	6.4 Stormwater Quantity	8
	6.5 Stormwater Quality	8
	6.5.1 Stormwater Quality Objectives (Water Sensitive Urban Design)	8
	6.5.2 Stormwater Quality Management Strategy	8
7	Siteworks	9
	7.1 General	9
	7.2 Signage & Linemarking	2
	7.3 Pavement Design	2
	7.4 Retaining Walls	2
8	Utilities	3
9	Conclusion	4
	int of Tables	
	List of Tables	
Та	able 1 - 53A & 53B Warriewood Road Drawing Reference	2
L	ist of Figures	
	igure 1 - Integrated Housing Lots 5 – 13 Site Plan	1
	igure 2 - Proposed Road Layout	

# **List of Appendices**

Appendix A Detail Survey

Appendix B 53A & 53B Warriewood Road (DA2024/1079)

Appendix C Lot 105 Lorikeet Grove



# 1 Introduction

Enspire Solutions (**Enspire**) have been engaged by **Sekisui House** to prepare the civil engineering and stormwater management design and documentation in support of a Development Application (**DA**) submission to Northern Beaches Council for the proposed Integrated Housing works associated with nine (9) x residential lots, as depicted in **Figure 1**.

Works associated with this Development Application include:

- Sediment and erosion controls;
- Bulk earthworks;
- Construction of housing;
- · Construction of residential driveways;
- · Construction of retaining walls; and
- Installation and commissioning of essential utility services.



Figure 1 – Integrated Housing Lots 5 – 13 Site Plan

(Source: Nearmap)



# 2 Related Reports and Documents

This report is to be read in conjunction with the following reports and documents.

1) Development Application documentation prepared by Enspire Solutions

Table 1 - 53A & 53B Warriewood Road Drawing Reference

Drawing Number	Drawing Title
220122-01-DA-C01.01	COVER SHEET AND DRAWING SCHEDULE
220122-01-DA-C01.21	SPECIFICATION NOTES – SHEET 01
220122-01-DA-C01.41	GENERAL ARRANGEMENT PLAN
220122-01-DA-C03.01	EROSION AND SEDIMENTATION CONTROL PLAN
220122-01-DA-C03.21	EROSION AND SEDIMENTATION CONTROL DETAILS
220122-01-DA-C04.01	BULK EARTHWORKS - CUT AND FILL PLAN
220122-01-DA-C04.21	BULK EARTHWORKS - CUT AND FILL SECTIONS
220122-01-DA-C05.01	SITEWORKS AND STORMWATER MANAGEMENT PLAN – SHEET 01
220122-01-DA-C05.02	SITEWORKS AND STORMWATER MANAGEMENT PLAN – SHEET 02
220122-01-DA-C14.01	SITEWORK DETAILS
220122-01-DA-C21.01	CATCHMENT PLAN

- 2) Northern Beaches Council Water Management for Development Policy, version 2, dated February 2021.
- 3) Northern Beaches Councill Warriewood Valley Roads Masterplan, dated June 2018.
- 4) Northern Beaches Council Warriewood Valley Urban Land Release, water management specification, Revised Version, adopted by Pittwater Council on 12 February 2001.
- 5) Warriewood Valley Draft Planning Framework.
- 6) Northern Beaches Engineering Design Code (AUSPEC 1).
- 7) Development Application engineering plans associated with the parent subdivision, prepared by Enspire Solutions [DA2024/1079];
- 8) Development Application engineering plans associated with 53C prepared by Jones Nicholson Consulting Engineers, dated November 2015.
- 9) Engineering plans associated (DA N0511/10), prepared by Proust and Gardner, dated July 2010 (neighbouring development to the north)



# 3 The Development

# 3.1 Proposed Development Works

The development site is located within the Northern beaches Local Government Area (LGA) and occupies a total area of approximately 0.21ha.

The development is generally bound by the following and reflected on Figure 1:

- Existing neighbouring residential development to the north; and
- Proposed residential subdivision development to the south, east and west. The parent subdivision is subject to DA2024/1079.
  - An extension of Lorikeet Grove is proposed directly to the west of the site and is expected to be constructed prior to these works commencing.
  - Local road known as 'Road 01' is proposed directly to the south of the site and is expected to be constructed prior to these works commencing.

The proposed development seeks consent for the construction of nine (9) residential dwellings, stormwater works, minor retaining walls and associated landscaping.

The proposed development has been prepared in accordance with the relevant planning requirements and design specifications referenced in Section 2.

Reference shall be made to DA2024/1079 for details pertaining to the parent subdivision.

# 3.2 Existing Site Conditions

To facilitate development of the residential allotments and dwellings, levels across the site have been designed to closely replicate levels proposed under the parent subdivision DA2024/1079. Levels vary from RL 9.5 at the northern corner, to RL 6.0 at the western corner adjacent to Lorikeet Grove.

The proposed development is also largely constrained by works that are proposed to be completed under the parent subdivision, including but not limited to the following:

- Internal road network known as Lorikeet Grove, Road 01 and Road 02;
- Major and minor stormwater pit and pipe network;
- On-Site Detention tanks in Roads 01 and 02;
- Site retaining walls;
- Utilities: and
- Creek corridor rehabilitation works.

An existing sewer carrier main is also located directly east of the site, shall remain un-impeded, retain its current alignment, and be protected throughout all phases of development. Works around the sewer main will require consultation with the relevant authority.

Reference shall be made to DA2024/1079 for further details.



# 4 Erosion and Sediment Control

The objectives of the erosion and sediment control for the development site are to ensure:

- Adequate erosion and sediment control measures are applied prior to the commencement of construction and are maintained throughout construction; and
- Construction site runoff is appropriately treated in accordance with Northern Beaches Council requirements.

As part of the works, the erosion and sedimentation control will be constructed in accordance with Council requirements and the NSW Department of Housing Manual, "Managing Urban Stormwater Soil & Construction" 2004 (Blue Book) prior to any earthworks commencing on site.

### 4.1 Sediment Basin

As part of the works, the erosion and sedimentation control will be constructed in accordance with Council requirements and the NSW Department of Housing Manual, "Managing Urban Stormwater Soil & Construction" 2004 (Blue Book) prior to any earthworks commencing on site.

The sediment basin is proposed to be constructed under the parent subdivision works and maintained throughout construction of these works. The sediment basin has been designed to capture site runoff during construction of these works.

To ensure the sediment basin is working effectively it will be maintained throughout the construction works. Maintenance includes ensuring adequate settlement times or flocculation and pumping of clean water to reach the minimum storage volume at the lower level of the settling zone. The settling zone will be identified by pegs to clearly show the level at which design storage capacity is available.

The pumped water from the sediment basin can be reused for dust control during construction.

Reference shall be made to DA2024/1079 for further details.

### 4.2 Sediment and Erosion Control Measures

Prior to any earthworks commencing on site, sediment and erosion control measure shall be implemented generally in accordance with the Development Application drawings and the "Blue Book". The measures shown on the drawings are intended to be a minimum treatment only as the contractor will be required to modify and stage the erosion and sedimentation control measures to suit the construction program, sequencing and techniques. These measures will include:

- A temporary site security/safety fence is to be constructed around the site;
- Sediment fencing provided downstream of disturbed areas, including any stockpiles;
- Dust control measures including covering stockpiles, installing fence hessian and watering exposed areas;
- Placement of hay bales or mesh and gravel inlet filters around and along proposed catch drains and around stormwater inlets pits;
- Maintenance of the temporary sediment basin constructed under DA2024/1079; and
- Stabilised site access at the construction vehicle entry/exits.

Any stockpiled material, including topsoil, shall be located as far away as possible from any associated natural watercourses or temporary overland flow paths. Sediment fences shall be



installed to the downstream side of stockpiles and any embankment formation. All stockpiles and embankment formations shall be stabilised by hydroseeding or hydro mulching on formation.



# 5 Bulk Earthworks

# 5.1 Cut and Fill Operations

The proposed earthworks operations for the site will consist of cut to fill operations to facilitate construction of the public and private roads, residential allotments, retaining walls and public reserve.

The works associated with this Development Application details the following:

- Earthworks and operations to achieve required finished levels;
- Erosion and sediment controls; and
- Retaining wall structures.

Earthworks on the site will consist of cut and fill operations to achieve the desired levels.

Approximate cut to fill earthworks operations for the works subject to this development application are summarised within Enspire's engineering drawing package.

The cut and fill earthworks volumes provided are concept only and are subject to change pending final coordination and detailed civil design. It should be noted the cut and fill operations for this development are based on the following assumptions and parameters:

- · No allowance for earthworks bulking factors;
- No allowance for spoil generated from utility service and stormwater drainage trenching;
- Allowance for topsoil stripping of the existing ground plane;
- A preliminary bulk earthworks surface has been adopted and includes benching of the residential dwellings;

Reference shall be made to Enspire's drawing package for further details.



# 6 Stormwater Management Strategy

# 6.1 Objectives and Controls

The stormwater strategy has been developed in accordance with Northern beaches council's Water Management for Development Policy and the proposed stormwater management report prepared by Enspire Solutions under DA2024/1079.

The objectives of Council's Water Management for Development Policy are:

- a) Improve the quality of water discharged to our natural areas to protect the ecological and recreational condition of our, beaches, waterways, riparian areas and bushland.
- b) Minimise the risk to public health and safety.
- c) Reduce the risk to life and property from any flooding and groundwater damage.
- d) A sustainable and holistic catchment wide approach is taken to development, of both private land uses and public facilities, on flood prone land.
- e) Climate change will inform decisions for future water infrastructure.
- f) Water sensitive urban design measures will be integrated into the built form to maximise liveability and reduce the impacts of climate change e.g. urban heat island effect and intensified rainfall events.
- g) Wherever possible, water courses are to be conserved or restored to their natural state.
- h) Reduce the consumption of potable water by encouraging water efficiency, the reuse of water and use of alternative water sources.
- i) Protect Council stormwater drainage assets during development works and to ensure Council's drainage rights are not compromised by development activities.

# 6.2 Proposed Stormwater Management Strategy

In accordance with Council's Water Management for Development Policy, the stormwater management strategy has been designed to ensure site stormwater runoff is managed in the following key areas:

- Existing and developed case catchments;
- Stormwater quantity;
- Stormwater quality; and
- Flooding.

The proposed civil engineering development package documents site levels, grading, and stormwater drainage components and catchments for the site. The overall stormwater management strategy for the site considers external upstream catchments as well as downstream conditions. The lawful point of discharge for the site remains to be to Narrabeen Creek and is consistent with existing conditions.

Reference shall be made to DA2024/1079 for further details around the proposed stormwater management strategy.

### 6.3 Flooding

Flood modelling of the site has been undertaken by Catchment Simulation Solutions (CSS). Results of the flood study are presented under the parent subdivision works (DA2024/1079) and results reflected in the flood study. Reference shall be made to the flood study for further details.



# 6.4 Stormwater Quantity

The proposed stormwater management strategy has been developed as part of the parent subdivision application, DA2024/1079, in accordance with Council's Water Management for Development Policy. As part of Council's policy, OSD is required to be implemented to ensure that the development does not increase stormwater discharge downstream and exceed that of the existing stormwater discharge conditions up to the 1% AEP storm event.

The development site is located within 'Region 1 – Northern Stormwater Region' as per Council's Water Management Policy, Section 9.3.1. To ensure post-development runoff is retained to pre-development flow regimes, two (2) separate OSD tanks are proposed under the parent subdivision to restrict outflows to pre-developed conditions.

Reference shall be made to DA2024/1079 for further details.

# 6.5 Stormwater Quality

# 6.5.1 Stormwater Quality Objectives (Water Sensitive Urban Design)

The stormwater strategy for the development has been developed in accordance with Northern beaches council's Water Management for Development Policy.

The objectives of Council's Water Management for Development Policy are:

- a) Stormwater quality (temperature, salinity, chemical makeup and sediment beds) discharging from the development shall not impact the receiving waters. Reference shall be made to local data if available, including the Warringah Creek Management Study and the Australian and New Zealand Guidelines for Fresh and Marine Water Quality (ANZECC), or other widely accepted guidelines. Stormwater and other drainage shall not be discharged into saltmarsh.
- b) Disturbance to stream and wetland sediments is to be minimised by regulated discharge of stormwater and dissipation of flows at discharge locations. Runoff from the development must be retained at natural discharge rates and sediments controlled at the source.
- c) Stormwater and groundwater flow is to mimic natural conditions and ensure a dispersed pattern of flow, avoiding centralised or concentrated discharge points into the wetland or waterway. Natural flow regimes must be retained. The reduction or increase in flows, alteration in seasonality of flows, changes to the frequency, duration, magnitude, timing, predictability and variability of flow events, altering surface and subsurface water levels and changing the rate of rise or fall of water levels must be avoided.

# 6.5.2 Stormwater Quality Management Strategy

A water quality analysis has been undertaken as part of the parent subdivision application, DA2024/1079, to assess the performance of the proposed WSUD strategy against the adopted stormwater quality targets.

The overall development will include a bio-retention basin in the downstream private buffer strip. The remaining treatment system will include the use of a Gross Pollutant Trap, and rainwater tanks for all residential lots as demonstrated on Enspire's engineering drawing package.

Reference shall be made to DA2024/20179 for the proposed MUSIC Model strategy.



# 7 Siteworks

### 7.1 General

The proposed development works will involve the construction of multiple new residential dwellings, driveways, and retaining walls. The road network servicing the development will include Lorikeet Grove to the West and Road 01 to the south, both to be constructed under DA2024/1079.

**Figure 5** demonstrates the proposed road layout for the parent subdivision.




Figure 2 - Proposed Road Layout



# 7.2 Signage & Linemarking

Signage, line marking, and road pavement surface treatments will be provided for appropriate warning to vehicles, traffic calming at local road intersections and improve driver awareness in critical locations.

Reference is to be made to DA2024/1079 for further details on proposed pavement, signage and line marking.

# 7.3 Pavement Design

Pavements for the residential driveways will be designed as part of the detailed design phase of the development in accordance with Northern Beaches Engineering Design Code (AUSPEC 1).

- Vehicular Crossings & Residential Driveways To Council Standard Detail. Indicative profile as follows:
  - 125mm Concrete (SL62 mesh 50 Top Cover) on
  - 25mm approved fine granular material, except where under the kerb and gutter line where this section is to be placed on
  - o 150mm DGB20 Sub-Base

Final pavement design is subject to future detail through the Subdivision Works Certificate phase of the development. Reference shall be made to Enspire's engineering plans for further details on proposed pavement treatments.

# 7.4 Retaining Walls

Retaining wall structures associated with the development are proposed to be constructed under this Development Application. Wall details and specifications will be provided during the detailed design phase of the development. Indicative sections are reflected on the submitted engineering plans to demonstrate feasibility.

Reference shall be made to Enspire's engineering drawing package for further details.

# 8 Utilities

New utility infrastructure is to be constructed under the parent subdivision DA2024/1079. Services will be placed in typical shared trench arrangements in accordance with the NSW Streets Opening Conference Guide to Codes and Practices for Streets Opening (2009) or equivalent alternative approved by the relevant authority.

The services that will be available to service this development include:

- 1. Potable Water;
- 2. Sewer:
- 3. Telecommunications;
- 4. High and low voltage electrical services, including street lighting; and
- 5. Natural Gas.

The design of all utilities will be submitted as part of the Subdivision Works Certificate application and to each relevant authority.

Reference shall be made to the parent subdivision works [DA2024/1079] for further details around utilities and overall servicing strategy.

# 9 Conclusion

This Civil Engineering report has been prepared to provide a summary of the road design assumptions and adopted design procedures, and a guide to the stormwater quantity and quality management techniques for the proposed development as depicted in **Figure 1**.

The overall stormwater management strategy for the site in its entirety has been prepared as part of the parent subdivision works, DA2024/1079. The stormwater management works, including water quantity and water quality, proposed under this package is consistent with the overall strategy.



# Appendix A Detail Survey

Colliers





# Appendix B 53A & 53B Warriewood Road (DA2024/1079)








# Appendix C Lot 105 Lorikeet Grove


Proust & Gardner & Alkira Homes











# ROAD

# SEKISUI HOUSE

# 53A & 53B WARRIEWOOD ROAD WARRIEWOOD NSW 2102 CIVIL ENGINEERING WORKS

DEVELOPMENT APPLICATION

220122-00-DA-C22.02

220122-00-DA-C22.03

220122-00-DA-C22.04

DRAWING SCHEDULE **DESCRIPTION** DRAWING NUMBER 220122-00-DA-C01.01 COVER SHEET AND DRAWING SCHEDULE 220122-00-DA-C01.21 SPECIFICATION NOTES 220122-00-DA-C01.41 GENERAL ARRANGEMENT PLAN 220122-00-DA-C02.01 **DEMOLITION PLAN** 220122-00-DA-C03.01 **EROSION AND SEDIMENTATION CONTROL PLAN** 220122-00-DA-C03.21 220122-00-DA-C04.01 220122-00-DA-C04.21 220122-00-DA-C04.22 220122-00-DA-C05.01 220122-00-DA-C05.02 220122-00-DA-C06.01 ROAD TYPICAL CROSS SECTIONS 220122-00-DA-C07.01 ROAD LONGITUDINAL SECTIONS 220122-00-DA-C11.01 PAVEMENT, SIGNAGE AND LINEMARKING PLAN 220122-00-DA-C13.01 SITE SECTIONS 220122-00-DA-C14.01 SITEWORKS DETAILS 220122-00-DA-C20.01 PRE-DEVELOPMENT CATCHMENT PLAN 220122-00-DA-C21.01 POST-DEVELOPMENT CATCHMENT PLAN

TURNING PATH PLAN - SHEET 01


TURNING PATH PLAN - SHEET 02

TURNING PATH PLAN - SHEET 03


TURNING PATH PLAN - SHEET 04

SS TPB RLE MC DESCRIPTION DRN. DES. VERIF. APPD





without the permission of Enspire Solutions Pty Ltd.





Phone: 02 9922 6135

FOR INFORMATION ONLY

# **GENERAL**

- ALL WORKS TO BE CONSTRUCTED IN ACCORDANCE WITH NORTHERN BEACHES COUNCIL STANDARDS.
- NORTHERN BEACHES COUNCIL STANDARDS DETAILS TO BE USED WHERE POSSIBLE.
- 3. UTILITY ADJUSTMENTS AT DEVELOPERS EXPENSE.
- 4. CONDUITS TO BE PLACED WHERE REQUIRED BY THE RELEVANT AUTHORITIES

# SURVEY

# ORIGIN OF SURVEY

PROJECT: 53A WARRIEWOOD ROAD DATE: 02/01/2021 CARRIED OUT BY: COLLIERS SURVEY NAME: 434-20G T01 [02] REFERENCE NO: 434-20 SSM/PM: SSM 24840 342191.825

13.902 THE EXISTING SITE CONDITIONS SHOWN ON THE FOLLOWING DRAWINGS HAVE BEEN SUPPLIED BY REGISTERED SURVEYORS TO PROVIDE A BASIS FOR DESIGN. THE USE OF THIS SURVEY BASE DOES NOT GUARANTEE THE ACCURACY OR COMPLETENESS OF THE SURVEY BASE OR ITS SUITABILITY

6271409.780

SHOULD DISCREPANCIES BE ENCOUNTERED DURING CONSTRUCTION BETWEEN THE SURVEY DATA AND ACTUAL FIELD DATA, CONTACT THE SUPERINTENDENT.

AS A BASIS FOR CONSTRUCTION DRAWINGS.

THE RELATIONSHIP OF IMPROVEMENTS TO BOUNDARIES ARE DIAGRAMMATIC ONLY. WHERE DISTANCES TO BOUNDARIES ARE CRITICAL THEY SHOULD BE CONFIRMED ON SITE PRIOR TO CONSTRUCTION BY FURTHER SURVEY.



# **EROSION AND SEDIMENT CONTROL**

# GENERAL INSTRUCTIONS

- . THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONTROL OF EROSION AND SEDIMENTATION TO THE SATISFACTION OF COUNCIL. NSW OFFICE OF WATER, OFFICE OF ENVIRONMENT AND HERITAGE. THE EROSION AND SEDIMENTATION CONTROLS SHOWN ON THE DRAWINGS SHALL ONLY BE USED AS A GUIDE BY THE CONTRACTOR, AND SHALL REPRESENT THE MINIMUM REQUIREMENT ONLY.
- THE CONTRACTOR SHALL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE LOCATED TO SUIT CONSTRUCTION STAGING AND WORK PRACTICES OR AS OTHERWISE DIRECTED BY THE SUPERINTENDENT.
- ALL WORK SHALL BE GENERALLY CARRIED OUT IN ACCORDANCE WITH a. LOCAL AUTHORITY REQUIREMENTS b. EPA REQUIREMENTS
- c. LANDCOM MANUAL "MANAGING URBAN STORMWATER, SOILS AND CONSTRUCTION", 4th EDITION, MARCH 2004.
- MAINTAIN THE EROSION CONTROL DEVICES TO THE SATISFACTION OF THE SUPERINTENDENT AND THE LOCAL AUTHORITY.

WHEN STORMWATER PITS ARE CONSTRUCTED, PREVENT SITE RUNOFF

EFFECTIVELY. REPAIRS AND OR MAINTENANCE SHALL BE UNDERTAKEN

ENTERING UNLESS SEDIMENT FENCES ARE ERECTED AROUND PITS. 5. CONTRACTOR IS TO ENSURE ALL EROSION & SEDIMENT CONTROL DEVICES ARE MAINTAINED IN GOOD WORKING ORDER AND OPERATE

AS REQUIRED, PARTICULARLY FOLLOWING STORM EVENTS.

# LAND DISTURBANCE

- 6. WHERE PRACTICAL, THE SOIL EROSION HAZARD ON THE SITE WILL BE KEPT AS LOW AS POSSIBLE. TO THIS END, WORKS SHOULD BE UNDERTAKEN IN THE FOLLOWING SEQUENCE:
- a. INSTALL A SEDIMENT FENCE ALONG THE BOUNDARIES AS SHOWN ON
- PLAN. REFER DETAIL. b. CONSTRUCT STABILISED CONSTRUCTION ENTRANCE TO LOCATION AS
- DETERMINED BY SUPERINTENDENT/ENGINEER. REFER DETAIL. c. INSTALL SEDIMENT BASIN AS SHOWN ON PLAN, INSTALL SEDIMENT
- TRAPS AS SHOWN ON PLAN. d. UNDERTAKEN SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. WHERE POSSIBLE, PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.

# **EROSION CONTROL**

- DURING WINDY WEATHER, LARGE, UNPROTECTED AREAS WILL BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL.
- FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION ACTIVITIES.

# SEDIMENT CONTROL

- 9. STOCKPILES WILL NOT BE LOCATED WITHIN 2 METRES OF HAZARD AREAS, INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS. WHERE THEY ARE BETWEEN 2 AND 5 METRES FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSTREAM WATERS, E.G. THROUGH INSTALLATION OF SEDIMENT FENCING.
- 0. ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD OVER THE SURFACE) WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.
- 11. WATER WILL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE, I.E. THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AN APPROVED STRUCTURE.
- 12. TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.
- 13. ACCEPTABLE RECEPTORS WILL BE PROVIDED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER.
- 14. ANY EXISTING TREES WHICH FORM PART OF THE FINAL LANDSCAPING PLAN WILL BE PROTECTED FROM CONSTRUCTION ACTIVITIES IN ACCORDANCE WITH SECTION 4 OF AS4970 "PROTECTION OF TREES ON DEVELOPMENT SITES" AND COUNCIL CONSENT CONDITIONS.

# **EARTHWORKS**

- AT THE COMMENCEMENT OF THE CUT AND FILLING OPERATIONS FOR BULK. EARTHWORKS A GEOTECHNICAL ENGINEER IS TO VISIT THE SITE & CONFIRM THE SUITABILITY OF THE METHODOLOGY OF ACHIEVING THE REQUIRED BUILDING PLATFORMS AND COMPACTION REQUIREMENTS. SUBSEQUENTLY, THE HEAD CONTRACTOR IS TO CONFIRM, IN WRITING TO THE SUPERINTENDENT THAT THE METHODOLOGY APPROVED AT THE TIME OF THE GEOTECHNICAL ENGINEERS VISIT WAS MAINTAINED DURING ALL THE BULK EARTHWORKS PROCESS.
- 2. STRIP TOPSOIL, ORGANIC MATTER AND RUBBLE FROM CONSTRUCTION AREA TO EXPOSE NATURALLY OCCURRING MATERIAL AND STOCKPILE ON SITE AS DIRECTED BY THE SUPERINTENDENT.
- . WHERE FILLING, STRUCTURAL SLABS OR PAVEMENTS ARE REQUIRED, PROOF ROLL THE EXPOSED NATURAL SURFACE WITH A MINIMUM OF TEN PASSES OF A SMOOTH DRUM NON-VIBRATING ROLLER (MINIMUM STATIC WEIGHT OF 10 TONNES) TO DETECT THEN REMOVE SOFT SPOTS (AREAS WITH MORE THAN 2mm MOVEMENT UNDER ROLLER) IN THE PRESENCE OF THE SUPERINTENDENT. THE CONTRACTOR IS TO ALLOW TO REMOVE AND REPLACE A PROVISIONAL QUANTITY OF UNSUITABLE SUBGRADE MATTER.
- 4. ALL SOFT, WET OR UNSUITABLE MATERIAL IS TO BE REMOVED AS DIRECTED BY THE SUPERINTENDENT AND REPLACED WITH APPROVED MATERIAL SATISFYING THE REQUIREMENTS LISTED BELOW.
- 5. EXCAVATED MATERIAL IS NOT TO BE USED AS STRUCTURAL FILL UNLESS APPROVED BY THE GEOTECHNICAL ENGINEER.
- 6. THE CONTRACTOR IS TO PROVIDE CERTIFICATES VERIFYING THE QUALITY OF IMPORTED MATERIAL FOR THE SUPERINTENDENTS APPROVAL.
- . ALL FILL MATERIAL SHALL BE PLACED IN MAXIMUM LAYER THICKNESS TO COUNCIL SPECIFICATIONS AND COMPACTED AT OPTIMUM MOISTURE CONTENT (+ OR - 2%) TO ACHIEVE A DRY DENSITY DETERMINED IN ACCORDANCE WITH AS1289 E3.1 OF NOT LESS THAN THE FOLLOWING STANDARD MINIMUM DRY DENSITY IN ACCORDANCE WITH AS1289 E5.1.1.1:

COMPACTION REQUIREMENT

UNDER BUILDING SLABS LANDSCAPED AREAS

98% SMDD 95% SMDD ROADS & PAVED AREAS 100% SMDD

- FOR NON COHESIVE MATERIAL, COMPACT TO NOT LESS THAN UNDER ROAD 80% DENSITY OTHER AREA 75% DENSITY
- THE CONTRACTOR IS TO ALLOW FOR COMPACTION TESTING BY NATA REGISTERED LABORATORY FOR PLATFORMS AND FILL LAYERS IN ACCORDANCE WITH THE LATEST VERSION OF AS3798 - FOR TYPE 1 OPERATIONS (MINIMUM 3 TESTS PER LAYER).
- 10. FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN: 1 TEST PER 200m3 OF FILL PLACED PER LAYER OF FILL B.
  - 3 TESTS PER VISIT 1 TEST PER 1000m<sup>2</sup> OF EXPOSED SUBGRADE
- 11. TESTING SHALL BE "LEVEL 1" UNDERTAKEN IN ACCORDANCE WITH AS3798.
- 12. WHERE TEST RESULTS ARE BELOW THE SPECIFIED COMPACTION, RECOMPACT AND RETEST UNTIL SPECIFIED COMPACTION STANDARD IS ACHIEVED.
- 13. ALLOW FOR EXCAVATION IN ALL MATERIALS AS FOUND U.N.O. NO ADDITIONAL PAYMENTS WILL BE MADE FOR EXCAVATION IN WET OR HARD GROUND.
- 14. WHERE THERE IS INSUFFICIENT EXCAVATED MATERIAL SUITABLE FOR FILLING OR SUBGRADE REPLACEMENT. THE CONTRACTOR IS TO ALLOW TO IMPORT FILL. IMPORTED FILL SHALL COMPLY WITH THE FOLLOWING: MAXIMUM SIZE 50mm. PASSING 75 MICRON SIEVE (<25%).
- PLASTICITY INDEX BETWEEN 2-15% AND CBR>8. B. FREE FROM ORGANIC AND PERISHABLE MATTER.
- 15. THE CONTRACTOR SHALL PROGRAM THE EARTHWORKS OPERATION SO THAT THE WORKING AREAS ARE ADEQUATELY DRAINED DURING THE PERIOD OF CONSTRUCTION. THE SURFACE SHALL BE GRADED AND SEALED OFF TO REMOVE DEPRESSIONS, ROLLER MARKS AND SIMILAR WHICH WOULD ALLOW WATER TO POND AND PENETRATE THE UNDERLYING MATERIAL. ANY DAMAGE RESULTING FROM THE CONTRACTOR NOT OBSERVING THESE REQUIREMENTS SHALL BE RECTIFIED AT THEIR COST.
- 16. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE AND MAINTAIN THE INTEGRITY OF ALL SERVICES, CONDUITS AND PIPES DURING CONSTRUCTION, SPECIFICALLY DURING THE BACKFILLING AND COMPACTION PROCEDURE. ANY AND ALL DAMAGE TO NEW OR EXISTING SERVICES AS A RESULT OF THESE WORKS SHALL BE REPAIRED BY THE CONTRACTOR AT NO EXTRA COST.
- 17. PROTECT FINAL SURFACE WITH EITHER A TEMPORARY LOOSE SOIL LAYER OR A GRANULAR SUB-BASE LAYER TO PREVENT DRYING OUT PRIOR TO ON-GROUND SLAB CONSTRUCTION.

without the permission of Enspire Solutions Pty Ltd.

# SITEWORKS

- ALL WORKS TO BE IN ACCORDANCE WITH LOCAL AUTHORITY REQUIREMENTS, SPECIFICATIONS AND AUSTRALIAN STANDARDS. CONFLICTS SHALL BE REFERRED TO THE SUPERINTENDENT FOR
- CONTRACTOR MUST VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO COMMENCEMENT OF WORK, ANY DISCREPANCIES TO BE REPORTED TO THE SUPERINTENDENT.
- THE CONTRACTOR IS TO DESIGN, OBTAIN APPROVALS AND CARRY OUT REQUIRED TEMPORARY TRAFFIC CONTROL PROCEDURES DURING CONSTRUCTION IN ACCORDANCE WITH TINSW AND LOCAL AUTHORITY REGULATIONS AND REQUIREMENTS.
- THE CONTRACTOR IS TO OBTAIN ALL AUTHORITY APPROVALS AS
- RESTORE ALL PAVED, COVERED, GRASSED AND LANDSCAPED AREAS TO THEIR ORIGINAL CONDITION ON COMPLETION OF WORKS.
- 6. ON COMPLETION OF ANY TRENCHING WORKS, ALL DISTURBED AREAS SHALL BE RESTORED TO THEIR ORIGINAL CONDITION, INCLUDING KERBS. FOOTPATHS, CONCRETE AREAS, GRAVEL, GRASSED AREAS AND ROAD PAVEMENTS.
- THE CONTRACTOR SHALL ARRANGE ALL SURVEY SETOUT TO BE CARRIED OUT BY A REGISTERED SURVEYOR.
- 8. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO LODGMENT OF TENDER AND ON SITE WORKS. THE PRICE AS TENDERED SHALL BE INCLUSIVE OF ALL WORKS SHOWN ON THE TENDER PROJECT DRAWINGS. ADDITIONAL PAYMENTS FOR WORKS SHOWN ON THE TENDER PROJECT DRAWINGS WILL NOT BE APPROVED.
- THESE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH THE ENGINEERING PLANS AND SPECIFICATIONS, AND ANY OTHER WRITTEN INSTRUCTIONS THAT MAY BE ISSUED RELATING TO DEVELOPMENT OF THE SUBJECT SITE.
- 10. THESE PLANS SHALL BE READ IN CONJUNCTION WITH ALL APPROVED DRAWINGS AND SPECIFICATIONS PREPARED BY OTHER PROJECT CONSULTANTS.
- 11. DO NOT OBTAIN DIMENSIONS BY SCALING THE DRAWINGS. ALL DIMENSIONS ARE IN MILLIMETERS (mm) AND ALL LEVELS ARE IN METRES (m), UNO. ALL LEVELS ARE TO AUSTRALIAN HEIGHT DATUM (AHD).
- 12. IN CASE OF DOUBT OR DISCREPANCY REFER TO THE SUPERINTENDENT FOR CLARIFICATION OR CONFIRMATION PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. OTHERWISE THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE COST OF REMEDIATION WORKS.
- 3. WHERE NEW WORKS ABUT EXISTING THE CONTRACTOR SHALL ENSURE THAT A SMOOTH EVEN PROFILE, FREE FROM ABRUPT CHANGES IS OBTAINED.
- 14. THE CONTRACTOR SHALL COMPLY WITH ALL STATUTORY AND INDUSTRIAL REQUIREMENTS FOR PROVISION OF A SAFE WORKING ENVIRONMENT INCLUDING TRAFFIC CONTROL.
- 5. THE CONTRACTOR SHALL ENSURE THAT AT ALL TIMES ACCESS TO ALL BUILDINGS ADJACENT THE WORKS IS NOT DISRUPTED.
- 16. WHERE NECESSARY THE CONTRACTOR SHALL PROVIDE SAFE PASSAGE OF VEHICLES AND/OR PEDESTRIANS THROUGH OR BY THE SITE.
- 17. WHERE NOTED ON THE DRAWINGS THAT WORKS ARE TO BE CARRIED BY OTHERS, (eg. ADJUSTMENT OF SERVICES), THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CO-ORDINATION OF THESE WORKS.
- 18. ALL VARIATIONS TO SPECIFIED PRODUCTS OR DESIGNS SHALL BE REFERRED TO THE DESIGN ENGINEER IN WRITING FOR APPROVAL.
- 19. EPA AND COUNCIL REQUIREMENTS MUST BE ADHERED TO REGARDING THE LEVEL OF NOISE AND WORKING HOURS, TO ENSURE THAT RESIDENTS AND OTHER APPLICABLE NEIGHBOURS TO THE SITE ARE NOT DISTURBED UNREASONABLY. THE GENERATION OF NOISE MUST BE MINIMISED.

# STORMWATER DRAINAGE

- 1. ALL INTERNAL WORKS WITHIN PROPERTY BOUNDARIES ARE TO COMPLY WITH THE REQUIREMENTS OF AS 3500 3.1 AND AS/NZS 3500
- 2. SUBSOIL DRAINAGE LINES SHALL BE INSTALLED BEHIND ALL KERBS EXCEPT WHERE STORMWATER DRAINAGE IS LOCATED ALONG THE KERBLINE.
- 3. A MINIMUM OF 3m OF SUBSOIL LINE SHALL BE LAID INTO UPSTREAM
- SIDE OF ALL DRAINAGE PITS. 4. FLUSHING POINTS SHALL BE INSTALLED TO COUNCIL SPECIFICATION.
- 5. PIPES UP TO 300 DIA SHALL BE SEWER GRADE uPVC (CLASS SN4) WITH SOLVENT WELDED JOINTS.
- 6. PIPES 375 DIA. AND LARGER TO BE REINFORCED CONCRETE MIN CLASS '2' APPROVED SPIGOT AND SOCKET WITH RUBBER RING JOINTS. U.N.O.
- 7. ALL PIPES ARE TO BE LAID AT (min) 1.0% GRADE (UNO)
- 8. ALL PIPES ARE TO BE UNIFORMLY SUPPORTED ALONG THE LENGTH OF THE BARREL BY SUITABLE FILL MATERIAL. REFER TO BEDDING SUPPORT TYPE.
- 9. PIPES WITH SOCKETS SHALL BE LAID IN BEDDING WHERE SUITABLE RECESSES HAVE BEEN PROVIDED TO ENSURE PIPES DO NOT BEAR ON THEIR SOCKETS.
- 10. ENLARGERS, CONNECTIONS AND JUNCTIONS TO BE PREFABRICATED FITTINGS WHERE PIPES ARE LESS THAN 300 DIA.
- 11. ALL STORMWATER DRAINAGE LINES UNDER PROPOSED BUILDING SLABS TO BE uPVC PRESSURE PIPE GRADE
- 12. ENSURE ALL VERTICALS AND DOWNPIPES ARE uPVC PRESSURE PIPE, GRADE 6 FOR A MIN OF 3.0m IN HEIGHT.
- 13. WHERE WORKING METHODS REQUIRE HIGHER CLASS PIPE, THE CONTRACTOR SHALL REFER TO AS 3725 TO DETERMINE THE APPROPRIATE PIPE CLASS. ANY CHANGES IN PROPOSED PIPE CLASS SHALL BE SUBMITTED TO THE SUPERINTENDENT FOR APPROVAL PRIOR TO INSTALLATION.
- 14. CARE IS TO BE TAKEN WITH LEVELS OF STORMWATER LINES. GRADES SHOWN ARE NOT TO BE REDUCED WITHOUT APPROVAL.
- 15. PRECAST PITS MAY BE USED SUBJECT TO WRITTEN APPROVAL BY THE SUPERINTENDENT.
- 16. ALL PIPE PENETRATIONS (EXISTING, IN-SITU AND PRECAST) ARE TO BE FINISHED FLUSH WITH THE INTERNAL PIT WALL AND PROPERLY SEALED WITH CEMENT RENDER. MASS CONCRETE BENCHING IS TO BE INSTALLED TO MATCH THE OUTLET PIPE INVERT LEVEL AND A LOCKABLE HINGED GRATE AND FRAME WITH CONCRETE SURROUND INSTALLED U.N.O.

- USE HOT DIPPED GALVANISED GRATES AND CONCRETE FILLED COVERS WITH HINGES AND HOLD DOWN BOLTS COMPLYING WITH AS3996 AND OTHER RELEVANT AUSTRALIAN AND COUNCIL STANDARDS.
- ALL COVERS AND GRATES TO BE POSITIONED IN A FRAME AND MANUFACTURED AS A UNIT.
- ALL COVERS AND GRATES TO BE FITTED WITH POSITIVE
- COVER LIFTING KEYS. OBTAIN SUPERINTENDENT'S APPROVAL FOR THE USE OF CAST IRON SOLID COVERS AND GRATES, CAST IRON SOLID COVERS (IF APPROVED) TO CONSIST OF CROSS-WEBBED, CELLULAR CONSTRUCTION WITH THE RIBS UPPERMOST TO ALLOW INFILLING WITH CONCRETE. INSTALL POSITIVE COVER LIFTING KEYS AND PLASTIC
- UNLESS DETAILED OR SPECIFIED OTHERWISE COVERS AND GRATES TO BE CLASS "D" IN VEHICULAR PAVEMENTS AND CLASS "B" ELSEWHERE.
- 18. NOTE THAT THE PIT COVER LEVEL NOMINATED IN GUTTERS ARE TO THE INVERT OF THE GUTTER WHICH IS 40mm LOWER THAN THE PAVEMENT LEVEL AT LIP OF GUTTER.
- 19. Ø100mm SUB-SOIL DRAINAGE LINES SHALL BE CONNECTED TO A STORMWATER DRAINAGE PIT AND PROVIDED IN THE FOLLOWING
- LOCATIONS: A. ADJACENT ALL TRAFFICKED AND CARPARK PAVEMENT AREAS (BEHIND KERB);
- ALL PLANTER AND TREE BEDS PROPOSED ADJACENT TO PAVEMENT AREAS; BEHIND RETAINING WALLS (IN ACCORDANCE WITH
- DRAWINGS): BELOW ALL TRAFFICABLE DISH DRAINS; ALL OTHER AREAS SHOWN ON THE DRAWINGS.
- 20. THE CONTRACTOR SHALL INSTALL FLUSHING POINTS TO ALL SUBSOIL DRAINAGE LINES AND DOWNPIPE LINES AS SPECIFIED ON DRAWINGS, AT MAXIMUM CENTRES TO COUNCIL SPECIFICATION AND AT ALL UPSTREAM ENDPOINTS.
- 21. PROVIDE 3.0m LENGTH OF Ø100 SUBSOIL DRAINAGE PIPE WRAPPED IN A NON-WOVEN GEOTEXTILE FABRIC, TO THE UPSTREAM SIDE OF STORMWATER PITS, LAID IN STORMWATER PIPE TRENCHES AND CONNECTED TO THE DRAINAGE PIT.
- 22. SUBSOIL TRENCHES SHALL BE BACKFILLED WITH SINGLE SIZED 10mm AGGREGATE WRAPPED IN NON-WOVEN GEOTEXTILE FABRIC. SUBSOIL TRENCHES BELOW TRAFFICABLE PAVEMENTS SHALL BE BACKFILLED WITH NO FINES CONCRETE WRAPPED IN NON-WOVEN GEOTEXTILE FABRIC, U.N.O.
- 23. ALL RECTANGULAR HOLLOW SECTIONS (RHS) SPECIFIED AS STORMWATER CONDUITS TO BE HOT DIPPED GALVANISED AND HAVE (MINIMUM) 5mm WALL THICKNESS.

# STORMWATER DRAINAGE (CONT.)

- 24. ALL BOX CULVERTS SHALL BE STRUCTURALLY DESIGNED BY THE MANUFACTURER AND DELIVERED TO SITE AS FIT FOR PURPOSE.
- 25. ELECTRICAL PITS ARE TO DRAIN TO THE NEAREST STORMWATER PIT WITH VERMIN PROOF NON-RETURN FLAP VALVES AS REQUIRED. THE CONTRACTOR IS TO CONFIRM WITH THE ELECTRICAL DESIGNER AS PART OF THE TENDER.
- 26. THE CONTRACTOR SHALL ENSURE AND PROTECT THE INTEGRITY OF ALL STORMWATER PIPES DURING CONSTRUCTION. ANY AND ALL DAMAGE TO THESE PIPES AS A RESULT OF THESE WORKS SHALL BE REPAIRED BY THE CONTRACTOR UNDER THE DIRECTION OF THE SUPERINTENDENT, AND AT NO EXTRA COST.
- 27. AT ALL TIMES DURING CONSTRUCTION OF STORMWATER PITS, ADEQUATE SAFETY PROCEDURES SHALL BE TAKEN TO ENSURE AGAINST THE POSSIBILITY OF PERSONNEL FALLING DOWN PITS.
- 28. ALL EXISTING STORMWATER DRAINAGE LINES AND PITS THAT ARE TO REMAIN ARE TO BE INSPECTED AND CLEANED. DURING THIS PROCESS ANY PART OF THE STORMWATER DRAINAGE SYSTEM THAT WARRANTS REPAIR SHALL BE REPORTED TO THE SUPERINTENDENT/ENGINEER FOR FURTHER DIRECTIONS.
- 29. ANY VARIATION TO SPECIFIED PRODUCTS OR DETAILS SHALL BE REFERRED TO THE SUPERINTENDENT FOR APPROVAL.

# **PAVEMENTS**

- ALL PAVEMENT MATERIALS SHALL COMPLY WITH CURRENT TINSW SPECIFICATIONS. PROVIDE MECHANICAL ANALYSIS FOR EACH BATCH OF PAVEMENT MATERIAL TO ENSURE CONFORMITY.
- 2. COMPACTION STANDARDS:

CONTACT THE SUPERINTENDENT.

- BASE: 98% MODIFIED MAXIMUM DRY DENSITY SUBBASE: 98% MODIFIED MAXIMUM DRY DENSITY
- THE CONTRACTOR SHALL CONFIRM THE DESIGN CBR WITH A MINIMUM OF 3 TESTS TAKEN AT SUBGRADE LEVEL. WHERE DISCREPANCY IS FOUND,
- . ALLOW FOR COMPACTION TESTING BY NATA REGISTERED LABORATORY FOR: BASE LAYER, SUBBASE LAYER, SUBGRADE IN ACCORDANCE WITH THE LATEST VERSION OF AS3798 FOR PAVEMENTS. ALLOW FOR AT LEAST TWO SUCCESSFUL COMPACTION TESTS IN EACH LAYER.
- MATCH NEW PAVEMENT LAYERS NEATLY AND FLUSH WITH EXISTING WHERE REQUIRED.
- . KEY NEW BASE AND SUBBASE LAYERS INTO EXISTING WITH 150mm WIDE STEPS, ASPHALTIC CONCRETE WEARING COURSE IS TO EXTEND 150mm (MIN) PAST BASECOURSE INTERFACE.
- TRENCHES THROUGH EXISTING ROAD AND CONCRETE PAVEMENTS SHALL BE SAWCUT TO FULL DEPTH OF CONCRETE AND A MIN 50mm IN BITUMINOUS PAVING.
- B. ALL ASPHALTIC CONCRETE (AC) WORK TO BE PREPARED AND CARRIED OUT IN ACCORDANCE WITH GOOD ASPHALTIC PAVING PRACTICE AS DESCRIBED IN AS2734 "ASPHALT (HOT-MIXED) PAVING - GUIDE TO GOOD PRACTICE" AND CURRENT THISW SPECIFICATIONS (R116).
- . WHERE NOMINATED, THE CONTRACTOR SHALL ALLOW FOR ALL COMPONENTS OF PROPRIETARY JOINTING SYSTEMS INCLUDING FIXING. TEMPLATES & PEGGING TO ENSURE THAT ALL DOWEL BARS REMAIN IN THE CORRECT ALIGNMENT AND POSITION.
- 10. ALL BASECOURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH TINSW. SPECIFICATION 3051, COMPACTED TO MINIMUM 98% MODIFIED DENSITY IN ACCORDANCE WITH AS 1289 5.2.1 FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m3 OF BASECOURSE MATERIAL PLACED.
- 1. ALL SUB-BASE COURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH TINSW. SPECIFICATION 3051, AND COMPACTED TO MINIMUM 98% MODIFIED DENSITY IN ACCORDANCE WITH A.S 1289 5.2.1 FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m3 OF SUB-BASE COURSE MATERIAL PLACED.
- 2. AS AN ALTERNATIVE TO THE USE OF IGNEOUS ROCK AS A SUB-BASE MATERIAL IN (11) A CERTIFIED RECYCLED CONCRETE MATERIAL COMPLYING WITH TINSW. SPECIFICATION 3051 WILL BE CONSIDERED. SUBJECT TO MATERIAL SAMPLES AND APPROPRIATE CERTIFICATIONS BEING PROVIDED TO THE SATISFACTION OF THE COUNCIL ENGINEER.
- 3. SHOULD THE CONTRACTOR WISH TO USE A RECYCLED PRODUCT THIS SHALL BE CLEARLY INDICATED IN THEIR TENDER AND THE PRICE DIFFERENCE BETWEEN AN IGNEOUS PRODUCT AND A RECYCLED PRODUCT SHALL BE CLEARLY INDICATED.

28/06/2024 ISSUED FOR DEVELOPMENT APPLICATION SS | TPB | RLE | MC DESCRIPTION DRN. DES. VERIF. APPI V. DATE



Enspire Solutions Pty Ltd

Level 4, 153 Walker Street, North Sydney NSW 2060 The copyright of this drawing remains with Enspire Solutions Pty Ltd and must not be copied wholly or in part ABN: 71 624 801 690 Phone: 02 9922 6135

53A & 53B WARRIEWOOD ROAD WARRIEWOOD NSW 2102 VIL ENGINEERING WORKS SPECIFICATION NOTES

28/06/2024

FOR INFORMATION ONLY NOT TO BE USED FOR CONSTRUCTION


220122-00-DA-C01.21


CAD File: P:\220122 WarriewoodRd\D-Civil\00-SiteWide\Drawings\6-DACC\1 - DA\220122-00-DA-C01.21 SPECIFICATION NOTES.dwg


oject Number/Drawing Number


N.T.S

MGA2020










# TEMPORARY CONSTRUCTION EXIT (SHAKER PAD DETAIL)

THE EXIT SHALL BE MAINTAINED IN A CONDITION WHICH PREVENTS TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS OF WAY. THIS MAY REQUIRE REPAIR AND OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS OF WAY MUST BE REMOVED IMMEDIATELY.




# CONSTRUCTION NOTES

- 1. FABRICATE A SEDIMENT BARRIER MADE FROM GEOTEXTILE OR STRAW BALES.
- 2. FOLLOW STANDARD DRAWING 6-7 AND STANDARD DRAWING 6-8 FOR INSTALLATION PROCEDURES FOR THE STRAW BALES OR GEOFABRIC. REDUCE THE PICKET SPACING TO 1 METRE CENTRES.
- 3. IN WATERWAYS, ARTIFICIAL SAG POINTS CAN BE CREATED WITH SANDBAGS OR EARTH BANKS AS SHOWN IN THE DRAWING.
- 4. DO NOT COVER THE INLET WITH GEOTEXTILE UNLESS THE DESIGN IS ADEQUATE TO ALLOW FOR ALL WATERS TO BYPASS IT.

# GEOTEXTILE INLET FILTER (SD 6-12)


DRN. DES. VERIF. APPO




# **CONSTRUCTION NOTES**

- 1. PLACE STOCKPILES MORE THAN 2m (PREFERABLY 5m) FROM EXISTING VEGETATION, CONCENTRATED WATER FLOW, ROADS AND HAZARD AREAS.
- 2. CONSTRUCT ON THE CONTOUR AS LOW, FLAT, ELONGATED MOUNDS.
- 3. WHERE THERE IS SUFFICIENT AREA, TOPSOIL STOCKPILES SHALL BE LESS THAN 2m IN HEIGHT.
- 4. WHERE THEY ARE TO BE IN PLACE FOR MORE THAN 10 DAYS, STABILISE FOLLOWING THE APPROVED ESCP OR SWMP TO REDUCE THE C-FACTOR TO LESS THAN 0.10.
- 5. CONSTRUCT EARTH BANKS (STANDARD DRAWING 5-5) ON THE UPSLOPE SIDE TO DIVERT WATER AROUND STOCKPILES AND SEDIMENT FENCES (STANDARD DRAWING 6-8) 1 TO 2m DOWNSLOPE.

# STOCKPILES (SD 4-1)



# SEDIMENT TRAP FOR KERB INLET (AT LOW POINT - SANDBAG) NOT TO SCALE



# SEDIMENT TRAP FOR KERB INLET (ON GRADE - SANDBAG)

NOT TO SCALE

Scale

O 0.5 1 1.5 2m

SCALE 1:20

Characteristics of this drawing remains with Enspire Solutions Pty Ltd and must not be copied wholly or in part without the permission of Enspire Solutions Pty Ltd.

North

Enspire Solutions Pty Ltd and must not be copied wholly or in part without the permission of Enspire Solutions Pty Ltd.

North

Enspire Solutions Pty Ltd and must not be copied wholly or in part without the permission of Enspire Solutions Pty Ltd.

Phone: 02 9922 6135



Project
53A & 53B WARRIEWOOD ROAD
WARRIEWOOD NSW 2102
CIVIL ENGINEERING WORKS


Title
EROSION AND SEDIMENTATION CONTROL DETAILS

Scale
N.T.S
Date
28/06/2024

Status
FOR INFORMATION ONLY
NOT TO BE USED FOR CONSTRUCTION

Size
Project Number/Drawing Number
220122-00-DA-C03.21

1




CONSTRUCTION NOTES

- 1. CONSTRUCT SEDIMENT FENCES AS CLOSE AS POSSIBLE TO BEING PARALLEL TO THE CONTOURS OF THE SITE, BUT WITH SMALL RETURNS AS SHOWN IN THE DRAWING TO LIMIT THE CATCHMENT AREA OF ANY ONE SECTION. THE CATCHMENT AREA SHOULD BE SMALL ENOUGH TO LIMIT WATER FLOW IF CONCENTRATED AT ONE POINT TO 50 LITRES PER SECOND IN THE DESIGN STORM EVENT, USUALLY THE 10-YEAR EVENT.
- 2. CUT A 150mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE
- ENTRENCHED.

  3. DRIVE 1.5 METRE LONG STAR PICKETS INTO GROUND AT 2.5 METRE INTERVALS (MAX) AT THE DOWNSLOPE EDGE
- OF THE TRENCH. ENSURE ANY STAR PICKETS ARE FITTED WITH SAFETY CAPS.


  4. FIX SELF-SUPPORTING GEOTEXTILE TO THE UPSLOPE SIDE OF THE POSTS ENSURING IT GOES TO THE BASE OF THE TRENCH. FIX THE GEOTEXTILE WITH WIRE TIES OR AS RECOMMENDED BY THE MANUFACTURER. ONLY USE GEOTEXTILE SPECIFICALLY PRODUCED FOR SEDIMENT FENCING. THE USE OF SHADE CLOTH FOR THIS PURPOSE IS NOT SATISFACTORY.
- 5. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150mm OVERLAP.
- 6. BACKFILL THE TRENCH OVER THE BASE OF THE FABRIC AND COMPACT IT THOROUGHLY OVER THE GEOTEXTILE.

# SEDIMENT FENCE (SD 6-8)



DESCRIPTION

V. DATE



1/07/2024 ISSUED FOR DEVELOPMENT APPLICATION

DESCRIPTION


DRN. DES. VERIF. APPD


EV. DATE



- NO ALLOWANCE HAS BEEN MADE FOR BULKING FACTORS. NOTE ALL VOLUMES DEPICTED ARE SOLID VOLUMES ONLY AND MAY NOT REFLECT DETAILED EARTHWORKS.
- NO ALLOWANCE HAS BEEN MADE FOR DETAILED EARTHWORKS. ie SERVICE TRENCHING, DETAILED EXCAVATION AND THE LIKE.
- APPROXIMATE BULK EARTHWORKS VALUES AS FOLLOWS;
  - CUT 2,787m<sup>3</sup> FILL 15,079m<sup>3</sup>
- BALANCE 12,292m<sup>3</sup> (IMPORT) 4. VOLUMES BASED ON;
- EXISTING SURFACE STRIPPED 200mm. PRELIMINARY BULK EARTHWORKS SURFACE
- 400mm BELOW ULTIMATE DESIGN LEVELS. EXCAVATED MATERIAL TO BE ASSESSED DURING
- DETAILED DESIGN TO CONFIRM STABILITY FOR REUSE ON SITE.


MGA2020





# LONGITUDINAL SECTION C HORIZONTAL SCALE 1:500@A1

VERTICAL SCALE 1:100@A1



# PRELIMINARY BULK SURFACE ROAD 01 ULTIMATE DESIGN LEVEL PHEASANT PLACE EXISTING SURFACE STRIPPED DATUM RL -2.0 **EXISTING SURFACE** BULK SURFACE CHAINAGE

# LONGITUDINAL SECTION D HORIZONTAL SCALE 1:500@A1

VERTICAL SCALE 1:100@A1


LONGITUDINAL SECTION E HORIZONTAL SCALE 1:500@A1

VERTICAL SCALE 1:100@A1


SS TPB RLE MC DRN. DES. VERIF. APPD. 1 28/06/2024 ISSUED FOR DEVELOPMENT APPLICATION REV. DATE DESCRIPTION



Scale								North
	H:	0	10	2	20 30	) 40	50m	
	V:	0 SCALE:	2 H:1:500	V:1:100	4 6	8	10m @A1	



Project Son MARRIENICOR ROAD	Scale	Status	
53A & 53B WARRIEWOOD ROAD	AS SHOWN	FOR INFORMATION ONLY	
WARRIEWOOD NSW 2102 CIVIL ENGINEERING WORKS	Date 28/06/2024	NOT TO BE USED FOR CONSTRUCTION	
Title	Size	Project Number/Drawing Number	Revision
BULK EARTHWORKS	A1	220422 00 DA CO4 22	1 4
CUT AND FILL SECTIONS	Datum	220122-00-DA-C04.22	
SHEET 02	MGA2020		





CATCHMENT AREA = 1.654 ha LGA = NORTHERN BEACHES COUNCIL REGION = NORTHERN STORMWATER REGION 1.

# A - WATER QUANTITY

- OSD REQUIRED IN ACCORDANCE WITH COUNCIL'S WATER
- MANAGEMENT FOR DEVELOPMENT POLICY REFER DRAINS MODEL BY ENSPIRE SOLUTIONS FOR DETAILS.

STORM EVENT		POST-DEVELOPMENT FLOWS (m³/s)
20% AEP	0.509	0.487
5% AEP	0.717	0.631
1% AEP	0.921	0.777

# **B-WATER QUALITY**

WATER QUALITY REQUIREMENTS IN ACCORDANCE WITH NORTHERN BEACHES COUNCIL WATER MANAGEMENT FOR DEVELOPMENT POLICY.

POLLUTANT	TARGET	REDUCTION
GP	90%	96%
TSS	85%	85%
TP	65%	65%
TN	45%	51.1%


- 2. WATER QUALITY TREATMENT PROVIDED BY:
- 2.1. PROPRIETARY FILTER CARTRIDGES SYSTEM LOCATED WITHIN OSD/WATER QUALITY TANKS.
- OCEAN SAVE PIT BASKETS.
- RAINWATER TANKS IN FUTURE RESIDENTIAL LOTS.
- 3. REFER MUSIC MODEL PREPARED BY ENSPIRE SOLUTIONS FOR DETAILS.
- 4. FILTER CARTRIDGE SYSTEM TO BE INSTALLED AFTER 80% OF CATCHMENT IS DEVELOPED.


# C - FLOOD STORAGE

- 1. FLOOD STORAGE HAS BEEN MAINTAINED AS PART OF THIS DEVELOPMENT AS FOLLOWS:
- PEAK SURFACE WATER LEVELS AS PER C&R WATER MANAGEMENT REPOR


STORM EVENT	EXISTING	PROPOSED
20% AEP	2001m <sup>3</sup>	3104m <sup>3</sup>
5% AEP	3303m <sup>3</sup>	3908m <sup>3</sup>
1% AEP	4736m <sup>3</sup>	4664m <sup>3</sup>










without the permission of Enspire Solutions Pty Ltd.





WARRIEWOOD NSW 2102 NOT TO BE USED FOR CONSTRUCTION **CIVIL ENGINEERING WORKS** 06/05/2024 SITEWORKS AND STORMWATER MANAGEMENT PLAN 220122-00-DA-C05.01 MGA2020 SHEET 01


































TURN PATH 01 -12.5m HEAVY RIGID VEHICLE






VEHICLE PROFILE:


12.50

CHECKING VEHICLE












		Proje
		53 <i>P</i>
	enshire	WA
		CIV
		Title
	Enspire Solutions Pty Ltd	TUI
	Level 4, 153 Walker Street, North Sydney NSW 2060	
t	ABN: 71 624 801 690	
	Phone: 02 9922 6135	SHI


ect A & 53B WARRIEWOOD ROAD	Scale 1:200
RRIEWOOD NSW 2102 /IL ENGINEERING WORKS	Date 01/07/202
RNING PATH PLAN	Size A1
FFT 02	Datum MGA2020

FOR INFORMATION ONLY NOT TO BE USED FOR CONSTRUCTION 220122-00-DA-C22.02











VEHICLE PROFILE:


CHECKING VEHICLE

TURN PATH 04 -12.5m HEAVY RIGID VEHICLE SCALE 1:200











	Pr
	53
enshire	W
	С
	Tit
Enspire Solutions Pty Ltd	ті
Level 4, 153 Walker Street, North Sydney NSW 2060	l ' '
ABN: 71 624 801 690	

Phone: 02 9922 6135


	Project	Scale	Status
	53A & 53B WARRIEWOOD ROAD	1:200	FOR
7	WARRIEWOOD NSW 2102	Date	
	CIVIL ENGINEERING WORKS	01/07/2024	NOT TO
	Title	Size	Project Number/Drawing
	TURNING PATH PLAN	A1	220420
		Datum	220122
	SHEET 03	MGA2020	




TURN PATH 05 -12.5m HEAVY RIGID VEHICLE





TURN PATH 05 -12.5m HEAVY RIGID VEHICLE
















Project	Scale	Status	
53A & 53B WARRIEWOOD ROAD	1:200	FOR INFORMATION ONLY	
WARRIEWOOD NSW 2102	Date		
CIVIL ENGINEERING WORKS	01/07/2024	NOT TO BE USED FOR CONSTRUCTION	
Title	Size	Project Number/Drawing Number	Revision
TURNING PATH PLAN	A1	000400 00 DA 000 04	
	Datum	220122-00-DA-C22.04	1
SHEET 04	MGA2020		
CAD File: D/\220122 \West	overadDd/D Civil\00	CitalMidalDrawingalC DACC/1 DA/220122 00 DA C22 01 TUDNING DAT	TH DLAN due







LORIKEET GROVE **EXTENSION** GROUND FLOOR PLAN LOT 12 COMMUNITY ROAD <u>N</u> (LOT 1)

> THREE

DELICE ..... CONSENT PLANS

NOTE: THESE PLAN THESE PLANT NUST BE READ IN CONDITIONS OF

Figure 8

HOUSING DETAIL GROUND FLOOR

LOT 105 LORIKEET GROVE

DATE 2 SEPT 2010 PLAN NO 22441/HD 1

The builder shall check and verify all dimensions and service and verify of arrors and developes to the Architect. Do not used the of everige. Thereings shall not be used for counter-unders purposes until seased by the Architect for communion.

BSC LICENCE NO 20338
UNIX 25 NO 11 Romford Rd
Kings Park, NSW 2148
Telephone (02) 9671 8880
Facsimite (02) 9671 4331

Link Tow to

LEGEND
symbol description
1 timeters high fending


ABAX Contracting
Reset New
Integrated Housing Development
AT THE REPOSED SUBDIVISION OF PROPOSED OF LOT LIS IN A
SUBDIVISION OF LOT 1 DF 1115977 WARRENTOOD ROAD
WARRENTOOD GROUND FLOOR LAYOUT GROUND FLOOR PLAN Scale as noted Checked By

2010 137

4of17A

Legart No

REVISION A 28/8/2019 lleira NEW GENERATION



PILL COUNCIL

CONSENT PLANS 

ICHON WILL ... E CONDITIONS OF THE PI WIST BE READ IN **DEVELOPMENT CONSENT** 

Figure 8

HOUSING DETAIL FIRST FLOOR

LOT 105 LORIKEET GROVE

DATE 2 SEPT 2010 PLAN NO 22441/HD 2


BSC LICENCE No. 20238
Unik 25 No. 11 Romford Rd
Kings Park, NSW 2148
Telephone (02) 9571 4331
Telephone (02) 9571 4331
Telephone (02) 9571 4331

If works to be set out by regetered surveyor

ABAX Contracting
ABAX Contracting
Project Name
Integrated Housing Development
AT THE PICTORED SUBDINISTIN OF PROPOSED LOT 105 IN A
SUBDINISTIN OF 107 1 DP 1115877 WARRIEWOOD ROAD
WHARREWOOD FIRST FLOOR LAYOUT
FIRST FLOOR PLAN

2010 137 Stetu DA 5of17A On chand By Layout No

A NEW GENERATION Omes




REVISION A 28/8/2010 Provide rannels tanks 3000for

LEIVA


omes

GENERATION

1 STREETSCAPE ROAD Not



STREET SCAPE ROAD No!



CONJUNCTION WITH THE CONDITIONS OF DEVELOPMENT CONSENT APPROVED DEVELOPMENT CONCE VELOPILLAT CONSENT PLANS Figure ဖ

LOT 105 LORIKEET GROVE STREETSCAPES

DATE 2 SEPT 2010 PLAN NO 22441/SS

The builder shall check and warfy all dissertances and levels and warfy all enters and cheapons to the Architect. Do not soile the dissertance. Or serve the not be used for orestruction purposes until seased by the Architect for constitution.

BSC LICENCE NO 20388
Unit 25 No 11 Romford Rd
Kings Park, NSW 2148
Telephone (92) 9671 4880
Facslimite (92) 9671 4331

ABAX Contracting
ABAX Contracting
Provide Mann
Integrated Housing Development
AT THE ROPOSED SUBDIVISION OF PROPOSED LOT 105 IN A
SUBDIVISION OF LOT 1 DP 1115977 WARRIEWOOD ROAD
WARRIEWOOD

Status DA Proped No 2010 137 LORIKEET GROVE Craming Tile ELEVATIONS STREETSCAPE STREETSCAPE-ROAD Not STREETSCAPE Checked By Layout No

60f17A









Table of Materials & Finishes
cement rendered & painted brickwork
concrete rppf tiles as selected
aluminium framed windows as selected
stainless steel balustrade as selected to comply with BCA requirements
aluminium framed sliding door as selected
cement rendered & painted blueboard cladding
colorbond capping
aluminium framed silicone joined corner windows
aluminium framed glazed swing door as selected
metal deck roof sheeting as selected installed to manufacturers specifications
sheet flooring on timber floor joists to manufacturers specifications
sheet flooring on timber floor joists to manufacturers specifications
plasterboard wall & ceiling lining
selected timber entry door with glazed panels & aluminium framed highlight & sidelight
reinforced concrete slab to engineers details
blueboard lined timber awnings cement rendered & painted finish
aluminium framed bi-fold doors as selected











The builder shall check and werky all dimensions and levels and werity all errors and omissions to the Architect. Do not scale the drawings. Drawings shall not be used for construction purposes until issued by the Architect for construction.

10872

Cert# 86906350



NEW RIVA

GENERATION

OMES

# **BASIX Commitments DW2**

WATER FIXTURES: Showerheads Rating: Toilet Flushing System: Kitchen Tag Fittings:	ALTERNATIVE WATER: Rain Water Tank Volume: Roof Area Connected to Tank: Rainwater Usages: Remainder of Roof Water to Easement: Hydrauk: Design System Required:	PROJECT DETAILS:  No. Bedrooms: Conditioned Floor Area: Unconditioned Floor Area: Roof Area: Garden & Jawn Area:	SITE DETAILS: Lot No: DP Number: Site Area:
3 Star (Min.) 4 Star (Min.)	3090 L 279,19m² Toilets, One Outdoor Tap & Laundry Yes Yes	4 142.08m² 15.23m² 279.15m² 165.05m²	331814M 3 1115877 620.10m <sup>2</sup>

ENERGY:
Hot Water System:
3 Phase Air Conditionage (SER à 5-3.9)
Verillation:
\*Fan Durett in Faculo(Roof (Manual Switch))
Water All Verillation:
\*Fan Durett in Faculo(Roof (Manual Switch))
Water al Upitring:
Water all Upitring:
Water al Upitring:
Water all Upitring: THERMAL COMFORT:

External Wall & Floor Specifications:

Bick Vener

Brack Vener

Brack Vener

Brack Celling Specifications:

R4.0 (Foll/Swining & R1.5 Foll + Batts)

Internal Walls:

R1.5 (Garage Wall Only)

Whotows Gaared Doors & Syrlights:

W9-20, 22-26 Improved Aluminium Single Clean(SHGC: 0.77 U-Value: 6.35)


W1-5, 21-22 Improved Aluminium Low e (SHGC: 0.47 U-Value: 4.32) Basin Tap Fittings: 4 Star (Min.) 4 Star (Min.)


NOTE: THESE PLANS MUST BE READ IN CTION WITH THE COMDITIONS OF Yes Yes Gas Cooktop & Bectric Oven


SOUTH WESTERN ELEVATION LOTS 2 & 3 1:200 I.L. New & Associates MBDA, NSW BSC LICENCE No. 20388
Unit 25. No. 11 Romford Rd Kings Park, NSW 2148
Telephone: (02) 9671 4331


Designon Association Facsimile: (02) 9671 4331 WESTERNAME VATION LOTS 2 & 3, NORT BASSEAR ELEVATION LOTS 2 & 3, SECT Drawing Title
- LOTS 2 & 3
SOUTH WESTERN ELEVATION LOTS 2 & 3, Integrated Housing Development
AT: THE PROPOSED SUBDIVISION OF PROPOSED LOT 105 IN A ABAX Contracting SOUTH EASTERN ELEVATION, NORTH DIVISION OF LOT 1 DP 1115877 WARRIEWOOD ROAD,


2010:137 8of17A(a3)































Table of Materials & Finishes
cement rendered & painted brickwork
concrete rppf tiles as selected
aluminium framed windows as selected
stainless steel balustrade as selected to comply with BCA requirements
aluminium framed sliding door as selected
cement rendered & painted blueboard cladding
colorbond capping
aluminium framed silicone joined corner windows
aluminium framed glazed swing door as selected
metal deck roof sheeting as selected installed to manufacturers specifications
sheet flooring on timber floor joists to manufacturers specifications
sheet flooring on timber floor joists to manufacturers specifications
sleeted timber entry door with glazed panels & aluminium framed highlight & sidelight
reinforced concrete slab to engineers details
blueboard lined timber awnings cement rendered & painted finish
aluminium framed bi-fold doors as selected

3

20 30

100

length in millimeters at full size

ä



REVISION A 28/8/2010 Provide rainwater tanks 3000litre

lkira NEW

GENERATION omes

DEF THESE PLANS Mary and Mar ENTRY ON SENTENCE TO SNOTTIONS OF MUST BE READ HE

NORTH EASTERN ELEVATION LOTS 11 & 12/

1 200

- 2012 L -

SETT COT

- MES 121

The builder shall check and verify all dimensions and levels and verify all errors and ornszors to the levels and verify all errors and ornszors to the Architect. Do not scale the drawings. Drewings shall not be used tire construction purposes until issued by the Architect for construction

orise to be set out by registered surveyor

BSC LICENCE No 20388
Unit 25 No 11 Romford Rd
Kings Park, NSW 2148
Telephone (02) 9671 6880
Facsimile (02) 9671 4331

NORTH EASTERN ELEVATION LOTS 11 & 12
SCHOTHERSTERN ELEVATION NORTH

PRESTERN ELEVATION Story

Chocked By Drawing Tife
LOT 11 & 12
SOUTHWESTERN ELEVATION LOTS 11 & 12 Drawing No


2010 137


17of17A(a3


Integrated Housing Development
AT THERROOSED SUBDIVISION OF PROPOSED FOT 105 IN A
SUBDIVISION OF 107 1 DP 1115877 WARRIEMOOD ROAD
WARRIEMOOD

ABAX Contracting









## Figure 15

REVISION: A 28/8/2010 Provide rainwater tanks 3000/fire

LIRLYA

GENERATION

# SOIL, WATER & WASTE MANAGEMENT PLAN LOT 105 LORIKEET GROVE DATE: 2 SEPT 2010 PLAN NO.22441/SWW

The builder shall check and we'lly all dimensions and seeks and we'lly all errors and onesizons to the Architect. Do not acide the diseasons to the not be used for constitucion purposes until issued by the Architect for constitucion.


I.L. New & Associates MBDA, NSW
BSC LICENCE No. 20388
Unit 25 No. 11 Romford Rd
Kings Park, NSW 2148
Telephone: (02) 9571 4331

For
ABAX Contracting
Project Name
Integrated Housing Development
ATTHEROCOSED SUBDIVISION OF PROPOSED LOT 105 IN A
SUBDIVISION OF LOT 1 DP 1115977 WARRIEWOOD ROAD,
WASTE MANAGEMENT PLAN
WASTE MANAGEMENT PLAN
WASTE MANAGEMENT PLAN
Scale: as noted

State: DA

Date:

Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Date:
Dat



#### SEKISUI HOUSE

# LOT 5, LORIKEET GROVE & LOTS 6-13, ROAD 01, WARRIEWOOD NSW 2102 INTEGRATED HOUSING STAGE 01

#### DRAWING SCHEDULE

DRAWING NUMBER

220122-01-DA-C01.01

220122-01-DA-C01.21

220122-01-DA-C01.41


220122-01-DA-C03.01

EROSION AND SEDIMENTATION CONTROL F

220122-01-DA-C03.01 EROSION AND SEDIMENTATION CONTROL PLAN
220122-01-DA-C03.21 EROSION AND SEDIMENTATION CONTROL DETAILS
220122-01-DA-C04.01 BULK EARTHWORKS CUT AND FILL PLAN
220122-01-DA-C04.21 BULK EARTHWORKS CUT AND FILL SECTIONS
220122-01-DA-C05.01 SITEWORKS AND STORMWATER MANAGEMENT PLAN

220122-01-DA-C05.02 SITEWORKS AND STORMWATER MANAGEMENT PLAN - SHEET

220122-01-DA-C14.01 SITEWORKS DETAIL 220122-01-DA-C21.01 CATCHMENT PLAN



















FOR INFORMATION ONLY
NOT TO BE USED FOR CONSTRUCTIO

Project Number/Drawing Number

220122-01-DA-C01-01

#### **GENERAL**

- ALL WORKS TO BE CONSTRUCTED IN ACCORDANCE WITH NORTHERN BEACHES COUNCIL STANDARDS.
- NORTHERN BEACHES COUNCIL STANDARDS DETAILS TO BE USED WHERE POSSIBLE.
- 3. UTILITY ADJUSTMENTS AT DEVELOPERS EXPENSE.
- 4. CONDUITS TO BE PLACED WHERE REQUIRED BY THE RELEVANT AUTHORITIES

#### SURVEY

#### ORIGIN OF SURVEY

PROJECT: 53A WARRIEWOOD ROAD DATE: 02/01/2021 CARRIED OUT BY: COLLIERS SURVEY NAME: 434-20G T01 [02] REFERENCE NO: 434-20 SSM/PM: SSM 24840 342191.825

ACCURACY OR COMPLETENESS OF THE SURVEY BASE OR ITS SUITABILITY

6271409.780 13.902 THE EXISTING SITE CONDITIONS SHOWN ON THE FOLLOWING DRAWINGS HAVE BEEN SUPPLIED BY REGISTERED SURVEYORS TO PROVIDE A BASIS FOR DESIGN. THE USE OF THIS SURVEY BASE DOES NOT GUARANTEE THE

AS A BASIS FOR CONSTRUCTION DRAWINGS.

- SHOULD DISCREPANCIES BE ENCOUNTERED DURING CONSTRUCTION BETWEEN THE SURVEY DATA AND ACTUAL FIELD DATA, CONTACT THE SUPERINTENDENT.
- THE RELATIONSHIP OF IMPROVEMENTS TO BOUNDARIES ARE DIAGRAMMATIC ONLY. WHERE DISTANCES TO BOUNDARIES ARE CRITICAL THEY SHOULD BE CONFIRMED ON SITE PRIOR TO CONSTRUCTION BY FURTHER SURVEY.



|19/12/2024| ISSUED FOR DEVELOPMENT APPLICATION

V. DATE

DESCRIPTION

SS TPB

DRN. DES. VERIF. APPI

#### **EROSION AND SEDIMENT CONTROL**

#### GENERAL INSTRUCTIONS

- . THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONTROL OF EROSION AND SEDIMENTATION TO THE SATISFACTION OF COUNCIL. NSW OFFICE OF WATER, OFFICE OF ENVIRONMENT AND HERITAGE. THE EROSION AND SEDIMENTATION CONTROLS SHOWN ON THE DRAWINGS SHALL ONLY BE USED AS A GUIDE BY THE CONTRACTOR, AND SHALL REPRESENT THE MINIMUM REQUIREMENT ONLY.
- THE CONTRACTOR SHALL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE LOCATED TO SUIT CONSTRUCTION STAGING AND WORK PRACTICES OR AS OTHERWISE DIRECTED BY THE SUPERINTENDENT.
- ALL WORK SHALL BE GENERALLY CARRIED OUT IN ACCORDANCE WITH a. LOCAL AUTHORITY REQUIREMENTS b. EPA REQUIREMENTS
- c. LANDCOM MANUAL "MANAGING URBAN STORMWATER, SOILS AND CONSTRUCTION", 4th EDITION, MARCH 2004.
- SUPERINTENDENT AND THE LOCAL AUTHORITY. WHEN STORMWATER PITS ARE CONSTRUCTED, PREVENT SITE RUNOFF ENTERING UNLESS SEDIMENT FENCES ARE ERECTED AROUND PITS.

MAINTAIN THE EROSION CONTROL DEVICES TO THE SATISFACTION OF THE

5. CONTRACTOR IS TO ENSURE ALL EROSION & SEDIMENT CONTROL DEVICES ARE MAINTAINED IN GOOD WORKING ORDER AND OPERATE EFFECTIVELY. REPAIRS AND OR MAINTENANCE SHALL BE UNDERTAKEN AS REQUIRED, PARTICULARLY FOLLOWING STORM EVENTS.

#### LAND DISTURBANCE

- 6. WHERE PRACTICAL, THE SOIL EROSION HAZARD ON THE SITE WILL BE KEPT AS LOW AS POSSIBLE. TO THIS END, WORKS SHOULD BE UNDERTAKEN IN THE FOLLOWING SEQUENCE:
- a. INSTALL A SEDIMENT FENCE ALONG THE BOUNDARIES AS SHOWN ON
- PLAN. REFER DETAIL.
- b. CONSTRUCT STABILISED CONSTRUCTION ENTRANCE TO LOCATION AS DETERMINED BY SUPERINTENDENT/ENGINEER. REFER DETAIL. c. INSTALL SEDIMENT BASIN AS SHOWN ON PLAN, INSTALL SEDIMENT
- TRAPS AS SHOWN ON PLAN. d. UNDERTAKEN SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. WHERE POSSIBLE, PHASE DEVELOPMENT SO

THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.

#### **EROSION CONTROL**

- DURING WINDY WEATHER, LARGE, UNPROTECTED AREAS WILL BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL.
- FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION ACTIVITIES.

#### SEDIMENT CONTROL

- 9. STOCKPILES WILL NOT BE LOCATED WITHIN 2 METRES OF HAZARD AREAS, INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS. WHERE THEY ARE BETWEEN 2 AND 5 METRES FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSTREAM WATERS, E.G. THROUGH INSTALLATION OF SEDIMENT FENCING.
- 0. ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD OVER THE SURFACE) WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.
- 11. WATER WILL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE, I.E. THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AN APPROVED STRUCTURE.
- 12. TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.
- 13. ACCEPTABLE RECEPTORS WILL BE PROVIDED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER.
- 14. ANY EXISTING TREES WHICH FORM PART OF THE FINAL LANDSCAPING PLAN WILL BE PROTECTED FROM CONSTRUCTION ACTIVITIES IN ACCORDANCE WITH SECTION 4 OF AS4970 "PROTECTION OF TREES ON DEVELOPMENT SITES" AND COUNCIL CONSENT CONDITIONS.

#### **EARTHWORKS**

- AT THE COMMENCEMENT OF THE CUT AND FILLING OPERATIONS FOR BULK EARTHWORKS A GEOTECHNICAL ENGINEER IS TO VISIT THE SITE & CONFIRM THE SUITABILITY OF THE METHODOLOGY OF ACHIEVING THE REQUIRED BUILDING PLATFORMS AND COMPACTION REQUIREMENTS. SUBSEQUENTLY, THE HEAD CONTRACTOR IS TO CONFIRM, IN WRITING TO THE SUPERINTENDENT THAT THE METHODOLOGY APPROVED AT THE TIME OF THE GEOTECHNICAL ENGINEERS VISIT WAS MAINTAINED DURING ALL THE BULK EARTHWORKS PROCESS.
- 2. STRIP TOPSOIL, ORGANIC MATTER AND RUBBLE FROM CONSTRUCTION AREA TO EXPOSE NATURALLY OCCURRING MATERIAL AND STOCKPILE ON SITE AS DIRECTED BY THE SUPERINTENDENT.
- . WHERE FILLING, STRUCTURAL SLABS OR PAVEMENTS ARE REQUIRED, PROOF ROLL THE EXPOSED NATURAL SURFACE WITH A MINIMUM OF TEN PASSES OF A SMOOTH DRUM NON-VIBRATING ROLLER (MINIMUM STATIC WEIGHT OF 10 TONNES) TO DETECT THEN REMOVE SOFT SPOTS (AREAS WITH MORE THAN 2mm MOVEMENT UNDER ROLLER) IN THE PRESENCE OF THE SUPERINTENDENT. THE CONTRACTOR IS TO ALLOW TO REMOVE AND REPLACE A PROVISIONAL QUANTITY OF UNSUITABLE SUBGRADE MATTER.
- 4. ALL SOFT, WET OR UNSUITABLE MATERIAL IS TO BE REMOVED AS DIRECTED BY THE SUPERINTENDENT AND REPLACED WITH APPROVED MATERIAL SATISFYING THE REQUIREMENTS LISTED BELOW.
- 5. EXCAVATED MATERIAL IS NOT TO BE USED AS STRUCTURAL FILL UNLESS APPROVED BY THE GEOTECHNICAL ENGINEER.
- 6. THE CONTRACTOR IS TO PROVIDE CERTIFICATES VERIFYING THE QUALITY OF IMPORTED MATERIAL FOR THE SUPERINTENDENTS APPROVAL.
- . ALL FILL MATERIAL SHALL BE PLACED IN MAXIMUM LAYER THICKNESS TO COUNCIL SPECIFICATIONS AND COMPACTED AT OPTIMUM MOISTURE CONTENT (+ OR - 2%) TO ACHIEVE A DRY DENSITY DETERMINED IN ACCORDANCE WITH AS1289 E3.1 OF NOT LESS THAN THE FOLLOWING STANDARD MINIMUM DRY DENSITY IN ACCORDANCE WITH AS1289 E5.1.1.1:

COMPACTION REQUIREMENT

UNDER BUILDING SLABS LANDSCAPED AREAS

98% SMDD 95% SMDD ROADS & PAVED AREAS 100% SMDD

- FOR NON COHESIVE MATERIAL, COMPACT TO NOT LESS THAN UNDER ROAD 80% DENSITY OTHER AREA 75% DENSITY
- THE CONTRACTOR IS TO ALLOW FOR COMPACTION TESTING BY NATA REGISTERED LABORATORY FOR PLATFORMS AND FILL LAYERS IN ACCORDANCE WITH THE LATEST VERSION OF AS3798 - FOR TYPE 1 OPERATIONS (MINIMUM 3 TESTS PER LAYER).
- 10. FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN: 1 TEST PER 200m3 OF FILL PLACED PER LAYER OF FILL B. 3 TESTS PER VISIT
- 1 TEST PER 1000m<sup>2</sup> OF EXPOSED SUBGRADE
- 11. TESTING SHALL BE "LEVEL 1" UNDERTAKEN IN ACCORDANCE WITH AS3798.
- 12. WHERE TEST RESULTS ARE BELOW THE SPECIFIED COMPACTION, RECOMPACT AND RETEST UNTIL SPECIFIED COMPACTION STANDARD IS ACHIEVED.
- 13. ALLOW FOR EXCAVATION IN ALL MATERIALS AS FOUND U.N.O. NO ADDITIONAL PAYMENTS WILL BE MADE FOR EXCAVATION IN WET OR HARD GROUND.
- 14. WHERE THERE IS INSUFFICIENT EXCAVATED MATERIAL SUITABLE FOR FILLING OR SUBGRADE REPLACEMENT. THE CONTRACTOR IS TO ALLOW TO IMPORT FILL. IMPORTED FILL SHALL COMPLY WITH THE FOLLOWING: MAXIMUM SIZE 50mm. PASSING 75 MICRON SIEVE (<25%).
- B. PLASTICITY INDEX BETWEEN 2-15% AND CBR>8. FREE FROM ORGANIC AND PERISHABLE MATTER.
- 15. THE CONTRACTOR SHALL PROGRAM THE EARTHWORKS OPERATION SO THAT THE WORKING AREAS ARE ADEQUATELY DRAINED DURING THE PERIOD OF CONSTRUCTION. THE SURFACE SHALL BE GRADED AND SEALED OFF TO REMOVE DEPRESSIONS, ROLLER MARKS AND SIMILAR WHICH WOULD ALLOW WATER TO POND AND PENETRATE THE UNDERLYING MATERIAL. ANY DAMAGE RESULTING FROM THE CONTRACTOR NOT OBSERVING THESE REQUIREMENTS SHALL BE RECTIFIED AT THEIR COST.
- 16. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE AND MAINTAIN THE INTEGRITY OF ALL SERVICES, CONDUITS AND PIPES DURING CONSTRUCTION, SPECIFICALLY DURING THE BACKFILLING AND COMPACTION PROCEDURE. ANY AND ALL DAMAGE TO NEW OR EXISTING SERVICES AS A RESULT OF THESE WORKS SHALL BE REPAIRED BY THE CONTRACTOR AT NO EXTRA COST.
- 17. PROTECT FINAL SURFACE WITH EITHER A TEMPORARY LOOSE SOIL LAYER OR A GRANULAR SUB-BASE LAYER TO PREVENT DRYING OUT PRIOR TO ON-GROUND SLAB CONSTRUCTION.

without the permission of Enspire Solutions Pty Ltd.

#### SITEWORKS

- ALL WORKS TO BE IN ACCORDANCE WITH LOCAL AUTHORITY REQUIREMENTS, SPECIFICATIONS AND AUSTRALIAN STANDARDS. CONFLICTS SHALL BE REFERRED TO THE SUPERINTENDENT FOR
- CONTRACTOR MUST VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO COMMENCEMENT OF WORK, ANY DISCREPANCIES TO BE REPORTED TO THE SUPERINTENDENT.
- THE CONTRACTOR IS TO DESIGN, OBTAIN APPROVALS AND CARRY OUT REQUIRED TEMPORARY TRAFFIC CONTROL PROCEDURES DURING CONSTRUCTION IN ACCORDANCE WITH TINSW AND LOCAL AUTHORITY REGULATIONS AND REQUIREMENTS.
- THE CONTRACTOR IS TO OBTAIN ALL AUTHORITY APPROVALS AS
- RESTORE ALL PAVED, COVERED, GRASSED AND LANDSCAPED AREAS TO THEIR ORIGINAL CONDITION ON COMPLETION OF WORKS.
- 6. ON COMPLETION OF ANY TRENCHING WORKS, ALL DISTURBED AREAS SHALL BE RESTORED TO THEIR ORIGINAL CONDITION, INCLUDING KERBS. FOOTPATHS, CONCRETE AREAS, GRAVEL, GRASSED AREAS AND ROAD PAVEMENTS.
- THE CONTRACTOR SHALL ARRANGE ALL SURVEY SETOUT TO BE CARRIED OUT BY A REGISTERED SURVEYOR.
- 8. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO LODGMENT OF TENDER AND ON SITE WORKS. THE PRICE AS TENDERED SHALL BE INCLUSIVE OF ALL WORKS SHOWN ON THE TENDER PROJECT DRAWINGS. ADDITIONAL PAYMENTS FOR WORKS SHOWN ON THE TENDER PROJECT DRAWINGS WILL NOT BE APPROVED.
- THESE DRAWINGS ARE TO BE READ IN CONJUNCTION WITH THE ENGINEERING PLANS AND SPECIFICATIONS, AND ANY OTHER WRITTEN INSTRUCTIONS THAT MAY BE ISSUED RELATING TO DEVELOPMENT OF THE SUBJECT SITE.
- 10. THESE PLANS SHALL BE READ IN CONJUNCTION WITH ALL APPROVED DRAWINGS AND SPECIFICATIONS PREPARED BY OTHER PROJECT CONSULTANTS.
- 11. DO NOT OBTAIN DIMENSIONS BY SCALING THE DRAWINGS. ALL DIMENSIONS ARE IN MILLIMETERS (mm) AND ALL LEVELS ARE IN METRES (m), UNO. ALL LEVELS ARE TO AUSTRALIAN HEIGHT DATUM (AHD).
- 12. IN CASE OF DOUBT OR DISCREPANCY REFER TO THE SUPERINTENDENT FOR CLARIFICATION OR CONFIRMATION PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. OTHERWISE THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE COST OF REMEDIATION WORKS.
- 3. WHERE NEW WORKS ABUT EXISTING THE CONTRACTOR SHALL ENSURE THAT A SMOOTH EVEN PROFILE, FREE FROM ABRUPT CHANGES IS OBTAINED.
- 14. THE CONTRACTOR SHALL COMPLY WITH ALL STATUTORY AND INDUSTRIAL REQUIREMENTS FOR PROVISION OF A SAFE WORKING ENVIRONMENT
- INCLUDING TRAFFIC CONTROL. 5. THE CONTRACTOR SHALL ENSURE THAT AT ALL TIMES ACCESS TO ALL
- BUILDINGS ADJACENT THE WORKS IS NOT DISRUPTED. 16. WHERE NECESSARY THE CONTRACTOR SHALL PROVIDE SAFE PASSAGE OF VEHICLES AND/OR PEDESTRIANS THROUGH OR BY THE SITE.
- 17. WHERE NOTED ON THE DRAWINGS THAT WORKS ARE TO BE CARRIED BY OTHERS, (eg. ADJUSTMENT OF SERVICES), THE CONTRACTOR SHALL BE
- RESPONSIBLE FOR THE CO-ORDINATION OF THESE WORKS. 18. ALL VARIATIONS TO SPECIFIED PRODUCTS OR DESIGNS SHALL BE

REFERRED TO THE DESIGN ENGINEER IN WRITING FOR APPROVAL.

19. EPA AND COUNCIL REQUIREMENTS MUST BE ADHERED TO REGARDING THE LEVEL OF NOISE AND WORKING HOURS, TO ENSURE THAT RESIDENTS AND OTHER APPLICABLE NEIGHBOURS TO THE SITE ARE NOT DISTURBED UNREASONABLY. THE GENERATION OF NOISE MUST BE MINIMISED.

#### STORMWATER DRAINAGE

- 1. ALL INTERNAL WORKS WITHIN PROPERTY BOUNDARIES ARE TO COMPLY WITH THE REQUIREMENTS OF AS 3500 3.1 AND AS/NZS 3500
- 2. SUBSOIL DRAINAGE LINES SHALL BE INSTALLED BEHIND ALL KERBS EXCEPT WHERE STORMWATER DRAINAGE IS LOCATED ALONG THE KERBLINE.
- 3. A MINIMUM OF 3m OF SUBSOIL LINE SHALL BE LAID INTO UPSTREAM SIDE OF ALL DRAINAGE PITS.
- 4. FLUSHING POINTS SHALL BE INSTALLED TO COUNCIL SPECIFICATION.
- 5. PIPES UP TO 300 DIA SHALL BE SEWER GRADE uPVC (CLASS SN4) WITH SOLVENT WELDED JOINTS.
- 6. PIPES 375 DIA. AND LARGER TO BE REINFORCED CONCRETE MIN CLASS '2' APPROVED SPIGOT AND SOCKET WITH RUBBER RING
- 7. ALL PIPES ARE TO BE LAID AT (min) 1.0% GRADE (UNO)

JOINTS. U.N.O.

- 8. ALL PIPES ARE TO BE UNIFORMLY SUPPORTED ALONG THE LENGTH OF THE BARREL BY SUITABLE FILL MATERIAL. REFER TO BEDDING SUPPORT TYPE.
- 9. PIPES WITH SOCKETS SHALL BE LAID IN BEDDING WHERE SUITABLE RECESSES HAVE BEEN PROVIDED TO ENSURE PIPES DO NOT BEAR ON THEIR SOCKETS.
- 10. ENLARGERS, CONNECTIONS AND JUNCTIONS TO BE PREFABRICATED FITTINGS WHERE PIPES ARE LESS THAN 300 DIA.
- 11. ALL STORMWATER DRAINAGE LINES UNDER PROPOSED BUILDING SLABS TO BE uPVC PRESSURE PIPE GRADE
- 12. ENSURE ALL VERTICALS AND DOWNPIPES ARE uPVC PRESSURE PIPE, GRADE 6 FOR A MIN OF 3.0m IN HEIGHT.
- 13. WHERE WORKING METHODS REQUIRE HIGHER CLASS PIPE, THE CONTRACTOR SHALL REFER TO AS 3725 TO DETERMINE THE APPROPRIATE PIPE CLASS. ANY CHANGES IN PROPOSED PIPE CLASS SHALL BE SUBMITTED TO THE SUPERINTENDENT FOR APPROVAL PRIOR TO INSTALLATION.
- 14. CARE IS TO BE TAKEN WITH LEVELS OF STORMWATER LINES. GRADES SHOWN ARE NOT TO BE REDUCED WITHOUT APPROVAL.
- 15. PRECAST PITS MAY BE USED SUBJECT TO WRITTEN APPROVAL BY THE SUPERINTENDENT.
- 16. ALL PIPE PENETRATIONS (EXISTING, IN-SITU AND PRECAST) ARE TO BE FINISHED FLUSH WITH THE INTERNAL PIT WALL AND PROPERLY SEALED WITH CEMENT RENDER. MASS CONCRETE BENCHING IS TO BE INSTALLED TO MATCH THE OUTLET PIPE INVERT LEVEL AND A LOCKABLE HINGED GRATE AND FRAME WITH CONCRETE SURROUND INSTALLED U.N.O.

- USE HOT DIPPED GALVANISED GRATES AND CONCRETE FILLED COVERS WITH HINGES AND HOLD DOWN BOLTS COMPLYING WITH AS3996 AND OTHER RELEVANT AUSTRALIAN AND COUNCIL STANDARDS.
- ALL COVERS AND GRATES TO BE POSITIONED IN A FRAME AND MANUFACTURED AS A UNIT.
- ALL COVERS AND GRATES TO BE FITTED WITH POSITIVE
- COVER LIFTING KEYS. OBTAIN SUPERINTENDENT'S APPROVAL FOR THE USE OF CAST IRON SOLID COVERS AND GRATES. CAST IRON SOLID COVERS (IF APPROVED) TO CONSIST OF CROSS-WEBBED, CELLULAR CONSTRUCTION WITH THE RIBS UPPERMOST TO ALLOW INFILLING WITH CONCRETE. INSTALL POSITIVE COVER LIFTING KEYS AND PLASTIC
- UNLESS DETAILED OR SPECIFIED OTHERWISE COVERS AND GRATES TO BE CLASS "D" IN VEHICULAR PAVEMENTS AND CLASS "B" ELSEWHERE.
- 18. NOTE THAT THE PIT COVER LEVEL NOMINATED IN GUTTERS ARE TO THE INVERT OF THE GUTTER WHICH IS 40mm LOWER THAN THE PAVEMENT LEVEL AT LIP OF GUTTER.
- 19. Ø100mm SUB-SOIL DRAINAGE LINES SHALL BE CONNECTED TO A STORMWATER DRAINAGE PIT AND PROVIDED IN THE FOLLOWING
- LOCATIONS: A. ADJACENT ALL TRAFFICKED AND CARPARK PAVEMENT AREAS (BEHIND KERB);
- ALL PLANTER AND TREE BEDS PROPOSED ADJACENT TO PAVEMENT AREAS; BEHIND RETAINING WALLS (IN ACCORDANCE WITH
- DRAWINGS); BELOW ALL TRAFFICABLE DISH DRAINS; ALL OTHER AREAS SHOWN ON THE DRAWINGS.
- 20. THE CONTRACTOR SHALL INSTALL FLUSHING POINTS TO ALL SUBSOIL DRAINAGE LINES AND DOWNPIPE LINES AS SPECIFIED ON DRAWINGS, AT MAXIMUM CENTRES TO COUNCIL SPECIFICATION AND AT ALL UPSTREAM ENDPOINTS.
- 21. PROVIDE 3.0m LENGTH OF Ø100 SUBSOIL DRAINAGE PIPE WRAPPED IN A NON-WOVEN GEOTEXTILE FABRIC, TO THE UPSTREAM SIDE OF STORMWATER PITS, LAID IN STORMWATER PIPE TRENCHES AND CONNECTED TO THE DRAINAGE PIT.
- 22. SUBSOIL TRENCHES SHALL BE BACKFILLED WITH SINGLE SIZED 10mm AGGREGATE WRAPPED IN NON-WOVEN GEOTEXTILE FABRIC. SUBSOIL TRENCHES BELOW TRAFFICABLE PAVEMENTS SHALL BE BACKFILLED WITH NO FINES CONCRETE WRAPPED IN NON-WOVEN GEOTEXTILE FABRIC, U.N.O.
- 23. ALL RECTANGULAR HOLLOW SECTIONS (RHS) SPECIFIED AS STORMWATER CONDUITS TO BE HOT DIPPED GALVANISED AND HAVE (MINIMUM) 5mm WALL THICKNESS.

#### STORMWATER DRAINAGE (CONT.)

- 24. ALL BOX CULVERTS SHALL BE STRUCTURALLY DESIGNED BY THE MANUFACTURER AND DELIVERED TO SITE AS FIT FOR PURPOSE.
- 25. ELECTRICAL PITS ARE TO DRAIN TO THE NEAREST STORMWATER PIT WITH VERMIN PROOF NON-RETURN FLAP VALVES AS REQUIRED. THE CONTRACTOR IS TO CONFIRM WITH THE ELECTRICAL DESIGNER AS PART OF THE TENDER.
- 26. THE CONTRACTOR SHALL ENSURE AND PROTECT THE INTEGRITY OF ALL STORMWATER PIPES DURING CONSTRUCTION. ANY AND ALL DAMAGE TO THESE PIPES AS A RESULT OF THESE WORKS SHALL BE REPAIRED BY THE CONTRACTOR UNDER THE DIRECTION OF THE SUPERINTENDENT, AND AT NO EXTRA COST.
- 27. AT ALL TIMES DURING CONSTRUCTION OF STORMWATER PITS, ADEQUATE SAFETY PROCEDURES SHALL BE TAKEN TO ENSURE AGAINST THE POSSIBILITY OF PERSONNEL FALLING DOWN PITS.
- 28. ALL EXISTING STORMWATER DRAINAGE LINES AND PITS THAT ARE TO REMAIN ARE TO BE INSPECTED AND CLEANED. DURING THIS PROCESS ANY PART OF THE STORMWATER DRAINAGE SYSTEM THAT WARRANTS REPAIR SHALL BE REPORTED TO THE SUPERINTENDENT/ENGINEER FOR FURTHER DIRECTIONS.
- 29. ANY VARIATION TO SPECIFIED PRODUCTS OR DETAILS SHALL BE REFERRED TO THE SUPERINTENDENT FOR APPROVAL.

#### **PAVEMENTS**

- ALL PAVEMENT MATERIALS SHALL COMPLY WITH CURRENT TINSW SPECIFICATIONS. PROVIDE MECHANICAL ANALYSIS FOR EACH BATCH OF PAVEMENT MATERIAL TO ENSURE CONFORMITY.
- 2. COMPACTION STANDARDS:
- BASE: 98% MODIFIED MAXIMUM DRY DENSITY SUBBASE: 98% MODIFIED MAXIMUM DRY DENSITY
- THE CONTRACTOR SHALL CONFIRM THE DESIGN CBR WITH A MINIMUM OF 3 TESTS TAKEN AT SUBGRADE LEVEL. WHERE DISCREPANCY IS FOUND, CONTACT THE SUPERINTENDENT.
- . ALLOW FOR COMPACTION TESTING BY NATA REGISTERED LABORATORY FOR: BASE LAYER, SUBBASE LAYER, SUBGRADE IN ACCORDANCE WITH THE LATEST VERSION OF AS3798 FOR PAVEMENTS. ALLOW FOR AT LEAST TWO SUCCESSFUL COMPACTION TESTS IN EACH LAYER.
- MATCH NEW PAVEMENT LAYERS NEATLY AND FLUSH WITH EXISTING WHERE REQUIRED.
- . KEY NEW BASE AND SUBBASE LAYERS INTO EXISTING WITH 150mm WIDE STEPS, ASPHALTIC CONCRETE WEARING COURSE IS TO EXTEND 150mm (MIN) PAST BASECOURSE INTERFACE.
- TRENCHES THROUGH EXISTING ROAD AND CONCRETE PAVEMENTS SHALL BE SAWCUT TO FULL DEPTH OF CONCRETE AND A MIN 50mm IN BITUMINOUS PAVING.
- B. ALL ASPHALTIC CONCRETE (AC) WORK TO BE PREPARED AND CARRIED OUT IN ACCORDANCE WITH GOOD ASPHALTIC PAVING PRACTICE AS DESCRIBED IN AS2734 "ASPHALT (HOT-MIXED) PAVING - GUIDE TO GOOD PRACTICE" AND CURRENT TINSW SPECIFICATIONS (R116).
- . WHERE NOMINATED, THE CONTRACTOR SHALL ALLOW FOR ALL COMPONENTS OF PROPRIETARY JOINTING SYSTEMS INCLUDING FIXING. TEMPLATES & PEGGING TO ENSURE THAT ALL DOWEL BARS REMAIN IN THE CORRECT ALIGNMENT AND POSITION.
- 10. ALL BASECOURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH TINSW. SPECIFICATION 3051, COMPACTED TO MINIMUM 98% MODIFIED DENSITY IN ACCORDANCE WITH AS 1289 5.2.1 FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m3 OF BASECOURSE MATERIAL PLACED.
- 1. ALL SUB-BASE COURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH TINSW. SPECIFICATION 3051, AND COMPACTED TO MINIMUM 98% MODIFIED DENSITY IN ACCORDANCE WITH A.S 1289 5.2.1 FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m3 OF SUB-BASE COURSE MATERIAL PLACED.
- 2. AS AN ALTERNATIVE TO THE USE OF IGNEOUS ROCK AS A SUB-BASE MATERIAL IN (11) A CERTIFIED RECYCLED CONCRETE MATERIAL COMPLYING WITH TINSW. SPECIFICATION 3051 WILL BE CONSIDERED. SUBJECT TO MATERIAL SAMPLES AND APPROPRIATE CERTIFICATIONS BEING PROVIDED TO THE SATISFACTION OF THE COUNCIL ENGINEER.
- 3. SHOULD THE CONTRACTOR WISH TO USE A RECYCLED PRODUCT THIS SHALL BE CLEARLY INDICATED IN THEIR TENDER AND THE PRICE DIFFERENCE BETWEEN AN IGNEOUS PRODUCT AND A RECYCLED PRODUCT SHALL BE CLEARLY INDICATED.







Enspire Solutions Pty Ltd

Phone: 02 9922 6135

Level 4, 153 Walker Street, North Sydney NSW 2060 The copyright of this drawing remains with Enspire Solutions Pty Ltd and must not be copied wholly or in part ABN: 71 624 801 690

SPECIFICATION NOTES


53A & 53B WARRIEWOOD ROAD


WARRIEWOOD NSW 2102 19/12/2024 TEGRATED HOUSING STAGE 01


FOR INFORMATION ONLY NOT TO BE USED FOR CONSTRUCTION oject Number/Drawing Number

N.T.S

MGA2020








### TEMPORARY CONSTRUCTION EXIT (SHAKER PAD DETAIL)

THE EXIT SHALL BE MAINTAINED IN A CONDITION WHICH PREVENTS TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS OF WAY. THIS MAY REQUIRE REPAIR AND OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS OF WAY MUST BE REMOVED IMMEDIATELY.



#### CONSTRUCTION NOTES


DESCRIPTION

V. DATE

- 1. FABRICATE A SEDIMENT BARRIER MADE FROM GEOTEXTILE OR STRAW BALES.
- 2. FOLLOW STANDARD DRAWING 6-7 AND STANDARD DRAWING 6-8 FOR INSTALLATION PROCEDURES FOR THE STRAW BALES OR GEOFABRIC. REDUCE THE PICKET SPACING TO 1 METRE CENTRES.
- 3. IN WATERWAYS, ARTIFICIAL SAG POINTS CAN BE CREATED WITH SANDBAGS OR EARTH BANKS AS SHOWN IN THE DRAWING.
- 4. DO NOT COVER THE INLET WITH GEOTEXTILE UNLESS THE DESIGN IS ADEQUATE TO ALLOW FOR ALL WATERS

#### GEOTEXTILE INLET FILTER (SD 6-12)


DRN. DES. VERIF. APPD




#### **CONSTRUCTION NOTES**

- 1. PLACE STOCKPILES MORE THAN 2m (PREFERABLY 5m) FROM EXISTING VEGETATION, CONCENTRATED WATER FLOW, ROADS AND HAZARD AREAS.
- 2. CONSTRUCT ON THE CONTOUR AS LOW, FLAT, ELONGATED MOUNDS.
- 3. WHERE THERE IS SUFFICIENT AREA, TOPSOIL STOCKPILES SHALL BE LESS THAN 2m IN HEIGHT.
- 4. WHERE THEY ARE TO BE IN PLACE FOR MORE THAN 10 DAYS, STABILISE FOLLOWING THE APPROVED ESCP OR SWMP TO REDUCE THE C-FACTOR TO LESS THAN 0.10.
- 5. CONSTRUCT EARTH BANKS (STANDARD DRAWING 5-5) ON THE UPSLOPE SIDE TO DIVERT WATER AROUND STOCKPILES AND SEDIMENT FENCES (STANDARD DRAWING 6-8) 1 TO 2m DOWNSLOPE.

#### STOCKPILES (SD 4-1)



## SEDIMENT TRAP FOR KERB INLET (AT LOW POINT - SANDBAG) NOT TO SCALE



### SEDIMENT TRAP FOR KERB INLET (ON GRADE - SANDBAG)

NOT TO SCALE

Scale

0 0.5 1 1.5 2m

SCALE 1:20 @A1

Enspire Solutions Pty L
1302/83 Mount Street,
ABN: 71 624 801 690

without the permission of Enspire Solutions Pty Ltd.



Phone: 02 9922 6135


Project
53A & 53B WARRIEWOOD ROAD
WARRIEWOOD NSW 2102
INTEGRATED HOUSING STAGE 01

Title
EROSION AND SEDIMENTATION CONTROL DETAILS

Scale
N.T.S
Date
19/12/2024

Size
Project Number/Drawing Number
220122-01-DA-C03.21


MGA2020




CONSTRUCTION NOTES


- 1. CONSTRUCT SEDIMENT FENCES AS CLOSE AS POSSIBLE TO BEING PARALLEL TO THE CONTOURS OF THE SITE, BUT WITH SMALL RETURNS AS SHOWN IN THE DRAWING TO LIMIT THE CATCHMENT AREA OF ANY ONE SECTION. THE CATCHMENT AREA SHOULD BE SMALL ENOUGH TO LIMIT WATER FLOW IF CONCENTRATED AT ONE POINT TO 50 LITRES PER SECOND IN THE DESIGN STORM EVENT, USUALLY THE 10-YEAR EVENT.
- 2. CUT A 150mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE ENTRENCHED.
- 3. DRIVE 1.5 METRE LONG STAR PICKETS INTO GROUND AT 2.5 METRE INTERVALS (MAX) AT THE DOWNSLOPE EDGE OF THE TRENCH. ENSURE ANY STAR PICKETS ARE FITTED WITH SAFETY CAPS.
- 4. FIX SELF-SUPPORTING GEOTEXTILE TO THE UPSLOPE SIDE OF THE POSTS ENSURING IT GOES TO THE BASE OF THE TRENCH. FIX THE GEOTEXTILE WITH WIRE TIES OR AS RECOMMENDED BY THE MANUFACTURER. ONLY USE GEOTEXTILE SPECIFICALLY PRODUCED FOR SEDIMENT FENCING. THE USE OF SHADE CLOTH FOR THIS PURPOSE IS NOT SATISFACTORY.
- 5. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150mm OVERLAP.
- 6. BACKFILL THE TRENCH OVER THE BASE OF THE FABRIC AND COMPACT IT THOROUGHLY OVER THE GEOTEXTILE.

#### SEDIMENT FENCE (SD 6-8)



SEKISUI HOUSE







SECTION

HORIZONTAL SCALE 1:500@A1

VERTICAL SCALE 1:100@A1






SECTION

HORIZONTAL SCALE 1:500@A1
VERTICAL SCALE 1:100@A1


CO4.01






C04.01


HORIZONTAL SCALE 1:500@A1 VERTICAL SCALE 1:100@A1






Project	Scale	Status	
53A & 53B WARRIEWOOD ROAD	AS SHOWN	FOR INFORMATION ONLY	
WARRIEWOOD NSW 2102	First Issue Date		i
INTEGRATED HOUSING STAGE 01	19/12/2024	NOT TO BE USED FOR CONSTRUCTION	
Title	Size	Project Number/Drawing Number	Revision
BULK EARTHWORKS CUT	A1		4
AND FILL SECTIONS	Datum	220122-01-DA-C04.21	
	MGA2020		









150mm THICKNESS CONCRETE (SL72 MESH - 40 TOP COVER)


100mm THICKNESS COMPACTED DGB 20


DRIVEWAY PAVEMENT
SCALE 1:10



NOTE: NO BULK FILL OR CUT AS PART OF HOUSE CONSTRUCTION HATCHED AREA DENOTES TOPSOIL PLACEMENT









Scale	0		1	2	3	4	5m	North
	SCAL	E 1:50	)				@A1	
	0	1	2	4	6	8	10m	
	SCAL	E 1:10	00				@A1	
				ng remains w nspire Soluti	•	olutions Pty l	Ltd and must n	ot be copied wholly or in p



Project	Scale	Status		
53A & 53B WARRIEWOOD ROAD	AS SHOWN	FOR INFORMATION ONLY		
WARRIEWOOD NSW 2102	Date			
INTEGRATED HOUSING STAGE 01	19/12/2024	NOT TO BE USED FOR CONSTRUCTION		
Title	Size	Project Number/Drawing Number	Revision	
SITEWORKS DETAILS	A1	220122 01 DA C14 01	4	
	Datum	220122-01-DA-C14.01		
	MGA2020			

