

STORMWATER DOWNPIPE AND GUTTER SCHEDULE			
MARK	TYPE OF GUTTER	SIZE OF GUTTER	SIZE OF DOWNPIPES
GS1	Eaves Gutter	200 Wide x 150 Deep	150 DIA.
GS2	Box Gutter	450 Wide x 150 Deep	150 DIA
SG1	Soaker Gutter	400 Wide x 50 Deep	N/A
EBG	Ex. Box Gutter	TBC	TBC
EEG	Ex. Eaves Gutter	TBC	TBC
	MARK GS1 GS2 SG1 EBG	MARK TYPE OF GUTTER GS1 Eaves Gutter GS2 Box Gutter SG1 Soaker Gutter EBG Ex. Box Gutter	MARKTYPE OF GUTTERSIZE OF GUTTERGS1Eaves Gutter200 Wide x 150 DeepGS2Box Gutter450 Wide x 150 DeepSG1Soaker Gutter400 Wide x 50 DeepEBGEx. Box GutterTBC

NOTE: All Gutter Systems shall be GS1, UNO.

GENERAL

- G1 These drawings shall be read in conjunction with the architectural and other consultants' drawings / specifications and with other such written instructions as may be issued during the construction. Any discrepancy shall be referred to the Engineer before commencing the work.
- G2 All dimensions are in millimeters, UNO (unless noted
- G3 These drawings shall not be scaled, refer to dimensions given only or refer to the Architectural drawings.
- G4 All levels and setting out dimensions shown on the drawings shall be checked on site prior to the commencement of the
- G5 During construction the structure shall be maintained in a stable condition with no part being overstressed.
- G6 Existing services, where shown, have been drawn based on supplied information and as such their accuracy can not be guaranteed. It is the responsibility of the contractor to determine their exact location prior to the commencement of
- G7 All service trenches under vehicular pavements shall be back filled in accordance with the respective authorities requirements
- G8 All trench backfill material shall be compacted to the same
- density as the surround material. G9 All site disturbed areas shall be reinstate to the original condition, including kerbs, footpaths, concrete areas, gravel and grassed areas, etc.
- G10It is the contractors responsibility to obtain all authority approvals.

STORMWATER DRAINAGE

- S1 The stormwater drainage design has been carried out in accordance with AS / NZS 3500.3 "Stormwater Drainage" & AS / NZS 3500.2.3 "Stormwater Drainage - Acceptable
- S2 Any variations to the design levels shall be referred to the engineer immediately for approval.
- S3 Any variations to specified products or details shall be referred to the engineer for approval prior to their
- S4 Subsoil drainage shall be provided to all retaining walls & embankments. They shall be a minimum of 100 slotted pipe in filter sock surrounded by crushed rock. They shall drain to the stormwater drainage system.

SEDIMENT & EROSION CONTROL NOTES E1 The sediment & erosion controls shall be maintained effectively for the duration of the project. They shall not be removed until the site has been stabilized or landscaped to

- the principal certifying authorities satisfaction. E2 A single all weather access way shall be provided at the front of the property consisting of 50-80 mm aggregate or similar material with a minimum thickness of 150 mm laid over needle-punched geotextile fabric (Bidim A14 or similar) and installed prior to any works being commenced on site.
- E3 Where the building works are greater than a single dwelling development, a shaker pad must be installed as part of the vehicular accessway. The shaker pad shall be: - Established on suitable prepared & compacted
 - material. - Constructed such that it is flush with the adjoining
 - surfaces. - A minimum of 5000 mm in length and breadth. - Designed with rungs spaced 200-250 mm apart &
- with a maximum width of 75 mm each. E4 The contractor shall ensure that no spoil or fill encroaches
- upon adjacent areas during the project. E5 The contractor shall ensure that all kerb inlets and drains affected by stormwater flow from the site are protected at all times during the project. Kerb inlet sediment traps shall be installed along the immediate vicinity along the street frontage. These shall be regularly maintained during the
- E6 The street / road shall be kept clean from dirt and debris
- from vehicles departing the site. E7 Sediment fencing shall be secured to posts (please note that if star pickets or similar are used then high visibilty plastic safety caps shall be installed on top of the posts) at 2000 mm intervals with the geotextile fabric embedded a minimum of 200 mm in to the
- E8 All the topsoil stripped from the site shall be stockpiled such that it does not interfere with drainage lines and stormwater inlet pits. The stockpile shall be suitably covered with an impervious membrane and screened by sediment fencing.

SOIL CONSERVATION NOTE:


- C1 Prior to the commencement of the site works the following shall be provided to capture water borne sediments: - Sediment fencing
 - Sediment trap
- Washout area C2 These shall be maintained regularly during the course of the construction with the sediment trap cleaned after each storm

SEDIMENT TRAP

T1 A 1000 x 1000 mm square by 500 mm deep pit located at the lows point of the site.

WASHOUT AREA


W1 The washout are shall be 1800 x 1800 mm allocated for the washing of tools & equipment in accordance with the detail



SEDIMENT FENCE

F1 Provide sediment fence on down slope boundary as shown

F2 Geotextile fabric to be buried 200 mm below tim tam at the




Stakes driven 600 mm 600 into the ground with the first stake Strawbale angle towards the previously - & geotextile sediment fence Geotextile filter fabric fasten on top edge Disturbed Area Undisturbed

F3 Drainage area is 0.5 HA with a maximum slope gradient 1:2 maximum and a maximum slope length of 50 m.

VEHICLE ACCESS TO SITE

V1 Vehicle access to the building site shall be restricted to a single point so as to reduce the amount of soil deposited on the street pavement.




BUILDING MATERIAL STOCKPILES

- M1 Where there are stockpiles of material on site they shall be located at least 2000 mm away from any hazard including surfaces with grades greater than 15%, away from zones of concentrated stormwater flows, away from driveways, temporary vehicular accessways, footpaths, nature strips, kerbs, open swales & the drip zone of trees.
- M2 Sediment fencing shall be installed downslope of all stockpiles.
- M3 The stockpile shall be covered with a impervious cover and held down firmly at all corners and sides.



SANDBAG KERB SEDIMENT TRAP


K1 In certain circumstances extra sediment trapping maybe needed in the street gutter.



06.10.21 **GENERAL REVISIONS REVISION** DATE AMENDMENT DESCRIPTION

COPYRIGHT

Mitchell Howes Civil & Structural Engineers Pty Ltd is the owner of the copyright subsisting in these drawings, plans, designs and specifications. They must not be used, reproduced or copied in whole or in part without prior written consent of Mitchell Howes Civil & Structural Engineers Pty Ltd



ABN 69 101 621 390 Suite 11a, 4 Central Ave Thornleigh NSW 2120 Ph: (02) 9980 1444 Fax: (02) 99801499

Approved:

MIEAust CPEng RPEQ 6469 RBP EC 20844

Mitchell L Howes BE (Hons)

Proposed Development

145 Old Pittwater Road, Brookvale

For Williams River Steel

Concept Stormwater Drainage Plan

DRAWN: PROJECT: 16289 2 Sept 2021 DESIGN: SCALE: DWG / REV: SW01 A