


CONCEPT STORMWATER DRAWINGS FOR PROPOSED NEW DUAL OCCUPANCY



SUIT 2.04, L2, BLDG 3,
35-41 WATERLOO RD., MACQUARIE PARK, NSW 2113
info@smartstrucs.com.au | T: (02) 9052 6467

CLIENT
MR & MRS BRYDEN

ARCHITECT
ALEX BRYDEN
ARCHITECTURE



AS 3500.3- TABLE 8.2
SIZE OF MINIMUM INTERNAL DIMENSIONS FOR
STORMWATER AND INLET PITS

DEPTH OF INVERT OF OUTLET	MINIMUM INTERNAL DIMENSIONS (mm)		
	RECTANGULAR WIDTH	LENGTH	CIRCULAR DIAMETER
≤450	350	350	
≤600	450	450	600
>600 ≤900	600	600	900
>900 ≤1200	600	900	1000
>1200	900	900	1000



IMPORTANT:
CONTRACTOR TO OBTAIN CURRENT SET OF
"DIAL BEFORE YOU DIG" PLANS ON SITE ALL
TIMES AND PRIOR TO CONSTRUCTION WORKS

SYMBOLS

RL	PIT SURFACE LEVEL	PG	PLANTER GRATE
IL	INVERT LEVEL	DP	DOWN PIPE
TK	TOP OF KERB	CO	CLEAN OUT
B.O.W	BOTTOM OF WALL	IO	INSPECTION OPENING
T.O.W	TOP OF WALL	VD	VERTICAL DROP
SW SV	STORMWATER DRAINAGE PIPE	VR	VERTICAL RISER
RVT	DOWNPIPE TO RAINWATER TANK	OF	OVERFLOW (DOME TYPE)
SW SV	OVERFLOW PIPE FROM RAINWATER TANK	OF	CONCRETE COVER JUNCTION PIT
Ø100	SUBSOIL PIPE	IP	GRATED INLET PIT
Ø100	SUBSOIL PIPE	WD	WIDE GRATED DRAIN
FW	FLOOR WASTE 150X150	OF	OVERLAND FLOW PATH
FW	FLOOR WASTE 1500	SV	CAST IN SLAB PIPE
RWO	RAINWATER OUTLET 3000		

DRAWING LIST	
DRAWING NUMBER	DRAWING NAME
D00	COVER SHEET, LEGEND & DRAWING SCHEDULE
D01	BASEMENT STORMWATER DRAINAGE PLAN
D02	GROUND FLOOR STORMWATER DRAINAGE PLAN
D04	ROOF STORMWATER DRAINAGE PLAN
D05	PRE & POST DEVELOPMENT CATCHMENT ANALYSIS
D10	STORMWATER DRAINAGE SECTIONS AND DETAILS SHEET 1
D11	STORMWATER DRAINAGE SECTIONS AND DETAILS SHEET 2
D15	EROSION AND SEDIMENT CONTROL PLAN AND DETAILS

NOTES

- ALL LINES ARE TO BE MIN. 1000 UPVC @ MIN 1.0% GRADE UNLESS NOTED OTHERWISE.
- IT IS THE CONTRACTORS RESPONSIBILITY TO LOCATE & LEVEL ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF ANY EARTHWORKS. ALL DESIGN LEVELS SHOWN ON PLAN SHALL BE VERIFIED ON SITE PRIOR TO THE COMMENCEMENT OF ANY WORK.
- ALL PIPES TO HAVE MIN 200mm COVER IF LOCATED WITHIN PROPERTY.
- ALL PITS IN DRIVEWAYS BE HEAVY DUTY GRATES. DIRECT SURFACE FLOW TO ALL GRATED SURFACE INLET PITS.
- ALL WORK DO BE DONE IN ACCORDANCE WITH AS/NZ 3500.3 (CURRENT EDITION), COUNCIL SPECIFICATIONS, RELEVANT VOLUME OF NCC (NATIONAL CONSTRUCTION CODE)
- LOCATION OF DOWNPIPES & FLOOR WASTES ARE INDICATIVE ONLY. DOWNPIPE & FLOOR WASTE SIZE, LOCATION & QUANTITY TO BE DETERMINED BY BUILDER & IN ACCORDANCE WITH RELEVANT AUSTRALIAN STANDARDS.
- ALL STORMWATER LINES' JOINTS BE FULLY SEALED AND WATERTIGHT IN ACCORDANCE WITH AS3500.3:2021
- THIS PLAN IS TO BE READ IN CONJUNCTION WITH THE ARCHITECTURAL, LANDSCAPE AND STRUCTURAL AND ALL OTHER RELEVANT CONSULTANT'S PLANS.
- ALL RAINWATER TANKS TO BE FITTED WITH A FIRST FLUSH DEVICE TO PREVENT POTENTIAL CONTAMINANTS FROM ENTERING THE TANKS.
- ANY DISCREPANCIES OR OMISSIONS SHALL BE REFERRED TO THE DESIGN ENGINEER FOR RESOLUTION.
- ALL PITS OR GRATES IN TRAFFICABLE AREAS TO BE HEAVY DUTY.
- ALL LIFT PITS ARE TO BE FULLY TANKED UNLESS NOTED OTHERWISE.
- CHILD -PROOF LOCKING SYSTEM MUST BE EMPLOYED FOR ALL GRATES AND LIDS IN COMMON AREAS
- ALL GUTTERS WILL BE FITTED WITH LEAF GUARDS AND SHOULD BE INSPECTED AND CLEANED TO ENSURE LEAF LITTER CANNOT ENTER THE DOWNPIPES
- PROVIDE EMERGENCY OVERFLOW TO ALL PLANTER BOX AND BALCONIES.
- ALL PITS WITH DEPTH MORE THAN 900mm MUST HAVE IRON STEPS AND TO BE BENCHED AND STREAMLINED
- PROVIDE STORMWATER GRATE 200wx200D AT THE BASE OF ALL MECHANICAL SHAFTS AND UNCOVERED STAIRS OR OPENINGS.
- PRESSURIZED PIPES / RISING MAINS FROM PUMP OUT TANK TO BE CONNECTED DIRECTLY AND INDEPENDENTLY TO EITHER OSD TANK OR BOUNDARY PIT AS PER DESIGN PLANS.
- ENSURE ALL DRAINAGE WORKS ARE AWAY FROM TREE ROOTS
- SERVICES SHOWN ON THESE PLANS HAVE BEEN LOCATED FROM INFORMATION SUPPLIED BY THE RELEVANT AUTHORITIES AND FIELD INVESTIGATION AND ARE NOT GUARANTEED COMPLETE NOR CORRECT. IT IS THE CLIENT AND CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL PRIOR TO CONSTRUCTION.
- ALL VARIATIONS TO THE WORKS AS SHOWN ON THE APPROVED DRAWINGS ARE TO BE CONFIRMED BY SMART STRUCTURES AUSTRALIA PRIOR TO COMMENCEMENT OF WORKS.
- THE MINIMUM SIZES OF THE STORMWATER DRAINS SHALL NOT BE LESS THAN DN90 FOR CLASS 1 BUILDINGS AND DN100 FOR OTHER CLASSES OF BUILDING OR AS REQUIRED BY THE REGULATORY AUTHORITY
- ALL STORMWATER DRAINAGE PITS IN GARDEN OR TURFED AREAS TO BE FITTED WITH PERFORATED GALVANISED STEEL MESH UNDER THE LIDS TO PREVENT DEBRIS ENTERING STORMWATER NETWORK.
- PIPE INSTALLATION TO BE IN ACCORDANCE WITH THE REQUIREMENTS OF CURRENT AS3500.3 AND RELEVANT VOLUME OF NCC (NATIONAL CONSTRUCTION CODE). THIS IS CONTRACTOR'S RESPONSIBILITY TO CHECK IMPACT OF PIPE TRENCHING TO SURROUNDING STRUCTURAL AND NON STRUCTURAL ELEMENTS.

Project Number
250091

Address
**54 GARDERE AVENUE,
CURL CURL NSW 2096**

Revision
A

Sheet Number
D00

Address
**54 GARDERE AVENUE,
CURL CURL NSW 2096**

Start Date: **APRIL 2024**
Project No. **250091**

Client:
MR & MRS BRYDEN

Architect:
ALEX BRYDEN ARCHITECTURE

Approved by: **K.E.**

Internal Revisions:			
Rev. #	Drafter	Engineer	Date
A	F.E.	K.E.	17.04.25
ISSUE FOR D.A.			

- Notes
1. Drawings to be read in conjunction with architectural drawings.
 2. Refer to architectural drawings for all setout, levels.
 3. Do not scale any dimensions
 4. Drawings to be read & printed in colour.

**PRELIMINARY
NOT FOR CONSTRUCTION**


Project North

Scale @ A1: **AS SHOWN**


Sheet Name:
**BASEMENT
STORMWATER
DRAINAGE PLAN**


Sheet Number:

Revision:
D01
A



BASEMENT STORMWATER DRAINAGE PLAN
SCALE 1:100





D02
Revision:
A



SMART
STRUCTURES
AUSTRALIA

SUITE 2.04, L2, BLDG 3,
35-41 WATERLOO RD., MACQUARIE PARK, NSW 2111
info@smartstructs.com.au | T: (02) 9052 6467

54 GARDERE AVENUE,
CURL CURL NSW 2096

Client:
MR & MRS BRYDEN

Architect:
ALEX BRYDEN ARCHITECTURE

Approved by: **K.E**

Internal Revisions

Rev. #	Drafter	Engineer	Date
	Revision	Description	
A	F.E.	K.E.	04.04.25
	ISSUE FOR D.A.		

Notes

1. Drawings to be read in conjunction with architectural drawings.
2. Refer to architectural drawings for all setout, levels.
3. Do not scale any dimensions
4. Drawings to be read & printed in colour.

**PRELIMINARY
NOT FOR CONSTRUCTION**

Project North



Scale @ A1: AS SHOWN

Sheet Name:

GROUND FLOOR STORMWATER DRAINAGE PLAN

Sheet Number:

Revisions:

Address
**54 GARDERE AVENUE,
CURL CURL NSW 2096**

Start Date: **APRIL 2024**
Project No. **250091**

Client:
MR & MRS BRYDEN
Architect:
ALEX BRYDEN ARCHITECTURE

Approved by: **K.E.**

Internal Revisions:

Rev. #	Drafter	Engineer	Date
	Revision	Description	
A	F.E.	K.E. ISSUE FOR D.A.	17.04.25

Notes

1. Drawings to be read in conjunction with architectural drawings.
2. Refer to architectural drawings for all setout, levels.
3. Do not scale any dimensions
4. Drawings to be read & printed in colour.

**PRELIMINARY
NOT FOR CONSTRUCTION**

Project North



Scale @ A1: **AS SHOWN**


Sheet Name:
**ROOF STORMWATER
DRAINAGE PLAN**

Sheet Number:

D04

Revision:

A




COOKSEY AVENUE

AVENUE

GARDERE

ROOF STORMWATER DRAINAGE PLAN
SCALE 1: 100





SUIT 2.04, L2, BLDG 3,
35-41 WATERLOO RD., MACQUARIE PARK, NSW 2113
info@smartstructs.com.au | T: (02) 9052 6467

Address

54 GARDERE AVENUE,
CURL CURL NSW 2096

Start Date: APRIL 2024

Project No. 250091

Client:
MR & MRS BRYDEN

Architect:
ALEX BRYDEN ARCHITECTURE

Approved by: **K.E.**


Rev. #	Drafter	Engineer	Date
	Revision	Description	
A	F.E.	K.E.	04.04.25
	ISSUE FOR D.A.		

Notes

1. Drawings to be read in conjunction with architectural drawings.
2. Refer to architectural drawings for all setout, levels.
3. Do not scale any dimensions
4. Drawings to be read & printed in colour.

PRELIMINARY
NOT FOR CONSTRUCTION

Project North



Sheet Name:





**PRE & POST
DEVELOPMENT
CATCHMENT ANALYSIS**

Sheet Number:

D05

Revision:

A







PUMP SPECIFICATIONS
STANDARD PUMP-OUT NOTES

THE PUMP-OUT SYSTEM IS DESIGNED TO WORK IN THE FOLLOWING MANNER -


- 1. A LOW LEVEL FLOAT SHALL BE PROVIDED TO ENSURE THAT THE MINIMUM REQUIRED WATER LEVEL IS MAINTAINED WITHIN THE SUMP AREA OF THE BELOW GROUND TANK. IN THIS REGARD LOW LEVEL FLOAT WILL FUNCTION AS AN OFF SWITCH FOR THE PUMP AND TO SET 100mm ABOVE BOTTOM OF TANK TO ALLOW 100mm DEPTH OF WATER MAINTAINED AT ALL TIMES.
- 2. A SECOND FLOAT SHALL BE PROVIDED AT A HIGHER LEVEL, APPROXIMATELY 300mm ABOVE THE MINIMUM WATER LEVEL (I.E. 300mm ABOVE LOWER LEVEL FLOAT), WHEREBY THE PUMP WILL OPERATE & DRAIN THE TANK TO THE LEVEL OF THE LOW LEVEL FLOAT.
- 3. A THIRD FLOAT SHALL BE SET NOT HIGHER THAN 100mm ABOVE THE INVERT OF THE INLET PIPE. THIS FLOAT SHOULD ACTIVATE THE ALARM.
- 4. AN ALARM SYSTEM SHALL BE PROVIDED WITH A FLASHING STROBE LIGHT ALARM AND AN AUDIBLE ALARM WHICH ARE TO BE LOCATED AT THE DRIVEWAY ENTRANCE TO THE BASEMENT LEVEL. THE ALARM SYSTEM SHALL BE PROVIDED WITH A BATTERY BACK-UP IN CASE OF POWER FAILURE.
- 5. THE PUMP CONTROLS SHALL BE SET UP TO ENABLE ALTERNATE PUMP OPERATION AT EACH START. IN THE EVENT A PUMP FAILS TO OPERATE WHEN THE WATER LEVEL IN THE WET WELL REACHES THE PUMP START, THE OTHER PUMP SHALL BE ACTIVATED, AND A FLASHING STROBE LIGHT ALARM INITIATED. IN THE EVENT THAT BOTH PUMPS FAIL TO OPERATE, AN AUDIBLE ALARM SHALL BE INITIATED.
- 6. PUMPS SHALL BE FITTED WITH A GATE VALVE AND NON-RETURN VALVE ON THE DELIVERY SIDE OF EACH PUMP. THE VALVES SHOULD BE ACCESSIBLE WITHOUT HAVING TO ENTER THE WELL.

PUMP WELL DETAILS

MIN. VOLUME REQUIRED BY AS 3500 = 3.00 m³
STORAGE PROVIDED 2.0x1.50x1.0m = 3.00 m³
MIN. PUMP CAPACITY BY AS 3500 = 10.0 L/s
DUAL ZSS-220 PUMP OR EQUIVALENT TO BE INSTALLED IN SUMP AND CONNECTED TO CONTROL PANEL WHICH WILL ALLOW FOR THE PUMPS TO OPERATE SIMULTANEOUSLY ON HIGH LEVEL ALARMS AT 5.0L/sec (PER PUMP) AT 7.00m HEAD.




STEP IRON DETAIL
SCALE NTS
NOTE: INSTALL WHERE PITS ARE DEEPER THAN 900




SECTION THROUGH PUMP OUT PIT
SCALE: NTS


PUMP OUT PIT PLAN VIEW
SCALE NTS



SECTION THROUGH PUMP OUT PIT
SCALE: NTS



TYPICAL BASEMENT SECTION
SCALE NTS



SMART STRUCTURES AUSTRALIA
54 GARDERE AVENUE, CURL CURL NSW 2096
Address
Start Date: APRIL 2024
Project No. 250091
Client: MR & MRS BRYDEN
Architect: ALEX BRYDEN ARCHITECTURE
Approved by: K.E.
Internal Revisions:
Rev. # Drafter Engineer Date
Revision Description
A F.E. K.E. 17.04.25
ISSUE FOR D.A.
Notes
1. Drawings to be read in conjunction with architectural drawings.
2. Refer to architectural drawings for all setout, levels.
3. Do not scale any dimensions
4. Drawings to be read & printed in colour.
PRELIMINARY NOT FOR CONSTRUCTION
Project North
Scale @ A1: AS SHOWN
Sheet Name: STORMWATER DRAINAGE SECTIONS AND DETAILS SHEET 1
Sheet Number:
Revision:
D10
A

OSD DESIGN DETAILS
BASED ON Northern beaches COUNCIL'S water managment development policy 2021,(REGION2-CENTRAL CATCHMENT 9.3.2.3) OSD VOLUME REQUIRED IS CALCULATED AS PER BELOW:

TOTAL SITE AREA-LOT1: 266.10m²

SSR: 200X0.0266=5.322m³
PSD: 400X0.0266=10.644 l/s
ADJUSTED OSD VOLUME: 5.32-2.5=2.82m³
OSD VOLUME PROVIDED: 5.12m³
OSD VOLUME PROVIDED: 2.5 m³


2X 3000 LITER COMBINED OSD/RWT SYSTEM ARE PROPOSED FOR LOT 1 TO SATISFY COUNCIL'S REQUIREMENTS.

TOTAL SITE AREA-LOT2: 201.25m²

SSR: 200X0.0201=4.025m³
PSD: 400X0.0201=8.05 l/s
ADJUSTED OSD VOLUME: 4.025-2.5=1.52m³
OSD VOLUME PROVIDED: 2.72m³
RWT VOLUME PROVIDED: 2.50m³





2X 2500 LITER COMBINED OSD/RWT SYSTEM ARE PROPOSED FOR LOT 2 TO SATISFY COUNCIL'S REQUIREMENTS.

AS PER SECTION 9.3.2.1 , TO ACHIEVE A FULL CREDIT AGAINST THE DETERMINED OSD VOLUME RAINWATER REUSE MUST BE USED FOR FLUSHING OF TOILETS AS A MINIMUM, HOWEVER RAINWATER CAN BE USED FOR NON-POTABLE USAGE SUCH AS WATERING OF GARDENS, WASHING CARS, CLOTHES WASHING ETC.



RAINWATER TANK

TANK DETAILS SHOWN ARE A SUGGESTED CONFIGURATION ONLY. ANY MODIFICATION TO TANK VOLUME OR INLET AND OUTLET LEVELS MUST BE APPROVED BY ENGINEER PRIOR TO COMMENCEMENT OF CONSTRUCTION. TANK SHAPE , & DEVICES SHOWN ARE DIAGRAMMATIC ONLY. MINIMUM OF 450 CLEARANCE (UNLESS L.G.A. REQUIRES LARGER SETBACK) TO SIDE BOUNDARIES MUST BE MAINTAINED. CLIENT IS RESPONSIBLE TO ENSURE COMPLIANCE WITH THIS IN THE INSTALLED STATE. CHARGED STORM WATER LINES FROM ROOF AREAS ONLY TO RAINWATER TANK. ALL JOINTS TO BE SOLVENT WELDED. ALL EXPOSED PIPEWORK TO BE PAINTED TO WITHSTAND EXTERNAL ELEMENTS. FIRST FLUSH WATER DIVERTER AT TANK TO COMPLY WITH SYDNEY WATER AND COUNCIL DCP'S. AN APPROVED SWITCH SYSTEM SIMILAR TO 'RAINBANK' TO BE USED VIA MAINS. PUMPS TO MANUF. SPECS. RAIN TANK TO BE INSTALLED AND MAINTAINED TO MANUFACTURER'S SPECIFICATIONS AND TO COMPLY WITH ALL SYDNEY WATER GUIDELINES. CLIENT TO BE RESPONSIBLE FOR MAINTENANCE SYSTEM OF CHARGED PIPELINES. DEBRIS ACCUMULATION SIGNIFICANTLY AFFECT SYSTEMS PERFORMANCE. MAINTENANCE PROGRAM ESSENTIAL. STRUCTURAL DETAILS FOR TANK BASE BY MANUFACTURERS OR OTHERS.




Notes

- Drawings to be read in conjunction with architectural drawings.
- Refer to architectural drawings for all setout, levels.
- Do not scale any dimensions
- Drawings to be read & printed in colour.

**PRELIMINARY
NOT FOR CONSTRUCTION**

Project North



Scale @ A1: **AS SHOWN**

Sheet Name:

**EROSION AND
SEDIMENT CONTROL
PLAN AND DETAILS**


Sheet Number:

D15


Revision:

A


NOTES THIS DRAWING
1. ALL DOCUMENTS WILL BE SUBMITTED TO COUNCIL FOR APPROVAL.
2. ALL SEDIMENT CONTROL MEASURES ARE TO BE IN PLACE.
3. INSTALLATION OF SILT FENCING, SEDIMENTATION BARRIERS AROUND DRAINS.
4. FENCING IS TO BE 1.8m(min) HEIGHT, PLACED AROUND THE SITE UNTIL THE WORK COMPLETE.
5. THE SITE GATES WILL BE LOCATED AT COOKSEY AVENUE.
6. THE HARDSTAND AREAS OR CATTLE GRIDS WILL BE PLACED AT THE SITE ENTRANCES AND EXITS. TO REMOVE THE BULK OF DIRT AND MUD THAT MAY ACCUMULATE ON TRUCK TYRES.
7. CONTRACTOR WILL CONDUCT REGULAR STREET SWEEPS ALONG THE ACCESS ROUTE TO ENSURE THE ROADS ADJACENT TO THE SITE ENTRANCES ARE KEPT CLEAN OF ANY DIRT AND DEBRIS.
8. REGULAR ENVIRONMENTAL INSPECTIONS WILL BE CARRIED OUT BY CONTRACTOR'S PERSONNEL TO ENSURE COMPLIANCE WITH THIS PLAN.




CATTLE GRID ALTERNATIVE




TREE PROTECTION DETAIL




**GEOTEXTILE FILTER FABRIC DROP
INLET SEDIMENT TRAP**




SOIL STOCK PILE




SEDIMENT FENCE




SILT FENCE DETAIL




TEMPORARY CONSTRUCTION EXIT




HAY BALE DETAIL



TYPICAL DETAIL OF FILTRATION UNIT



STRAW BALE SEDIMENT FILTER



EROSION AND SEDIMENT CONTROL PLAN

SCALE 1:200

GENERAL INSTRUCTIONS:

SWM01
THESE PLANS PRESENT A CONCEPTUAL SOIL AND WATER MANAGEMENT PLAN (SWMP) ONLY AND SHOWS A POSSIBLE WAY OF MANAGING SOIL AND EROSION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE ESTABLISHMENT AND MANAGEMENT OF THE SITE AND PREPARING A DETAILED PLAN AND OBTAINING APPROVAL FROM THE RELEVANT AUTHORITY PRIOR TO THE COMMENCEMENT OF ANY WORKS.

SWM02
THIS PLAN IS TO BE READ IN CONJUNCTION WITH THE ENGINEERING PLANS AND ANY OTHER PLANS, WRITTEN INSTRUCTIONS, SPECIFICATION OR DOCUMENTATION THAT MAY BE ISSUED AND RELATING TO DEVELOPMENT OF THE SUBJECT SITE.

SWM03
THE CONTRACTOR WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE CONSISTENT WITH 'MANAGING URBAN STORMWATER - SOILS AND CONSTRUCTION' - ALSO KNOWN AS 'THE BLUE BOOK'.

SWM04
ALL BUILDERS AND SUB-CONTRACTORS SHALL BE INFORMED OF THEIR RESPONSIBILITIES IN MINIMISING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS.

EROSION CONTROL:

SWM05
WATER SHALL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNTIL SEDIMENT CONCENTRATION IS LESS THEN OR EQUAL TO 50MG/L. IE THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/ OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AND APPROVED STRUCTURE.

SWM06
ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD THE SURFACE WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.

SWM07
ACCEPTABLE RECEPTORS WILL BE CONSTRUCTED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER.

SWM08
'SEDIMENT' FENCING WILL BE INSTALLED AS INDICATED ON THE PLANS AND AT THE DIRECTION OF SITE SUPERINTENDENT TO ENSURE CONTAINMENT OF SEDIMENT. THE SEDIMENT FENCING WILL OUTLET OR OVERFLOW UNDER STABILISED CONDITIONS INTO THE SEDIMENT BASIN, TO SAFELY CONVEY WATER INTO A SUITABLE FILTERING SYSTEM SHOULD THE PORES IN THE FABRIC BLOCK.

SWM09
THE SEDIMENT BASINS WILL BE CONSTRUCTED WITH THE MINIMUM WET SEDIMENT CAPACITY OF CUM CURB METERS AND DESIGNED TO REMAIN STABLE IN AT LEAST THE 1 IN CDSE YEAR CRITICAL DURATION STORM EVENT. ARTIFICIAL FLOCCULATION OF THE FINER PARTICLES MAY NOT BE NECESSARY IN THIS INSTANCE.

SWM10
STOCKPILES SHOULD NOT BE LOCATED WITHIN 5M OF TREES AND HAZARD AREAS, INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS, DRAINAGE LINES, PAVED AREAS AND DRIVEWAYS. WHERE THEY ARE WITHIN 5M FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSTREAM WATERS. MEASURE SHOULD ALSO BE APPLIED TO PREVENT THE EROSION OF THE STOCKPILE.

SWM11
ALL CUT AND FILL BATTERS ARE TO BE SEEDED AND MULCHED WITHIN 14 DAYS OF COMPLETION OF FORMATION.

SWM12
ANY EXISTING TREES WHICH FORM PART OF THE FINAL LANDSCAPING PLAN WILL BE PROTECTED FROM CONSTRUCTION ACTIVITIES BY -
A. PROTECTING THEM WITH BARRIER FENCING OR SIMILAR MATERIALS INSTALLED OUTSIDE THE DRIP LINE.
B. ENSURING THAT NOTHING IS NAILED TO THEM.
C. PROHIBITING PAVING GRADING SEDIMENT WASH OR PLACING OF STOCKPILES WITHIN THE DRIP LINE EXCEPT UNDER THE FOLLOWING CONDITIONS :

- ENCROACHMENT ONLY OCCURS ON ONE SIDE AND NO CLOSER TO THE TRUNK THAN EITHER 1.5 METRES OR HALF THE DISTANCE BETWEEN THE OUTER EDGE OF THE DRIP LINE AND THE TRUNK, WHICHEVER IS THE GREATER.
- A DRAINAGE SYSTEM THAT ALLOWS AIR AND WATER TO CIRCULATE THROUGH THE ROOT ZONE (E.G. A GRAVEL BED) IS PLACED UNDER ALL FILL LAYERS OF MORE THAN 300 MILLIMETRES DEPTH,
- CARE IS TAKEN.

SWM13
DURING WINDY WEATHER, LARGE DISTURBED UNPROTECTED AREAS SHOULD BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL.

SWM14
TEMPORARY PROTECTION FROM EROSION FORCES WILL BE UNDERTAKEN ON LANDS WHERE FINAL SHAPING HAS NOT BEEN COMPLETED BUT WORKS ARE UNLIKELY TO PROCEED FOR PERIODS OF TWO MONTHS OR MORE (EG. ON TOP SOIL STOCKPILES). THIS MAY BE ACHIEVED WITH A VEGETATIVE COVER. A RECOMMENDED LISTING OF PLANT SPECIES FOR SOIL AND WATER MANAGEMENT NOTES:
TEMPORARY COVER IS -
I) AUTUMN/WINTER SOWING -OATS/RYECORN AT 20KG/HA
-JAPANESE MILLET AT 10KG/HA
II) SPRING/SUMMER SOWING -JAPANESE MILLET AT 20KG/HA
- OATS/RYECORN AT 10 KG/HA

SWM15
DIVERSION BANKS/ CHANNELS WILL BE REHABILITATED AS SOON AS POSSIBLE AND WITHIN 5 WORKING DAYS FROM THEIR FINAL SHAPING. OTHER THAN IN THE WINTER MONTHS, SUITABLE MATERIALS/S INCLUDE TURF GRASSES SUCH S COUCH OR KIKUYU. DURING WINTER, OR AT OTHER TIMES WHEN TEMPORARY REHABILITATION (MORE THAN 3 MONTHS) IS REQUIRED, IT IS SUGGESTED THAT HESSIAN CLOTH IS USED BUT ONLY IF TACKED WITH APPROPRIATE PEES AND AN ANIONIC BITUMEN EMULSION. FOOT AND VEHICULAR TRAFFIC SHOULD BE KEPT AWAY FROM THESE AREAS.

SWM16
UNDERTAKE SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. WHERE POSSIBLE, PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.

CONSTRUCTION SEQUENCE

SWM17
WHERE PRACTICAL, THE SOIL EROSION HAZARD ON THE SITE SHOULD BE KEPT AS LOW AS POSSIBLE. TO THIS END, WORKS SHOULD BE UNDERTAKEN IN THE FOLLOWING SEQUENCE -
I) INSTALL INLET SEDIMENT TRAPS TO ALL GULLY PITS FRONTING THE SITE.
II) INSTALL A 1.8M CHAIN WIRE FENCE AROUND THE BOUNDARIES AND ATTACH HESSIAN CLOTH OR SIMILAR TO IT ON THE WINDWARD SIDE (TIES AT THE TOP, CENTRE AND BOTTOM AND AT 1M INTERVALS OR AS INSTRUCTED BY THE SUPERINTENDENT).

III) INSTALL GEOFABRIC SEDIMENT FENCE AND SEDIMENT TRAPS AROUND ALL PERMANENT STORMWATER RETICULATION STRUCTURES AS SHOWN ON THE PLAN.
IV) CONSTRUCT STABILISED CONSTRUCTION ENTRANCE AS SHOWN ON THE PLAN OR TO LOCATION AS DETERMINED BY SUPERINTENDENT.
V) INSTALL DIVERSION BANKS ALONG THE BOUNDARY WHERE REQUIRED, REHABILITATE DISTURBED LANDS DOWNSLOPE FROM THE BASINS WITHIN 20 WORKING DAYS.
VI) ENSURE THAT THE SEDIMENT BASIN IS DIRECTED ONTO A TURED AREA AND DRAINS TO A SUITABLE LOCATION. A TEMPORARY STORMWATER LINE MAY BE NECESSARY TO CONVEY THE FLOWS TO THIS LOCATION. CONSTRUCT DIVERSION CHANNELS AT THE BOUNDARY TO DRAIN INTO THE SEDIMENT BASIN AS SHOWN ON PLANS.

VII) AT COMPLETION STABILISE SITE AND DECOMMISSION SEDIMENT BASIN AND ALL EROSION CONTROL DEVICES.

SWM18
TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.

SWM19
FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION ACTIVITIES.

SWM20
AT LEAST WEEKLY AND AFTER EVERY RAIN FALL EVENT, THE CONTRACTOR WILL INSPECT THE SITE AND ENSURE THAT -
I) DRAINS AND ALL SEDIMENT CONTROL DEVICES OPERATE EFFECTIVELY AND INITIATE REPAIR OR MAINTENANCE AS REQUIRED.

II) RECEPTORS FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER ARE TO BE EMPTED AS NECESSARY. DISPOSAL OF WASTE SHALL BE IN A MANOR APPROVED BY THE SUPERINTENDENT.


III) SPILL SAND (OR OTHER MATERIALS) IS REMOVED FROM HAZARD AREAS, INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS, GUTTERS, PAVED AREAS AND DRIVEWAYS.

IV) SEDIMENT IS REMOVED FROM BASINS AND / OR TRAPS WHEN LESS THAN 20M³ OF TRAPPING CAPACITY REMAIN PER 100M² OF DISTRIBUTED LANDS, AND OR LESS THAN 500 DEPTH REMAINS IN THE SETTLING ZONE. ANY COLLECTED SEDIMENT WILL BE DISPOSED IN AREAS WHERE FURTHER POLLUTION TO DOWN SLOPE LANDS AND WATERWAYS IS UNLIKELY.

V) REHABILITATED LANDS HAVE EFFECTIVELY REDUCED THE EROSION HAZARD AND INITIATE UPGRADING OR REPAIR AS APPROPRIATE.

SWM 21
THE CONTRACTOR SHALL PROVIDE ALL MONITORING CONTROL AND TESTING.

SYMBOLS



EROSION CONTROL NOTES

- ALL EROSION & SEDIMENT CONTROL MEASURES ARE TO BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH 'MANAGING URBAN STORMWATER, 3RD EDITION' PRODUCED BY THE NSW DEPARTMENT OF HOUSING.
- ALL EROSION AND SILTATION CONTROL DEVICES ARE TO BE PLACED PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION AND REMOVED REGULARLY DURING CONSTRUCTION
- ALL TREES ARE TO BE PRESERVED UNLESS INDICATED OTHERWISE ON THE ARCHITECT'S OR LANDSCAPE ARCHITECT'S DRAWINGS. EXISTING GRASS COVER SHALL BE MAINTAINED EXCEPT IN AREAS CLEARED FOR BUILDINGS, PAVEMENTS ETC- CONTRACTOR TO MINIMISE DISTURBED AREAS.
- INSTALL TEMPORARY SEDIMENT BARRIERS TO ALL INLET PITS LIKELY TO COLLECT SILT LADEN WATER
- NOT WITHSTANDING DETAILS SHOWN, IT IS THE CONTRACTORS' SOLE RESPONSIBILITY TO ENSURE THAT ALL SITE ACTIVITIES COMPLY WITH THE REQUIREMENTS OF THE CLEAN WATERS ACT.
- ALL DISTURBED AREAS AND STOCKPILES TO BE STABILISED WITHIN 14 DAYS. ALL STOCKPILES TO BE CLEARED FROM DRAINS, GUTTERS AND FOOTPATHS.
- TOPSOIL TO BE STRIPPED, STOCKPILED AND RE-SPREAD ON COMPLETION OF EARTHWORKS. NONE TO BE REMOVED.
- NO DISTURBANCE OF SITE PERMITTED OTHER THAN IMMEDIATE AREA OF THE WORKS.
- DRAINAGE IS TO BE CONNECTED TO STORMWATER SYSTEM AS SOON AS POSSIBLE. NON-COMPLIANCE MAY RESULT IN A \$1500 FINE