



ANTICIPATED DUST DISTURBANCE

NOTE: THE FOLLOWING CONSTRUCTION PROCESSES ARE ANTICIPATED TO GENERATE DUST:
SITE CLEARANCE
GROUND EXCAVATION
MASONRY MATERIAL DELIVERY

TO CONTROL DUST, A COMBINATION OF THE FOLLOWING MEASURES WILL BE IMPLEMENTED:
BOUNDARY FENCES FITTING WITH SHADE CLOTH
EXCAVATION - TO BE WATERED DOWN AT THE EXCAVATION FACE
MATERIAL STOCK PILES - TO BE WATERED DOWN AND COVERED WITH PLASTIC
SCAFFOLD - TO BE FITTED WITH SHADE CLOTH
TRUCKS - TIPPER TRAYS TO BE COVERED WITH PROTECTIVE SHADE CLOTH
SITE DISTURBANCE - KEEP TO A MINIMUM AT ANY ONE TIME
REDUCE WORKS ON HIGH WIND DAYS
REGULAR CLEAR DRY SEDIMENT MATERIAL FROM SEDIMENT BARRIERS
BROOM SWEEPING TO BE KEPT TO A MINIMUM

