

Nominated paver

Concrete filled block wall with

Waterproof membrane

- Blue metal aggregate

- PVC Ag slotted pipe

for concrete blocks


- Backfill


horizontal and vertical steel reinforcing

Reinforced concrete footing. Starter bars


Ground level


Existing soil





DETAIL DRAWINGS







All landscape drawings are to be read in conjunction with the architect and additional consultants' drawings, specifications, and All landscape drawings are to be read in conjunction with the architect and additional consultants' drawings, specifications, and reports.

All public utility services are to be located on site by the contractor prior to the commencement of works. The location, presence and extent of services shown are not guaranteed complete or correct.

Perform excavation in the vicinity of underground utilities with care and if necessary, by hand. The contractor bears all responsibility for the works. Disruption or damage to utilities shall be repaired immediately and no expense to the owner.

All paving is indicative and to be set out on site.

All work to be carried out in accordance with the local council's approval standards and codes.

The contractor is to ensure that all the works area carried out in accordance with the workplace health and safety act.

Nelson Thomas to review plant material at source prior to purchase and delivery. Exact locations of new plant materials to be set out and approved by Nelson Thomas before installation.

PRELIMINARIES

The following general information should be considered prior to the commencement of landscape works: landscape plans should be read in conjunction with architectural plans, hydraulic plans, service plans and survey prepared for the proposed development. All services should be accurately located and clearly marked prior to the commencement of any landscape installation. Installation of all conduits required for irrigation, electrical and other services shall be completed before any commencement of hardscapes works and hardstand pours.

All out outdoor lighting specified must be installed by a licenced electrician. Irregularities associated with this plan should be brought to the immediate attention of Nelson Thomas. Where an Australian Standard applies for any landscape materials or installation techniques, those standards shall be applied.

SITE PREPARATION
Pollution and sediment control
The contractor shall take proper precautions to prevent the erosion of soils from the site. Erosion and sediment control barriers shall be set up as required by council and maintained throughout the construction period.

TREE PROTECTION Any existing trees and vegetation to be retained shall be preserved and protected from damage of any sort during the execution of landscape works. Root systems of existing plants must not be disturbed. Any nearby site works should be carried out carefully using hand tools. Trees shall not be removed or lopped unless specific written approval to do so is given or is indicated on plan. Storage of materials, mixing of materials, vehicle parking, disposal of liquids, machinery repairs and refuelling, site office and sheds shall not occur within three (3) metres of any existing or new trees. Do not stockpile soil, rubble or other debris cleared from the site, or building materials within the drip line of existing or new trees.

All proposed planting areas to be deep ripped to 300mm. Clay soils to be combined with 50-100mm of A.N.L 'Organic clay breaker'. 75mm depth of A.N.L 'Organic garden mix' to be imported and combined with 25mm depth of A.N.L 'Greenlife' compact or approved.

TOPSOIL AND SOIL TESTING

Where possible, site topsoil should be used for garden beds and lawns. Strip the top 100mm layer of vegetation and stockpile on the site. Soil for use in garden bed and lawn areas may then be obtained from the stockpile soil provided the soil is clean and free from unwanted matter such as gravel, clay lumps, grass, weeds, building waste and any materials toxic to plants.

The soil must have a PH between 5.5 and 7.

Use 100% imported mix as above when site soils run out.

EXCAVATIONAll excavations are to be carried out in a safe manner. No excavations are to be carried out within the "zone of influence" of any adjacent/surrounding structures. Any excavation works are to include measures to ensure the temporary and long-term stability of any existing structure within its vicinity. During construction, the structure and surrounds shall be always kept stable utilizing temporary shoring, bracing etc.

INSTALLATION

CONCRETE SUB BASE AND FOOTINGS

All workmanship and materials shall be in accordance with AS3600. Concrete quality shall be verified by tests and all construction joints shall be located to the approval of the engineer. All concrete is to be cured by keeping the surfaces continuously wet for a period of 3 days followed by the prevention of loss of moisture for a further 7 days. All formworks shall be installed and stripped in accordance with AS3610. All formwork is to be free of debris prior to pouring of concrete.

All concrete is to engineer's specifications and inspection.

HARD CONSTRUCTION

All civil, structural, and hydraulic work associated with this project shall be to consulting engineers' details. All external stairs to be constructed in accordance with clause d2.13 of the building code of Australia. Materials specified include recycled brick, travertine pavers and sandstone blocks. Retaining walls all retaining walls over 600mm to be constructed to engineer's specifications.

RETAINING WALLS
Will be constructed in a variety of materials including recycled bricks and rendered block walls. Refer to drawings.

PAVING

All paving to be selected by client.

All paving to be laid to manufacturers recommendations. All paving adjacent to house to have a minimum fall of 1:100 directed away from residence. Sealing of all paving should be a consideration with the supplier.

DRAINAGE

To intercept rainwater at the bottom of a fall, install a grated surface drain at the edge of the paving. If draining a large area or you are likely to get a lot of silt in the runoff captured by the drain, install a sump or clean-out section between the drain and the stormwater pipe to collect soil and sand. Clean it out periodically.

ADVANCED TREES AND STAKING
Newly planted advanced trees are to be secured with 3 @ 1.8mm x 22mm x 22mm hardwood stakes with hessian ties to prevent excessive movement. Planting holes for plants are to be large enough to take the root ball with additional space for back fill with soil prepared as specified.

PLANTING AND ESTABLISHMENT

All plant material shall be planted as soon after delivery as possible.
Planting holes for trees and shrubs shall be excavated as detailed and specified.
Plant containers shall be removed and discarded.
The outer roots shall be gently teased from the soil mass. Immediately set plant in hole and backfill with specified soil mix incorporating the approved fertilizer for each plant type. Ensure that plants are set plumb vertically and root crown is level with finished soil level.
Hand water immediately.
Substitution of plant species/varieties must be signed off by client or landscape designer.
PLANTING

If the work to be done includes the provision and installation of grass and/or plants then the Client acknowledges that the grass and/or plants must be maintained by the Owner from the date that the landscape contractor is last on the site to carry out work.
The Owner agrees that Nelson Thomas will not be liable for any defect or damage to grass and/or plants unless written notification of any such defect or damage is given to within 7 days of landscape contractor last being on site to carry out work.
For the avoidance of doubt, the Client acknowledges that grass and plants are highly perishable and deteriorate rapidly in the absence of proper maintenance and that 7 days is sufficient time for the Client to identify any defect or damage and to notify Nelson Thomas of such defect or damage.

TURFTurf to be Buffalo sapphire. Turf to be laid on 50mm topsoil over 200mm deep rotary hoed prepared area. Turf areas to be evenly graded. Adequate drainage to be provided under lawn area. Keep irrigated.

MULCHING
All planting areas, unless otherwise specified to me mulched with A.N.L 'Droughtmaster' to 50mm deep with catchment dish to be left around base of plants.

FERTILISER

On completion of work all planting areas are to be fertilised with 'Osmocote pro (8-9mo) controlled release fertiliser' which is to be sufficiently watered in.

GARDEN EDGING
All planter beds adjacent to lawn areas to have flush 3mm ZAM steel.

WEED CONTROL Identify weed species and eradicate as per best horticultural practice. Ongoing maintenance plan to be discussed with client.

DRAINAGE AND IRRIGATION NOTES

Refer to engineer's utility and drainage plans for utility location and drainage information.

Requirements for landscape drainage to be confirmed on site unless otherwise shown on the landscape plans.

All planter boxes to have drip or spray irrigation.

All lawn areas to have pop up rotors. All garden beds to have fixed solid risers with sprays locations of irrigation lines, valves, spray heads etc are shown indicatively only and exact location will be nominated by the irrigation provider.

Plants require hand watering until established, in addition to irrigation.

Irrigation to be supplied by others.

POOL AND ENCLOSURE Nominated pool construction contractor to build pool to engineer's specifications.

Pool fencing material to comply Australian standards for pool enclosure requirements regarding height and gate fixtures. AS1926


EXTRAS80mm dia conduit required under all paving and paths for cable access.


GARDEN LIGHTS
See lighting plan. All works shall be completed by an authorised electrician.



<u>LEGEND</u>

LOWER GROUND FLOOR Scale: 1:150





GROUND FLOOR Scale: 1:150 BOUNDARY179° 44' 30" - 46.25 KITCHEN 5.8M x 4.0M TERRACE 5.5M - 1.2M x 13.0M ———— 15-Ligularia dentata reniformis

PERSPECTIVE VIEWS







FIRST FLOOR
Scale: 1:150 18-Poa 'Eskdale' — - 4-Euphorbia ingens 3-Euphorbia tirucalli 'Green Sticks' ——


PLANT SCHEDULE

ID	Qtv	Common Name	Botanical Name	Pot Size	Matura Haight	Mature Spread	TN
Trees	City	Common Name	Botanicai Name	r ot size	iviature rieigiit	Mature Spreau	۳
Bi	3	Coastal Banksia	Banksia integrifolia	75L	9000mm	4000mm	1
TIL	4	Water Gum Luscious	Tristaniopsis laurina	75L	8000mm	4000mm	1
Shrubs		Water Gam Eastroas	moterno por rearma	, 52	000011111	100011111	Ť
AcMB	8	New Zealand Rock Lilv	Arthropodium cirratum 'Matapouri Bay'	200mm	900mm	900mm	+
Bifs-1	7	Sentinel Banksia	Banksia integrifolia fastigiata 'Sentinel'	400mm	2500mm	1000mm	1
GI-1	12	White Gaura	Gaura lindheimeri 'White'	140mm	1000mm	1000mm	+
Ldr	15	Tractor Seat Plant	Ligularia dentata reniformis	200mm	800mm	800mm	t
Par	23	Plectranthus argentatus	Plectranthus argentatus	200mm	800mm	1000mm	1
WJG	15	Jervis Gem	Westringia 'Jervis Gem'	200mm	1200mm	1500mm	ī
Ground Covers							T
Cg	8	Aussie Rambler	Carpobrotus glaucescens	140mm	300mm	1000mm	1
CoCn	22	Silver Bush	Convolvulus cneorum	140mm	600mm	600mm	ī
Мра	6	Creeping Boobialla	Myoporum parvifolium	140mm	200mm	2000mm	1
Sm	13	Blue Chalk Sticks	Senecio mandraliscae	140mm	300mm	600mm	ī
Grasses							Ι
LirJR-1	75	Mat-rush	Lomandra confertifolia 'Seascape'	140mm	600mm	600mm	۱
Mss	26	Chinese Silver Grass	Miscanthus sinensis	140mm	1200mm	1200mm	ı
Pek	28	Tussock Grass	Poa 'Eskdale'	140mm	600mm	500mm	۱
Cacti							ı
Csi	5	Silver Torch	Cleistocactus strausii	200mm	2500mm	500mm	T
Succulents							Т
Aoo	4	Aloe Outback Orange	Aloe 'Outback Orange'	200mm	1000mm	900mm	Ť
EtGS	5	Green Sticks	Euphorbia tirucalli 'Green Sticks'	200mm	3000mm	1500mm	ī
Euln	7	Candelabra Tree	Euphorbia ingens	200mm	3000mm	900mm	T
CrMC	16	Jade Plant Max Cook	Crassula 'Max Cook'	200mm	600mm	600mm	ī
Abe	1	Tree Aloe	Aloidendron barberae	25L	6000mm	2000mm	ı
Ferns							Ι
Arm-1	20	Maindenhair Fern	Adiantum aethiopicum	140mm	500mm	500mm	I
Fwf	9	Fishbone Water Fern	Blechnum nudum	140mm	800mm	800mm	ı
Cci	3	Scaly Tree Fern	Cyathea cooperi	25L	8000mm	3000mm	۱

Council requirments

50% native plant count

Native plant count: 63%











DATE DRAWN 08.12.22

1458