

## Landscape Referral Response

<b>Application Number:</b>	DA2021/1801
<b>Date:</b>	05/11/2021
<b>Responsible Officer:</b>	Nick Keeler
<b>Land to be developed (Address):</b>	Lot 23 DP 23447 , 55 Woolgoolga Street NORTH BALGOWLAH NSW 2093

### Reasons for referral

This application seeks consent for the following:

- Construction / development works within 5 metres of a tree or
- New residential works with three or more dwellings. (RFB's, townhouses, seniors living, guesthouses, etc). or
- Mixed use developments containing three or more residential dwellings.
- New Dwellings or

### Officer comments

The application seeks consent for construction of a new dwelling with pool and associated landscape works.

Councils Landscape Referral section has considered the application against the Warringah Local Environmental Plan, and the following Warringah DCP 2011 controls:

I D1 Landscaped Open Space and Bushland Setting

I E1 Preservation of Trees or Bushland Vegetation

The Arboricultural Report prepared by Tree Talk and Landscape Plans provided are noted.

The Arborist's Report notes one non-exempt tree requires removal. Several other exempt tree species are also to be removed from the site and five other trees on the site are to be retained

The Tree to be removed, Tree 1 (*Eucalyptus* sp.) is indicated to have basal decay and adjacent to rock floaters which are to be removed for the works. In view of the above, retention of the tree is not considered desirable or achievable. No objections are raised to its removal.

Two Significant *Angophora costata* trees are located near the western boundary, and are indicated for retention. The Arborist's Report indicates that the trees can be retained subject to Arboricultural supervision. In view of the extent of excavation for the Ground level immediately adjacent to the calculated structural root zone, it is recommended that tree root mapping be undertaken in the areas of excavation to establish the presence or otherwise to significant roots that may be affected. The root mapping also requires liaison with structural engineers to address construction techniques to protect important roots prior to issue of Construction Certificate.

The Landscape Plan indicates replacement tree shrub and groundcover planting which is not objected to.

No objections are raised with regard to landscape issues subject to conditions as recommended.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

#### **Recommended Landscape Conditions:**

### **CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE**

#### **Tree Root Investigation and Tree Root Map**

Prior to the issue of a Construction Certificate a tree root mapping investigation for excavation areas adjacent to Trees 2 and 3 (*Angophora costata*) as identified in the Arboricultural Impact Assessment dated September 2021 prepared by Tree Talk Arboricultural Consulting, shall be undertaken and a Tree Root Map must be documented that will be the basis for determining construction methodology near existing trees 2 and 3.

An Arborist with minimum AQF Level 5 in arboriculture shall supervise the works to verify tree root locations. A non-destructive root investigation shall be conducted complying with clause 3.3.4 of AS 4970-2009 Protection of Trees on Development Sites.

The root investigation shall map existing roots of significance that must not be impacted by construction works. The tree root investigation shall be conducted to confirm the following data to be used for the location/alignment of any new proposed works:

- i) confirmation of the location of any tree roots at or >25mm (Ø) diameter to areas that require excavation for proposed works. Alternative alignment of proposed works shall be provided as necessary to avoid major roots, and
- ii) mapping of the suitable location/alignment of proposed works.

The Tree Root Map shall be issued to a qualified Structural Engineer as a basis for structural design, and for determining the final location/alignment and construction methodology of proposed works within the tree protection zone (TPZ).

Prior to the issue of a Construction Certificate, the Arborist shall provide certification to the Certifying Authority that the tree root investigation and clear distance recommendations have been adequately addressed in the Construction Certificate plans.

Reason: To ensure protection of vegetation proposed for retention or adjacent to the site.

### **CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT**

#### **Project Arborist**

A Project Arborist, with minimum AQF Level 5 in arboriculture, shall be engaged to provide tree protection measures in accordance with the Tree Root Mapping report, the Arboricultural Impact Assessment dated September 2021 prepared by Tree Talk Arboricultural Consulting and Australian Standard 4970-2009 Protection of Trees on Development Sites. The Project Arborist is to specify and oversee all tree protection measures such as tree protection fencing, trunk and branch protection and ground protection.

The Project Arborist is to supervise all demolition, excavation and construction works near all trees to be retained including construction methods near the existing trees to protect tree roots, trunks, branches and canopy. Where required, manual excavation is to occur ensuring no tree root at or >25mm (Ø) is damaged by works unless approved by the Project Arborist.

Existing ground levels shall be maintained within the tree protection zone of trees to be retained unless authorised by the Project Arborist.

All tree protection measures specified must:

- i) be in place before work commences on the site, and
- ii) be maintained in good condition during the construction period, and
- iii) remain in place for the duration of the construction works.

The Project Arborist shall provide certification to the Certifying Authority that all recommendations listed for the protection of the existing trees have been carried out satisfactorily to ensure no impact to the health of the trees. Photographic documentation of the condition of all trees to be retained shall be recorded including at commencement, during the works and at completion.

- Note:
- i) A separate permit or development consent may be required if the branches or roots of a protected tree on the site or on an adjoining site are required to be pruned or removed.
  - ii) Any potential impact to trees as assessed by the Project Arborist will require redesign of any approved component to ensure existing trees upon the subject site and adjoining properties are preserved and shall be the subject of a modification application where applicable.

Reason: Tree protection.

### **Tree Removal Within the Property**

This consent approves the removal of the following tree(s) within the property:

Tree number 1 as identified in the Arboricultural Impact Assessment dated September 2021 prepared by Tree Talk Arboricultural Consulting

- i)

Note: Exempt Species as listed in the Development Control Plan or the Arboricultural Impact Assessment do not require Council consent for removal.

Reason: To enable authorised building works.

## **CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK**

### **Protection of Landscape Features and Sites of Significance**

All natural landscape features including natural rock outcrops, natural vegetation, soil and watercourses are to remain undisturbed during demolition, excavation and construction works except where affected by works detailed on approved plans.

Should any Aboriginal Cultural Heritage items be uncovered during earthworks, works should cease in the area and the Aboriginal Heritage Office contacted to assess the finds.

Under Section 89a of the NPW Act should the objects be found to be Aboriginal, NSW Biodiversity and

Conservation Division, Heritage NSW and the Metropolitan Local Aboriginal Land Council (MLALC) should be contacted.

Reason: Preservation of significant environmental features.

### **Tree and Vegetation Protection**

- a) Existing trees and vegetation shall be retained and protected including:
  - i) all trees and vegetation within the site not approved for removal, excluding exempt trees and vegetation under the relevant planning instruments of legislation,
  - ii) all trees and vegetation located on adjoining properties,
  - iii) all road reserve trees and vegetation.
- b) Tree protection shall be undertaken as follows:
  - i) tree protection shall be in accordance with the Tree Root Mapping report, the Arboricultural Impact Assessment dated September 2021 prepared by Tree Talk Arboricultural Consulting and Australian Standard 4970-2009 Protection of Trees on Development Sites including the provision of temporary fencing to protect existing trees within 5 metres of development,
  - ii) existing ground levels shall be maintained within the tree protection zone of trees to be retained unless authorised by the Project Arborist,
  - iii) removal of existing tree roots at or >25mm (Ø) diameter is not permitted without consultation with the Project Arborist,
  - iv) no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,
  - v) structures are to bridge tree roots at or >25mm (Ø) diameter unless directed by the Project Arborist,
  - vi) excavation for stormwater lines and all other utility services is not permitted within the tree protection zone without consultation with the Project Arborist including advice on root protection measures,
  - vii) should either or all of v), vi) and vii) occur during site establishment and construction works, the Project Arborist shall provide recommendations for tree protection measures. Details including photographic evidence of works undertaken shall be submitted by the Arborist to the Certifying Authority,
  - viii) any temporary access to or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of Australian Standard 4970-2009 Protection of Trees on Development Sites,
  - ix) the activities listed in section 4.2 of Australian Standard 4970-2009 Protection of Trees on Development Sites shall not occur within the tree protection zone of any tree on the lot or any tree on an adjoining site,
  - x) tree pruning from within the site to enable approved works shall not exceed 10% of any tree canopy and shall be in accordance with Australian Standard 4373-2007 Pruning of Amenity Trees,
  - xi) the tree protection measures specified in this clause must: i) be in place before work commences on the site, and ii) be maintained in good condition during the construction period, and iii) remain in place for the duration of the construction works.

The Certifying Authority must ensure that:

- c) The activities listed in section 4.2 of Australian Standard 4970-2009 Protection of Trees on Development Sites do not occur within the tree protection zone of any tree and any temporary access to or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained on the site during the construction is undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of that standard.

Note: All street trees within the road verge and trees within private property are protected under Northern Beaches Council development control plans except where Council's written consent for removal has been obtained. The felling, lopping, topping, ringbarking or removal of any tree (s) is prohibited.

Reason: Tree and vegetation protection.

## CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

### **Landscape Completion**

Tree, shrub and groundcover planting is to be implemented in accordance with the approved Landscape Plan

Prior to the issue of any Occupation Certificate details (from a qualified horticulturalist, landscape architect or landscape designer) shall be submitted to the Principal Certifying Authority certifying that the landscape works have been completed in accordance with any conditions of consent.

Reason: Environmental amenity.

### **Condition of Retained Vegetation - Project Arborist**

Prior to the issue of any Occupation Certificate a report prepared by the project arborist shall be submitted to the Certifying Authority assessing the health and impact on all existing trees required to be retained including the following information:

- a) compliance to any Arborist recommendations for tree protection generally and during excavation works,
- b) extent of damage sustained by vegetation as a result of the construction works,
- c) any subsequent remedial works required to ensure the long term retention of the vegetation.

Reason: Tree protection.