GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER FORM NO. 1 – To be submitted with Development Application

Development Applicat	on for
	Name of Applicant
Address of site	45 Hillcrest Avenue, Mona Vale
	vers the minimum requirements to be addressed in a Geotechnical Risk Declaration made by r engineering geologist or coastal engineer (where applicable) as part of a geotechnical report
I, Ben White (Insert Name)	on behalf of White Geotechnical Group Pty Ltd (Trading or Company Name)

on this the ________ certify that I am a geotechnical engineer or engineering geologist or coastal engineer as defined by the Geotechnical Risk Management Policy for Pittwater - 2009 and I am authorised by the above organisation/company to issue this document and to certify that the organisation/company has a current professional indemnity policy of at least \$10million.

I:

Please mark appropriate box

- have prepared the detailed Geotechnical Report referenced below in accordance with the Australia Geomechanics Society's Landslide Risk Management Guidelines (AGS 2007) and the Geotechnical Risk Management Policy for Pittwater - 2009
- am willing to technically verify that the detailed Geotechnical Report referenced below has been prepared in accordance with the Australian Geomechanics Society's Landslide Risk Management Guidelines (AGS 2007) and the Geotechnical Risk Management Policy for Pittwater 2009
- have examined the site and the proposed development in detail and have carried out a risk assessment in accordance with Section 6.0 of the Geotechnical Risk Management Policy for Pittwater - 2009. I confirm that the results of the risk assessment for the proposed development are in compliance with the Geotechnical Risk Management Policy for Pittwater - 2009 and further detailed geotechnical reporting is not required for the subject site.
- have examined the site and the proposed development/alteration in detail and I am of the opinion that the Development Application only involves Minor Development/Alteration that does not require a Geotechnical Report or Risk Assessment and hence my Report is in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009 requirements.
- have examined the site and the proposed development/alteration is separate from and is not affected by a Geotechnical Hazard and does not require a Geotechnical Report or Risk Assessment and hence my Report is in accordance with the Geotechnical Risk Management Policy for Pittwater 2009 requirements.
- □ have provided the coastal process and coastal forces analysis for inclusion in the Geotechnical Report

Geotechnical Report Details:

Report Title: Geotechnical Report **45 Hillcrest Avenue, Mona Vale** Report Date: 16/12/24

Author: **BEN WHITE**

Author's Company/Organisation: WHITE GEOTECHNICAL GROUP PTY LTD

Documentation which relate to or are relied upon in report preparation:

Australian Geomechanics Society Landslide Risk Management March 2007.

White Geotechnical Group company archives.

I am aware that the above Geotechnical Report, prepared for the abovementioned site is to be submitted in support of a Development Application for this site and will be relied on by Pittwater Council as the basis for ensuring that the Geotechnical Risk Management aspects of the proposed development have been adequately addressed to achieve an "Acceptable Risk Management" level for the life of the structure, taken as at least 100 years unless otherwise stated and justified in the Report and that reasonable and practical measures have been identified to remove foreseeable risk.

Signature	lut
Name	Ben White
Chartered Professional Stat	us MScGEOLAusIMM CP GEOL
Membership No.	222757
Company	White Geotechnical Group Pty Ltd



GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER FORM NO. 1(a) - Checklist of Requirements for Geotechnical Risk Management Report for Development Application

Deve	elopment Application for
	Name of Applicant
Addı	ress of site 45 Hillcrest Avenue, Mona Vale
	Illowing checklist covers the minimum requirements to be addressed in a Geotechnical Risk Management Geotechnica t. This checklist is to accompany the Geotechnical Report and its certification (Form No. 1).
	chnical Report Details:
Repo	ort Title: Geotechnical Report 45 Hillcrest Avenue, Mona Vale
Repo	ort Date: 16/12/24
Auth	or: BEN WHITE
Auth	nor's Company/Organisation: WHITE GEOTECHNICAL GROUP PTY LTD
Please	e mark appropriate box
\triangleleft	Comprehensive site mapping conducted 14/10/20
	(date)
\boxtimes	Mapping details presented on contoured site plan with geomorphic mapping to a minimum scale of 1:200 (as appropriate)
\triangleleft	Subsurface investigation required
	□ No Justification
	⊠ Yes Date conducted <u>14/10/20</u>
\triangleleft	Geotechnical model developed and reported as an inferred subsurface type-section
\triangleleft	Geotechnical hazards identified
	⊠ Above the site
	\boxtimes On the site
	⊠ Below the site
	Beside the site
\triangleleft	Geotechnical hazards described and reported
\times	Risk assessment conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009
	⊠ Consequence analysis
	⊠ Frequency analysis
\times	Risk calculation
\times	Risk assessment for property conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 200
\triangleleft	Risk assessment for loss of life conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 20
\mathbf{X}	Assessed risks have been compared to "Acceptable Risk Management" criteria as defined in the Geotechnical Risk
	Management Policy for Pittwater - 2009
\mathbf{X}	Opinion has been provided that the design can achieve the "Acceptable Risk Management" criteria provided that the
	specified conditions are achieved.
\triangleleft	Design Life Adopted:
	⊠ 100 years
	□ Other
	specify
_	
\boxtimes	Geotechnical Conditions to be applied to all four phases as described in the Geotechnical Risk Management Policy for
	Pittwater - 2009 have been specified
X X	

I am aware that Pittwater Council will rely on the Geotechnical Report, to which this checklist applies, as the basis for ensuring that the geotechnical risk management aspects of the proposal have been adequately addressed to achieve an "Acceptable Risk Management" level for the life of the structure, taken as at least 100 years unless otherwise stated, and justified in the Report and that reasonable and practical measures have been identified to remove foreseeable risk.

Signature	ul	ite
Name		Ben White
Chartered Professional S	Status	MScGEOLAusIMM CP GEOL
Membership No.		222757
Company	White	e Geotechnical Group Pty Ltd





J5834. 16th December, 2024. Page 1.

GEOTECHNICAL INVESTIGATION:

Balcony Extension at **45 Hillcrest Avenue, Mona Vale**

1. Proposed Development

- **1.1** Extend the existing balcony at the downhill side.
- Details of the proposed development are shown on 14 drawings prepared by JJ Drafting, job number 1077/24, drawings numbered DA.01 to DA.14, Revision C, dated 16/12/24.

2. Site Description

2.1 The site was inspected on the 4th December, 2024 and previously on the 10th November, 2021 and the 14th October, 2020.

2.2 This residential property is on the low side of the road and has a SW aspect. It is located on the gentle to moderately graded upper reaches of a hillslope. The natural slope falls across the property at an average angle of ~12°. The slopes above and below the property decrease in grade.

2.3 At the road frontage, a concrete driveway runs down the slope to a garage attached to the house (Photo 1). Between the road frontage and the house is a garden area. The fill for the garden area is supported by a stable low rendered masonry retaining wall. The part two storey house is supported on masonry walls (Photos 2 & 3). The external supporting walls show no significant signs of movement. A cut provides a level platform for the N side of the house. The cut is lined by low sandstone flagging retaining wall or is supported by a stable sandstone block retaining wall up to ~1.6m high (Photo 4). A pool that shows no significant signs of movement is located downslope of the house (Photo 5). Stable rendered masonry and keystone retaining walls up to ~3.6m high support fills for lawn and paved areas across the



J5834. 16th December, 2024. Page 2.

downhill side of the property (Photos 6 to 8). No signs of slope instability were observed on the property. The adjoining neighbouring properties were observed to be in good order as seen from the street and subject property.

3. Geology

The Sydney 1:100 000 Geological Sheet indicates the site is underlain by the Newport Formation of the Narrabeen Group. This is described as interbedded laminite, shale, and quartz to lithic quartz sandstone.

4. Subsurface Investigation

Ten Dynamic Cone Penetrometer (DCP) tests were put down to determine the relative density of the overlying soil and the depth to weathered rock. The locations of the tests are shown on the site plan attached. It should be noted that a level of caution should be applied when interpreting DCP test results. The test will not pass through hard buried objects so in some instances it can be difficult to determine whether refusal has occurred on an obstruction in the profile or on the natural rock surface. This may have occurred for DCP5. Due to the possibility that the actual ground conditions vary from our interpretation there should be allowances in the excavation and foundation budget to account for this. We refer to the appended "Important Information about Your Report" to further clarify. The results are as follows:

DCP TEST RESULTS ON NEXT PAGE

White geotechnical group

Sydney, Northern Beaches & beyond. Geotechnical Consultants

J5834. 16th December, 2024. Page 3.

Equipment: 9	DCP TEST RESULTS – Dynamic Cone PenetrometerEquipment: 9kg hammer, 510mm drop, conical tip.Standard: AS1289.6.3.2 - 1997				
Depth(m) Blows/0.3m	DCP 1 (~RL41.0)	DCP 2 (~RL41.1)	DCP 3 (~RL41.0)	DCP 4 (~RL41.0)	DCP 5 (~RL41.0)
0.0 to 0.3	10	5	16	14	12
0.3 to 0.6	20	6	16	17	10
0.6 to 0.9	13	4	9	14	#
0.9 to 1.2	37	7	13	14	
1.2 to 1.5	19	8	8	33	
1.5 to 1.8	11	16	#	30	
1.8 to 2.1	17	40		19	
2.1 to 2.4	25	#		18	
2.4 to 2.7	40			18	
2.7 to 3.0	#			30	
3.0 to 3.3				#	
	End of Test @ 2.6m	End of Test @ 2.1m	Refusal on Rock @ 1.3m	Refusal on Rock @ 2.9m	Refusal @ 0.5m

#refusal/end of test. F=DCP fell after being struck showing little resistance through all or part of the interval.

DCP TEST RESULTS – Dynamic Cone Penetrometer Equipment: 9kg hammer, 510mm drop, conical tip. Standard: AS1289.6.3.2 - 199					S1289.6.3.2 - 1997
Depth(m) Blows/0.3m	DCP 6 (~RL41.0)	DCP 7 (~RL39.7)	DCP 8 (~RL36.6)	DCP 9 (~RL35.7)	DCP 10 (~RL36.8)
0.0 to 0.3	16	13	7	5	5
0.3 to 0.6	18	11	7	9	6
0.6 to 0.9	10	5	13	10	7
0.9 to 1.2	12	5	40	14	37
1.2 to 1.5	9	#	#	20	#
1.5 to 1.8	16			#	
1.8 to 2.1	40				
2.1 to 2.4	#				
	End of Test @ 2.0m	Refusal on Rock @ 1.0m	End of Test @ 1.2m	Refusal on Rock @ 1.3m	Refusal on Rock @ 1.2m

#refusal/end of test. F=DCP fell after being struck showing little resistance through all or part of the interval.

White geotechnical group

Sydney, Northern Beaches & beyond. Geotechnical Consultants

J5834. 16th December, 2024. Page 4.

DCP Notes:

DCP1 – End of Test @ 2.6m, DCP still very slowly going down, brown orange rock fragments on dry tip.

DCP2 – End of Test @ 2.1m, DCP still very slowly going down, orange clayey rock fragments on dry tip.

DCP3 – Refusal on Rock @ 1.3m, DCP bouncing off rock surface, orange clayey rock fragments on dry tip.

DCP4 – Refusal on Rock @ 2.9m, DCP bouncing, white, orange and red rock fragments on dry tip.

DCP5 – Refusal @ 0.5m, DCP bouncing, brown soil on dry tip.

DCP6 – End of Test @ 2.0m, DCP still very slowly going down, orange clay on dry tip.

DCP7 – Refusal on Rock @ 1.0m, DCP bouncing off rock surface, orange and white impact dust on dry tip.

DCP8 – End of Test @ 1.2m, DCP still very slowly going down, orange and white impact dust on dry tip.

DCP9 – Refusal on Rock @ 1.3m, DCP bouncing off rock surface, orange brown rock fragments on dry tip.

DCP10 – Refusal on Rock @ 1.2m, DCP bouncing off rock surface, white impact dust on dry tip.

5. Geological Observations/Interpretation

The slope materials are colluvial at the near surface and residual at depth. In the test locations, the ground materials consist of fill and topsoil over firm to stiff clays. Fill has been placed to form level lawn and paved areas at the downhill side of the property. The clays merge into the weathered zone of the under lying rocks at depths of between 1.0m to 2.9m below the current surface, being deeper in the filled areas. The weathered zone of the underlying rock is interpreted as Extremely Low to Low Strength Rock. It is to be noted that this material is a soft rock and can appear as a mottled stiff clay when it is cut up by excavation equipment. See Type Section attached for a diagrammatical representation of the expected ground materials.



J5834. 16th December, 2024. Page 5.

6. Groundwater

Ground water seepage is expected to move over the denser and less permeable clay and weathered rock layers in the sub-surface profile. Due to the slope and elevation of the block, the water table is expected to be many metres below the base of the proposed works.

7. Surface Water

No evidence of surface flows were observed on the property during the inspection. Normal sheet wash from the slope above will be intercepted by the street drainage system for Hillcrest Avenue above.

8. Geotechnical Hazards and Risk Analysis

No geotechnical hazards were observed beside the property. The gentle to moderately graded slope that falls across the property and continues above and below is a potential hazard (Hazard One).

Geotechnical Hazards and Risk Analysis - Risk Analysis Summary

HAZARDS	Hazard One	
	The gentle to moderate slope that falls across the property and	
ТҮРЕ	continues above and below failing and impacting on the	
	property.	
LIKELIHOOD	'Unlikely' (10 ⁻⁴)	
CONSEQUENCES TO	(Madium' (12%)	
PROPERTY	'Medium' (12%)	
RISK TO PROPERTY	'Low' (2 x 10 ⁻⁵)	
RISK TO LIFE	8.3 x 10 ⁻⁷ /annum	
COMMENTS	This level of risk is 'ACCEPTABLE'.	

(See Aust. Geomech. Jnl. Mar 2007 Vol. 42 No 1, for full explanation of terms)

White geotechnical group

Sydney, Northern Beaches & beyond. Geotechnical Consultants

J5834. 16th December, 2024. Page 6.

9. Suitability of the Proposed Development for the Site

The proposed development is suitable for the site. No geotechnical hazards will be created by the completion of the proposed development provided it is carried out in accordance with the requirements of this report and good engineering and building practice.

10. Stormwater

The fall is away from the street. The stormwater engineer is to refer to council stormwater policy for suitable options.

11. Excavations

Apart from those for footings, no excavations are required.

12. Site Classification

The site classification in accordance with AS2870-2011 is Class P due to the depth of the fill. The natural clays below the fill are interpreted to be moderately reactive.

13. Foundations

The proposed balcony extension is to be supported on piers taken to and embedded no less than 0.6m from the downhill edge of the footing into Extremely Low Strength Rock or better. This ground material is expected at depths of between ~1.3m to ~3.0m below the current surface, being deeper where the fill is deeper. A maximum allowable bearing pressure of 600kPa can be assumed for footings embedded in Extremely Low Strength Rock or better. It should be noted that this material is a soft rock and a rock auger will cut through it so the builders should not be looking for refusal to end the footings.

The foundations supporting the existing house and balcony are currently unknown. Ideally, footings should be founded on the same footing material across the old and new portions of the structure. Where the footing material does change across the structure construction joints or similar are to be installed to prevent differential settlement, where the structure cannot tolerate such movement.



J5834. 16th December, 2024. Page 7.

As the bearing capacity of weathered rock reduces when it is wet we recommend the footings be dug, inspected and poured in quick succession (ideally the same day if possible). If the footings get wet, they will have to be drained and the soft layer of weathered rock on the footing surface will have to be removed before concrete is poured.

If a rapid turnaround from footing excavation to the concrete pour is not possible a sealing layer of concrete may be added to the footing surface after it has been cleaned and inspected.

NOTE: If the contractor is unsure of the footing material required it is more cost effective to get the geotechnical professional on site at the start of the footing excavation to advise on footing depth and material. This mostly prevents unnecessary over excavation in clay like shaly rock but can be valuable in all types of geology.

14. Geotechnical Review

The structural plans are to be checked and certified by the geotechnical engineer as being in accordance with the geotechnical recommendations. On completion, a Form 2B will be issued. This form is required for the Construction Certificate to proceed.

15. Inspection

The client and builder are to familiarise themselves with the following required inspection as well as council geotechnical policy. We cannot provide geotechnical certification for the Occupation Certificate if the following inspection has not been carried out during the construction process.

 All footings are to be inspected and approved by the geotechnical consultant while the excavation equipment and contractors are still onsite and before steel reinforcing is placed or concrete is poured.



J5834. 16th December, 2024. Page 8.

White Geotechnical Group Pty Ltd.

dulan

Dion Sheldon BEng(Civil)(Hons) MIEAust NER, Geotechnical Engineer.



Reviewed By:

landner

Nathan Gardner B.Sc. (Geol. & Geophys. & Env. Stud.) AIG., RPGeo Geotechnical & Engineering. No. 10307 Engineering Geologist & Environmental Scientist.





J5834. 16th December, 2024. Page 9.



Photo 1



Photo 2

White Geotechnical Group ABN 96164052715 www.whitegeo.com.au Phone 027900 3214



J5834. 16th December, 2024. Page 10.



Photo 3



Photo 4

White Geotechnical Group ABN 96164052715

www.whitegeo.com.au Phone 027900 3214



J5834. 16th December, 2024. Page 11.



Photo 5



Photo 6

White Geotechnical Group ABN 96164052715

www.whitegeo.com.au Phone 027900 3214



J5834. 16th December, 2024. Page 12.



Photo 7



Photo 8

White Geotechnical Group ABN 96164052715 www.whitegeo.com.au Phone 027900 3214



J5834. 16th December, 2024. Page 13.


Important Information about Your Report

It should be noted that Geotechnical Reports are documents that build a picture of the subsurface conditions from the observation of surface features and testing carried out at specific points on the site. The spacing and location of the test points can be limited by the location of existing structures on the site or by budget and time constraints of the client. Additionally, the test themselves, although chosen for their suitability for the particular project, have their own limiting factors. The testing gives accurate information at the location of the test, within the confines of the test's capability. A geological interpretation or model is developed by joining these test points using all available data and drawing on previous experience of the geotechnical consultant. Even the most experienced practitioners cannot determine every possible feature or change that may lie below the earth. All of the subsurface features can only be known when they are revealed by excavation. As such, a Geotechnical report can be considered an interpretive document. It is based on factual data but also on opinion and judgement that comes with a level of uncertainty. This information is provided to help explain the nature and limitations of your report.

With this in mind, the following points are to be noted:

- If upon the commencement of the works the subsurface ground or ground water conditions prove different from those described in this report, it is advisable to contact White Geotechnical Group immediately, as problems relating to the ground works phase of construction are far easier and less costly to overcome if they are addressed early.
- If this report is used by other professionals during the design or construction process, any questions should be directed to White Geotechnical Group as only we understand the full methodology behind the report's conclusions.
- The report addresses issues relating to your specific design and site. If the proposed project design changes, aspects of the report may no longer apply. Contact White Geotechnical if this occurs.
- This report should not be applied to any other project other than that outlined in section 1.0.
- This report is to be read in full and should not have sections removed or included in other documents as this can result in misinterpretation of the data by others.
- It is common for the design and construction process to be adapted as it progresses (sometimes to suit the previous experience of the contractors involved). If alternative design and construction processes are required to those described in this report, contact White Geotechnical Group. We are familiar with a variety of techniques to reduce risk and can advise if your proposed methods are suitable for the site conditions.

SITE PLAN – showing test locations




by a practicing engineer.

ACN 651 698 346

	DATE:	DRAWN BY:	SCALE:
	DEC/24	PP	1:200 @ A3
JOB No:		CHECKED BY:	DRAWING Nα
1077/24		JJ	DA.02

TYPE SECTION – Diagrammatical Interpretation of expected Ground Materials





SPECIFICATION NOTES

INTERNAL LINING - PROVIDE PLASTERBOARD LINING. INSTALL TO MANUFACTURERS SPECIFICATIONS & AS 2589

EXTERNAL WALLS:

BRICK VENEER WALLS WITH SELECTED BRICKS TO DWELLING

LIGHTWEIGHT TIMBER OR COMPOSITE WALL CLADDING IN ACCORDANCE WITH NCC VOL 2 PART 3.54. LIGHTWEIGHT METAL WALL CLADDING IN ACCORDANCE WITH NCC VOL 2 PART 3.5.5.

FLOOR: - GROUND FLOOR TO BE REINFORCED CONCRETE SLAB IN ACCORDANCE WITH AS2870. FIRST FLOOR TO BE TIMBER FRAMED FINISHED WITH TAG HARDWOOD FLOORING.

WET AREAS:

ALL WATERPROOFING TO AS 3740 PROVIDE A GUARANTEED FLEXIBLE WATERPROOF MEMBRANE TO ALL WET AREA FLOORS & SHOWERS WALLS TO MANUFACTURES INSTRUCTIONS

BEARERS AND JOISTS:

SHALL BE INSTALLED TO COMPLY WITH AS1684 AS AMENDED FOR TIMBER COMPONENTS OR AS3620 FOR LIGHTWEIGHT STEEL FRAMING SECTIONS OR AS PER THE NASH ALTERNATIVES TO AS 3623.

ANT CAPS:

- SHALL BE INSTALLED IN ACCORDANCE WITH AS3680.

PROFILED STEEL ROOF:

- COLORBOND ROOF CLADDING NCC VOL 2 PART 3.5.1. DESIGN AND INSTALLATION SHALL BE IN ACCORDANCE WITH ASINZS 1562.

ROOF TILES OR SHINGLES: - NCC VOL 2 PART 3.5.2

CONCRETE:

SHALL BE IN ACCORDANCE WITH NCC VOL 1 PART B1.4 OR VOL 2 PART 3.2.3. ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH CURRENT EDITIONS OF THE

FOOTINGS:

 FOOTINGS TO BE IN ACCORDANCE WITH AS 1480.
 FOOTINGS TO BE IN ACCORDANCE WITH NCC VOL2 PARTS 3.2.3, 3.2.4 AND 3.2.5 ALL REINFORCEMENTS SHALL CONFORM TO AS1302, AS1303 AND AS1304

BRICK AND BLOCKWORK: - CONSTRUCTION OF MASONRY BUILDINGS SHALL BE AS PER AS3700 OR AS4773.

CARPENTRY

TIMBER TO COMPLY WITH AS 1170.2 OR AS4055. ALL WORKMANSHIP AND MATERIALS SHALL BE N ACCORDANCE WITH AS 1684 AND 1720 AS APPLICABLE.

TIMBER FRAMING:

TO COMPLY WITH NCC VOL2 PART 3.4 - GROUND FLOOR TIMBERS SHALL BE ONLY OF HARDWOOD, CYPRESS PINE OR PRESSURE TREATED RADIATA OR CANADA PINE BELOW A HEIGHT OF 300mm ABOVE FINISHED GROUND LEVEL AND MUST NOT BE BUILT INTO BRICKWORK.

- SUBFLOOR VENTILATION SHALL CONFORM TO NCC VOL 2 PART 3.4.1. IN BUSHFIRE PRONE AREAS SPECIAL CONDITIONS APPLY. WHERE TERMITE BARRIERS NEED TO BE INSPECTED, 400mm CLEARANCE IS REQUIRED BETWEEN THE
- UNDERSIDE OF BEARER AND GROUND SURFACE. USE TREATED TIMBER WHERE REQUIRED FOR DURABILITY.

DO NOT USE TIMBER UNSUITABLE FOR EXPOSURE TO MOISTURE IN EXPOSED LOCATION. PROVIDE STRUCTURE BRACING IN ACCORDANCE WITH AS 1684 PROVIDE STRUCTURE TIEDOWN IN ACCORDANCE WITH AS 1684 USE GALVANISED FIXINGS WHERE EXPOSED TO WEATHER

TERMITE CONTROL: - TO BE IN ACCORDANCE WITH TO AS3660.1

SHALL BE IN ACCORDANCE WITH NCC VOL 2 PART 3.1.4 OR VOL 1 PART B1.4.

FLASHING AND CAPPINGS:

SELECTION AND INSTALLATION OF METAL RAINWATER GOODS REFER TO A\$2180 FLASH PROJECTIONS ABOVE THE ROOF WITH TWO PART FLASHINGS CONSISTING OF AN APRON FLASHING AND OVER FLASHING, WITH AT LEAST 100mm OVERLAP PROVIDE FOR INDEPENDENT MOVEMENT BETWEEN ROOF AND PROJECTION.

CONCRETE BLOCKS OR BRICKS:

COMPLY WITH TO AS4455 MASONRY BUILDING BLOCKS/PAVER

LIGHTING:

- 40% OF NEW OR ALTERED LIGHT FIXTURES TO BE FITTED WITH FLUORESCENT, COMPACT FLUORESCENT, OR LIGHT-EMITTING-DIODE (LED) LAMPS

DOORS & WINDOWS:

ALL FRAMED WINDOWS SHALL BE INSTALLED IN ACCORDANCE WITH AS2047-48 FOR ALUMINIUM WINDOWS AND AS2047 FOR TIMBER WINDOWS.

ALUMINIUM FRAMED WINDOWS AND DOORS.

WEATHER STRIPPING IS TO BE PROVIDED TO ALL EXTERNAL WINDOWS AND DO ORS.

STAIRS. HANDRAILS AND BALUSTRADES:

- NCC VOL 2 PARTS 39.1 AND 39.2 RELATIONSHIP OF RISER TO GOING SHALL BE BETWEEN 12 AND 1:1.35 UNLESS OTHERWISE DIRECTED TO GOING SHALL BE BETWEEN 12 AND 1:1.35 UNLESS OTHERWISE DIRECTED OR AS PERMIT TED IN

AS1657 BALLISTRADES SHALL BE PROVIDED TO ALL LANDINGS, RAMPS, DECKS, ROOFS AND OTHER ELEVATED PLATFORMS WHERE THE VERTICAL DISTANCE FROM THAT LEVEL IS MORE THAN 1m ABOVE THE ADJOINING FLOOR OR FINISHED GROUND LEVEL

- THE HEIGHT OF BALLISTRADE MUSTBE A MINIMUM OF 1m HIGH ABOVE LANDING AND NOT LESS THAN 865mm ABOVE THE NOSINGS OF ANY STAR TREADS OR FLOOR RAMP AND HAVE NO OPENING GREATER THAN 125mm


THE HEIGHT OF BALUSTRADE TO THE NEW STAIRCASES IS TO BE MEASURED A MINIMUM 865mm ABOVE THE NOSING LINE AND HAVE NO OPENING GREATER NO OPENING GREATER THAN 125mm

SLIP RESISTANCE:

MATERIALS TO BE USED FOR SURFACES OF FLOORS, STAIR LANDING, STEPS AND NOSINGS SHALL BE IN ACCORDANCE WITH THE CLASSIFICATIONS FOR SLIP RESISTANCE AS APPLY IN AS4586 AND HB198.

STORNWATER:

EAVES GUTTERS, VALLEY GUTTERS AND DOWPIPES TO COMPLY WITH ASINZS 2179 FOR METAL AND AS1273 FOR UPVC COMPONENTS. IN ACCORDANCE WITH NCC VOI 2 PART 35.3 NEW DOWNPIPES TO BE CONNECTED INTO EXISTING STORMWATER LINE - COLORBOND GUTTERS AND DOWNPIPES MINIMUM SLOPE OF EAVES AND GUTTERS 1:200



Narrabeen Group Rocks – Extremely Low to Low Strength Rock - after being cut up by excavation equipment can resemble a stiff to hard clay.

ENDED & SQUARED OFF
D
-NEW POSTS & STRUCTURE BY ENG.
SECTION A
WATER ROOFING FOR EXTERNAL TILED BALCONES:
- WATERPROOFING TO COMPLY WITH A\$4654
GLAZING: - NCC VOL.1 PARTS B 1.4, D 3.12, F1.13 OR NCC VOL.2 PART 3.6
SMOKE DETECTORS/ALARMS: - NCC VOL 2PART 3.7.5. FIRE/SMOKE DETECTORS COMPLYING WITH THE REQUIREMENTS OF THE LOCAL
GOVERNMENT ACT AND/OR STATE OR TERRITORY REGULATIONS MUST BE FITTED IN THE LOCATIONS REQUIRED AND APPROVED BY THE AUTHORITY AND SHALL BE INSTALLED IN ACCORDANCE WITH AS3786.
 INSTALLATIONS IN BUILDINGS OTHER THAN CLASS 1 AND 10 MUST BE INSTALLED AND MANAGED TO COMPLY WITH NCC SPEC. E2.2a.
 MULTIPLE ALARMS WITHIN HOUSES AND SOLE OCCUPANCY UNITS MUST BE HARD WIRED AND INTERCONNECTED.
WASTE MANAGEMENT:

- ALL WASTE SHALL BE TAKEN AWAY BY TRUCKS TO A SUITABLE LANDFILL OR RECYCLE DEPOT. - ALL WASTE SHALL BE COVERED DURING TRANSPORTATION. - WASTE GENERATED DURING CONSTRUCTION SHALL BE PLACED IN STEEL BINS AND TAKEN AWAY BY AN APPROVED CONTRACTOR TO A APPROVED LANDFILL SITE.

SEDMENT CONTROL:

- A FILTER CLOTH SYSTEM SHALL BE INSTALLED TO STOP ANY SEDIMENT ENTERING COUNCILS STORMWATER SYSTEM.

NOTE:

ALL PLANS ARE TO BE READ IN CONJUNCTION AND COMPLY WITH THE BASIX CERTIFICATE, BUSHFIRE AND GEOTECH REPORTS.

DATE:	DRAWN BY:	scale:
DEC/24	PP	1:100 @ A3
 JOB No:	CHECKED BY:	DRAWING Nα
1077/22	JJ	DA.12



EXAMPLES OF **POOR** HILLSIDE PRACTICE

