

STORMWATER

NOTES

- All roof collection components (ie gutters / DPs etc) are to be located / sized by the Developments Hydraulic Consultant to BCA / NCC requirements and is to accommodate the 2% AEP storm event.
- All Trunk Drainage pipes, as shown on this plan are to be minimum of 90mm dia uno.
- All pipes to be uPVC to AS 1254:2002.
- All pipes to be laid at the grade required to match pit invert levels.
- All pipes to be installed and laid in accordance with AS 3500.3:2003.
- Thrust blocks to be installed to the trunk drainage pipes in accordance with AS 3500.3:2003.
- All roof guttering/ down pipes / valley gutters / box gutters etc are to be sized and installed in accordance with AS 3500.3:2003.
- All pits are to be proprietary uv resistant polypropylene or similar unless noted (approved by the Engineer) and are to include a min 50mm sediment trap in the base and a maximesh screen laid at 45° across the pit to protect the outlet pipe.
- All pits greater than 600mm in depth are to be proprietary precast concrete (approved by the Engineer).
- All pits greater than 1000mm in depth are to have adequate access requirements in accordance with OH&S/Workover requirements (ie; minimum dimensions 900x600mm with step irons).
- All works are to be inspected and certified by the Principle Certifying Authority prior to backfilling.
- All works requiring certification by the Engineer will require a works as executed survey prepared by a registered Surveyor detailing all levels etc as on the Engineering plans.
- The system is to be flushed and cleaned of all sediment and debris annually.
- The system will require regular cleaning and maintenance to ensure its ability to function is maintained.
- To ensure the system's ability to function is maintained it is to be inspected and certified as operating effectively by a licensed plumber every 5 years, and a engineer every 20yrs.

SITE STORMWATER MANAGEMENT PLAN


~1:100

Proposed residential development refer to plans by Gartner Trovato Architects for details FFLs 4.46 / 7.66. All roof areas to drain to BASIX tanks as per BASIX certificate requirements (detailing by others with CC documentation). **System disposal to be via on site absorption trenches located below each building** (note approx. 1m elevation/suspension of buildings from NGLs for flood protection). Trunk Drainage system only shown, detailed drainage/hydraulic system to be issued by a hydraulic consultant for Construction Certificate documentation. Variations to layout to be reviewed and approved by Barrenjoey Consulting Engineers before construction.

Councils Water Management for Development Policy -


5.5 Stormwater Drainage from Low Level Properties Section 5.5.1.1.2 Stage 2 – Onsite Stormwater Absorption. Noting means of disposal in Stage 1 are not available, the use of an on-site absorption system to be adopted, refer site storm water / sub strata / absorption calculation summary for details.

Section 9.3.1 Onsite Stormwater Disposal Requirements Region 1 – Northern Catchments Onsite Stormwater Detention is not applicable/ practical due to the sites location within the predicted 1% AEP flood extents and considering that any stormwater detention system may exacerbate flood conditions / extents etc.




EXISTING SITE SURVEY

CC SURVEYING Job No 5190
~ NTS



**PIT DETAIL
SEDIMENT / GROSS
POLLUTANT CONTROL**

NTS



**TYPICAL PIPE
& TRENCH DETAIL**

~ NTS

ISSUE:	DATE:	DESCRIPTION:
Prelim	05. 02. 2024	Issued for comment
DA	22. 02. 2024	Issued for DA submission
DA - A	26. 09. 2024	revised outlet to onsite absorption

Barrenjoey Consulting Engineers Pty Ltd
Stormwater Structural Civil
PO Box 672
Avalon NSW 2107
M: 0418 620 350
E: lucas@barrenjoey.com.au
ABN: 13124694917
ACN: 124694917

PROJECT:
**PROPOSED DUPLEX
8 SEA BEACH AVENUE
MONA VALE**

DRAWING :
**STORMWATER MANAGEMENT
PLAN**

Job No :
240105

Drawing No
SW1A-A


Document Certification
Barrenjoey Consulting Engineers Pty Ltd
per
Lucas Molloy MEA CPEng NER Director

SITE STORM WATER / SUB-STRATA / ABSORPTION CALCULATION SUMMARY


as per Barrenjoey Consulting Engineer pty ltd site investigation 25 / 09 / 2024

Section 5.5.1.1.2 Stage 2 – Onsite Stormwater Absorption
Appendix 3 On-site Absorption Design Guideline

Depth to rock	- approx 3m (ie RL 0.0m AHD)
Depth to the water table	- none encountered
Measured infiltration rate	- 1.6 l / s / m ²
Infiltration rate that can be maintained in the long term (infiltration rate is based on bore hole geometry)	- 0.8 l / s / m ²
Minimum distance any infiltration system should be located clear of property boundaries	- 3m
Whether the use of infiltration is likely to cause seepage problems to the proposed structure or to any adjoining properties	- no likely problems as absorption systems used on the existing and adjoining properties
The use of any waterproofing to protect underground areas	- not applicable as no underground areas to the proposed development or to surrounding properties
Any special requirements for the design of walls or footings on the site.	- foundations to be piered / piled to below RL 2.0m AHD (ie 1m below the proposed absorption system)
The absorption pit is designed for a 2% AEP storm using DRAINS computer software - based on the infiltration rate that can be maintained in the long term.	
Western system	
Area draining to western absorption system	- 230m ²
2% AEP storm flow rate	- 17 l/s
Infiltration rate that can be maintained in the long term	- 0.8 l / s / m ²
Proposed absorption trench base area	- 22m ²
Total infiltration that can be maintained in the long term	- 17.6 l/s > 2% AEP storm flow rate
Eastern system	
Area draining to western absorption system	- 200m ²
2% AEP storm flow rate	- 15 l/s
Infiltration rate that can be maintained in the long term	- 0.8 l / s / m ²
Proposed absorption trench base area	- 19m ²
Total infiltration that can be maintained in the long term	- 15.2 l/s > 2% AEP storm flow rate
An overflow mechanism in the form of a level spreader must be provided for all storms greater than the 2% AEP storm, up to and including the 1% AEP storm.	- not applicable as site inundated with floodwaters during the 1% AEP storm.



SUB STRATA ABSORPTION DETAIL
COARSE SAND
as per BCE_{pty ltd} site investigation 25 / 09 / 2024



EXISTING SITE STORMWATER DISPOSAL / ABSORPTION
as per BCE_{pty ltd} site investigation 25 / 09 / 2024

ISSUE:		
DA - A	26. 09. 2024	revised outlet to onsite absorption

Barrenjoey Consulting Engineers pty ltd
Stormwater Structural Civil
PO Box 672
Avalon NSW 2107
M: 0918 620 350
E: lucas@bcebigpond.com
ABN: 13124694917
ACN: 124694917

PROJECT:
PROPOSED DUPLEX
8 SEA BEACH AVENUE
MONA VALE

DRAWING :
STORMWATER MANAGEMENT
DETAILING 1

Job No :
240105

Drawing No
SW1_{DA}

Document Certification
Barrenjoey Consulting Engineers pty ltd
per
Lucas Molloy MEA CPEng NER Director

09'24