

## Water Management Referral Response

<b>Application Number:</b>	DA2020/0021
<b>Date:</b>	28/02/2020
<b>To:</b>	Lashta Haidari
<b>Land to be developed (Address):</b>	Lot 11 DP 1193189 , Pittwater Road COLLAROY NSW 2097

### Reasons for referral

Council's Water Management Officers are required to consider the likely impacts.

### Officer comments

No objections are raised to the proposed development, subject to conditions.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

### Recommended Water Management Conditions:

## CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

### Soil and Water Management Plan

A Soil and Water Management Plan (SWMP) shall be prepared by a suitably qualified Civil Engineer, who has membership to the Institution of Engineers Australia, National Professional Engineers Register (NPER-3) and implemented onsite prior to commencement. The SWMP must meet the requirements outlined in the Landcom publication Managing Urban Stormwater: Soils and Construction - Volume 1, 4th Edition (2004) and Council's Water Management Policy. The SWMP must include the following as a minimum:-

- Site boundaries and contours;
- Vehicle access points, proposed roads and other impervious areas (e.g. parking areas and site facilities)
- Location of all drains, pits, downpipes and waterways on and nearby the site;
- Planned stages of excavation, site disturbance and building;
- Stormwater management and discharge points;
- Integration with onsite detention/infiltration;
- Sediment control basin locations and volume (if proposed);
- Proposed erosion and sediment controls and their locations;
- Location of washdown and stockpile areas including covering materials and methods;
- Vegetation management including removal and revegetation;
- A schedule and programme of the sequence of the sediment and erosion control works or devices to be installed and maintained.
- Inspection and maintenance program;
- North point and scale.

All Site drainage and sediment and erosion control works and measures as described in the SWMP, and any other pollution controls, as required by these conditions, shall be implemented prior to commencement of any other works at the Site.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Construction Certificate.

Reason: To promote the long-term sustainability of ecosystem functions.

## **CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK**

### **Installation and Maintenance of Sediment and Erosion Control**

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) and the Erosion and Sediment Control Plan prepared by <INSERT>.

Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and the site is sufficiently stabilised with vegetation.

Reason: To protect the surrounding environment from the effects of sedimentation and erosion from the site.