

PO Box 979 Level 1, 91 George Street PARRAMATTA NSW 2150

Office 02 9891 5033 Fax 02 9891 3898 admin@sparksandpartners.com.au

sparksandpartners.com.au

ABN 95 161 152 969

# INTEGRATED WATER CYCLE MANAGEMENT REPORT

# RESIDENTIAL DEVELOPMENT

3 CENTRAL ROAD, AVALON

Date: 12 December 2019

Revision: 1
Issue: 1

Ref. No.: 19279\_C\_RPT\_IWCM Report

Prepared for: Avalon Central Pty Ltd C/o Cottee Parker

JPRA

Client Details: Email: Roland.Martinez@cotteeparker.com.au

Phone: 9366 1133











# Disclaimer

This specification (including any enclosures and attachments) has been prepared for the exclusive use and benefit of the addressee(s) and solely for the purpose for which it is provided. Unless we provide express prior written consent, no part of this report should be reproduced, distributed or communicated to any third party. We do not accept any liability if this report is used for an alternative purpose from which it is intended, nor to any third party in respect of this report.

#### **Document Control**

Revision	Date	Description	Prepared	Reviewed	Approved
1	12.12.19	Issued for DA	DL	BB	BB

Prepared by	Danya Leiva	Revision	1
Approved by	Benjamin Barrett	Revision	1



# **TABLE OF CONTENTS**

1.	EXEC	UTIVE SUMMARY	. 1
2.	INTR	ODUCTION	. 2
		Existing Site	
	2.2	Proposed Development	
3.	INTE	GRATED WATER MANAGEMENT	. 3
	3.7	General	
	3.2	Rainwater Reuse	. G
	3.3	Stormwater Quality	
	3.4	Stormwater Quantity	. E
	3.5	Maintenance and Monitoring	. 5
CONC	LUSIC	N	. 6
APPE	NDIX A	A. CONCEPT DRAINAGE PLANS	. 7
APPE	NDIX E	3. ON-SITE DETENTION CHECKLIST	. 8
APPE	NDIX (	C. MAINTENANCE & MONITORING SCHEDULE	. g



## 1. EXECUTIVE SUMMARY

Sparks & Partners have been engaged by Avalon Central Pty Ltd to provide civil engineering services to support the proposed Development Application for 3 Central Avenue, Avalon Beach. The engineering services include the design and documentation of the stormwater drainage infrastructure for the proposed development.

Northern Beaches Council being the approval authority for the proposed development, require an Integrated Water Cycle Management Plan be prepared that takes into consideration the objectives and controls under the relevant DCP and engineering guidelines. In response to this requirement Sparks and Partners has undertaken modelling of the proposed integrated water management measures and prepared this report to demonstrate that the proposed residential development identifies and incorporates water conservation and stormwater management measures into its design and operation in accordance with the requirements of the Northern Beaches Council DCP and Pittwater Council DCP.





# 2. INTRODUCTION

## 2.1 Existing Site

The site is situated within the former Pittwater area within Northern Beaches Council. The site currently contains a two storey residential unit building of masonry construction and associated driveway pavement, lawns and landscaping. The site perimeter is lined by a mix of timber, cyclone and aluminum fencing. The site falls steeply to the southern rear boundary at an average of 8.9% grade. A Sydney water sewer main traverses the rear and western boundaries in a east/west alignment.

#### 2.2 Proposed Development

The proposed development occupies a total site area of 1,418m² and consists of two basement carparks, two residential unit buildings two stories above ground level, pedestrian pavement and landscaping. The development consists of roofed area occupying 726m², pavement area occupying 294m² and the landscaping occupies 398m². The site is bounded by Central Road on the northern boundary, Patterson Lane on the eastern boundary, 5 Central Road on the western boundary and Dunbar Park along the northern boundary.



#### 3. INTEGRATED WATER MANAGEMENT

#### 3.1 General

The objective of integrated water management is to provide a strategy that brings together the different aspects of the water cycle as a whole rather than an ad hoc approach to water management. This includes the management aspects of freshwater, wastewater and stormwater. The following integrated water management strategies have been considered and addressed for the proposed development:

- 1. Employ an integrated water collection and recycling system for capturing and recycling roofwater;
- 2. Control the quality of stormwater that is disposed from the site;
- 3. Control the quantity of stormwater that is discharged for the site.

To demonstrate the above concept stormwater drainage plans and associated details have been prepared along with detailed modelling using the Council endorsed MUSIC software package. The concept stormwater drainage plans detail the location of the water management infrastructure including pits, pipes, on-site detention (OSD) tank, rainwater tanks (RWT), enviropods and stormfilter cartridges, and are included in Appendix A.

#### 3.2 Rainwater Reuse

Through the reuse of collected roofwater for non-potable reuse the proposed demand on potable water resources is reduced. The proposed development will capture roof water from part of the building roof area (718m²). This collected roofwater will be conveyed to two 10,000 Litre tanks for storage and reuse throughout the development. Re-use purposes will primarily include toilet flushing and irrigation uses. Rainwater tanks have been sized according to the table provided within Clause B5.5 of Pittwater Council's DCP for a development less than 1000m².

A water balance of the proposed reuse system has been completed to model the effectiveness and efficiency of the system. The water balance model was constructed using the MUSIC software package with the following inputs:

- Sydney Observatory rainfall data station 066062 from 1981 to 1985.
- Total approximate non-potable reuse of is based on:
  - Allowing 0.1kL/day per toilet, with 16 toilet facilities provided, equates to approx. 1.6kL per day.
  - 396m² or irrigated area requiring 20mm rainfall per week equates to approx.
     434L per day.



Using the above determined non-potable demand the MUSIC model determines the rainwater tank has an approximate efficiency of 70.50%. This efficiency results in an approximate reduction in the proposed demand on potable water supplies of 520,000 litres per year.

## 3.3 Stormwater Quality

To ensure the quality of stormwater leaving the site is acceptable and meets council's requirements specific water quality treatment measures are to be employed. These treatment measures are to treat the collected stormwater runoff prior to discharge to the council drainage system located in Patterson Lane. The treatment measures consist of Ocean Protect Enviropods within inlet pits, two 10kL rainwater tanks for reuse and three 460mm PSorb StormFilter Cartridges The combination of these measures provides a treatment train approach to the treatment of stormwater runoff.


Alternate treatment measures such as swales and infiltration basins have been considered in the design. The steep slope of the site and layout of landscaping area available make these measures prohibitive to practically implement with sufficient capacity to meet council's reduction targets, drain adequately, and meet the requirement to capture all impervious area. The existing council drainage pit within Patterson Lane has been utilised as the site discharge point, in lieu of infiltration.

Modelling of the proposed treatment measures has been undertaken using the MUSIC software package version 6. The modelling inputs have been based on the source node parameters outlined in Northern Beaches Council WSUD & MUSIC Modelling Guidelines. The modelling results of the water quality achieved for the site is detailed in Table 1 – MUSIC Model Results below, along with a figure of the prepared model.

			%	NBC %	Compliance
	Source	Residual	Reduction	Reduction	with NBC
	Load	Load	Achieved	Requirement	Requirement
Total Suspended Solids (kg/yr)	91.3	13.7	85	85	YES
Total Phosphorus (kg/yr)	0.262	0.0647	75.3	65	YES
Total Nitrogen (kg/yr)	2.85	0.959	66.3	45	YES
Gross Pollutants (kg/yr)	30.4	0.778	97.4	90	YES

Table 1. MUSIC Model Results





# 3.4 Stormwater Quantity

The proposed development requires the implementation of on-site detention (OSD) as per the Council DCP to control stormwater discharge from the site. The proposed development has an approximate area of 1,384m² (97.6%) draining to the proposed on-site detention (OSD) facility which includes pavement (262m²), roof (726m²) and landscaped (396m²) areas. A catchment plan of the proposed development is included in the Appendix A.

Pittwater Council's DCP Clause B5.7 has been utilised to determine the required volume and discharge for the proposed development. Based on the above catchment areas the storage required for the proposed development is approx. 60m³ with a maximum discharge of 30L/sec. The On-Site Detention Checklist is located in the Appendix B for review.

# 3.5 Maintenance and Monitoring

To ensure the continued efficient and correct operation of the proposed integrated water management infrastructure a 'maintenance and monitoring schedule' is included in the Appendix C of this plan. The schedule details the frequency of inspections, what is to be inspected and what rectifications to make if required for the water management infrastructure located within the proposed development. The schedule is to be implemented upon commissioning of the water management infrastructure and remain in place for the life of the development; with all records kept on site for inspection should the approval authority deem it necessary.



#### CONCLUSION

Based on the preparation of the concept stormwater drainage plans and MUSIC modeling results it is demonstrated that the principles of integrated water management have been incorporated into the design and operation of the proposed development at 3 Central Avenue, Avalon Beach in accordance with Northern Beaches Council DCP and Pittwater Council DCP. It is demonstrated that the proposed development achieves reductions in potable water import by capturing rainwater on site and reusing this for non-potable uses including irrigation and toilet flushing, achieves pollution reduction targets set by council, and employs OSD for the control of stormwater discharge from the site in accordance with targets set by council. It is also demonstrated that the proposed developments employed water conservation measures will continue to operate effectively and efficiently through the implementation and use of a monitoring and maintenance schedule ensuring the integrity of the system is maintained.



# **APPENDIX A. CONCEPT DRAINAGE PLANS**

# 3 CENTRAL ROAD, AVALON BEACH **CONCEPT STORMWATER MANAGEMENT**

#### SITE WORKS - GENERAL

- 1. ALL WORKS ARE TO BE UNDERTAKEN IN ACCORDANCE WITH LOCAL
- 2. ALL TRENCHING WORKS ARE TO BE RESTORED TO ORIGINAL CONDITION 3. THE INTEGRITY OF ALL EXISTING AND NEW SERVICES IS TO BE MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD.
- 4. ALL PLANS ARE TO BE READ IN CONJUNCTION WITH APPROVED ARCHITECTS, STRUCTURAL ENGINEERS AND OTHER CONSULTANT'S PLANS. ANY DISCREPANCIES ARE TO BE NOTIFIED TO THE ENGINEER FOR CLARIFICATION.
- 5. THE ENGINEER SHALL BE GIVEN A MIN. OF 48 HOURS NOTICE FOR ALL STORMWATER DRAINAGE AND PAVEMENT INSPECTIONS. CONCRETE SHALL NOT BE DELIVERED UNTIL ENGINEERS APPROVAL IS OBTAINED.

#### SITE WORKS - ACCESS AND SAFETY

- 1. ALL WORKS ARE TO BE UNDERTAKEN IN A SAFE MANNER IN REQUIREMENTS.
- 2. ACCESS TO ADJACENT BUILDINGS AND PROPERTIES SHALL BE MAINTAINED AT ALL TIMES.

NOT TO SCALE

3. WHERE NECESSARY SAFE PASSAGE SHALL BE PROVIDED FOR VEHICLES AND PEDESTRIANS THROUGH OR ADJACENT TO THE SITE.

DATE AMENDMENT

#### SEDIMENT AND EROSION CONTROL

- 1 THE CONTRACTOR SHALL INSTIGATE ALL SEDIMENT AND EROSION AND THE "BLUE BOOK" (MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION, PRODUCED BY THE DEPARTMENT OF HOUSING). THESE MEASURES ARE TO BE REGULARLY INSPECTED AND MAINTAINED.
- 2. THE SEDIMENT & EROSION CONTROL PLAN PRESENTS CONCEPTS ONLY, THE CONTRACTOR SHALL AT ALL TIMES BE RESPONSIBLE FOR THE ESTABLISHMENT & MANAGEMENT OF A DETAILED SCHEME MEETING COUNCIL'S DESIGN, AND ALL OTHER REGULATORY AUTHORITY
- NUMBER PRACTICAL, THE SOIL EROSION HAZARD ON THE SITE SHALL BE KEPT AS LOW AS POSSIBLE. TO THIS END, WORKS SHOULD BE UNDERTAKEN IN THE FOLLOWING SEQUENCE:
- A. INSTALL ALL TEMPORARY SEDIMENT FENCES AND BARRIER FENCES.
  WHERE FENCES ARE ADJACENT TO EACH OTHER THE SEDIMENT
  FENCE CAN BE INCORPORATED INTO THE BARRIER FENCE.
- b. CONSTRUCT TEMPORARY STABILISED SITE ACCESS. INCLUDING SHAKE DOWN AND WASH PAD.
- c. INSTALL SEDIMENT CONTROL MEASURES AS OUTLINED ON THESE SEDIMENT AND CONTROL PLANS (ONCE APPROVED)
- 4. THE CONTRACTOR SHALL UNDERTAKE SITE DEVELOPMENT WORKS SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF MINIMUM WORKABLE SIZE.
- 5. AT ALL TIMES AND IN PARTICULAR DURING WINDY AND DRY WEATHER, LARGE, UNPROTECTED AREAS WILL BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL. TACIFIERS MAY BE USED TO CONTROL DUST DURING EXTENDED PERIODS OF DRY
- 6. ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD OVER THE SURFACE) SHALL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.
- 7. WATER SHALL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS THE CATCHMENT AREA HAS BEEN STABILISED AND/OR ANY LIKELY SEDIMENT HAS BEEN FILTERED OUT.
- 8. TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES SHALL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE STABILISED / REHABILITATED.
- 9. THE CONTRACTOR SHALL ALLOW FOR THE ESTABLISHMENT OF ANY OTHER EROSION PROTECTION MEASURES. (IF APPLICABLE).
- 10.THE CONTRACTOR SHALL REGULARLY INSPECT (MINIMUM TWICE PER WEEK) ALL EROSION AND SEDIMENT CONTROL MEASURES TO ENSURE THEY ARE OPERATING EFFECTIVELY, REPAIRS AND/OR MAINTENANCE SHALL BE UNDERTAKEN REGULARLY AND AS REQUIRED. PARTICULARLY FOLLOWING STORM EVENTS.
- 11. ACCEPTABLE RECEPTORS SHALL BE USED FOR CONCRETE AND MORTAR SLURRIES PAINTS ACID WASHINGS LIGHT-WEIGHT WASTE MATERIALS SLURRICS, PAINTS, ACID WASHINDS, LIURIT-WEIGHT WASTE HATERIALS
  AND LITTER, WASTE FROM THESE RECEPTORS SHALL BE DISPOSED OF IN
  ACCORDANCE WITH REGULATORY AUTHORITY REQUIREMENTS, PAY ALL
  FEES AND PROVIDE EVIDENCE OF SAFE DISPOSAL.

#### STORMWATER

- ALL WORKS ARE TO BE LINDERTAKEN IN ACCORDANCE WITH THE
- 2. REFER TO INTEGRATED WATER CYCLE MANAGEMENT REPORT [1] (DATED: 12/12/19) FOR FURTHER DETAILS ON STORMWATER SYSTEM
- 3. ALL PIPES LESS THAN OR EQUAL TO Ø300mm IN SIZE ARE TO BE SOLVENT WELD-JOINTED UPVC CLASS SN6 U.N.O
- 4. ALL PIPES Ø375mm OR GREATER IN SIZE ARE TO BE MIN. CLASS 2 REINFORCED CONCRETE PIPE (RCP) WITH SPIGGOT AND SOCKETED JOINT OR VANTAGE PIPE PLUS (VPIPE+) FIBRE REINFORCED CONCRETE (FRC) WITH VANTAGE PIPE PLUS JOINT U.N.O.
- 5. ALL PIPES ARE TO BE LAID AT MIN. 1.0% GRADE U.N.O.
- 6. PIPE BEDDING IS TO BE HS2 UNDER ROADS AND TRAFFICKED AREAS AND SHALL BE H2 IN LANDSCAPED AND PEDESTRIAN TRAFFICKED AREAS U.N.O.
- 7. ALL PIPE BENDS AND JUNCTIONS ARE TO BE MADE WITH EITHER PURPOSE MADE FITTINGS OR STORMWATER DRAINAGE PITS.
- 8. MINIMUM COVER FROM THE OBVERT OF THE STORMWATER PIPE OF 300mm IS TO BE PROVIDED IN LANDSCAPED AREAS AND 600mm IN VEHICULAR TRAFFICKED AREAS U.N.O.
- WHERE MINIMUM COVER CANNOT BE ACHIEVED CONCRETE ENCASEMENT OF THE AFFECTED PIPE IS MAY BE UNDERTAKEN WITH 20MPa CONCRETE WITH A MIN. COVER OF 150mm TO ALL SIDES OF THE PIPE. THE CONTRACTOR SHALL CONFIRM THIS REQUIREMENT WITH THE ENGINEER OR SUPERINTENDENT
- 10. LAID PIPELINES ARE TO HAVE THE FOLLOWING CONSTRUCTED TOLERANCES:
- a. HORIZONTAL-1:300 ANGULAR DEVIATION FROM REQUIRED ALIGNMENT b. VERTICAL-1:300 ANGULAR DEVIATION FROM REQUIRED ALIGNMENT.
- 10. ALL DRAINAGE PITS ARE TO BE CAST IN-SITU, PRECAST DRAINAGE PITS MAY BE USED WITH APPROVAL FROM THE ENGINEER. THE CONTRACTOR SHALL SUBMIT A PRECAST PIT INSTALLATION WORK METHOD STATEMENT FOR ASSESSMENT BY THE ENGINEER FOR
- DRAINAGE PIT COVERS ARE TO BE FITHER GALVANISED STEEL OR DRAINAGE PIT LOVERS ARE TO DE TITLER DALVANISED STEEL OR CAST IRON CLASS 'B' IN LANDSCAPED AND PEDESTRIAN TRAFFICKED AREAS AND CLASS 'D' IN ALL VEHICULAR TRAFFICKED AREAS U.N.O.
- 12. DRAINAGE PIT COVERS ARE TO BE 'HEELSAFE' TYPE IN ALL PEDESTRIAN TRAFFICKED AREAS U.N.O.
- 13. EXISTING STORMWATER PIT LOCATIONS AND INVERT LEVELS TO BE CONFIRMED PRIOR TO COMMENCING WORKS ON SITE. 14. PROVIDE CLEANING EYES (RODDING POINTS) TO PIPES AT ALL CORNERS.
- AND T-JUNCTIONS WHERE NO PITS ARE PRESENT 15. DOWN PIPES CONNECTED DIRECT TO PIPES TO BE CONNECTED AT 45° TO THE FLOW DIRECTION WITH A CLEANING EYE PROVIDED AT GROUND

#### DRAWING SCHEDULE

DA1.01 COVER SHEET, DRAWING SCHEDULE & LOCALITY PLAN

DA2.01 CONCEPT SEDIMENT & EROSION CONTROL PLAN & DETAILS

DAL 01 CONCEPT STORMWATER MANAGEMENT PLAN \_ BASEMENT 01

DA4.02 CONCEPT STORMWATER MANAGEMENT PLAN - LOWER GROUND

DA4.03 CONCEPT STORMWATER MANAGEMENT PLAN - GROUND

DA4.10 CONCEPT STORMWATER CATCHMENT PLAN DA4.11 STORMWATER MANAGEMENT DETAILS SHEET 1

DA4.12 STORMWATER MANAGEMENT DETAILS SHEET 2



LOCALITY PLAN

**DA ISSUE** 

12/12/19 ISSUED FOR DA

INIT | REV | DATE | AMENDMENT

AVALON BEACH CENTRAL PTY. LTD. 3 CENTRAL ROAD, AVALON BEACH

COTTEEPARKER (D JPRA

**SPARKS**+PARTNERS

FPA


& LOCALITY PLAN וח DEC 2019 N.T.S SIZE A1

COVER SHEET, DRAWING SCHEDULE

CIVIL DESIGN

INIT REV

DA1.01




-200 THICK

INIT REV DATE AMENDMENT

COMPACTED DGB20

EXISTING ROADWAY



PLACE STOCKPILES MORE THAN 2 (PREFERABLY 5) METRES FROM EXISTING VEGETATION, CONCENTRATED WATER FLOW, ROADS AND HAZARD AREAS.

CONSTRUCT ON THE CONTOUR AS LOW, FLAT, ELONGATED MOUNDS.
WHERE THERE IS SUFFICIENT AREA, TOPSOIL STOCKPILES SHALL BE LESS THAN 2

METRES IN HEIGHT. WHERE THEY ARE TO BE IN PLACE FOR MORE THAN 10 DAYS. STABILISE FOLLOWING THE

APPROVED ESCP OR SWMP TO REDUCE THE C-FACTOR TO LESS THAN 0.10.

CONSTRUCT EARTH BANKS ON THE UPSLOPE SIDE TO DIVERT WATER AROUND

STOCKPILES AND SEDIMENT FENCES 1 TO 2 METRES DOWNSLOPE.


SANDBAGS OVERLAP ONTO KERB THREE LAYERS OF SANDBAGS GAP BETWEEN BAGS —

SEDIMENT TRAP FOR DROP INLET PIT

GROUND LEVEL AT END OF SANDBAG BARRIER MUST BE HIGHER THAN

SEDIMENT TRAP FOR KERB INLET (AT LOW POINT - SANDBAG)

3 CENTRAL ROAD, AVALON BEACH




#### NOTES


RUNOFF

DROP INLET SANDBAG LAYER.

REFER TO DRAWING DA1.01 FOR GENERAL NOTES AND SPECIFICATIONS

SANDBAG BARRIER TO PREVENT-RUNOFF BYPASSING DROP INLET PIT





GEOTEXTILE

SECTION DETAIL

ON SOIL, 200mm x 100mm TRENCH WITH COMPACTED BACKFILL AND ON ROCK, SET INTO SURFACE CONCRETE

# SEDIMENT\_FENCE

#### NOTES:

-SANDBAGS PLACED SECURELY

AROUND DROP INLET PIT

1.5m STAR PICKETS AT

MAX 20m CENTRES

- CONSTRUCT SEDIMENT FENCES AS CLOSE AS POSSIBLE TO BEING PARALLEL TO THE CONTOURS OF THE SITE, BUT WITH SMALL RETURNS AS SHOWN IN THE DRAWING TO LIMIT THE CATCHMENT AREA OF ANY ONE SECTION. THE CATCHMENT AREA SHOULD BE SMALL ENOUGH TO LIMIT WATER FLOW IF CONCENTRATED AT ONE POINT TO
- SOL/S IN THE DESIGN STORM EVENT, USUALLY THE 10-YEAR EVENT.
  CUT A 200mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE
  FOR THE BOTTOM OF THE FABRIC TO BE ENTRENCHED.
- DRIVE 1.5m LONG STAR PICKETS INTO GROUND AT 2.0m INTERVALS (MAX) AT THE DOWNSLOPE EDGE OF THE TRENCH. ENSURE ANY STAR PICKETS ARE FITTED WITH SAFETY CAPS.
- FIX SELF-SUPPORTING GEOTEXTILE TO THE UPSLOPE SIDE OF THE POSTS ENSURING IT GOES TO THE BASE OF THE TRENCH. FIX THE GEOTEXTILE WITH WIRE TIES OR AS RECOMMENDED BY THE MANUFACTURER. ONLY USE GEOTEXTILE SPECIFICALLY PRODUCED FOR SEDIMENT FENCING. THE USE OF SHADE CLOTH FOR THIS PURPOSE IS NOT SATISFACTORY.

  JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150mm
- OVERLAP.
- BACKFILL THE TRENCH OVER THE BASE OF THE FABRIC AND COMPACT

# MAINTENANCE

GEOTEXTILE-

FILTER FABRIC

RUNOFF FROM PAD

DIRECTED TO SEDIMENT TRAF

THE TEMPORARY ACCESS SHALL BE MAINTAINED IN A CONDITION THAT PREVENTS TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS OF WAY,

HIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL GRAVEL AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT,

ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS OF WAY MUST BE REMOVED IMMEDIATELY.

INSTALL BARRIER ON EITHER SIDE OF SHAKER PAD

EXISTING-


- TO ENSURE VEHICLES ARE GUIDED ON TO THE PAD.

   INVERT OF SHAKER PAD TO BE DRAINED VIA AGRICULTURAL PIPE WRAPPED IN GEOTEXTILE FABRIC.

DATE AMENDMENT

12/12/19 ISSUED FOR DA

STABILISED SITE ACCESS



# **DIVERSION BANK**

AVALON BEACH CENTRAL PTY. LTD.

**DA ISSUE** 


INIT REV


COTTEEPARKER @ JPRA


FPA


**SPARKS**+PARTNERS CIVIL DESIGN CONCEPT SEDIMENT & EROSION CONTROL PLAN & DETAILS וח DL


DEC 2019 SCA SIZE A1 AS SHOWN 19279 DA2.01
















# **APPENDIX B. ON-SITE DETENTION CHECKLIST**





# Appendix 16 – On-site Detention Checklist

This checklist is to be used to determine the on-site stormwater disposal requirement for developments and must be completed and included with the submission of any development application for these works. Please read this form carefully for its notes, guidelines, definition and relevant policies.

For assistance and support, please contact Council's Development Engineering and Certification team on 1300 434 434.

Part 1 Location of the Property					
House Humber	3	Legal Property Descripti	on		
Street	Central Road	Lot	27		
Suburb	Avalon Beach	Section	Null		
Postcode	2107	DP	DP9151		

Part 2 Site Details			
Northern Beaches Stormwater Regions (refer to Map 2 of Northern Beaches Council's Water Management for Development policy)	1	Total Site Area	1,418m²
Pre-Development Impervious Area	465m²	Post-Development Impervious Area	1,020m²
Is the site of the development located with referred to Council's Local Environmental I	Yes □ No 💆		
If yes, On-site stormwater Detention system to part 5 of this checklist If no, please proceed to part 3 of this checklish	` ′	not required and please proceed	

# Part 3: Northern Beaches Stormwater Regions (refer to Map 2 of Northern Beaches Council's Water Management for Development policy) If the site of the development located within Region 1, please proceed to the part 4.1 of this checklist If the site of the development located within Region 2, please proceed to the part 4.2 of this checklist If the site of the development located within Region 3, please proceed to the part 4.3 of this checklist If the site of the development located within Region 4, please refer to Council's Warriewood Valley Water Management Specification.



# Part 4 Determination of OSD Requirements

Part 4.1 Northern Beaches Stormwater Region 1	
Is the additional impervious area of the development more than 50 m <sup>2</sup> on a cumulative basis since February 1996?	Yes ♥ No □
If yes, OSD is required and please refer to section 9.3.1 of Council's Water Mana Policy If no, OSD is not required and please proceed to the part 5 of this checklist	agement for Development

Part 4.2 Northern Be	Part 4.2 Northern Beaches Stormwater Region 2					
Part 4.2.1 Descriptio	Part 4.2.1 Description of Work					
resulting in the creation accordance with the s	Residential flat building, commercial, industrial, multiple occupancy development and subdivisions resulting in the creation of three lots or more, will require OSD in all case. Please provide a design in accordance with the section 9.3.2 of Council's Water Management for Development Policy. Any single residential building development, please proceed to part 4.2.2 of this checklist.					
Part 4.2.2 Exemption						
Is the site area less th	an 450m <sup>2</sup> ?	Yes □ No □				
Does the site of the development drain directly to the ocean without the need to pass through a drainage control structure such as pipe, bridge, culvert, kerb and gutter or natural drainage system?						
Is it an alternation and	Is it an alternation and addition development to the existing dwellings? Yes □ No □					
	If yes to any of the above questions, OSD is not required. If no to all the above questions, proceed to part 4.2.3					
Part 4.2.3 Determina	tion of OSD Requirements					
Calculation	a) Site area m² x 0.40 (40%) =	. m² Yes □ No □ 3.2 of Council's Water				



# Part 4.3 Northern Beaches Stormwater Region 3 Part 4.3.1 Stormwater Zone In the region, the method of stormwater control to be applied shall depend on the location of the site. Please refer to Map 3 of Northern Beaches Council's Water Management for Development policy. If the site of the development located within stormwater zone 1, please proceed to the part 4.3.2 of this checklist If the site of the development located within stormwater zone 2, please provide a design in accordance with the section 9.3.3.3 of Council's Water Management for Development Policy. If the site of the development located within stormwater zone 3, please provide a design in accordance with the section 9.3.3.4 of Council's Water Management for Development Policy. If the site of the development located within stormwater zone 4, please provide a design in accordance with the section 9.3.3.5 of Council's Water Management for Development Policy. Part 4.3.2 Determination of OSD requirements in Stormwater Zone 1 Part 4.3.2.1 For A New Building Yes □ No □ 1) Exemption a) Is the site area less than 400? Yes □ No □ b) Is the post-development impervious area less than 190 m<sup>2</sup>? If yes to both questions, OSD is not required. If no to any of the above questions, please process to calculation $m^2 \times 0.35 =$ $m^2 + 50 =$ 2) Calculation a) Site area b) Post- development impervious area m<sup>2</sup> OSD will not be required when (b) is less than 250 m<sup>2</sup> and (a) is greater than (b) Is OSD required for this development? Yes □ No □ If yes, provide a design in accordance with the section 9.3.3.2 of Council's Water Management for Development Policy. If no, OSD is not required and please proceed to part 5. Part 4.3.2.2 For Alterations and Additions If the current impervious area of the site is more than 60% of the site area, OSD will be required. Alternatively, please proceed to the next calculation section. 1) Calculation Is the post development impervious area increased by less than 50 m<sup>2</sup>? Yes □ No □ Is the post development impervious area less than 60% of the site area? Yes $\square$ No $\square$ If yes to both questions, OSD is not required. If no to any of the above questions, provide a design in accordance with section 9.3.3.2 of Council's Water Management for Development Policy



Part 5 Disposal of Stormwater	
Does the site fall naturally towards the street?	Yes ♥ No □
If yes, provide a design in accordance with section 5.1 of Co Policy.	ouncil's Water Management for Development
If no, provide a design in accordance with section 5.5 of Cou Policy.	uncil's Water Management for Development

# Designed to help you fill out this application Site area: This refers to the area of the land bounded by its existing or proposed boundaries. Impervious area: This refers to driveways, parking spaces, pathways, paved areas, hardstand areas, roofed areas, garages and outbuildings. Pre Development Impervious area: This refers all impervious areas of the site before the development. Post Development Impervious areas: This refers all the impervious areas within the site after the development is completed.



# **APPENDIX C. MAINTENANCE & MONITORING SCHEDULE**



Job No.:	Date: Click or tap to enter a date.
Author Name:	Signature:

#### PROJECT ADDRESS: 3 Central Road, Avalon Beach

#### **General Notes:**

- 1. Maintenance is to be carried out with regard to relevant occupational health and safety guidelines and standards. This includes all confined space, traffic management, fall arrest and other requirements.
- 2. Initial monitoring and inspections of the stormwater system post commissioning are to be carried out every 3 months for the first year of operation. The amount and type of debris is to be noted and recorded. This information shall be used to determine if modification of the frequency of inspections is required.
- 3. The frequency of inspections shown in the stormwater maintenance schedule are the maximum periods. Inspection frequencies may be reduced upon completion of the initial monitoring and inspection program as noted in note 2.
- 4. Blank copies of the maintenance schedule are to be made and filled out during each subsequent inspection with the details kept on site for future reference.

Inspected by:
Date of Inspection:
Date of Next Inspection:

Item to be Inspected	Frequency	Performed by	Inspected	spected Maintenance Required Maintenance Procedure		Maintenance Completed
			Yes/No	Yes/No		Date
General						
Eaves/Box Guttering System and Downpipes	Six Monthly/ After Major Storm	Owner / Maintenance Contractor			Inspect and remove any build up of sediment, debris, litter and vegetation within gutter system.	
Stormwater surface inlet and junction pits	Four Monthly/ After Major Storm	Owner / Maintenance Contractor			Remove grate and inspect internal walls and base, repair where required. Remove any collected sediment, debris, litter and vegetation. (e.g. Vacuum/eductor truck) Inspect and ensure grate is clear of sediment, debris, litter and vegetation. Ensure flush placement of grate on refitment	
General inspection of complete stormwater drainage system (that's visible)	Bi-annually	Owner / Maintenance Contractor			Inspect all drainage structures noting any dilapidation, carry out required repairs.	



Rainwater Tank			
First Flush Device	6 Monthly	Owner / Maintenance Contractor	Inspect first flush device to ensure correct operation. Remove accumulated litter & debris. If device is not functioning properly repair or replace.
Internal Inspection	6 Monthly	Owner / Maintenance Contractor	Check for evidence of access by animals, birds or insects including the presence of mosquito larvae. If present, identify access point and close. If evidence of algal growth, find and close points of light entry.
Tank and tank roof	6 Monthly	Owner / Maintenance Contractor	Check structural integrity of tank including roof and access covers.  Any dilapidation including holes or gaps are to be noted and repaired.
Proprietary Treatment Devices			
OceanProtect OceanGuard	Refer Manufactures Manual	Maintenance / Specialised Contractor	Refer to manufacturers operation and maintenance manual.
OceanProtect PSorb StormFilter Cartridges	Refer Manufactures Manual	Maintenance / Specialised Contractor	Refer to manufacturers operation and maintenance manual.
On-Site Detention Tank			
Trash Screen	Six Monthly/ After Major Storm	Owner / Maintenance Contractor	Inspect trash screen to ensure correct operation. Remove accumulated litter & debris. If device is not functioning properly repair or replace.
Orifice Plate	Six Monthly/ After Major Storm	Owner / Maintenance Contractor	Inspect orifice plate to ensure correct operation. Check orifice diameter size is correct and no damage is present to orifice edge. Check orifice plate is securely fastened to wall with no gaps present between plate and face of wall. If gaps are present fill with sealant or mortar to provide water tight seal.
Weep Holes in base of sump	Six Monthly/ After Major Storm	Owner / Maintenance Contractor	Inspect weep holes in base of sump. Ensure weep holes are able to drain effectively and remove accumulated sediment and debris if present.
Tank and tank roof	6 Monthly	Owner / Maintenance Contractor	Check structural integrity of tank including roof and access covers.  Any dilapidation including holes or gaps are to be noted and repaired.