

Traffic Engineer Referral Response

Application Number:	DA2019/1280
Date:	29/03/2020
Responsible Officer	
Land to be developed (Address):	Lot 3B DP 164259 , 62 Beaconsfield Street NEWPORT NSW 2106 Lot 4A DP 159498 , 11 Queens Parade NEWPORT NSW 2106 Lot 3A DP 164259 , 9 Queens Parade NEWPORT NSW 2106 Lot 2 DP 209106 , 7 Queens Parade NEWPORT NSW 2106 Lot 5A DP 158658 , 13 Queens Parade NEWPORT NSW 2106 Lot 4B DP 159498 , 60 Beaconsfield Street NEWPORT NSW 2106

Officer comments

The application proposes the removal of 7 x dwellings and a 40 place child care and the construction of 18 townhouses.

Traffic:

The anticipated change of use is expected to provide significant reductions to the traffic being generated from this site. No objections are raised.

Parking:

Parking numbers are compliant with the DCP. No objections are raised.

Access and Car Park:

The access arrangements are deemed acceptable with the amendments provided by the applicant.

The provision of the 'No Parking' space adjacent to the driveway is deemed suitable as it will enable the waiting of vehicles and also assist with the drop-off of passengers to the precinct.

Further, additional swept path analysis is required demonstrating that all vehicles can enter and exit each designated space and enter and leave the site in a forward direction.

Servicing:

On-street servicing is deemed acceptable. The applicant will be conditioned to provide a signage plan to restrict parking during waste collection days. This will require approval of the Local Traffic Committee prior to occupation certificate.

Conclusion:

No further objections are raised.

The proposal is therefore supported.

Responsible Officer.

Recommended Traffic Engineer Conditions:

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

Compliance with Standards

The development is required to be carried out in accordance with all relevant Australian Standards.

(Note: At the time of determination the following (but not limited to) Australian Standards applied:

- (a) AS2601.2001 - Demolition of Structures**
- (b) AS4361.2 - Guide to lead paint management - Residential and commercial buildings**
- (c) AS4282:1997 Control of the Obtrusive Effects of Outdoor Lighting**
- (d) AS 4373 - 2007 'Pruning of amenity trees' (Note: if approval is granted) **
- (e) AS 4970 - 2009 'Protection of trees on development sites'**
- (f) AS/NZS 2890.1:2004 Parking facilities - Off-street car parking**
- (g) AS 2890.2 - 2002 Parking facilities - Off-street commercial vehicle facilities**
- (h) AS 2890.3 - 1993 Parking facilities - Bicycle parking facilities**
- (i) AS 2890.5 - 1993 Parking facilities - On-street parking**
- (j) AS/NZS 2890.6 - 2009 Parking facilities - Off-street parking for people with disabilities**
- (k) AS 1742 Set - 2010 Manual of uniform traffic control devices Set**
- (l) AS 1428.1 – 2009* Design for access and mobility - General requirements for access – New building work**
- (m) AS 1428.2 – 1992*, Design for access and mobility - Enhanced and additional requirements - Buildings and facilities**

*Note: The Australian Human Rights Commission provides useful information and a guide relating to building accessibility entitled "the good the bad and the ugly: Design and construction for access". This information is available on the Australian Human Rights Commission website [www.hreoc.gov.au/disability rights /buildings/good.htm](http://www.hreoc.gov.au/disability%20rights/buildings/good.htm). <www.hreoc.gov.au/disability%20rights%20/buildings/good.htm.>

**Note: the listed Australian Standards is not exhaustive and it is the responsibility of the applicant and the Certifying Authority to ensure compliance with this condition and that the relevant Australian Standards are adhered to.)

Details demonstrating compliance with the relevant Australian Standard are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure the development is constructed in accordance with appropriate standards.
(DACPLC02)

Construction Traffic Management Plan.

As a result of the site constraints, limited vehicle access and parking, a Construction Traffic Management Plan (CTMP) and report shall be prepared by an RMS accredited person and submitted to and approved by the Northern Beaches Council Traffic Team prior to issue of any Construction Certificate.

Due to heavy traffic congestion throughout the town centre, truck movements will be restricted during the major commuter peak times being 8.00-9.30am and 4.30-6.00pm.

The CTMP must address following:-

- The proposed phases of construction works on the site, and the expected duration of each construction phase;
- The proposed order in which works on the site will be undertaken, and the method statements on how various stages of construction will be undertaken;
- Make provision for all construction materials to be stored on site, at all times;
- The proposed areas within the site to be used for the storage of excavated materials, construction materials and waste containers during the construction period;
- The proposed method of access to and egress from the site for construction vehicles, including access routes and truck routes through the Council area and the location and type of temporary vehicular crossing for the purpose of minimising traffic congestion and noise in the area, with no access across public parks or reserves being allowed;
- The proposed method of loading and unloading excavation and construction machinery, excavation and building materials, formwork and the erection of any part of the structure within the site. Wherever possible mobile cranes should be located wholly within the site;
- Make provision for parking onsite. All Staff and Contractors are to use the basement parking once available.
- Temporary truck standing/ queuing locations in a public roadway/ domain in the vicinity of the site are not permitted unless approved by Council prior.
- Include a Traffic Control Plan prepared by a person with suitable RMS accreditation for any activities involving the management of vehicle and pedestrian traffic.
- The proposed manner in which adjoining property owners will be kept advised of the timeframes for completion of each phase of development/construction process. It must also specify that a minimum Fourteen (14) days notification must be provided to adjoining property owners prior to the implementation of any temporary traffic control measure.
- Include a site plan showing the location of any site sheds, location of requested Work Zones, anticipated use of cranes and concrete pumps, structures proposed on the footpath areas (hoardings, scaffolding or shoring) and any tree protection zones around Council street trees.
- Take into consideration the combined construction activities of other development in the surrounding area. To this end, the consultant preparing the CTMP must engage and consult with developers undertaking major development works within a 250m radius of the subject site to ensure that appropriate measures are in place to prevent the combined impact of construction activities, such as (but not limited to) concrete pours, crane lifts and dump truck routes. These communications must be documented and submitted to Council prior to work commencing on site.
- The proposed method/device to remove loose material from all vehicles and/or machinery before entering the road reserve, any run-off from the washing down of vehicles shall be directed to the sediment control system within the site;
- Specify that the roadway (including footpath) must be kept in a serviceable condition for the duration of construction. At the direction of Council, undertake remedial treatments such as patching at no cost to Council.
- The proposed method of support to any excavation adjacent to adjoining properties, or the road reserve. The proposed method of support is to be designed and certified by an appropriately qualified and practising Structural Engineer, or equivalent;
- Proposed protection for Council and adjoining properties;
- The location and operation of any on site crane; and

The CTMP shall be prepared in accordance with relevant sections of Australian Standard 1742 – “Manual of Uniform Traffic Control Devices”, RMS’ Manual – “Traffic Control at Work Sites”.

All fees and charges associated with the review of this plan is to be in accordance with Council’s Schedule of Fees and Charges and are to be paid at the time that the Construction Traffic Management Plan is submitted.

Reason: To ensure public safety and minimise any impacts to the adjoining pedestrian and vehicular traffic systems. Confirming appropriate measures have been considered for site access, storage and the operation of the site during all phases of the construction process in a manner that respects adjoining owner's property rights and protects amenity in the locality, without unreasonable inconvenience to the community. The CTMP is intended to minimise impact of construction activities on the surrounding community, in terms of vehicle traffic (including traffic flow and parking) and pedestrian amenity adjacent to the site. (DACTRCPC1)

Vehicular Swept Paths.

20. Vehicular manoeuvring paths must be provided to demonstrate all vehicles can enter or depart the site in a forward direction without encroaching on required car parking spaces. The drawings must be compliant with Australian/New Zealand Standard AS/NZS 2890.1:2004 - Parking facilities - Off-street car parking. Drawings must be submitted with the Construction Certificate application.

Reason: To ensure compliance with Australian Standards relating to manoeuvring, access and parking of vehicles. (DACTRCPC2)

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

Implementation of Construction Traffic Management Plan

All works and construction activities are to be undertaken in accordance with the approved Construction Traffic Management Plan (CTMP). All controls in the CTMP must be maintained at all times and all traffic management control must be undertaken by personnel having appropriate RMS accreditation. Should the implementation or effectiveness of the CTMP be impacted by surrounding major development not encompassed in the approved CTMP, the CTMP measures and controls are to be revised accordingly and submitted to Council for approval. A copy of the approved CTMP is to be kept onsite at all times and made available to Council on request.

Reason: to ensure compliance of the developer/builder in adhering to the Construction Traffic Management procedures agreed and are held liable to the conditions of consent. (DACTREDW1)

CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

Signage and Linemarking – External.

A plan demonstrating the proposed signage and line marking within Council's Public Domain shall be prepared by a suitably qualified person and submitted to and approved by the Local Traffic Committee prior to the issue of any Occupation Certificate.

Note: The applicant is advised that the plan will require approval by the local Traffic Committee if the proposal requires change in existing parking conditions and hence, adequate time should be allowed for this process

Reason: To ensure consistent parking amenity. (DACTRFPOC1)

Basement Garage Traffic Signal System.

To prevent conflicting vehicle flows on the internal basement garage ramp and avoid vehicles having to reverse up/ down the ramp, a traffic signal system must be installed at each ramp entry, designed to warn drivers about to enter the road of any conflicting vehicle approaching.

The signal system must;

- be clearly visible from ramp entrances and where applicable the on street waiting space,
- is to clearly indicate to an approaching driver, by way of red light or wording, that an opposing vehicle

has entered the ramp,

- Incorporate linemarking to delineate traffic flow and nominate waiting bay locations to allow vehicles to overtake another.

Details of the system, including the system operation, components and placement within the development, must be specified by a practising Traffic Engineer. This engineer is to submit a compliance certificate to the Accredited Certifier that the system has been installed and operating as designed, in accordance with the requirements of this condition, prior to the issue of any Occupation Certificate issued for the development.

Reason: To ensure no vehicle conflicts within the basement carpark (DACTRFPOC2)